NOVEMBER · 1953
PRICE 75 CENTS

ics

A McGRAW-HILL PUBLICATION



SOLDERLESS
CIRCUIT
ASSEMBLY

ULTRA COMPACT UNITS...OUNCER UNITS

HIGH FIDELITY . . . . SMALL SIZE . . . . FROM STOCK

UTC Ultra compact audio units are small and light in weight, ideally suited to remote amplifier and similar compact equipment. High fidelity is obtainable in all individual units, the frequency response being ± 2 DB from 30 to 20,000 cycles.

True hum balancing coil structure combined with a high conductivity die cast outer case, effects good inductive shielding.

Type No.	Application	Primary Impedance	Secondary Impedance	List Price
A-10	Low impedance mike, pickup, or multiple line to grid	50, 125/150, 200/250, 333, 500/600 ohms	50 ohms	$16.00
A-11	Low impedance mike, pickup, or line to 1 or 2 grids (multiple alloy shields for low hum pickup)	50, 200, 500	50,000 ohms	16.00
A-12	Low impedance mike, pickup, or multiple line to grids	50, 125/150, 200/250, 333, 500/600 ohms	80,000 ohms overall, in two sections	16.00
A-14	Dynamic microphone to one or two grids	30 ohms	50,000 ohms overall, in two sections	17.00
A-20	Mixing, mike, pickup, or multiple line to line	50, 125/150, 200/250, 333, 500/600 ohms	50, 125/150, 200/250, 333, 500/600 ohms	16.00
A-21	mixing, low impedance mike, pickup, or line to line (multiple alloy shields for low hum pickup)	50, 200/250, 500/600	50, 200/250, 500/600	16.00
A-16	Single plate to single grid	15,000 ohms	60,000 ohms, 2:1 ratio	15.00
A-17	Single plate to single grid 8 MA unbalanced D.C.	As above	As above	17.00
A-18	Single plate to two grids. Split primary	15,000 ohms	80,000 ohms overall, 2.3:1 turn ratio	16.00
A-19	Single plate to two grids 8 MA unbalanced D.C.	15,000 ohms	80,000 ohms overall, 2.3:1 turn ratio	19.00
A-24	Single plate to multiple line	15,000 ohms	50, 125/150, 200/250, 333, 500/600 ohms	16.00
A-25	Single plate to multiple line 8 MA unbalanced D.C.	15,000 ohms	50, 125/150, 200/250, 333, 500/600 ohms	17.00
A-26	Push pull low level plates to multiple line	30,000 ohms plate to plate	50, 125/150, 200/250, 333, 500/600 ohms	16.00
A-27	Crystal microphone to multiple line	100,000 ohms	50, 125/150, 200/250, 333, 500/600 ohms	16.00
A-30	Audio choke, 250 henrys @ 5 MA 6000 ohms D.C.. 65 henrys @ 10 MA 1500 ohms D.C.			12.00
A-32	Filter choke 60 henrys @ 15 MA 2000 ohms D.C.. 15 henrys @ 30 MA 500 ohms D.C.			10.00



TYPE A CASE
1½" x 1½" x 2" high

UTC OUNCER components represent the acme in compact quality transformers. These units, which weigh one ounce, are fully impregnated and sealed in a drawn aluminum housing ⅞" diameter... mounting opposite terminal board. High fidelity characteristics are provided, uniform from 40 to 15,000 cycles, except for O-14, O-15, and units carrying DC which are intended for voice frequencies from 150 to 4,000 cycles. Maximum level 0 DB.

OUNCER
CASE
⅞" Dia. x 1⅛" high

Type No.	Application	Pri. Imp.	Sec. Imp.	List Price
O-1	Mike, pickup or line to 1 grid	50, 200/250 500/600	50,000	$14.00
O-2	Mike, pickup or line to 2 grids	50, 200/250 500/600	50,000	14.00
O-3	Dynamic mike to 1 grid	7.5/30	50,000	13.00
O-4	Single plate to 1 grid	15,000	60,000	11.00
O-5	Plate to grid, D.C. in Pri.	15,000	60,000	11.00
O-6	Single plate to 2 grids	15,000	95,000	13.00
O-7	Plate to 2 grids, D.C. in Pri.	15,000	95,000	13.00
O-8	Single plate to line	15,000	50, 200/250, 500/600	14.00
O-9	Plate to line, D.C. in Pri.	15,000	50, 200/250, 500/600	14.00
O-10	Push pull plates to line	30,000 ohms plate to plate	50, 200/250, 500/600	14.00
O-11	Crystal mike to line	50,000	50, 200/250, 500/600	14.00
O-12	Mixing and matching	50, 200/250	50, 200/250, 500/600	13.00
O-13	Reactor, 300 Hys.—no D.C.; 50 Hys.—3 MA. D.C.,		6000 ohms	10.00
O-14	50:1 mike or line to grid	200	½ megohm	14.00
O-15	10:1 single plate to grid	15,000	1 megohm	14.00

150 VARICK STREET • NEW YORK 13, N. Y.
EXPORT DIVISION: 13 EAST 40th STREET, NEW YORK 16, N. Y. CABLES: "ARLAB"

electronics

NOVEMBER • 1953
A McGRAW-HILL PUBLICATION

SOLDERLESS CIRCUIT ASSEMBLY—Multiple-spindle wire-wrapping machine developed jointly by Bell Laboratories and Western Electric Co. makes 76 solderless wrapped connections in a-m radio set each time operator brings chassis down on spindles. Inset shows finished wrapped connection (see p 202) ..... COVER

FIGURES OF THE MONTH, includes Electronic Output Index, a business barometer for management 4
INDUSTRY REPORT, top-level news, trends and market interpretations 5
ELECTRONIC CONTROL OF A NUCLEAR REACTOR, by J. E. Binns 130
COLOR TELEVISION CONVERTER FOR CABLE NETWORKS, by J. G. Reddeck and H. C. Gronberg 132
FILM SYNCHRONIZER FOR AERIAL CAMERAS, by Herbert E. Meinema 135
POLYCATHODE COUNTER TUBE APPLICATIONS, by J. H. L. McAuslan and K. J. Brimley 138
ANTENNA-MATCHING NETWORK EFFICIENCY, by R. L. Tanner 142
BRIDGES MEASURE TRANSISTOR PARAMETERS, by L. J. Giacoletto 144
MULTIPLE FEEDBACK AUDIO AMPLIFIER, by Joseph M. Diamond 148
RADIATION MONITOR PROTECTS LAB WORKERS, by R. H. Delgado 150
UNIVERSAL MEDICAL TIMER AND PULSE STIMULATOR, by Robert G. Roush and Edmund T. Urbanski 154
CURRENT-SLOPE CONTROL FOR RESISTANCE WELDERS, by R. O. Johnsen 158
MICROPHONES MEASURE HIGH-INTENSITY SOUND, by John K. Hilliard 160
STEP-SWITCH CONVERTER DIGITIZES ANALOG DATA, by R. R. Bennett and H. Low 164
GROUNDED EMITTER AND COLLECTOR CIRCUITS, by Abraham Coblenz and Harry L. Owens 166
PCM CODING SYSTEM USES SPECIAL TUBES, by Arthur G. Fitzpatrick 173
WIDE-RANGE VACUUM GAGE, by Clifton B. Sibley and Jonathan R. Roehrig 176
ZERO-INTERCEPT PHASE COMPARISON METER, by Y. P. Yu 178
MOVABLE-ANODE TUBE GAGES SURFACE ROUGHNESS, by Joseph B. Bidwell 181
HIGH INPUT IMPEDANCE PREAMPLIFIER CIRCUIT, by E. W. Hogue 184
SWITCHING SYSTEM SPEEDS CAPACITANCE TESTS, by R. E. Graham 186
TRANSIENT ANALYSIS OF TRANSISTOR AMPLIFIERS, by W. F. Chow and J. J. Suran 189
MATCHING NONSTANDARD WAVEGUIDE SECTIONS, by A. Chlavin 192
MICROPHONE SENSITIVITY CONVERSION (Reference Sheet), by Leo Rosenman 194
MAGNETIC DRUM DESIGN (Reference Sheet), by D. G. O'Connor 196

CROSSTALK.....129 ELECTRONS AT WORK.....198 PRODUCTION TECHNIQUES.....244 NEW PRODUCTS.....248
PLANTS AND PEOPLE.....412 NEW BOOKS.....453 BACKTALK.....464 INDEX TO ADVERTISERS.....511

W. W. MacDONALD, *Editor;* VIN ZELUFF, *Managing Editor;* John Markus, A. A. McKenzie, James Fahnestock, *Associate Editors;* William P. O'Brien, John M. Carroll, William G. Arnold, David A. Findlay, *Assistant Editors;* Marilyn Wood, *Editorial Assistant;* Gladys T. Montgomery, *Washington Editor;* Harry Phillips, *Art Director;* Eleanor Luke, *Art Assistant*

KEITH HENNEY, *Editorial Director*

H. W. MATEER, *Publisher;* WALLACE B. BLOOD, *Manager;* R. S. Quint, *Buyers' Guide Manager;* Frank Ward, *Business Manager;* N. F. Cullinan, *Promotion & Research Assistant;* H. E. Hilty, *Classified Manager;* D. H. Miller, James Girdwood, *New York;* Wm. S. Hodgkinson, *New England;* Warren W. Shew, *Philadelphia;* Charles Wardner, James T. Hauptli, *Chicago;* J. L. Phillips, *Cleveland;* T. H. Carmody, R. C. Alcorn, *San Francisco;* Carl W. Dysinger, *Los Angeles;* Robert H. Sidur, *Atlanta*

November, 1953 ELECTRONICS Vol. 26, No. 11
Member ABC and ABP

Published monthly with an additional issue in June by McGraw-Hill Publishing Company, Inc., James H. McGraw (1860-1948), Founder. **Publication Office, 99-129 North Broadway, Albany 1, N. Y.**

Executive, Editorial and Advertising Offices: McGraw-Hill Building, 330 W. 42 St., New York 36, N. Y. Donald C. McGraw, President; Willard Chevalier, Executive Vice-President; Joseph A. Gerardi, Vice-President and Treasurer; John J. Cooke, Secretary; Paul Montgomery, Senior Vice-President, Publication Division; Ralph B. Smith, Vice-President and Editorial Director; Nelson Bond, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Director of Circulation.

Subscriptions: Address correspondence to Electronics—Subscription Service, 99-129 N. Broadway, Albany 1, N.Y., or 330 W. 42nd St., New York 36, N. Y. Allow one month for change of address. Subscriptions are solicited only from persons engaged in theory, research, design, production, maintenance and use of electronic and industrial control components, parts and end products. Position and company connection must be indicated on subscription orders.

Single copies 75¢ for United States and possessions, and Canada; $1.50 for Latin America; $2.00 for all other foreign countries. Buyers' Guide $2.00. Subscription rates—United States and possessions, $6.00 a year; $9.00 for two years. Canada, $10.00 a year; $16.00 for two years. Other western hemisphere countries, $15.00 a year; $25.00 for two years. All other countries $20.00 a year; $30.00 for two years. Entered as second class matter August 29, 1936, at the Post Office at Albany, N. Y., under act of Mar. 3, 1879. Printed in U.S.A. Copyright 1953 by McGraw-Hill Publishing Co., Inc.—All Rights Reserved. BRANCH OFFICES: 520 North Michigan Avenue, Chicago 11, Ill.; 68 Post Street, San Francisco 4; McGraw-Hill House, London, E.C. 4; Washington, D. C. 4; Philadelphia 3; Cleveland 15; Detroit 26; St. Louis 8; Boston 16; 1321 Rhodes-Haverty Bldg., Atlanta 3, Ga.; 1111 Wilshire Blvd., Los Angeles 17; 738-9 Oliver Building, Pittsburgh 22. ELECTRONICS is indexed regularly in The Engineering Index.

when power fluctuations affect processes . . . you NEED SORENSEN AC line regulators

here's a case where installing a SORENSEN AC REGULATOR saves $$$ in an RF gluing process

Timber Structures, Inc., of Portland, Oregon, are the largest producers of engineered timber structures in the country. RF is used for pre-gluing scarf joints of lumber to be laminated into very large arches, and also for gluing the firm's "Timberib" barn rafters on a mass production basis. The RF presses were developed by Timber Structures, Inc., engineers.

Voltage to the four RF generators varied greatly due to constantly changing loads throughout the plant. The serious fluctuations necessitated the repair of 5% of total output and scrapping of another 5% as total loss. Unsuccessful attempts were made to remedy the condition through the use of additional and separate service transformers.

The local Sorensen representative surveyed the situation and recommended installation of a 15KVA Sorensen Regulator. The result — complete elimination of product loss or damage through erratic voltage.

The installation was made nearly five years ago. Since then — complete satisfaction! The only service required by the Sorensen Regulator during this period has been the installation of one set of new tubes.

We know that a great many manufacturing difficulties are caused by line fluctuations, most of which could be eliminated quickly and economically by Sorensen AC Regulators. Find out more about this, at no obligation, from your Sorensen representative — write us for his address. Sorensen & Co., Inc., 375 Fairfield Avenue, Stamford, Conn.

SORENSEN

375 FAIRFIELD AVENUE, STAMFORD, CONN.



THE D-649 18" MUFAX CHART RECORDER

All the world's weather on an 18" Facsimile Receiver

The D-649 18" Mufax Chart Recorder offers the most convenient method yet devised of receiving facsimile weather maps transmitted by radio or landline. It can be used side by side with American equipment on existing systems; alternatively, a private network can be set up by using it in conjunction with the D-658 18" Mufax Chart Transmitter. Recording is on inexpensive Mufax paper supplied in 100-foot rolls, enabling the recorder to operate unattended for days at a time. The transmitted map, measuring 18" x 22", is received full size, and can be examined while recording is still taking place. Picture quality is better than that obtainable by any other direct recording system, even when using the double speed facility which is exclusive to Mufax equipment. The record, which is black on white, is instantly visible and requires no processing. No other system can offer these advantages—write now for full descriptive literature.

MUIRHEAD & CO. LIMITED · BECKENHAM · KENT · ENGLAND



FIGURES OF THE MONTH

RECEIVER PRODUCTION (Source: RETMA)	Year Ago Aug. '52	Previous Month Jul. '53	Latest Month Aug. '53
Television sets	397,769	316,289	603,760
Home sets	235,728	172,197	299,939
Clock Radios	108,753	87,620	169,301
Portable sets	105,006	78,434	145,460
Auto sets	94,315	336,208	376,937

RECEIVER SALES (Source: RETMA)	Aug. '52	Jul. '53	Aug. '53
Television sets, units	.....	340,406	430,101
Radio sets (except auto)	.....	366,666	491,431

RECEIVING TUBE SALES (Source: RETMA)	Aug. '52	Jul. '53	Aug. '53
Receiv. tubes, total units	30,141,536	26,462,069	38,600,494
Receiving tubes, new sets	19,583,879	15,393,307	25,837,055
Rec. tubes, replacement	7,463,893	9,480,208	10,460,032
Receiving tubes, gov't.	1,706,868	313,684	560,565
Receiving tubes, export	1,386,896	1,274,870	1,742,842
Picture tubes, to mfrs.	394,605	421,248	704,495

SEMICONDUCTOR SALES (Source: RETMA)	Aug. '52	July '53	Aug. '53
Germanium Diodes	.....	742,102-r	836,334

INDUSTRIAL TUBE SALES (Source: NEMA)	Year Ago 2nd '52	Quarterly Figures: Previous Quarter 1st '53	Latest Quarter 2nd '53
Vacuum (non-receiving)	$12,110,000	$11,340,000	$10,400,000
Gas or vapor	$3,150,000	$3,140,000	$3,300,000
Phototubes	$480,000	$930,000	$700,000
Magnetrons and velocity modulation tubes	$9,830,000	$10,070,000	$10,500,000
Gaps and T/R boxes	$2,140,000	$2,050,000	$1,700,000

TV AUDIENCE (Source: NBC Research Dept.)	Year Ago Sept. '52	Previous Month Aug. '53	Latest Month Sept. '53
Sets in Use—total	18,711,800	24,895,000	25,233,000

BROADCAST STATIONS (Source: FCC)	Sept. '52	Aug. '53	Sept. '53
TV Stations on Air	111	253	288
TV Stns CPs—not on air	51	270	246
TV Stns—Applications	855	521	415
AM Stations on Air	2,364	2,476	2,488
AM Stns CPs—not on air	119	117	113
AM Stns—Applications	276	177	183
FM Stations on Air	624	579	571
FM Stns CPs—not on air	18	18	21
FM Stns—Applications	10	7	5

COMMUNICATION AUTHORIZATIONS (Source: FCC)	Jul. '52	June '53	Jul. '53
Aeronautical	33,462	39,315	40,655
Marine	36,068	40,357	41,473
Police, fire, etc.	11,274	13,631	13,869
Industrial	13,968	17,378	17,951
Land Transportation	5,120	5,922	6,069
Amateur	113,863	111,289	110,862
Citizens Radio	1,697	3,829	3,877
Disaster	80	191	191
Experimental	489	414	463
Common carrier	985	1,214	1,222

EMPLOYMENT AND PAYROLLS (Source: Bur. Labor Statistics)	July '52	June '53	July '53
Prod. workers, comm. equip.	264,700	399,300-r	391,800
Av. wkly. earnings, comm.	$62.96	$66.83-r	$65.67
Av. wkly. earnings, radio	$60.25	$64.80-r	$63.67
Av. weekly hours, comm.	39.4	40.5 -r	39.8
Av. weekly hours, radio	39.2	40.0 -r	39.3

STOCK PRICE AVERAGES (Source: Standard and Poor's)	Sept. '52	Aug. '53	Sept. '53
Radio—TV & Electronics	304.3	280.0	265.5
Radio Broadcasters	288.3	274.8	263.1

p—provisional; r—revised

FIGURES OF THE YEAR

	1952 Total	TOTALS FOR FIRST EIGHT MONTHS 1952	1953	Percent Change
Television set production	6,096,279	2,914,925	4,754,285	+ 63.1
Radio set production	10,934,872	6,588,303	8,932,638	+ 36.2
Television set sales	6,144,990	2,569,384	3,546,407	+ 38.0
Radio set sales (except auto)	6,878,547	3,505,516	3,875,293	+ 10.6
Receiving tube sales	368,519,243	211,269,893	308,222,911	+ 45.8
Cathode-ray tube sales	6,120,292	2,479,539	5,276,426	+112.8

INDUSTRY REPORT

New York City Tests Conelrad

RECENT Civil Defense drill staged by New York City gave the first large-scale test of Conelrad during daylight hours. Between 9:30 and 9:45 a.m. the big city's radio and television listeners and lookers had an opportunity to discover how their habits will be changed in the event of enemy aircraft attack.

Television and f-m stations go off the air after a brief explanatory announcement. Radio carries on, using 640 and 1,240 kc. Individual stations lose their identity by reducing power and broadcasting program from a central source. While some stations go off the air completely, others take turns carrying the program.

► **Classified Information**—Official evaluation has not been published, and may not be, to show how well the technique denied navigational information to aircraft while furnishing citizens with vital information. Unofficial observers had comments to make upon the effectiveness of the scheme from the listeners' viewpoint.

One individual using a crystal receiver in nearby New Jersey reported that he could follow the program from the 1,240-kc chain, but lost a part of it when he was tuned to 640 kc. At the same location, the program was always good on a table-model receiver, although there was some fading and heterodyning.

Stations broadcasting seemed to stay on the air from 12 to 18 seconds and, while they broadcast in sequence, the sequence was not always the same.



SPHERICAL FACEPLATE shortcuts design problems, as . . .

CBS Ships Tricolor Tube Samples

Production of 15,000 monthly foreseen next year; possibly 21-inch rectangular types

SAMPLES of the Columbia Broadcasting System's spherical-faceplate tricolor tube for television will go out to tv set manufacturers this month.

Pilot plant production of the new tube will begin in February at Newburyport, Mass. Full-scale production of 15,000 tubes a month is scheduled for next fall, when much of CBS-Hytron's new 250,000 sq ft Kalamazoo, Mich. plant will be devoted to color-tube manufacture. Other tubemakers may be licensed when patents are granted.

Although the tube shown at last month's demonstration in Danvers, Mass. were 15-inch round ones, the spherical-faceplate design permits manufacture of larger-diameter units no longer than current monochrome models. The space-saving rectangular shape is also feasible.

► **How It Works**—The tube contains three electron guns, one for each color. The screen consists of 250,000 tiny phosphor dots of each color: red, green and blue. An aperture mask perforated with 250,000 holes 0.009-inch in diameter makes the three electron beams converge in such a manner that each beam hits only its corresponding phosphor dots.

For proper color reproduction, the phosphor-dot pattern and the aperture mask must be aligned with utmost precision. The spherical-shaped faceplate and aperture mask shown in the sketch are aligned by a unique photoengraving process in which the mask serves as the negative. The faceplate interior is coated with each of the color phosphors in turn. After each coat, a photosensitive emulsion is applied and exposed by a pencil of light following the path of one of the electron beams. The developed emulsion binds the dots in their proper places.

Three aperture mask v blocks clip to glass alignment hemispheres on the faceplate. The mask can expand and contract freely without undue strain. Thus heating of the mask by beam current or during degassing does not cause it to warp or become

Color TV Timetable

FORMAL demonstration by NTSC on Oct. 15 gave FCC something solid on which to base decision . . . conducted in New York, color telecasts by NBC, CBS and DuMont were picked up on color sets provided by Admiral, CBS-Columbia, Crosley, Emerson, General Electric, Hallicrafters, Hazeltine, Motorola, Philco, RCA, Sylvania, Westinghouse and Zenith . . . several mono-chrome receivers monitored . . . the program opened with studio program received directly from the NBC transmitter in N.Y.C. then transmitted by coaxial cable and then by microwave relay to Washington and back to New York . . . next was a pick-up of outdoor scenes from a local museum garden broadcast by CBS . . . program concluded with a transmission from the DuMont transmitter, showing NTSC color slides.

•••

Counterproposals to NTSC color tv by three dissidents dismissed under procedural rule adopted by Commission in 1950 . . . FCC characterized ideas as "merely paper systems" . . .

•••

Jockeying for favorable positions is spurring engineers to new heights of activity . . . NBC put on closed-circuit show for Chicago from New York Colonial studio . . . announced total color investment of $25 million to date and proposal to spend another $15 million to launch commercial color-casting. . .

•••

Chromacoder camera by CBS uses single image orthicon and converts sequenial signals to NTSC-type for compatible broadcasts . . . President Frank Stanton claims installation savings of $3.8 million for 100-station network and operating-cost savings of $6 million a year.

materially misaligned.

The spherical faceplate allows a wide electron-beam deflection angle that permits development of large-screen tubes and improves beam convergence at the edges of the picture; electron beams and mask holes are essentially at right angles even at the edges of the tube.

▶**Cost**—The "colortron" lends itself to mass production. The tubes are light, relatively easy to assemble and few rejects are expected. CBS predicts that by 1955 or 1956 mass production techniques will have reduced the price to roughly 30 percent over comparable monochrome models.

▶**Camera**—Following its showing at the Danvers plant, the Colortron was also featured in a New York demonstration of several new CBS color-television-system components. The camera used in this demonstration employed just one orthicon pickup tube. The unit was called as a refinement of the field-sequential camera, adapted for transmitting NTSC-standard pictures.

Estimated cost for studio equipment based upon the new camera range is from $9,690 for a network station to $781 for a medium-market station. A single operator reportedly can perform all master control functions necessary to operate the equipment satisfactorily.

D. C. McGraw Elected McGraw-Hill President

DONALD C. MCGRAW was elected President of the McGraw-Hill Publishing Company, Inc., publishers of ELECTRONICS, at a meeting of the Board of Directors at McGraw-Hill Building, 330 West 42nd Street. He succeeds his brother, the late Curtis W. McGraw.



Donald C. McGraw

Mr. McGraw, youngest son of the late James H. McGraw, Sr., founder, has been associated with the company since 1919. He has been a director since 1935, and vice-president since 1945. During World War II, he was a consultant to the Publishing and Printing Division of the War Production Board.

A native of Madison, N. J., Mr. McGraw now is a resident of Summit, N. J. He is a graduate of Lawrenceville School and attended Princeton University. During World War I, he served with the U. S. Navy.

Mr. McGraw joined McGraw-Hill in 1919 as a member of the advertising staff of Chemical and Metallurgical Engineering, which has since become Chemical Engineering. Two years later, he transferred to the pressroom and composing room. McGraw-Hill then operated its own printing plant in its building at 36th Street and Tenth Avenue. In 1924, he

(Continued on page 8)

DON'T MISS THIS...

Handy New Guide to TR and ATR Tubes

Be sure to get one of these time-saving reference guides to Sylvania's complete line of TR and ATR Tubes.

At a glance it tells you about power rating and frequency, and shows which tubes are band-pass and which are tunable. Color code identifies power rating quickly and accurately. Folds to compact, wallet size.

If your Sylvania Representative can't supply you, mail the coupon for a copy NOW!

SYLVANIA

In Canada: Sylvania Electric (Canada) Ltd.
University Tower Bldg., St. Catherine St., Montreal, P. Q.

LIGHTING • RADIO • ELECTRONICS • TELEVISION

Sylvania Electric Products Inc.
Dept. 3E-1011, 1740 Broadway,
New York 19, N. Y.

Please send me a copy of the new handy guide to TR and ATR Tubes.

Name_____

Street_____

City_____ Zone_____ State_____

Want more information? Use post card on last page.

assumed supervision of the operation of the building and of the printshop.

Since 1933, when he was made Secretary of the company and put in charge of production and manufacturing, he has been responsible for the handling of all contracts for printing and binding, engraving, and paper supply for the entire McGraw-Hill operation.

Mr. McGraw in 1945 was named Vice-President for Manufacturing and General Services, the position he has held until now. In 1950, he became a director of the McGraw-Hill Book Company, a McGraw-Hill subsidiary, and of the Newton Falls Paper Mill in which McGraw-Hill has a half-interest.

Guided Missile Production Lags

Army misses target date as critics query infallibility; steering-group head quits

VELVET CURTAIN of security for guided missiles was broken twice last month with apparently contradictory items. President Eisenhower accepted the resignation of Chrysler Board Chairman K. T. Keller, since 1950 director of the Defense Department's Office of Guided Missiles. Keller, in leaving, recommended that the agency he headed be abolished. The reason given was that guided missiles had now reached such an advanced stage of development that efforts of the steering group were no longer needed. No successor has been named to the post.

▶**Production**—On the heels of this development came an announcement by Army spokesmen that no unit armed with Nike, the Army's supersonic antiaircraft rocket, is ready to meet a surprise Russian air attack.

Promised for this summer, the missile characterized by Army Secretary Robert T. Stevens as the best antiaircraft weapon now available, is now slated to guard important industrial centers beginning this fall. In tests against remotely controlled B-17 bombers Nike rockets scored at least 65 kills out of 100.

▶**Planning**—Critics of the guided missile program have recently warned against lumping all our air defense eggs in one basket. Pointing to successful employment of electronic countermeasures against enemy radar during World War II, particularly during the Normandy invasion, they plug for piloted interceptors whose human pilot can overrule jammed or deceived electronic guidance equipment.

To keep up with today's high-flying supersonic bombers, piloted interceptors, too, need electronic equipment in the form of airborne radar and electronically controlled gunsights.

Thus the electronics industry will undoubtedly carry much of the responsibility for air defense.



RUBBER DOME protects intricate antennas from weather as . . .

Arctic Radar Fence Is Readied

Results of Project Lincoln are almost set for performance tests by the military

EXPERIMENTAL units of a line of radar stations 1,200 miles from the north pole, which will give at least six hours advance warning of an airborne threat from that direction, are nearing completion in the vicinity of Barter Island, Alaska. The decision to extend the line from Alaska to Greenland will hinge on the performance of this initial installation.

Known as the Distant Early Warning Line, the apparatus, some of it entirely new in concept, is the result of study and development work by Lincoln Laboratory of MIT working closely with Bell Telephone Laboratories of American Telephone & Telegraph.

▶**Equipment**—Unlike World War II radar, which required constant observation, the new equipment automatically sounds an alarm whenever aircraft approach, reducing drastically the personnel required for service in the Arctic. Both the radar and radio transmitters which link it with the command centers are designed to overcome magnetic storms which knock out conventional electronic

(Continued on page 10)

DEPENDABILITY

is why Sprague Type DFP Twist-Loks* are the *preferred*

ELECTROLYTIC CAPACITORS



Leading television set makers rely on Sprague as their major source for electrolytic capacitors.

Stability under maximum operating conditions plus outstandingly l-o-n-g service life are the engineering reasons for this preference.

From the business standpoint, it makes good sense to deal with a supplier whose quality of product is uniformly excellent and who has the largest production facilities in the industry.

And now a new plant is being completed to permit Sprague to accept an even larger portion of your requirements.

SPRAGUE ELECTRIC COMPANY
35 Marshall St., North Adams, Massachusetts

*Trademark

Sprague, on request, will provide you with complete application engineering service for optimum results in the design of equipment using electrolytic capacitors.

SPRAGUE

WORLD'S LARGEST CAPACITOR MANUFACTURER

Want more information? Use post card on last page.

equipment in the Arctic during substantial parts of the year.

▶**Project**—The system was started last December when top Bell officials were requested by the Defense Department to construct the initial section of the DEW line and have it functioning within a year. Every piece of the electronic equipment had to be specially made or converted and transported to the point of construction, 2,800 sea miles away from the loading point, all within two summer months beginning in July. Early during the same period, a pilot installation was assembled in the U. S. to test the equipment, train personnel and to learn the nature of the functional problems and solve them in advance of actual installation in the Arctic.

Electronic Firms Eye U.S. Spending

Pending shift in Pentagon strategy could spell more business for the industry

JOINT CHIEFS OF STAFF review of the entire military program which went to Defense Secretary Wilson in mid-October called for a beefing up of continental U.S. defenses. But the conclusions came too late to be inserted in the fiscal 1955 military appropriations requests that had already been prepared.

As a result, the military may push through a supplemental appriation which will, for the first time, put an open price tag on the cost of defending the country from direct attack. The report, however, must be approved by the National Security Council if it calls for any major change in strategy.

▶**Spending Increase**—Prior to the report, Wilson had estimated that defense spending beginning next July might run $40 billion, about $2 billion less than estimates for this year. But if the new JCS plan is approved, total military spending for the first full year of such a program, including maintenance of forces already active, may run between $43 and $45 billion with the bulk of the new money going to the electronics industry.

Depending on how fast the build up progressed and how much was required initially, spending might hit close to $50 billion in fiscal 1956. As a result, electronic manufacturers may have at least four more years of top defense business ahead.



▶**Breakdown**—Indication of how the military spends its appropriations is shown in the chart. Air Force, with an estimated $17.5 billion in its till, is expected to be the top spender in the present fiscal year which began last July, followed by Army and Navy, in that order. Secretary Wilson states that the U. S. is figuring on spending about a half billion dollars currently for the radar early warning network. That figure may increase as plans are completed and the U. S. and Canadian fences are merged.

More guided missile business for electronic manufacturers may also be available this fiscal year. The military may convert National Guard units to guided missile outfits equipped with the Army's Nike for better domestic defense. However, the plan is still tentative and may not become a part of home defense strategy.

Medical Sales Boost Betatron Business

Total for one firm will reach $10 million with installation of units now on order

ACCEPTANCE of the betatron in medical therapy to supplement high-voltage x-ray equipment has given another impetus to the fast-expanding medical electronic business. By early 1954, Allis-Chalmers alone will have installed the huge 24-million-electron-volt machines in the following seven hospitals:

University of Illinois Medical Center, Chicago
M. D. Anderson Hospital, Houston, Texas
Memorial Center for Cancer and Allied Diseases, New York City
Mallinckrodt Institute of Radiology, St. Louis, Mo.
Columbia Presbyterian Medical Center, New York City
Saskatchewan Cancer Clinic, Saskatoon, Canada
French Ministry of Public Health, Paris

Similar installations are in various stages of planning and construction at the following medical laboratories:

University of California Medical Center, Los Angeles
The Lincoln Laboratory, Bedford Air Base, Massachusetts
Royal Victoria Hospital, Montreal

▶**New Doughnut**—Delivery of the first permanently-sealed electron-beam betatron tube to New York City's Memorial Center installation (p 146, Oct. 1953 ELECTRONICS) makes available a new method of treating cancerous tumors in critical areas such as the brain. This new doughnut-shaped ceramic tube has a thin beryllium window that passes electrons yet preserves the required vacuum.

▶**Total Sales**—There are now 18 other betatrons in operation in industrial production and research locations, with two more being installed. Chief industrial use has been for inspection of ammunition having casings too thick for ready penetration by conventional industrial x-ray equipment.

Total cost of the 10 medical and 20 industrial betatrons now in use

(Continued on page 14)

1953



SPECIAL "PLUG-IN" STYLE COMPONENTS FOR PRINTED OR ETCHED CIRCUIT CHASSIS

135,000,000 (estimated) radio and TV sets in use.

1951 WORLD'S SMALLEST VARIABLE RESISTOR

114,000,000 radio and TV sets in use.

1947 1st TV HIGH VOLTAGE CERAMIC CAPACITORS

66,000,000 radio and TV sets in use.

1943 1st PRINTED ELECTRONIC CIRCUIT

58,000,000 radio sets in use.

1942 1st OFFERED FINE CERAMICS TO THE INDUSTRY

59,000,000 radio sets in use.

1938 1st 24-CONTACT PER SINGLE-SECTION SWITCH

41,000,000 radio sets in use.

1929 1st COMBINATION VARIABLE RESISTOR AND SWITCH

10,500,000 radio sets in use.

1922 1st COMPOSITION VARIABLE RESISTOR

400,000 radio sets in use.

Again

CENTRALAB is first

in developing NEW components for NEW advancements in electronic design

For new economies now possible with etched chassis . . . . .

SEE NEXT TWO PAGES

AM-FM-TV manufacturers...for your new etched or printed

New Centralab

Centralab is the only source for all three new components

1. *Faster assembly*

Look at the photo at right and you'll see what we mean! For many years Centralab has been associated with saving assembly time and money for manufacturers as well as service technicians. These special, new "Plug-in" Components are *still another example* of how Centralab is moving ahead with more firsts — so you can gain maximum benefits from new electronic developments. To gain *greatest advantages,* make sure you specify Centralab — it's the industry's *only* source of *all three* components. That means you can save assembly time three profitable ways!

2. *Eliminates costly conventional wiring and soldering*

Note that all components are designed with short leads for fast automatic or dip soldering. All solder tabs meet RETMA standards in length, thickness and mounting characteristics. You merely follow two simple steps: (1) plug-in, and (2) solder. That's all there's to it! By saving extra work, new Centralab "Plug-ins" bring extra profits wherever applied. It will pay you to examine your designs for "Plug-in" applications.



Sketch of etched plate underside shows how the one shot of solder-gun or dip soldering may be used to speed production.



AUDIO DETECTOR COUPLATE®

7 leads — eliminate 8 parts and 9 extra connections. Dimensions: $1\frac{9}{16}$" x $\frac{7}{8}$" x $1\frac{1}{64}$" thick. Terminals: thickness — .01", width — .047", length—$\frac{7}{32}$". *Technical data and samples available.*

PEC "Plug-ins" are available in *any* standard Printed Electronic Circuit — also Disc, Tubular and Plate Capacitors offered by Centralab.



DISC AND TUBULAR CAPACITORS

For by-pass, coupling, general use and T.C. requirements. Leads for plug-in discs are $\frac{7}{32}$" long from edge of disc . . . are .012" thick, .047" wide, $\frac{3}{32}$" ctr to ctr on large discs. They are $\frac{1}{8}$" ctr to ctr on $\frac{1}{4}$" to $\frac{3}{16}$" discs. *Technical data and samples available.*

TUBULARS have special length, special spaced wire leads. *Technical data and samples available.*

PLATE CAPACITORS

Ceramic flat plate HI-KAP Capacitors are available in standard units. *Technical data and samples available.*

chassis...Here are 2 NEW WAYS to NEW PROFITS with

Plug-in Components

(1) Capacitors (disc, tubular or plate) (2) PEC* plates (3) Controls

NEW CONTROLS

These special controls plug *directly* into any etched, printed or plated chassis. Reverse-bend tabs are 1.16" wide with a standard length of ⅛" from mounting surface on .679" radius. Plug-in controls are available in any standard taper and resistance value. †



This feature is *another* Centralab exclusive!

This Centralab designed SPST or DPST switch eliminates all conventional wiring in printed or etched paths. Switch solder lugs are so made that they, too, can be plugged directly into the chassis. One lug is automatically grounded to one control terminal, taking the place of the jumper wire which would otherwise be required. Gives you an *extra plus* in eliminating two extra steps!

†Plug-in components shown separately are actual size.

*Trademark — Printed Electronic Circuits

Adds still another advantage to etched or printed circuit flexibility

It's only natural that Centralab, pioneer of so many electronic "firsts," should bring users even greater potential profits, by broadening the money-saving advantages of printed or etched circuits.

You'll want *all the facts* on Centralab "plug-in" components so you can properly evaluate their many potential savings for you. Technical information and *manufacturer's samples* are available on request. Use handy coupon, or write for details on components of your choice.

Centralab

A Division of Globe-Union Inc.

In Canada, 804 Mt. Pleasant Rd., Toronto 12, Ont.

CENTRALAB, A Division of Globe-Union Inc.
914-K E. Keefe Ave., Milwaukee 1, Wisconsin

Please send technical data on NEW Centralab Plug-in style components for:

☐ CONTROLS ☐ TUBULAR CAPACITORS
☐ PRINTED ELECTRONIC CIRCUIT PLATES
☐ DISC CAPACITORS ☐ PLATE CAPACITORS

Name.....

Address.....

City..... State.....

or being installed will come to approximately $10,000,000. The machines sell for around $100,000 apiece, plus installation costs, associated electronic test equipment, construction of the required heavy-wall concrete room and, for industrial uses, cost of the heavy overhead crane used for positioning the machine with respect to the parts being inspected.

TV Manufacturers Get Color Set Data

Technical details of its basic color receiver are given to its licensees by RCA

ENGINEERS representing virtually all tv set manufacturers were given full details of design and performance of RCA's basic color tv receiver at a color tv symposium held by the company in New York City. The receiver described to the 250 tv industry representatives is the latest field-tested design from which will be evolved the production design for color sets.

Data on special components, tubes, circuitry and test equipment were provided along with latest technical information on the company's tricolor tube. The engineers were also briefed on color broadcast station equipment progress and the color plans of other divisions of the company.

▶**Production**—Within six to nine months, or sooner, after FCC approves compatible standards, RCA plans to have its first color receiver production line in operation, according to E. C. Anderson, vice-president of the company, who presided at the meeting. He stated that the company will supply domestic receiver licensees with complete manufacturing information on its first color set when it is placed in commercial production. This includes complete manufacturing drawings, bill of material, sources of supply and inspection of the production setup. Licensees would be invited to the plant before the commercial release of RCA color sets.

▶**Kit**—During the meeting, the company offered to supply tv set manufacturers with a limited quantity of developmental kits, containing specially designed color set components, to enable licensees to initiate experimental design and production programs for color tv sets. The kit includes a tricolor picture tube, receiver tubes, transformers and coils.



VACUUM-TUBE reliability demonstrates well-defined pattern, as . . .

Studies Probe Equipment Failures

Railroaders indict tubes as leading failure cause; Navy finds old tubes best

RESULTS of a 23-month study conducted by Missouri-Pacific radio engineers reveal that 63 percent of all mobile equipment faults arise from vacuum-tube failures. Four tube types, the 6AK5, 6J6, 2E26 and 6BH6 accounted for 78 percent of all tube failures. These types represented only 55 percent of the tubes in use. The figures were presented to the 30th annual session of the American Association of Railroads communications section.

The study involved 53 base and 936 mobile units incorporating 29,000 vacuum tubes. The railroad's activities extend over 9,600 track miles in 11 midwestern states.

▶**Tube Life**—On the basis of the study, average tube lives were extrapolated for the types studied. The results are given in the bar graph. Shortest predicted life was for the 6J6—20.2 months; while theoretically the type 1635 should last 28 years. Auto-battery type vibrators were found to have an average life of 21.5 months on the basis of 840 studied. Dynamotors, on the other hand, seemed destined to last indefinitely.

A low failure rate was noted for 7C5 and 7V7 loctal types while the 12AX7 had a life span three times as long as the similar 6J6. No pretested or selected tubes were employed in the equipment studied.

▶**Navy Test**—According to the U. S. Navy, one-third of the tubes replaced by maintenance technicians could be left in their sockets without malfunctioning of the equipment. This result, shown in the pie

(Continued on page 16)

SHOCK – VIBRATION – NOISE

ISOLATION NOTES



UNDISTORTED FLIGHT DATA are recorded by this Davies Laboratories aircraft data recorder. Tubes, relays, and recorder mechanism are protected against vibration by air-damped BARRYMOUNTS.



70% SIZE REDUCTION and 50% weight reduction, with no loss in performance, is achieved in this Minneapolis-Honeywell aircraft-fuel-gage power unit. Miniaturized air-damped BARRYMOUNTS helped make this saving possible, in protecting the reliability of the unit from vibrations and shock.



SENSITIVE ADJUSTMENTS ARE HELD when instrument and control panels are mounted on BARRYMOUNTS. Vibration from nearby heavy machinery cannot shake equipment out of calibration. Result: insured reliability of equipment and service.

NO SHIPPING DAMAGE, plus simplified packing, is Philco's experience with BARRYMOUNTS built into the packaging of microwave equipment. Pre-assembled equipments, with tubes and crystals in place, are shipped all over the world without damage, thanks to this modern packaging method. Write us for details.

The wide range of Barry products and the experience of Barry engineers can help you solve shock, vibration, and noise problems in any area of military or industrial activity. Call our nearby sales representative or write directly to us.

THE **BARRY** CORP.

707 PLEASANT ST., WATERTOWN 72, MASSACHUSETTS

SALES REPRESENTATIVES IN

Atlanta Baltimore Chicago Cleveland Dallas Dayton Detroit Los Angeles Minneapolis New York Philadelphia Phoenix Rochester St. Louis San Francisco Seattle Toronto Washington

chart, is based on a two-year study of tubes thrown out by maintenance men at 10 large military installations. Although a few of the good tubes had intermittent defects, the majority were either sound or had merely a slightly low transconductance.

According to the Navy, many of the tubes had just reached a condition of equilibrium and were at their peak of reliability when replaced. The other-defects classification shown on the chart refers to tubes used in special service that were changed for operational reasons.



Tubes discarded by military technicians

▶**Design Changes**—Pointing out that tube testing equipment is not adequate to determine whether a tube is functioning well in a particular equipment, the Navy announced that a small cathode-ray tube has been developed to be installed in equipment for checking critical waveforms.

Another design change recommended was soldering tubes permanently in plug-in circuits to ease maintenance chores and avoid tube-socket troubles.

Flexible-lead tubes were advocated to permit interchange of tubes with like electrical characteristics but different bases or pin connections. Other design changes listed included ceramic tubes and tubes having a flexible shield clamped to the bulb to ease mechanical shocks and provide cooling fins for heat dissipation.



MAGNETIC DRUM tallies mail-order data fed from keyboards, as . . .

Computers Aid Inventory Control

Several calculator firms aim at business market but output is still low

BUYERS for John Plain and Co., Chicago mail-order house are now supplied with up-to-the-minute inventory information that formerly took two weeks to process.

Heart of the system is a magnetic-drum memory device that is fed with order information from as many as ten adding-machine type keyboards. The machine can tally 13,000 items in each of three categories. Print-out is on adding-machine tape. Remington Rand's engineering research associates division believes the machine will prove useful for keeping perpetual inventory in a variety of business and industrial establishments.

▶**Multipurpose Unit**—Several dozen orders are reportedly on hand for IBM's model 650 medium-sized drum calculator currently in production at the company's Endicott, N. Y. plant. Users of the machine will include railroads, steel mills, public utilities, aircraft plants, universities, mail-order houses, a salt factory and a camera manufacturer.

▶**Other Firms**—The electronic computer division of the Underwood Corp. lists four machines in use and four on order. The firm specializes in low-cost ($80,000-250,000), general purpose calculators for business use. Customers include an electrical manufacturer, airplane maker and an oil company. The oil company will use its machine in connection with product distribution.

The Monrobot Corp. is concentrating exclusively on defense production at the Monroe Calculating Machine Company's new 100,000 sq ft plant in Morris Plains, N. J. Four machines have been completed and three are on order.

ARRL Warns UHF-TV Receiver Makers

DUAL-CONVERSION uhf-tv adapters, while providing uhf reception with uhf receivers at low cost, may be useless in certain areas in the vicinity of properly-operating amateur stations, according to an announcement by the American Radio Relay League. The ARRL report points out the possibility of trouble from beats between uhf-tv signals and amateur signals in the two-meter band.

Most vulnerable are receivers with 21.25-mc i-f's in areas serviced by tv stations on channels 14 to 18.

(Continued on page 18)

COMPACT, ACCURATE, DIRECT-READING EQUIPMENT

for VHF *and* UHF Balanced-Antenna Measurements

The equipment illustrated is an integrated and highly accurate system for the measurement of impedance and VSWR of either balanced or unbalanced circuits. This combination of G-R Admittance Meter, Constant-Impedance Adjustable Line, Balun and Unit Oscillators has found wide application. This system is now widely used in the design, production testing and installation of both receiving and transmitting antennas.

Measurements are rapid. The Admittance Meter's scales are direct reading and independent of both frequency and calibration of the detector. By properly setting the Type 874-LK Constant-Impedance Adjustable Line, the Admittance Meter can be made to read directly the balanced *impedance* of the device under measurement.

The adaptability of G-R's uhf measuring equipment is now further increased by a complete line of unit oscillators covering the whole VHF and UHF range. The scope of measurements is broadened by – new adapters from the G-R Type 874 connector to the Type N, C, BNC and UHF connectors – a component mount for minimizing "lead" and stray reactances when measuring impedance of components – a Mixer Rectifier – and an inexpensive Crystal-Diode Modulator. These and many other instruments and coaxial components are described in the G-R UHF Measurements Bulletin. Write for your copy today.



Characteristics of typical UHF television antenna. Admittance Meter readings (taken with setup shown) are plotted directly on a normalized Smith Chart. Impedance pattern and VSWR are indicated over the complete range.



G-R u-h-f instruments measuring impedance of broadband, high-gain UHF television antenna. Stacked BO-TY UHF Antenna (Two Model 114-065's) by courtesy of American Phenolic Corporation.

Electronics · Vol. 17, No. 1, pages 150-152, 316-320, Jan. 1944
Copyright 1943 by Kay Electric Co., Pine Brook, N. J.

Type 1602-B Admittance Meter – $285 . . . A versatile instrument for the rapid and accurate measurement of impedance, admittance or VSWR over a 20 to 1500 Mc range – direct reading between 41 and 1000 Mc. It can be used to match a load to a line, to compare directly the impedance of one circuit or component to that of another as well as for direct impedance measurements. There is no sliding balance – conductance (or reaistance) and susceptance (or reactance) adjustments are independent. Accuracy of both conductance and susceptance readings up to 1000 Mc is ± (3% + 0.2 millimho) over the 0 to 20 millimho range – from 20 to ∞ millimho, accuracy is ± (3 $\sqrt{M}$ % + 0.2 millimho) (M is scale multiplying factor). The Admittance Meter is supplied with an Adjustable Stub, Variable Air Capacitor, 50-ohm Termination, two Patch cords, a Panel Connector and a wooden storage case.

Type 874-UB Balun – $75 . . . A coaxial transformer which uses an artificial half-wave line for converting from balanced to unbalanced impedance. Range is 50 to 1000 Mc; the instrument is tuneable for maximum accuracy. The two adjustable stubs and two air-line lengths required to tune the Balun are available at additional cost.

Type 874-LK Constant-Impedance Adjustable Line – $36 . . . A 50-ohm line stretcher whose impedance remains constant over the adjustable 22 cm range. Electrical characteristics are excellent over the VHF and UHF bands; VSWR is less than 1.1 to 2000 Mc. This line stretcher is useful for eliminating line-length corrections, for converting the Admittance Meter to a direct reading impedance measuring instrument, and for general purpose use.

GENERAL RADIO Company
275 Massachusetts Avenue, Cambridge 39, Massachusetts, U. S. A.
90 West St. NEW YORK 6 · 920 S. Michigan Ave. CHICAGO 5 · 1000 N. Seward St. LOS ANGELES 38

Admittance Meters ☆ Coaxial Elements ☆ Decade Capacitors
Decade Inductors ☆ Decade Resistors ☆ Distortion Meters
Frequency Meters ☆ Frequency Standards ☆ Geiger Counters
Impedance Bridges ☆ Modulation Meters ☆ Oscillators
Variacs ☆ Light Meters ☆ Megohmmeters ☆ Motor Controls
Noise Meters ☆ Null Detectors ☆ Precision Capacitors
Pulse Generators ☆ Signal Generators ☆ Vibration Meters ☆ Stroboscopes ☆ Wave Filters
U-H-F Measuring Equipment ☆ V-T Voltmeters ☆ Wave Analyzers ☆ Polariscopes

41 to 48 and 69 to 77. Receivers having 41.25-mc i-f's may be incapable of receiving channels 20 to 25, 51 to 58 and 82 and 83 in the presence of strong two-meter signals.

▶**Goal**—The ARRL hopes that manufacturers of uhf converters and receivers with dual-conversion strips will take design steps to prevent interference of the type mentioned and to provide for service measures where such interference does occur. The league's aim is to prevent the country's 110,000-member amateur fraternity from having to "go through another difficult period, again not of its own making, carrying the burden of public misunderstanding and abuse which arises solely because of the inadequacy of television receiving apparatus."

Facsimile Speeds RR Ticket Sales

Customer at branch office receives ticket by facsimile from central sales bureau

TICKET sales at the Pennsylvania Railroad's Pittsburgh passenger station are greatly speeded up by a facsimile network that handles Pullman space reservations.

Customers' orders are received at the central ticket bureau from branch stations by facsimile and compared with a master file of preprinted tickets indicating available space on all trains out of Pittsburgh. The passenger's actual space coupon is transmitted to him by facsimile. Space information is displayed in the central sales office continuously on a 2 × 3-ft translucent screen in 1½-inch high letters.

Many firms with several men traveling Pullman daily are connected directly with the ticket-sales network by private facsimile wire. Heart of the system is Western Unions Deskfax equipment.

▶**Other Uses**—Several novel uses for facsimile have been in the news lately. The Federal Reserve Bank of New York transfers $1 billion daily between member banks over its private facsimile system. A bank in White Plains, N. Y. recently caught a check forger by using fax to compare check signatures with the depositer's record card.

A traffic judge in Baltimore uses fax to check an offender's violation record on file with the state motor vehicle bureau before pronouncing

Pullman ticket orders received by facsimile are compared with preprinted space coupons on file at central ticket bureau. Passenger receives space coupon by return fax. Translucent screen in background shows available Pullman space

sentence and American Express has a fax network to circulate numbers of stolen traveler's checks. In all, 10,000 units are installed in 50 different cities. Another 7,500 units will be installed during 1954.

Currently in the works at Western Union is a 300 word-per-minute letter facsimile unit and a special coupon transmitter for error-free transmission of waybills, wheel reports and other vital railroad operating data.

▶**Canadian Weather**—A newly installed facsimile system links stations of the Royal Canadian Air Force for transmission of weather maps throughout the Dominion and and its territories.

Television Factories Shift Work Load

SEASONAL business conditions are continuing to shape tv receiver production trends but some progress has been made in leveling output, as is shown in the chart.

Summer months are still the production low point for the industry, with the month of July representing the lowest point for most years. But there has been some shift in the heavy output load of the last quarter to earlier months of the year. In 1950, 55 percent of total production was completed in the first 8 months of the year and in 1951, for the same period, 67 percent was produced. Last year the lifting of the freeze altered the trend but so far this year, if production estimates of 6.6 million sets hold true, over 72 percent of 1953 production was completed by the end of last August.

▶**Changes**—The gradual shift of heavy production away from the last quarter of the year is seen by some manufacturers as being due to efforts of the industry to introduce new tv models in earlier summer months. The fact that some manufacturers are following the one-line-a-year policy is also having an effect.



Despite the trend, however, few

(Continued on page 20)

for you

- ***100% Microscopic Inspection***
- ***Lowest Vibrational Noise Output***
- ***Higher Plate Voltage Ratings***
- ***Higher Bulb Temperature Ratings . . . 265°C.***
- ***More Uniform Low Heater Voltage Performance***
- ***Higher Heater Cycle Life Test Voltage***

Each tube meets the latest military requirements for RELIABILITY — based on field and production tests for Shock, Vibration, 5000 Hour Life, Centrifugal Acceleration, Heater Cycle Life, High Temperature Life, Lead Fatigue.

All these Raytheon Reliable Subminiature Tubes must pass microscopic inspection

TYPE	DESCRIPTION	MAX. RATINGS			TYPICAL CHARACTERISTICS								
		Vibration Output mVac	Bulb Temp. °C	Plate Volts	Heater Volts	Heater Ma.	Plate Volts	Plate Ma.	Grid Volts or R_k	Screen Volts	Screen Ma.	Amp. Factor	Mut. Cond.
CK5702WA	RF Amplifier Pentode	**50**	**265**	**200**	6.3	200	120	7.5	200 ohms	120	2.6	—	5000
CK5703WA	High Frequency Triode	**10**	**265**	**275**	6.3	200	120	9.4	220 ohms	—	—	25.5	5000
CK5744WA	High Mu Triode	25	**265**	**275**	6.3	200	250	4.2	500 ohms	—	—	70	4000
CK5783WA	Voltage Reference	50	**175**	—	Operating voltage approximately 86 volts between 1.5 and 3.5 ma.								
CK5784WA	RF Mixer Pentode	100	**265**	**200**	6.3	200	120	5.2	-2	120	3.5	—	3200
CK5787WA	Voltage Regulator	—	220	—	Operating voltage approximately 100 volts between 1 and 25 ma.								
CK5829WA	Dual Diode	—	220	360*	6.3	150			Max. I_o = 5.5 ma. per plate				
CK6021	Medium Mu Dual Triode	50	250	165	6.3	300	100	6.5	150 ohms	—	—	35	5400
CK6111	Medium Mu Dual Triode	50	250	165	6.3	300	100	8.5	220 ohms	—	—	20	5000
CK6112	High Mu Dual Triode	25	250	165	6.3	300	100	0.8	1500 ohms	—	—	70	1800
CK6152	Low Mu Triode	**25**	**265**	**250**	6.3	200	100	10.0	270 ohms	—	—	17.5	5100
CK6247	Low Microphonic Triode	**1.0**	**250**	**275**	6.3	200	250	4.2	500 ohms	—	—	60	2650

*Peak inverse voltage

Note: All dual section tube ratings (except heater) are for each section.

RAYTHEON

RAYTHEON MANUFACTURING COMPANY

RAYTHEON MAKES ALL THESE

manufacturers have any hope that the summer dip in production will ever be entirely eliminated. They point out that because summer months are vacation months for both consumers and tv production workers, mid-year periods will continue to be low points in both tv production and sales.

Financial Roundup

REPORTS to shareholders by companies in the electronics field continue to show increases in profits over 1952. The following firms issued profit statements for the first six months of 1953:

Company	1953 Net Profit	1952
Bendix Av. (9m)	12,618,552	10,338,784
Bulova Watch (3m)	1,769,391	1,337,279
El. Engineering (6m)	14,517	17,156
Emerson Radio (39w)	2,333,227	1,005,359
Garrett Corp. (12m)	3,084,984	2,699,900
Indiana Steel (6m)	209,601	145,164
I-T-E Circ. Breaker (6m)	1,287,255	1,332,418
Magnavox (12m)	2,238,337	1,343,760
Olympic Radio (6m)	21,115	*36,511
Oxford Electric (6m)	57,000	6,886
Westinghouse (6m)	25,660,000	31,507,000

*Loss.

► **Securities**—Clary Multiplier offered 29,090 shares of common stock (par $1) at 62½ a share. Net proceeds will be added to working capital.

Raytheon stockholders approved an increase in authorized common stock to four million shares. The proceeds, when it is sold, will be used for working capital for future requirements.

Texas Instruments merged with Intercontinental Rubber. Stockholders of Intercontinental can exchange one share of their stock for one share of Texas Instruments.

IT&T withdrew its SEC registration for a $35.8 million offering of 20-year convertible debentures.

General Fuse, with stockholders approval, will increase its capital stock so that it can accept an offer to combine operations with another company with established earnings. Proceeds of a stock sale, if approved, will be used for working capital and for debts.

Business Is Good For Radio-TV Dealers

Independent and chain stores in the field are doing well but competition is increasing



ACCORDING to the latest RETMA survey, there are over 105,000 radio-tv dealers in the U.S., an increase of 9,750 in a ten-month period. At the present rate of business, according to the Commerce Department, total sales of radio-tv household-appliance stores, including chains, are seen reaching $4.2 billion this year, an increase of $0.6 billion over 1952 sales. Over half of this volume will be accounted for by radio and tv set sales, according to past ratios.

► **Income**—Basic factor accounting for the healthy trend in retail trade has been a growing volume of disposable consumer income, according to the Department of Commerce. It has been large enough so that increased radio-tv sales, as a percentage of disposable consumer income, have varied only slightly from past years. In 1951, 1952 and in the second quarter of this year, such sales took 1.6 percent of disposable consumer income.

All durable goods sales will take 25 percent of such income this year, at present rates. Automotive sales alone are taking 14 percent, an increase of 1.7 percent over last year. Radio-tv outlets may find that their biggest competition is coming from the automotive field.

► **Chains**—Sales by radio-tv-appliance chains of 11 or more stores are up so far this year. At annual rates, chain sales for the first seven months jumped to $427 million from $383 million last year and $392 million in 1951. As a percentage of total radio-tv retail outlet sales, however, the picture does not look far different. For the period from January to July of this year, chain sales accounted for 11 percent of total retail sales in the field, an 0.6 percent increase over last year. In 1951 the percentage was 11.2 percent. Chain stores in the radio-tv field still account for a larger share of sales than do chains in any in the other durable goods classifications.

FCC Approves Interim TV Station Operation

NEW WRINKLE in tv station applications bids to speed up television service to areas where station applications are in contest before FCC. Three competing applicants for channel 12 in Shreveport, La. formed the Interim Television Corp. which, as its name implies, will construct and operate a tv station jointly while they await the outcome of hearings.

► **Setup**—The three competitors each own equal shares of stock in the interim corporation and have equal director representation. They will equally share the cost of constructing and operating the station. They have agreed that the petitioner who is successful in the hearing will purchase, at cost, the interests of the losing parties and will repay them for their actual expenses in connection with interim operation.

► **Results**—Since the case was the first of its kind to be approved and required a waiver of the rules, FCC has retained the right to cancel the authorization at any time. The Commission also ruled

(Continued on page 22)

RIGHT ON TOP

Burnell records a few of it's most recent engineering achievements in Toroids and Filter Networks.



SIDE BAND FILTERS



Our most recent engineering achievement in communications filters has already stirred the interest of the leading receiver manufacturers in the country.

Our new side band filters which eliminate, for most applications, the necessity for expensive crystal filters are expected to accelerate the advancement of single side band communications.



SUB MINIATURE TOROIDS

Toroids for intermediate frequencies of 100KC to 1 megacycle. A wide variety of coils ranging in size from ¼ inch provides high Q in the frequency range between audio and RF.

The tiny toroid about the size of a dime has been welcomed by designers of sub miniature electronic equipment for the transistor, guided missile and printed circuit field.



PLUG IN DECADES

An entirely new development in inductance decades eliminating disadvantages of switch boxes. Inductance units plugged together in various combinations providing decade steps of inductance with minimum number of units required.

MINIATURE TELEMETERING FILTERS

In recognizing the need for miniaturization of the presently bulky telemetering equipment, our engineering staff has succeeded in reducing the size of telemetering filters to as little as 25 to 50% of the original volume.

BURNELL & COMPANY is very pleased to announce that it now has available a 12 page catalog which includes valuable and complete information on toroids, high quality coils, and various audio filter networks.

The catalog includes complete descriptions, attenuation and Q curves that will prove valuable for equipment design engineers.

Write for Catalog 101-A.

Burnell & Company
YONKERS 2, NEW YORK

that, in no event, will it extend the interim authorization beyond 10 days after the date a regular construction permit for channel 12 has been granted.

Armstrong Shows Binaural Multiplex

LATEST version of multichannel broadcasting first introduced in 1934 was recently demonstrated by Edwin H. Armstrong and John Bose at Columbia University. The new system, which has been undergoing secret field trials for several years, has the advantage of being compatible with existing f-m broadcasting techniques. Listeners will still be able to receive regular programs on existing receivers. Only those who wish to receive the side channel will require new receivers.

► **Binaural Reception**—Presently, radio station WQXR in New York is broadcasting all its live programs binaurally using both its a-m and its f-m transmitters for the two pickups. If Armstrong's multiplex were used, quality would be improved for those interested enough to purchase a new binaural f-m receiver.

During a part of the broadcast day, such a station could transmit a sponsored popular program, such as a ball game, on the side channel while a musical program is in progress on the main channel.

It would be easy, according to Major Armstrong, to substitute a communications channel (which uses a narrow band) for the additional broadcast channel. In fact, two communications channels might be squeezed in for taxi, police or other base station service.

► **Mobile Radio**—In conversations with an NARTB committee recently, Commissioner Sterling referred to the possibility of increasing f-m revenues by adding a multiplexed subscription-music channel. But his real shocker was the suggestion that f-m broadcasters supply the function of a base station for mobile communications systems. This would free the assigned base-station frequency for mobile use.



Receiving Tube Stocks Are Up

INDICATION of the state of business in the electronics industry as a whole is seen in the receiving tube inventories of leading tube manufacturers.

As shown in the chart, receiving tube inventories at the end of each month for the past year have steadily risen. Compared to July of 1952, inventories in July of this year were 20 million units higher. During the period, however, receiving tube sales rose nearly 50 percent.

► **Types**—Bulk of the receiving tubes on tube manufacturers shelves in July were of the type used in radio and tv receivers. In July, out of a 97.5 million tube total, 89.3 million tubes were of this type, enough to fully equip over 3 million tv receivers. The remaining 8.3 million were allied receiving types used in other commercial equipment.

► **In Sets**—Radio-tv receiver manufacturers also carry substantial tube inventories. Dollar value of receiving tube inventories in set manufacturers warehouses stood at $15,092,839 in April of this year, a slight increase over the $15,014,298 value computed for March. Tubes on hand are estimated to be enough to take care of two months of tv set production.

New Agency to Aid Business

Electronic manufacturers to be represented by two of 25 industry divisions

PROMOTION of business stability and growth are the dual aims of the Department of Commerce's newly established Business and Defense Services Administration.

The agency is intended to foster government-industry cooperation through the exchange of information, ideas and services. It takes over some of the defense and mobilization functions of the now defunct National Production Board.

► **Three Heads**—The BDSA will comprise three offices: the Office of Technical Services, a clearing house for technological information, the Office of Small Business, providing liaison with the Small Business Administration and the Office of Distribution that will be concerned largely with the wholesale, retail and marketing trades.

► **Divisions**—Industry advisory councils made up of representatives from government and private industry will be named for the twenty-five industry divisions within the agency. There will be additional product divisions within the industry divisions.

The electronics industry will be

(Continued on page 24)



Proven Design — new, high temperature pressure pickup uses same catenary diaphragm and tubular strain gage as NORWOOD CONTROLS' highly successful EP model. Immune to external vibration; mounts flush with negligible change in volume of pressure chamber; extremely high frequency response, flat to 10,000 cps, resonant frequency above 15,000 cps.

Withstands ultra-high temperatures — designed for use in rocket and jet engines, high temperature chemical reactions, etc. Efficient water-cooling system enables diaphragm to withstand gas temperatures above 5000°F. Heat transfer rate 11 BTU/sq. in./sec. with 85°F temperature rise of cooling water.

Corrosion resistant — All exposed parts of stainless steel, can safely be exposed to highly oxidizing conditions.

Full Scale Pressures — 500 and 1000 psi ranges down to 0 absolute with 1% of full scale accuracy and excellent temperature compensation. (Other ranges available on special order.)

A word about NORWOOD CONTROLS — *This name stands for an expanding line of commercial instruments for the measurement of pressure, flow, temperature and weight. It represents a fresh concept of creative engineering which, combined with New England manufacturing skill, is establishing new frontiers in the field of instrumentation.*

NC NORWOOD CONTROLS

CONTROL ENGINEERING CORPORATION
564 Providence Highway, Norwood, Massachusetts

Norwood Controls representatives are located in principal cities. Complete technical information will be supplied upon request.

represented in two divisions: communications equipment and electronics.

Donald Parris, former chief of NPA's electronics division, is acting director of the new electronics division. He is assisted now by a staff of six, including William Dulin, Edward Glacy and Charles Fess, all from NPA.

The electronics division will continue to review and make recommendations to the Office of Defense Mobilization on expansion goals, tax amortization and domestic loan applications. It will make recommendations on stockpiling or disposal of stockpiled strategic materials. It will collect, analyze and disseminate information on business activity as it affects the industry and will be the point of contact for the electronics industry in foreign trade.

Crystal Sets Are Still Selling

ONLY a handful of companies in the U. S. specialize in crystal-set manufacture, but the market for such sets is still active and sales so far this year have increased over last year for the same period.

One manufacturer in the field estimates that a total of 150,000 sets were sold in 1952. The handful of companies accounted for a retail sales volume of approximately a half-million dollars. Prices range from $1.15 to $5.00 each. Over the past 30 years, about 8 million crystal sets have been sold.

▶**Markets**—Manufacturers find their biggest sales in schools, hospitals and the youth market. Hospitals use crystal sets because head-phone operation prevents disturbance to other patients and because power is not needed. In the youth market, as in schools, many organizations find the sets an ideal and inexpensive way of keeping members interested. Other important markets are premium houses and nonelectrified areas.

Galena and catwhisker sets are still popular but two companies now supply germanium diodes in five-dollar models.



Britain's Electronics Industry Changes

PRODUCT structure of the radio and electronics industry in the United Kingdom has undergone a marked change since 1935, according to the *London Times Review Of Industry*. Companies and their products are far different now from prewar days.

▶**Past**—England's 1935 Census of Production shows that only six percent of the total radio equipment produced that year could be classified as industrial, as opposed to domestic. Domestic radio and sound reproduction apparatus accounted for the remaining 93 percent. Nearly 100 radio firms employing over 35,000 people turned out equipment valued at $49.5 million. At that time, 80 percent of the output came from the 20 largest firms and almost 90 percent of total output was from companies in the greater London area.

▶**Present**—Composition of Britain's electronic products output in 1952 shows that of an estimated total sales volume of $343 million, domestic radio accounted for only 25 percent, television took 30 percent and industrial apparatus, mainly defense items, 45 percent.

About 125,000 people are now employed by the industry and output is concentrated in the hands of a few large firms. Due to movement to suburbs, firms in the London area now account for about 65 percent of total sales.

▶**Radio-tv**—*The Financial Times*, reporting on the radio and television segments of the industry, charts the total production and export figures shown in the graphs.

The trend in radio set production has been down, with 1952 output lower than any year since before 1935. Television production has been on an upswing with an estimated demand for a million sets a year for the next five years.

A breakdown of the export figures for 1952 shows sales of about $21.8 million in components, $22.4 million in transmitters, $14.1 million in receivers and $10 million in tubes. Two-third to a half of these exports went to countries in the British Commonwealth and about a third went to Europe.

FCC Gets New Member

PRESIDENT EISENHOWER has appointed Robert E. Lee as a member of the Federal Communications Commission for a seven-year term subject to Senate confirmation. He succeeds Paul A. Walker, whose term expired last June, and brings Commission membership to its full complement.

Commissioner Lee was formerly director of surveys and investiga-

(Continued on page 26)



BETTER THAN WORDS!

. . . These curves demonstrate the superior electrical characteristics of Stackpole Ceramag cores—characteristics that are uniformly maintained regardless of size, shape, or production quantity.

Write for your copy of Bulletin RC-9A to ELECTRONIC COMPONENTS DIVISION,

STACKPOLE CARBON COMPANY

St. Marys, Pa.

STACKPOLE *Ceramag*®



tions for the House Committee on Appropriations where he has served since 1946. He entered Federal service in 1938 as a special agent for the FBI and in 1941 was made administrative assistant to J. Edgar Hoover. He was assigned to build the FBI staff for new responsibilities under the threat of war. Later he was made chief clerk of the FBI and was in charge of all fiscal matters.

SMPTE Convention Stresses Electronics

INCREASING influence of electronics on the motion picture industry was pointed up at the recent convention of the Society Of Motion Picture and Television Engineers in New York City.

It was stated that technological improvements and changes in motion pictures and tv which may add up to half a billion dollars or more were on the agenda of the meeting. About 40 or 50 percent of this cost figure applies to new techniques such as 3-D and stereophonic sound apparatus for motion pictures. The rest applied to color tv, theater tv, subscription tv and a few other new communications developments. One estimate puts sales of stereophonic sound equipment for theaters at $15 million for 1954.

► **Theater TV**—Although the matter of theater tv network facilities has already been handled by the FCC, the subject was widely discussed at the convention. In a paper, the members were told that if theater tv was to have simultaneous presentation and spontaneity it would require networks similar to those now furnished tv broadcasters.

► **Technical**—Other subjects discussed at the convention ranged from a new tv film scanner which is said to offer better reproduction of both black-and-white and color motion pictures on home tv sets to the latest information on 4-track magnetic stripping production. Because of the great interest in sterephonic sound, a special all-day session was added to the convention schedule.

MEETINGS

OCT. 26–28: Radio Fall Meeting, RETMA, RTMA of Canada and IRE, King Edward Hotel, Toronto, Ontario, Canada.

OCT. 30–31: Third Meeting Of The Industrial Council, Rensselaer Polytechnic Institute, Troy, N. Y.

Nov. 2–6: AIEE Fall General Meeting, Hotel Muehlebach, Kansas City, Mo.

Nov. 9–12: National Electrical Manufacturers Association, Haddon Hall Hotel, Atlantic City, N. J.

Nov. 9–12: Conference on Radio Meteorology, Austin, Texas.

Nov. 12–13: IRE Fourth Annual Meeting of Professional Group On Vehicular Communications, Hotel Somerset, Boston, Mass.

Nov. 13–14: Annual Electronics Conference, Hotel President, Kansas City, Missouri.

Nov. 19–20: Sixth Annual Conference On Electronic Instrumentation And Nucleonics In Medicine, IRE, AIEE and ISA joint sponsorship, Hotel New Yorker, New York, N. Y.

DEC. 1–2: Frequency Response Symposium, ASME, Hotel Statler, New York, N. Y.

DEC. 8–10: Joint AIEE-IRE-ACM Computer Conference and Exhibition, Statler Hotel, Washington, D. C.

DEC. 14–16: Second Annual Wire And Cable Symposium, sponsored by Signal Corps Labs and the wire and cable industry, Berkeley Carteret Hotel, Asbury Park, N. J.

JAN. 18–22, 1954: Winter Meeting of AIEE, Hotel Statler, New York, N. Y.

JAN. 26, 27, 1954: AIEE Scintillation Counters Conference, Washington, D. C.

JAN., 1954: Conference on Radio Astronomy, Carnegie Institute of Washington, California Institute of Technology and National Science Foundation, Washington, D. C.

FEB. 4–6, 1954: Sixth Annual IRE Conference And Electronics Show, Hotel Tulsa, Tulsa, Oklahoma.

FEB. 11–12, 1954: Joint IRE, AIEE, ACM West Coast Computer Conference, Ambassador Hotel, Los Angeles, Calif.

MAR. 22–25: IRE National Convention, Waldorf-Astoria Hotel and Kingsbridge Armory, New York, N. Y.

APRIL 22–23, 1954: AIEE Conference On Feedback Control, Claridge Hotel, Atlantic City, N. J.

APRIL 24, 1954: Eighth Annual Spring Technical Conference, Cincinnati IRE, Cincinnati, Ohio.

APRIL 27–29: AIEE Electronic Components Conference, Washington, D. C.

MAY 5–7, 1954: Third International Aviation Trade Show, 71st. Regiment Armory, New York, N. Y.

MAY 24–26, 1954: AIEE Conference On Telemetering, Morrison Hotel, Chicago, Ill.

JULY 6–9, 1954: International Conference On Electron Microscopy, Joint Commission on Electron Microscopy of International Council of Scientific Unions, London, England.

SEPT. 13–24, 1954: First International Instrument Congress And Exposition, Commercial Museum and Convention Hall, Philadelphia, Pa.

SEPT. 1954: International Scientific Radio Union, Amsterdam, Netherlands.

SEPT. 30–OCT 2, 1954: Second Annual International Sight and Sound Exposition, Palmer House Hotel, Chicago, Ill.

Industry Shorts

► **Figures** for the National Electronics Conference show that 6,880 visitors, 1,500 more than last year, attended exhibits of 114 manufacturers and listened to 98 technical papers.

► **Telecommunications** Planning Committee has been reestablished by the U. S. to provide immediate attention for telecommunications matters necessary to national defense.

► **Nippon** Television Network's first tv station JOAX-TV, took to the air on August 28 in Tokyo.

► **Work** will begin shortly on the construction of a $1 million Central Electronics Engineering Research Institute in Pilani, Central India, that will undertake research and development work in all aspects of electronics.

► **Television** broadcasting has not yet been approved in Australia by the government but nearly 120 preliminary tv station license applications have been made.

► **Hi-Fi** sales may reach between $200 and $300 million in 1954, according to RCA Victor.

Now—
Moldite Dependability
in all 3!



FERRICORES



MOLDED COIL FORMS



MAGNETIC IRON CORES

Moldite's famed precision production facilities
are now devoted to 3 major types of electronic components
—to give the industry a superlative core or coil form
for every electronic application.

Through years of continued engineering and research
Moldite has produced cores of guaranteed dependability,
economy, quality and uniformity. Our customers'
smooth running production lines tell the story best.

Specify a Moldite core specially designed
and precision made for you,
with absolute uniformity from first to last.

FERRITE CORES
MOLDED COIL FORMS
(iron and phenolic)
MAGNETIC IRON CORES
FILTER CORES
THREADED CORES
SLEEVE CORES
CUP CORES

Samples promptly submitted upon request
for design, pre-production, and test purposes

. . . Send for our new Catalog No. 110 — THE MOST COMPLETE LINE OF CORES IN THE INDUSTRY!

NATIONAL
MOLDITE
COMPANY
1410 CHESTNUT AVE., HILLSIDE 5, N. J.

Robert T. Murray	Jerry Golten Co.	Martin P. Andrews	Perlmuth-Coleman & Assoc.	Jose Luis Ponte
614 Central Ave.	2750 W. North Ave.	Mott Road	1335 South Flower	Cardoba 1472
East Orange, N.J.	Chicago 22, Ill.	Fayetteville, N.Y.	Los Angeles, Cal	Buenos Aires

Want more information? Use post card on last page.

Precision, high-speed winding equipment for IRC elements

ONLY IRC WINDING SKILL OFFERS



Wire element is uniformly and tightly wound on an insulated core. Axial leads or other terminations are secured to element by automatic machinery. Insulated housing may be used or omitted.

If you seek savings in component costs, IRC's winding skill may serve your need. IRC's mastery of winding wire elements dates back more than 25 years. Today, it provides a wide variety of unique units that offer realistic possibilities for savings. Cost-conscious IRC engineers will glady analyze your requirements.



14c savings per car

Type AW Wire Wound resistors save automobile manufacturers an average of 14c per car. For quantity requirements, these low-cost windings can be made specially to suit individual designs. This adaptability has proved profitable to numerous appliance manufacturers.



low cost—low wattage

Type BW insulated wire wounds offer excellent stability in low ranges—at low prices. Leading instrument manufacturers attest to their superiority. ½, 1 and 2 watt sizes are equivalent to Jan types RU-3, RU-4 and RU-6.



50% savings

IRC Insulated Chokes offer savings up to 50% over ordinary types. Available in two sizes, they are fully protected against humidity, abrasion, assembly damage and danger of shorting to chassis. A favorite source of savings for TV and radio set manufacturers.

THESE SAVINGS

inexpensive solution

4-watt Insulated Power Wire Wounds with axial leads can save several cents over conventional power resistors. Inorganic core and high-temperature plastic housing allow safe operation up to 165° C. Widely used in toys, juke boxes and amusement devices.

specifications

MIL-R-93A AMENDMENT 1

Government specifications for precision wire wound resistors have been revised. MIL-R-93A Amendment 1 is the new rigid standard.

IRC PRECISION WIRE WOUNDS

meet and beat these new specifications. They are equivalent to Mil types RB-15 through 19.

MAXIMUM STABILITY

Temperature cycling even beyond Mil requirements has only negligible effect. Send for new technical bulletin.

Boron & Deposited Carbon Precisitors • Power Resistors • Voltmeter Multipliers • Low Wattage Wire Wounds • Insulated Composition Resistors • Volume Controls •

Wherever the Circuit Says—

Precision Wire Wounds • Ultra HF and Hi-Voltage Resistors • Low Value Capacitors • Selenium Rectifiers • Insulated Chokes • Hermetic Sealing Terminals •

IRC

INTERNATIONAL RESISTANCE CO.
403 N. Broad St., Philadelphia 8, Pa.
In Canada: International Resistance Co., Ltd., Toronto, Licensee

Send me technical data on: ☐ Precision Wire Wounds; ☐ Insulated Chokes; ☐ BW Resistors; ☐ 4-Watt Power Resistors

Name_____

Title_____

Company_____

Address_____

City_____ State_____

TAPPING SCREWS

TYPES OF TAPPING SCREWS

AVAILABLE WITH SLOTTED, CLUTCH OR PHILLIPS HEAD RECESSES

POINTS AND THREADS		METAL THICKNESS	HOLE DIAM.	POINT DIAM.
TYPE "A"	Spaced thread with gimlet point. Use in light sheet metal, resin impregnated plywood, asbestos compositions etc.	From .018" To .048"	.128" To .149"	Sharp (for easy starting)
TYPE "B"	Spaced thread with pitches finer than type "A" but with some general uses. Blunt point for better appearance. Point requires less space.	From .018" To 3/16"	.144" To .173"	.130/.125
TYPE "C" COARSE OR FINE THREAD	Thread similar to machine screw threads. Used where a machine thread is preferable. May be used with machine nut for extra strength. Requires higher driving torques than "A" or "B".	From .037" To 5/16"	.154" To .177"	.147/.133

*These specs. apply only to #10 tapping screw in sheet steel

In selecting Tapping Screws it is extremely important to understand the proper application for each type. The type you require will vary with: 1. kind of material; 2. thickness of material; 3. the method used for making the hole.*

Lamson Tapping Screws are precision made to insure maximum holding even in thin material, fully hardened to permit the thread crests to form clean threads without stripping hole. They are available in a wide range of head and point combinations. A "special" Tapping Screw to many . . . is a "stock" item at Lamson.

***This information is available in tabular form for easy reference. Write for as many copies as you need.**

The LAMSON & SESSIONS Co.
1971 West 85th St. • Cleveland 2, Ohio
Plants at Cleveland and Kent, Ohio • Birmingham • Chicago

Lamson & Sessions

FOR PROMPT DELIVERY AND HELPFUL SERVICE, ORDER FROM YOUR LAMSON DISTRIBUTOR

PLUG NUTS — Ideal for blind or hard-to-reach places.

PIPE PLUGS — Forged steel, heat-treated.

"1035" SET SCREWS — Cup point type, hardened and heat-treated.

PLACE BOLTS — With "Built-in" spring action for positive locking.

LOCK NUTS — Economical, vibration proof. Can be used repeatedly.

"BENT BOLTS" — Including U bolts, eye bolts, hook bolts, etc.

MACHINE SCREWS — Clutch and Phillips recessed head screws.

SEMS — Pre-assembled lockwashers on tapping and machine screws.



L. G. Young, Bell Telephone Laboratories, Inc., inspects Eimac tubes in LD-T2 transmitter.

Western Electric multi-channel, single side band Transmitters use Eimac tubes in final RF stages

LD-T2 transmitters designed by Bell Telephone Laboratories, for overseas multi-channel communications, are another example of Bell System equipment that meets severe performance requirements. Manufactured by Western Electric, type LD-T2 single sideband suppressed carrier transmitters operating between 4 and 28 mc., handle numerous channels simultaneously with outstanding dependability and performance. Naturally, electron power vacuum tubes in the LD-T2 must meet exacting specifications.

Eimac 4E27A radial-beam power pentodes, 4-400A radial-beam power tetrodes and 3X2500F3 power triodes fill sockets in the final three stages of the RF sections in Western Electric LD-T2 transmitters.

Final Three RF Stages

For information about Eimac electron power tubes write our application engineering department.

Eimac TUBES

EITEL-McCULLOUGH, INC.
San Bruno, California

Want more information? Use post card on last page.

Put your product here → to shake-test it with 10,000 lbs force



MB produces the largest exciter ever built to meet heavy duty vibration test specifications

THERE's nothing like a good shaking to test out structural designs, electronic equipment, instruments or complete assemblies for faults or flaws. In fact, for many products put to military use, such tests are *specified*. However, since *all* products encounter some vibration or shock in service, many engineering departments use an MB Exciter to test all designs. By so doing, the "bugs" are discovered in the test laboratory instead of out in the field, at cost of good will.

Largest in the line of MB electromagnetic shakers, the Model C-100 shown delivers at least 5 tons continuous force. Its performance permits heavy duty vibration testing to MIL-E-5272 and other specifications. It incorporates a number of unusual design features for easy, quick, convenient operation—including interlocking controls for complete safety and provisions for cycling tests.

HOW TO HANDLE LARGE MASSES

MB can show you a setup of vibration exciter and resonating beam that multiplies the capacity of versatile MB Exciters many fold. Shaker being used in this fatigue strength test of aircraft engine mounts is the model S-3 rated at 200 lbs. Others available down to 10 lbs. force output.

Vibration is MB's specialty. You're invited to draw on the benefits of this specialization—and get highly qualified products for testing and control, and technical help on your problem.

Valuable bulletins for test engineers Calibrating vibration pickups to 2000 cps is comprehensively covered in MB Bulletin No. C-11-1. Bulletin No. 1-VE-1 describes vibration exciters and details their specifications. Write today.

THE MB MANUFACTURING COMPANY, INC.
1060 State Street, New Haven 11, Conn.

HEADQUARTERS FOR PRODUCTS TO INDUCE VIBRATION...TO MEASURE IT...TO ISOLATE IT

Bell ...First to transmit

the human voice electrically

Alexander Graham Bell

1847-1922

Bell, best known for his invention of the telephone, was also a teacher of deaf-mutes and a self-taught physicist. He first transmitted spoken words on March 10, 1876, to his assistant, Thomas A. Watson.

Bell subsequently interested himself in "photophone," the transmission of sound by light, and in aviation—but was principally dedicated to humanitarian works on behalf of the deaf. He was honored by membership in many learned societies, and was a Regent of the Smithsonian Institution.



From an original drawing made for Ohmite

OHMITE®

...First in resistors—today

For the resistors *preferred* by industry everywhere, look no further than Ohmite! Dependability and long, trouble-free life have made Ohmite resistors the favorite in their field. Moreover, they are available in an unusually wide range of sizes and types—which means you can select a resistor *precisely* suited to your needs. Don't just specify resistors . . . specify Ohmite!

Be Right with OHMITE

RHEOSTATS • RESISTORS • TAP SWITCHES

OHMITE®

FOR *Dependability*

RHEOSTATS

All-ceramic and metal, close control rheostats for unsurpassed dependability and smoothness of operation. Ten stock sizes, 25 to 1,000 watts.

TAP SWITCHES

Five compact models, 10 to 100 amperes, AC, up to 12 taps. All-ceramic and metal construction. Silver-to-silver contacts, with self-cleaning rotor.

RESISTORS

A wide range of dependable, fixed, adjustable, tapped, and non-inductive, power wire-wound resistors. Also a wide range of precision resistors.

R. F. CHOKES

Single layer R. F. plate chokes and power line chokes, on steatite or plastic cores. Protected by a special moisture-resistant coating.

Be Right with OHMITE

OHMITE MANUFACTURING COMPANY

3610 HOWARD STREET, SKOKIE, ILLINOIS (Suburb of Chicago)

WRITE on company letterhead for Catalog and Engineering Manual No. 40



ELECTRONICS PARK—G-E HEADQUARTERS FOR ELECTRONICS RESEARCH

Need a DUAL Regulated Power Supply?

Get the G-E ST-9A with *twin outputs* and featuring . . . ELECTRONIC OVERLOAD PROTECTION *plus* BUILT-IN MODULATOR

No power supply on the market today can match this new G-E unit for general laboratory purposes. Routine bench casualties are no problem for the ST-9A: the instruments cannot be harmed by short circuits on the regulated outputs. And—with the built-in modulator you can now observe hum and noise tolerances by actually duplicating them on the equipment. This saves you time by establishing final power supply design specifications quickly.

TYPE ST-9A ELECTRICAL SPECIFICATIONS

OUTPUT VOLTAGES

#1 Regulated—Continuously variable, 0-500 volts, maximum current 100 ma

#2 Regulated—Same as #1

Parallel #1 and #2—Continuously variable, 0-500 volts, maximum current 150 ma

Unregulated—Approximately 650 volts no load, maximum current 200 ma

—75 Volts—VR tube regulation, 0-2 ma

—150 Volts—VR tube regulation, 0-4 ma

Filament Supply—6.3 volts a-c at 10 amps

REGULATION

Better than ½% + ½ volt

RIPPLE AND NOISE

Less than 3.5 mv (10 mv peak-to-peak) on all regulated outputs

INSTRUMENTS

Milliameter 0-300 ma d-c; voltmeter 0-500 volts d-c; voltage and current can be metered at #1 and #2 Regulated and Unregulated outputs; total current drawn from all outputs can be metered and it should not exceed 200 ma

OVERLOAD PROTECTION

3 amp fuse in the a-c line; ⅜ amp fuse in the d-c line; overload of any degree on the regulated outputs will harm neither the supply itself nor the instruments.

G-E POWER SUPPLY YPD-2

Excellent for many laboratory applications. DC Voltage Output: 250-450 volts, (positive or negative may be grounded to chassis). DC Current Output: 0-300 milliamperes. AC Output: 6.3 volts 10 amperes unregulated. Regulation: Less than 1% of output voltage from minimum to maximum current. Ripple: Less than 5 mv peak to peak. Output Impedance: Approximately 2 ohms at 30 cycles, decreases with increasing frequency. Power Requirements: 105-125 volts, 50/60 cycle, 350 watts maximum.

1878 75 1953 YEARS OF ELECTRICAL PROGRESS

General Electric Company, Section 4113
Electronics Park, Syracuse, N. Y.

Please send me a copy of your G-E POWER SUPPLY CATALOG (ECB-6A).

NAME.....

COMPANY.....

ADDRESS.....

CITY.....STATE.....

GENERAL ELECTRIC

Want more information? Use post card on last page.

DX COMPONENTS

"the heart of a good television receiver"

DX RADIO PRODUCTS COMPANY

PRODUCTS *wired for life*

with WARREN WIRE



The new DX 90° Deflection Yoke for 27" tubes is especially designed for television receiver manufacturers who want a sharp full-screen focus with a minimum of pincushioning. This compact component blends advanced engineering skills with the finest materials to assure top performance and economy. Here, as in the manufacture of many other fine electric and electronic products, Warren Wire is used for its easy handling, efficiency and dependability. There's a Warren Wire Engineer near you trained to help you solve your wire problems right in your own plant. There is no obligation, of course.

NEW! ***Send for our new "Magnet Wire Reference Tables" Chart***

WW

WARREN WIRE COMPANY

Plant and Main Office: POWNAL, VERMONT

NEW YORK • SYRACUSE • NEW HAVEN • PHILADELPHIA • PITTSBURGH* • CLEVELAND* DETROIT • CHICAGO* • ST. LOUIS* • ST. PAUL • LOS ANGELES* • SAN FRANCISCO

Manufacturers of Plain Enamel, Nylon, Formvar, Teflon and Served Magnet Wires . . . Teflon Hook-up and Lead Wire . . . Tinned and Bare Copper Wire.

*Office and Warehouse

Want more information? Use post card on last page.

TO MAINTAIN CONSTANT OUTPUT VOLTAGES

STABILINE *Automatic* VOLTAGE REGULATORS

are available in 2 DISTINCT TYPES

TYPE IE INSTANTANEOUS ELECTRONIC



For the most exacting control featuring:

INSTANTANEOUS CORRECTION — as compared with any other type. Operation is entirely electronic without moving parts. Complete correction is effected in 3 to 10 cycles depending on variations in line voltage, load current, load power factor and other conditions.

EXCELLENT STABILIZATION AND REGULATION — The maximum change in output voltage will not exceed: ±0.25 per cent for any or all changes or variations in operating conditions — ±0.1 per cent for input voltage changes — ±0.15 per cent for load current or power factor changes from lagging 0.5 to leading 0.9.

MINIMUM WAVEFORM DISTORTION — Except under the most adverse conditions, distortion is usually under 2 per cent.

MUCH WIDER INPUT RANGE — than most competitive types. Ranges are 95-135 volts for a nominal output of 115 volts and 195-255 volts for a nominal output of 230 volts.

ADJUSTABLE OUTPUT VOLTAGE — Output from a nominally 115 volt unit is adjustable from 110 to 120 volts and from 220 to 240 volts on a nominally 230 volt unit.

INSENSITIVITY TO FREQUENCY CHANGES — but to maintain optimum correction characteristics, tolerances should not exceed ±10 per cent of the specified frequency.

STANDARD MODELS — are available in numerous ratings in capacities up to 5.0 KVA.

TYPE EM ELECTRO MECHANICAL

to control industrial loads — offer zero waveform distortion featuring:

UNUSUALLY HIGH EFFICIENCY — is an outstanding feature of the Type EM. It is comparable to that of the most conservatively designed fixed-ratio transformers.

ZERO WAVEFORM DISTORTION — is a primary requirement for many electronic applications. Type EM provides a constant output voltage which is a faithful and distortionless reproduction of the applied input waveform.

RAPID CORRECTION — Type EM is an electro mechanical device. While it does not correct instantaneously, it provides faster correction than most other automatic voltage regulators.

WIDE INPUT RANGE — is another important feature. Range is 95-135 volts for a nominally 115 volt unit; 195-255 volts for a 230 volt unit; 400-520 volts for the 460 volt units.

ADJUSTABLE OUTPUT VOLTAGE — Output from a 115 volt unit is adjustable from 110 to 120 volts; output from a 230 volt unit is adjustable from 220 to 240 volts; output from a 460 volt unit is adjustable from 420 to 460 volts.

INSENSITIVE TO FREQUENCY AND SYSTEM POWER FACTOR — Designed for 50/60 cycle power lines, all of the Type EM will perform satisfactorily at any frequency from 45 to 65 cycles. In addition, Type EM is insensitive to the magnitude and power factor of the load and has no effect on the system power factor.

STANDARD MODELS — are available for 115, 230 or 460 volt, 50/60 cycle, single and three phase operation in capacities up to 100 KVA.

. . . AND SPECIAL TYPES

application engineered to meet individual requirements

Specializing in the design, development and manufacture of Voltage Control Apparatus, The Superior Electric Company offers its experience to help in solving any voltage control problem. The Superior Electric Company is pleased to analyze your individual needs and will recommend the STABILINE Automatic Voltage Regulator best suited to your application.

SEND COUPON TODAY FOR BULLETIN S351 featuring engineering and application data on STABILINE Types IE and EM.

THE SUPERIOR ELECTRIC CO.
BRISTOL, CONNECTICUT

Manufacturers of

- POWERSTAT VARIABLE TRANSFORMERS
- STABILINE AUTOMATIC VOLTAGE REGULATORS
- VOLTBOX A-C POWER SUPPLIES
- POWERSTAT LIGHT DIMMING EQUIPMENT
- VARICELL D-C POWER SUPPLIES
- SUPERIOR 5-WAY BINDING POSTS

THE SUPERIOR ELECTRIC CO.
211 MAE AVENUE, BRISTOL, CONN.

Please send my copy of Bulletin S351.

NAME _____

POSITION _____

CO. NAME _____

CO. ADDRESS _____

CITY _____ ZONE ____ STATE _____

Observe and Measure...



Grid and plate waveforms of amplifier are displayed on common time base for accurate comparison. Grid waveform (top) observed on 100 millivolts full scale; plate waveform (bottom) observed on 100 volts full scale. Illuminated calibrated scale facilitates both visual observation and analysis of oscillogram.

...with the new

DU MONT TYPE 322-A

Dual-Beam Cathode-ray Oscillograph

PRICE $895

Observe and *accurately measure* two signals simultaneously on a single cathode-ray tube screen with the new Du Mont Type 322-A Cathode-ray Oscillograph.

In addition to the well-known advantages of observing the true relationship between two signals on the same screen, Du Mont offers built-in, accurate amplitude calibration of each of the two channels in the new Type 322-A. Push-button calibration, plus an illuminated scale permit rapid, convenient, wide-range voltage readings of signals.

The accuracy achieved in the new calibration system of the Type 322-A results from the use of the newly developed Du Mont Type 5AFP- tight tolerance cathode-ray tube.

FEATURES

- High-accuracy, dual-beam Type 5AFP- Cathode-Ray Tube.
- Essentially two complete time-tested Type 304-A cathode-ray voltmeters in one cabinet. Ranges of measurement from 100 millivolts full scale to 1000 volts full scale.
- Expansion to 5 times full scale vertically and 6 times full scale horizontally.
- Sweep ranges from 2 cps to 30 KC compatible with frequency range of d.c. to 10% down at 100 KC.
- New concentric knobs for easy manipulation and accurate resetting.
- Illumination of special calibrated scale can be varied for viewing and photography.

DU MONT

for Oscillography

WRITE FOR 322-A BROCHURE

INSTRUMENT DIVISION • ALLEN B. DU MONT LABORATORIES, INC. • 760 BLOOMFIELD AVENUE, CLIFTON, N. J.

telling the story of 'dag' dispersions



Can This Unique Material Help You? Check These Properties...

'dag' Colloidal Graphite

Chemically inactive, non-fusible, gray-to-black solid.
Electrically conductive, diamagnetic, electrophoretic.
Low in photoelectric sensitivity, resistant to electron bombardment.
Forms tenacious *dry film* which is opaque, conducts heat, adsorbs gas, and has low coefficient of friction.

In Vacuum Tubes—'Aquadag', a dispersion of colloidal graphite in water, applied to grids and plates minimizes secondary emission, "back" emission, and photoelectric effects.

In CRTs—A dispersion of colloidal graphite in distilled water applied to inside walls retards secondary emission, adsorbs gases, and serves as an electrical conductor. And another dispersion, in lacquer, will opaque exterior walls.

In Light-Sensitive Cells—Colloidal graphite does not react with selenium to form selenides; therefore, it is used as an electrode material in photo tubes.

In Other Applications—As a conductive coating on piezo-electric crystals, on high-voltage coils, on suspension-type insulators... generally *wherever* a conductive lubricant is required.

Write *today* for more detailed information. Ask for Bulletin No. 433-5L.

Dispersions of molybdenum disulfide are available in various carriers. We are also equipped to do custom dispersing of solids in a wide variety of vehicles.

dag DISPERSIONS

Acheson Colloids Company, Port Huron, Mich.
...also ACHESON COLLOIDS LIMITED, LONDON, ENGLAND
Units of Acheson Industries, Inc.

try 'dag' resin bonded dry films for permanent lubrication

MEPCO'S NEW SEALED Precision Resistors STOP Humidity Failures

Over 2 years of laboratory development and testing were required to achieve a sealed resistor design up to Mepco's standard of quality. No sacrifice of our standard time-proven features have been made in order to perfect this sealed resistor.

SPECIFICATIONS: Meets all requirements of MIL-R-93A and JAN-R-93.

SEALING: Completely encapsulated and bonded.

OPERATING TEMPERATURE: —65°C. to +125°C.

WINDINGS: Reversed and balanced PI-windings for low inductance with use of only the finest "certified" resistance alloys.

EXCLUSIVE INTERNAL FEATURES: Internal section's cross-over wire insulated from winding by 2000 v. insulation (patented). Special metal molded connecting feature, which bonds end of winding and terminal in a non-corrosive and mechanically secure manner — no solder or flux used.

TERMINALS: Rigid hot solder coated brass terminals for easier and more secure soldering.

TYPE	NOMINAL WATTAGE RATING	RESISTANCE MIN.	RESISTANCE MAX.	NO. SECTIONS	SUPERSEDES JAN-R-93 TYPE
RB15 (M15)	.25 .50	0.1 ohm 0.1 ohm	.185 meg. .6 meg.	2	RB10
RB16 (M16)	.35 1.00	0.1 ohm 0.1 ohm	.3 meg. 1.5 meg.	2	RB11
RB17 (M17)	.50 1.00	0.1 ohm 0.1 ohm	.3 meg. 2.0 meg.	4	RB12
RB18 (M18)	.50 1.00	0.1 ohm 0.1 ohm	.75 meg. 4.0 meg.	4	RB13
RB19 (M19)	1.00 2.00	0.1 ohm 0.1 ohm	4.0 meg. 15.0 meg.	8	RB14
RB52 (M52)	.25 .50	0.1 ohm 0.1 ohm	.1 meg. .5 meg.	2	RB51

MIL - R - 93A
WATTAGE & RESISTANCE TOLERANCE

TOLERANCE SYMBOL	RESISTANCE TOLERANCE	PERCENT OF NOMINAL WATTAGE
B	0.10 %	50 %
C	0.25 %	50 %
D	0.50 %	75 %
F	1.00 %	100 %

MIL - R - 93A
TEMPERATURE COEFFICIENT
(REFERRED TO 25°C)

SYMBOL	EXPRESSED IN PERCENT PER DEGREE C.	
	NEGATIVE, MAX.	POSITIVE, MAX.
E	0.0022	0.0022
J	0.0040	0.0155
K	0.0050	0.0255

SPECIAL REQUIREMENTS

Variations of the above ratings, tolerances, temperature coefficient, etc. can be supplied to special order.



MEPCO, INC.
MORRISTOWN, NEW JERSEY

Want more information? Use post card on last page.

In Addition to its Regular Line of Compression Seals
With Individually Glassed Terminals...

Hermetic

Offers a Complete Line of

MULTI-TERMINAL HEADERS & PLUGS

In "All-Glass" Compression CONSTRUCTION

"All-Glass"

Compression HERMETIC Seals offer many advantages for components which require headers of unusual ruggedness because of adverse design, assembly or shop handling conditions.

- The greater strength of these "all-glass" units is due to the controlled, compression-type construction.
- They offer greater economies over headers constructed with individual glass beads.
- The improved glass construction of the "all-glass" units prevents the formation of moisture pockets.
- There is also greater insulation resistance and voltage breakdown inherent in the longer leakage path of the "all-glass" construction.

Because there is infinite application for these new units, they are available in a wide variety of mounting flange arrangements to fit existing or new designs.

And, of course, HERMETIC also offers its complete regular line of individually glassed multi-headers and plugs, plus single terminals, feed-throughs and stand-offs.

Write

for complete information on how HERMETIC engineers can apply "All-Glass" Compression Seals to your regular or special applications. Available, too, is HERMETIC's Brochure CS on compression seals, as well as a 32-page catalog on its standard line.

Hermetic Seal Products Co.

31 South Sixth Street
Newark 7, New Jersey

FIRST AND FOREMOST IN MINIATURIZATION

This Electrical Reporter Stays on the Tough Jobs Longer...



Added Evidence that—

Everyone Can Count on VEEDER-ROOT

Compact and rugged . . . this electrically operated reset counter is specially designed for tough jobs that demand longer counter life.

Here's another instance of the *infinite applicability* of Veeder-Root *Count*rol — electrical, mechanical or manual. And here's another instance, too, of the endless resourcefulness of Veeder-Root engineering, and the ability to design a *complete counting package* that fits the job fully and exactly. Now . . . what's *your* problem?

VEEDER-ROOT INCORPORATED

"The Name That Counts"

HARTFORD 2, CONNECTICUT

Chicago 6, Ill. • New York 19, N.Y. • Greenville, S.C
Montreal 2, Canada • Dundee, Scotland
Offices and Agents in Principal Cities

CROMAG

-A CERAMIC PERMANENT MAGNET MATERIAL

For:

Focusing devices
Ion traps
Beam correctors
Loudspeakers
Polarized relays
Small motors
. . . and generators
High frequency attenuators
Magnetic attenuators
Meters and instruments
. . . . and countless other uses



SPECIFICATIONS:

- Hc ..... 1550 oersteds
- Br ..... 2000 gauss
- BH max. 800,000
- Resistivity ..... 1 x 10^6 ohms
- Permeability 1
- Specific Gravity ..... 4.3—4.7 grams/cm^3
- Curie Temperature ..... 400° C.

Cromag is the *tried and proved* ceramic magnetic material, produced by the leader and pioneer in steatite and powdered metallurgy. Cromag is a lightweight, magnetically-hard permanent magnet material containing no critical materals, therefore available for any application in any quantities.

This unique material is available in a wide variety of shapes produced by powdered metallurgy methods, and is also available in extruded lengths as rods, tubing, square, rectangular, or any other desired symmetrical shape.

Here is the permanent magnet material for you. Send us your magnetic problems and benefit by the engineering that has made Crowley the acknowledged leader in this field.

CROWLEY

PIONEER AND LEADER IN STEATITES AND POWDERED METALLURGY

Henry L. Crowley & Company, Inc., One Central Ave., West Orange, N. J.

introducing the GOODMANS PERMANENT MAGNET SHAKERS

THESE shakers provide vibratory sinusoidal forces of frequency and amplitude by which specific vibratory conditions can accurately be simulated. They provide the means of assesssing the effects of sudden acceleration on materials, structures and components; and are being extensively applied to FATIGUE TESTING, ELECTRICAL COMPONENT TESTING, FLEXTURE TESTING OF PLASTICS, ETC., and SPECIALISED GUIDED WEAPON RESEARCH. For certain pre-knowledge of vibration and its effects consult GOODMANS.

MODEL 390A A medium duty model producing an alternating force of approximately ±25 lbs.

Thrust	Force factor 4.7 lbs. per amp.
Max. Continuous Current Rating (R.M.S.)	2 amps. uncooled; 4 amps. with air cooling of approx. 5 lbs. per sq. in.
Stroke	0.5 in total excursion.
Impedance	8 ohms matching.
Frequency Range	Up to 10,000 c/s.
Weight of Moving System	0.16 lbs.
Stray Fields	Operating zone less than 100 gauss.
Flux Density	11,000 gauss.
Weight	26 lbs.

MODEL 790 For Vibrating heavy components, and is capable of producing a force of ± 50 lbs.
This unit has a force factor of approximately 9.2 lbs. per amp. and a total current capacity, with air cooling, of 4 amps. (R.M.S.).

Stroke	0.5 in total excursion.
Impedance	24 ohms matching (approx.)
Frequency Range	Up to 5,000 c/s.
Weight of Moving System	0.5 lbs. (approx.)
Stray Fields	Operating zone less than 100 gauss.
Flux Density	11,000 gauss.
Total Weight (inc. trunnion)	70 lbs.

MODEL V47 for the vibration of very light electronic components, optical-cell research, hair-spring torque testing etc.

Thrust	Force factor 0.9 lbs. per amp.
Max. Continuous Current Rating (R.M.S.)	1.5 amps.; 2.0 amps. up to 2 min. duration.
Stroke	0.2 in total excursion.
Impedance	Varies with frequency and load between 3 and 10 ohms.
Frequency Range	Up to 10,000 c/s.
Weight of Moving System	6.5 grams.
Stray Fields	Operating zone less than 25 gauss.
Flux Density	11,000 gauss.
Weight	2 lbs.





DRIVING EQUIPMENT

A range of appropriate driving equipments is available and takes the form of High-Power Amplifiers, Stabilised Power Supply Units and precisioned R.C. Oscillators specifically designed to give continuous power output to drive the particular shaker concerned.

MODEL 8/600
For the vibration of heavy loads or complete assemblies. Has a total force of approximately ± 300 lbs.

Stroke	1 in. total excursion.
Impedance	to suit driving equipment.
Frequency Range	Up to 3,000 c/s.
Weight of Moving System	6 lb. (approx.)
Stray Fields	Operating zone less than 25 gauss.
Flux Density	10,000 gauss.
Total Weight (inc. trunnion)	4 cwt. (approx.)

This unit can be fitted with (a) built in air cooling blower (b) switch to give high or low impedance armature coil and (c) pick-up unit for monitoring wave form and amplitude.



MAIL THIS COUPON

To GOODMANS INDUSTRIES LIMITED
AXIOM WORKS, WEMBLEY, MIDDX., ENGLAND

Please mail me your catalogue and technical data sheets in connection with your PERMANENT MAGNET Shakers.

NAME.....

COMPANY .....

.....

CITY.....ZONE.....STATE..... E/U

Cables:
GOODAXIOM
WEMBLEY, ENGLAND

GOODMANS INDUSTRIES LTD
AXIOM WORKS · WEMBLEY · MIDDX · ENGLAND

ERIE

Complete line of

DISC CERAMICONS®



HIGH VOLTAGE

HIGH VOLTAGE DISC CERAMICONS employ the same basic diameters that have been standardized in 500 volt Ceramic capacitors. Careful and detailed life testing has been accomplished over a long period of time to establish required dielectric thicknesses to assure conservative ratings in the high voltage line. Standard voltage ratings range from 1,000 through 6,000 Volts, D.C., Working.

TEMPERATURE COMPENSATING

TEMPERATURE COMPENSATING DISC CERAMICONS, in four sizes, offer all standard combinations of temperature coefficient and capacitance value. They are tested for conformance to Erie specifications for Tubular Ceramicons and meet all requirements for RTMA REC-107A Class 1 ceramic capacitors. They are available in capacity ranges up to 725 mmf.

GENERAL PURPOSE

GENERAL PURPOSE DISC CERAMICONS have low series inductance which assures efficient high frequency operation. They are made in sizes from 1/16" to 3/4" diameter, and in capacitance values ranging from 10 mmf to .02 mfd.



ERIE components are stocked by leading electronic distributors everywhere.

25th Anniversary ERIE TRADE MARK RESISTOR CORP.

ERIE RESISTOR CORPORATION . . . ELECTRONICS DIVISION

Main Offices: **ERIE, PA.**

Sales Offices: Cliffside, N. J. • Philadelphia, Pa. • Buffalo, N. Y. • Chicago, Ill. Detroit, Mich. • Cincinnati, Ohio • Los Angeles, Calif.

Factories: **ERIE, PA. • LONDON, ENGLAND • TORONTO, CANADA**

For *Critical* Applications

Triplett 630-A Has No Counterpart

Accuracy
to 1½%

Readability
with a Mirror-Scale

Adaptability
with ½% resistors

Try This Volt-Ohm-Mil-Ammeter at your distributor's

Triplett
TRIPLETT

TRIPLETT ELECTRICAL INSTRUMENT CO., BLUFFTON— OHIO

NEW G-E LOW-NOISE U-H-F AMPLIFIER TRIODE

Only 8.5 decibels at 1200 megacycles!

Greatly Improves Reception!

EQUIPMENT DESIGNERS! In G. E.'s new GL-6299, you have a low-level Class A amplifier for frequencies up to 3,000 mc, with an exceptionally low noise figure—8.5 db or better at 1,200 mc; under 14 db at 3,000 mc.

RESULT: better all-around reception. In radar, less "grass." To make this possible, the highest standards of tube precision workmanship have been observed. Grid-cathode spacing is only .0004 inch, or less than 1/10 the diameter of a human hair. Similar close tolerances and exact measurements mark the rest of this tiny, finely-engineered triode.

At the same time, the GL-6299 is sturdy—shock-resistant—mounts coaxially with large contact areas. An electrical plus is the tube's ability to (1) withstand spike voltages, (2) reduce their overloading effect on later circuit stages. Means stepped-up reliability of equipment! . . . Write for Booklet ETD-810, with full tube description, ratings and performance curves. *Tube Department, General Electric Company, Schenectady 5, N. Y.*



1 inch high.
Gold-plated.
Made like
a fine watch.

APPLICATIONS INCLUDE:

- Military radar and communications equipment.
- Commercial microwave communications and relay systems.
- Aircraft communications equipment.
- Electronic navigation aids.
- Signal generators.

1878 75 1953 YEARS OF ELECTRICAL PROGRESS
Diamond Anniversary

GENERAL ELECTRIC

163-1A9

LITTON ENGINEERING NEWS

NOW! Dependable pressure monitoring of high vacuum systems during processing

The new Litton Ionization Gauge is a rugged and completely dependable production tool for monitoring pressures from 10^{-4} to 10^{-7} mm Hg. The instrument is a Philips-type gauge*, specifically engineered for constant production monitoring of high vacuum pressures. It eliminates annoyance and costs of burned-out gauges, activation of poisoned cathodes, heating of grids, etc. Even in steady, day-after-day use, it requires no attention other than a chemical cleaning about twice a year.

Cold Cathode Emitter

The Type L-3032 gauge was developed within Litton Engineering Laboratories to facilitate our own manufacturing of vacuum tubes. It utilizes crossed electric and magnetic fields which enhance collision probability in a small volume so that a cold cathode emitter can be used. Thus operation, even at atmospheric pressure, will not damage the tube. (In normal use, the tube is not operated until black-out of the vacuum system is reached. Good relative pressure readings are available throughout the range of 10^{-4} to 10^{-7} mm Hg.) Type L-3032 tubes have been tested during the past two years on Litton vacuum tube production lines. They are now installed on every exhaust station in our plant.

Monel-Encased

The Ion Gauge Tube is composed of a monel-encased interaction space with the case near ground potential. A nichrome wire anode at 2,500 volts is centered within the case. An outgassing 6.3 volt heater is mounted near the

Type L-3032 Ionization Gauge (above) with adapter for glass systems

monel case, but insulated from it. A ¾" diameter kovar tube, insulated from the monel case by a glass seal, is supplied for connection to the vacuum line. The magnetic field is provided by permanent magnets mounted in a sheet steel shell. This shell also serves as a return magnetic path, connection block, package envelope and oven for the outgassing heater. Electrical connections are made to binding posts on the steel case. The tube weighs but 22 oz. and measures 7" x 5" x 3½". $60.00.

Model 4301 Ionization Gauge Amplifier

This amplifier is a companion instrument for Type L-3032 Ionization Gauge Tube. It includes a range switch for measuring from 10^{-4} to 10^{-8} mm Hg., a special leak-check control providing full scale deflection at any pressure, a zero adjustment control, and a gauge heater supply switch.

Model 4301 Amplifier

It consists of a high voltage rf power supply, a vacuum tube voltmeter circuit with current-sampling resistors, a 6.3-volt transformer (to provide current for the outgassing heater in Type L-3032 Ionization Gauge Tube) and a self-regulating low voltage power supply providing wide input voltage variation without affecting performance. Electrical connection is by cable with banana plugs to Type L-3032 Ion Gauge. Power supply requirements are 110 volts, 60 cps. The instrument measures 10" x 8" x 8". Weight is 17½ lbs. $255.00.

*Licensed under Philips Laboratories, Inc. Patent No. 2197079 Data subject to change without notice. Prices f.o.b. factory.

2743

LITTON ENGINEERING LABORATORIES

1049 BRITTAN AVENUE • SAN CARLOS 2, CALIFORNIA • U. S. A.

Manufacturers of glassworking lathes and attachments, vertical sealing machines, pumps, spotwelders and timers, burners, Molube, bell jars, hydrogen furnaces, thermopiles, ion gauges and amplifiers, U-lines, water loads, dielectric stubs, phase changers.



economical PHENOLITE low-loss block insulators... on famous *CHANNEL MASTER* TV antenna

Channel Master's famous Futuramic antenna combines Broad Band TV coverage with the high gain and directivity of the Yagi. Utilizing Phenolite low-loss block insulators—the Futuramic is the one antenna that solves *today's* reception problem, yet will also receive *tomorrow's* VHF channels.

This use of Phenolite is typical of its countless applications in the electrical field. Phenolite, about one-half the weight of aluminum, is the perfect insulating material for high and low voltage applications.

It possesses an unusual combination of properties. Phenolite has great mechanical strength and high resistance to moisture; ready machinability; is unaffected by solvents and oils. It can be easily punched, sawed and sheared. Tough and with high impact strength, Phenolite is one of the strongest materials per unit weight known.

Available in various grades and colors; in sheets, rods, tubes, and special shapes. Write for literature and engineering information—

NATIONAL VULCANIZED FIBRE CO.

Wilmington Offices in Delaware Principal Cities

Since 1873

Channel Master's two dipole system—connected by Phenolite low-loss block insulated harness—makes possible the high gain and directivity of the Futuramic broad band Yagi antennas.

Illustrated: Futuramic Model 1173 broad band Yagi antenna covering channels 7-13, Channel Master Corporation, Ellenville, New York.



Rely on **PHELPS DODGE** *for Magnet Wire and*

THE RIGHT WIRE TRANSFORMER,



First for Lasting Quality—from Mine to Market!

Application "Know-How"—

FOR YOUR MOTOR OR COIL!

- Vast and varied experience in every field of electrical and electronic manufacture.
- Unexcelled research, manufacturing and quality control facilities—most complete and up-to-date line of magnet wire in the industry.
- Practical help in selecting correct size, shape and insulation to meet exact design specifications.



PHELPS DODGE COPPER PRODUCTS CORPORATION

INCA MANUFACTURING DIVISION

FORT WAYNE, INDIANA

Drop that Soldering

Revolutionary new method wraps connections so tightly that soldering is unnecessary

Here is a method that produces electrical connections more reliable than the most skillfully soldered connections . . . in a fraction of the time . . . at a fraction of the cost. Operator training takes only minutes instead of days.

By replacing hand operations with pneumatic or electric Wire-Wrap Tools, you get consistently uniform connections all through the day. Rejects are greatly reduced . . . inspection becomes simple . . . production costs are cut.

Investigate this revolutionary new process—write for Bulletin No. 11, today.



1 INSERT WIRE



2 ZIP... AND

Wire-Wrap Tools

are now available from Keller—
the original manufacturer

Iron, Sister!!...

THIS NEW Wire-Wrap Tool

MAKES SOLDERLESS CONNECTIONS

...in half the time!

Manufactured under patent license agreement with Western Electric Company Incorporated



3 IT'S FASTENED

KELLER

Wire-Wrap

TOOLS

Wire-Wrap Division

KELLER TOOL CO.

Grand Haven, Michigan

AIR TOOL WEIGHS ONLY ONE POUND

"SPECIAL transformers?

. . . Oh, they're no problem with us. We let Electronic Transformer Company worry about 'em."

That's right. When we tackle those tricky special transformer jobs we relieve our customers of the complete headache. We're prepared to do *your* worrying, too, because custom-designing, custom-building transformers is our sole business. Government and industrial companies throughout the country have depended upon us since 1938.

Behind ETC transformer quality are a thoroughly trained engineering staff and the resources of our fully equipped laboratory and production department. We carry the ball from the circuitry stage right down the line to pilot and production runs.

What have *you* on the board or in your mind? Please telephone or write us without obligation.

ELECTRONIC TRANSFORMER COMPANY

Transformers, Reactors and Filters Engineered to your Needs

209 WEST 25th STREET • NEW YORK 1, N. Y.

Telephone: WAtkins 4-0880

ETC

SINCE 1938

The Only All Band

10 mc to 21,000 mc

Direct Reading Single Control

SPECTRUM ANALYZER Model LSA



The Model LSA provides direct means of rapid, accurate measurement of spectral display of r. f. signals from 10 to 21,000 MCS

Saves Engineering Manhours

The Model LSA Spectrum Analyzer is Polarad's answer to rising engineering costs when high performance and economy are essential.

This unique engineering tool helps get results faster with fewer personnel and in less space. Because of its ultra simplicity, tremendous frequency coverage and remarkable instrumentation the Model LSA can handle almost any problem in the radio spectrum (10 mc to 21,000 mc) with the greatest of ease, reliability and accuracy.

How The Model LSA Cuts Production Costs

In the factory, Model LSA's simplicity of operation, direct reading and "GO-NO-GO" electronic display speeds production and cuts costs. Uniform quality and high performance of your complete equipment is assured by checking it with a Polarad Spectrum Analyzer.

Expensive personnel training programs are eliminated by the Model LSA, which often actually takes the place of the microwave specialist and frees engineers for other work. For further details contact your nearest Polarad representative or write direct to us.

FEATURES:

Frequency Range 10 mc-21,000 mc; 4 tuning heads
Accuracy Frequency Calibration—1%
Spectrum Display variable from 250 kc to 25 mc
Frequency Marker for measuring frequency differences of 0-25 mc
Broad Band R.F. Attenuators 10 mc-12,000 mc
Automatic Voltage selector for each tuning head
Single Dial Control
Direct Frequency Reading
Spectrum Displayed on 5" cathode ray tube

USES:

Examine pulse spectrum of magnetrons and klystrons
Measure noise and interference spectrum
Act as broad band receiver from 10 mc to 21,000 mc
Observe and measure harmonic frequency differences
Measure band width of microwave cavities
Calibrate microwave oscillators and preselectors

More Megacycles Per Dollar Than Any Other Instrument

Polarad Electronics Corporation

Polarad Electronics Corporation

100 Metropolitan Avenue, Brooklyn 11, N. Y.

REPRESENTATIVES: Albuquerque • Atlanta • Boston • Chicago • Cleveland • Fort Worth • Kansas City • Los Angeles • New York • Ontario • Philadelphia • San Francisco • Seattle • Syracuse
WASHINGTON, D. C.

ALLIED CONTROL'S NE

- ✓ SIZE CUT 66%
- ✓ WEIGHT CUT 48%
- ✓ RELIABILITY DOUBLED
- ✓ WRIGHT FIELD APPROVED

Designed to withstand a shock of 50G, these new Allied Control double-throw miniature relays were developed to meet the rigid requirements of U.S.A.F. Specifications MIL-R-5757A.

Known as the Allied MH series, this new line of relays consists of the 6-pole MH-18, the 4-pole MH-12, and the 2-pole MH-6. Contacts are rated at 2 amps resistive or 1 amp inductive at 28 volts D. C.

The high performance of these relays has been achieved in an extremely compact, unitized construction and parallels the most recent advances in airborne equipment design. The "actual size" photographs shown above highlight the 66% savings in overall size, the 48% savings in weight and the 30% reduction in chassis area.

For detailed specifications and drawings of these new relays, contact your local Allied Control Representative or write us for Bulletin 1002.

Want more information? Use post card on last page.

W 50 G MINIATURE RELAY

APPROVED MIL-R-5757A

SIX DIFFERENT MOUNTINGS



1. Standard Mounting
2. Flush Mounting—2 Studs at 5/8" Centers
3. Thru-Chassis Mounting—Terminals Down
4. Plug-In Mounting With Socket
5. Thru-Chassis Mounting—Terminal Up
6. Flush Ring Mounting

FEATURES

Wide Ambient Temperature Range: *55°C to 85°C standard—65°C to 125°C MHB-type*
Vibration Resistant: *15G's vibration to 500 cycles* • **Operating Shock:** *no contact chatter to over 50G's*
High Altitude: *seal-tested to 70,000 feet*
Dependable Operation: *life expectancy of over 1 million operations at rated load*
High Speed: *operate-to-make time under 8 ms.*
release-to-make time under 4 ms.
release-to-break time under 2 ms.

ALLIED CONTROL COMPANY, INC.
2 EAST END AVENUE, NEW YORK 21, N. Y.

Want more information? Use post card on last page.



SPECIFICATIONS

Tubes Cooled
4X150A, 4X150G
5508 and 6161

Altitude
Up to 50,000'

Fan Model
Joy Axivane
AV-3.5-2.75-120D

Size
3½" diameter

Weight
5 lbs.

Duty
60 CFM @ 5" WG

Motor
27V DC—4.7 Amps.

Only a JOY AXIVANE® FAN can handle this Electronic Tube cooling job at altitudes up to 50,000 feet

Cooling the above-specified tubes in airborne applications is a critical problem because of the extremely light air. The difficulty is particularly severe at elevations of 40,000 or 50,000 feet.

An extensive series of tests were recently initiated in an attempt to determine an effective cooling process. The tubes and sockets were mounted in pairs in a special cabinet designed to equalize the air distribution for each tube. The problem was to discover a method of heat dissipation that would hold the temperature of the glass-to-metal seals below the design operating level.

Of all the blowers tested, only this Joy AXIVANE fan was able to meet the rigid specifications. The tubes were cooled with 25°C air at an elevation of 50,000 feet, easily surpassing all requirements.

This is just one of an extensive line of AXIVANE fans specially designed for economical efficiency in cooling electronic equipment. All are built of aluminum and magnesium for light weight, sturdily constructed for maximum resistance to shock and vibration, and feature the space-saving compactness inherent in vaneaxial design.

Each fan can be modified to fit individual requirements for cooling all types of electronic equipment under any conditions. Let us help solve *your* problem. ● *Joy Manufacturing Company, Oliver Building, Pittsburgh 22, Pa.* In Canada: *Joy Manufacturing Company (Canada) Limited, Galt, Ontario.*

Consult a Joy Engineer

JOY

WORLD'S LARGEST MANUFACTURER OF VANE-AXIAL TYPE FANS

W&D 1-4840

Now

PRECISION ENGINEERING
CUSTOM MANUFACTURING

TEST MICROWAVE CRYSTALS

Easily – Accurately

FACTS

- Accuracy

Relative Noise Figure:	1.0 db max. error 0.3 db mean error
Relative Sensitivity:	2.0 db max. error 0.6 db mean error
Pair Matching:	Sufficient to assure 20-db suppression of local oscillator noise
Conversion Loss:	0.9 db max. error 0.3 db mean error
Noise Temperature:	0.7 max. error 0.3 mean error

- Accepts ceramic cartridge and coaxial types of both normal and reversed polarities.
- Remote test jack permits testing crystals without removing them from receiver.
- Portable
- Self-contained

PRICE $97.00

MEASURES

- Relative Noise Figure
- Relative Sensitivity
- Match of Crystal Pairs
- Conversion Loss
- Noise Temperature

APPLICATIONS

- As field test set to determine receiver sensitivity, as determined by crystal quality.
- As laboratory test set to choose representative and extreme crystals from a group.
- As incoming inspection test set to cull crystals that arrive in damaged condition.

Airborne Instruments Laboratory

INCORPORATED

160 OLD COUNTRY ROAD MINEOLA, N.Y.

Why a Slide Rule Adds



In a mechanical sense, the slide rule merely adds and subtracts quantities. How these simple operations can be performed mechanically may be seen from the illustration above, which shows the addition of 2 and 3 by means of a pair of dividers applied to an ordinary 6-inch rule. Even many electronic calculators work basically on this principle.



With a different system of calibrations on the scale, if appropriate meanings are assigned to them, more difficult problems may be solved in the same way. An example of this is seen above where a pair of dividers is shown adding 2 and 3 on a logarithmic scale and obtaining the answer 6. Advantage is taken of the fact that the multiplication of numbers may be accomplished by the addition of their logarithms.



A handier method, which begins to approach the usefulness of a slide rule, is to place two similar logarithmic scales together. Seen above is the simple setting in which 2 is shown being multiplied by 3. Observing the illustration it can be seen that the same setting also multiplies 2 by 2 and 4. Without changing the setting, the device shows the corresponding operations in division.



to Multiply

The Right Angle



Problems in plane trigonometry require only appropriate logarithmic scales, calibrated to read in degrees so that operations can be performed on the functions of angles. Two scales of this kind are generally used: one for the sines of angles and the other for tangents. Above is seen a setting for finding $P = \frac{16 \text{ Sin } 68°}{\text{Sin } 27°}$.



Problems of greater complexity, involving higher powers and roots of numbers, including fractional and negative powers and roots, can also be made as easy as $2 + 3$ by means of appropriate logarithmic scales. Known as log log scales, they are calibrated to read in logarithms of logarithms. Above is seen a setting for finding $P = 1.15^{1.7}$.

The slide rule has been called the symbol of the engineer. The symbol that distinguishes the slide rule itself for leadership in design and workmanship is the K&E trade mark or the name KEUFFEL & ESSER CO.

Pioneers in the manufacture of slide rules in America, K&E have always been in the forefront with new ideas and improvements. The most recent example is the slide rule of today, the K&E Log Log Duplex Decitrig*, designed on the fundamental and simple principle of referring all its scales to the basic C-D scales. This enables problems involving arithmetic, trigonometric and exponential functions to be readily solved without reading any but the final answer.

Ask your K&E Distributor or Branch for full information about K&E Slide Rules.



If you'd like l-o-n-g mileage without re-sharpening, get a PARAGON* RED TIP ruling pen. They are tipped with tungsten carbide alloy butt-welded to stainless steel blades. Ideal for use on aluminum, glass cloth and other abrasive surfaces as well as on regular paper or cloth. Identify it by the red tip at the end of the handle.

A good way to make life easier is to give your drawing board a glass-smooth, non-glare working surface with a covering of LAMINENE†. This drawing board backing material is washable, hard enough to minimize pencil scoring, but yielding enough for pencil lines to take well. Comes either white or green, in rolls.

*Trade Mark ®
†Trade Mark

K+E

KEUFFEL & ESSER CO.

Drafting, Reproduction, Surveying Equipment and Materials, Slide Rules, Measuring Tapes

NEW YORK • HOBOKEN, N. J.
CHICAGO • ST. LOUIS • DETROIT
SAN FRANCISCO • LOS ANGELES • MONTREAL

PARTNERS IN CREATING

Want more information? Use post card on last page.

Meet the mechanical marvel behind

"PROJECT TINKERTOY"

'Project Tinkertoy'
Electronics Assembly Line Developed by U. S.
NAVY UNVEILS 'PUSHBUTTON' PLANT IN EAST
Electronic Circuits Are Its Products
BY LLOYD NORMAN
'Tinkertoy,' an Automatic System, Speeds Production in Electronics
By WALDEMAR KAEMPFFERT

This tiny electronic device is the secret behind that amazing U. S. Navy and National Bureau of Standards development you've been reading about . . .

Hush-hush for many months, "Project Tinkertoy" can now be revealed as one of the most remarkable developments in modern electronics . . . a Technique that will very probably revolutionize manufacturing methods in the electronics and allied fields. Radio, television, aviation, computing, and communications are five of the fields where it is immediately applicable . . . where its ability to produce a wide variety of electronic circuit combinations will produce tremendous savings in materials, time and labor. For further information on its possibilities, applications . . .

Contact Engineering Department

WILLYS ELECTRONICS DIVISION

OF WILLYS MOTORS, INC.
Toledo, Ohio Arlington, Va.

SYNTHANE—out of sight, but in the picture

Whenever you turn on television you are using a little-seen, but essential, material called Synthane.

Synthane is a laminated plastic of multiple virtues, which recommend it for many jobs in television.

Synthane is an excellent insulator, laminable with metal, hence, a good base for space-reducing "printed" circuits. Synthane is notable for low power factor, low moisture absorption, and ease of fabrication, three properties desirable for radio and television insulation. Synthane plays a supporting part in many behind-the-screen and behind-the-camera applications.

Synthane is also light in weight, strong, vibration absorbing, chemically resistant, high in dielectric strength, dimensionally stable, heat resistant to about 300°F.

There may be a place for Synthane in your product. To find out more about the possibilities of Synthane for your purpose, write for the complete Synthane Catalog. Synthane Corporation, 17 River Road, Oaks, Pennsylvania.

Synthane laminated plastics are produced under heat and pressure from laminations of resin-impregnated materials such as paper, fabric, glass cloth, asbestos, etc. Synthane plastics are available in sheets, rods, tubes, and fabricated or molded parts. Each of the many Synthane grades has a combination of useful properties.

Synthane in Television . . .

A-Television camera parts

B-Television receiver printed circuits—metal foil on Synthane sheets

C-Channel selector switch insulation

Synthane-one of industry's unseen essentials

SYNTHANE S LAMINATED PLASTICS

Why do so companies make

For one thing, it's *easy* to make an ordinary relay. Requirements are not rigid. Little equipment is needed. You can even *buy* the component parts in a pinch. Dozens of companies do a good job of making these relays, as long as the service requirements are not too severe.

But when you need top reliability, when you need relays that will withstand temperature extremes, tremendous shock loads, moisture, continuous service—come to an expert to get the kind of relay performance you need.

Union Switch & Signal has been making relays for over 70 years, most of them in vital railroad signaling service. Many of them operate continuously, yet remain unattended for years. In fact, we regularly encounter "Union" relays that have been in service for over 40 years. And they are still in good operating condition.

This vast relay engineering skill has been used to produce the "Union" type M miniature relay. Hermetically sealed, weighing only 3½ ounces, this 26.5 v.d.c. relay meets all requirements of Military Specifications MIL-R-5757 A & B.

"Union" type M relays are available in quantity *now*—in either 6-pole or 4-pole doublethrow models. Write for more information.

GENERAL APPARATUS SALES

UNION SWITCH & SIGNAL

DIVISION OF WESTINGHOUSE AIR BRAKE COMPANY

PITTSBURGH 18 PENNSYLVANIA

NEW YORK CHICAGO ST. LOUIS SAN FRANCISCO

many relays?

TYPICAL PERFORMANCE DATA

Service Temperature	-65°C to 125°C	-55°C to 85°C
Style FM (6-pole)	303125	303085
Coil Resistance	325 ohms	325 ohms
Nominal Voltage	26.5	26.5
Max. Pull-In Voltage at Max. Rated Temperature	18	18
Max. Drop-Out Voltage at Max. Rated Temperature	13	13
Service	Continuous	
Shock	40 G's for 10 milliseconds	
Vibration	10 to 55 cycles per sec.— 0.060 total excursion	
Life Expectancy	1,000,000 operations minimum	
Contact Rating	2 amps. at 26.5 Volts— Resistive Load	
Breakdown Voltage at Sea Level	1000 volts a.c. between case and contacts or coil	

General Apparatus Sales
Union Switch & Signal Division
Westinghouse Air Brake Company
Pittsburgh 18, Pa.

Please send additional information on "Union" type M relays.

Name ..... Title.....

Company .....

Address .....

City, Zone & State .....

An ordinary house key, brazed to the tool holder of the Cavitron, cuts quickly and easily into a glass paperweight. The tool vibrates 1,620,000 times a minute and uses a boron carbide abrasive in solution to remove the particles of glass without cracking it.

How Magnetostriction was harnessed

. . . to give industry a new tool

Remember those magnetostriction experiments in the physics lab?

You learned what happened when a ferro-magnetic material was placed in a magnetic field.

But what good was it?

Your instructor probably told you it was pretty much a laboratory curiosity.

And except for use in undersea sounding devices, it remained so until recent years.

Now scientists are harnessing it in many ways. One of the most interesting applications is in this ultrasonic machine tool.

Called the Cavitron, this tool vibrates 1,620,000 times a minute and, with the help of an abrasive solution, easily machines materials as hard as tungsten carbide.

The vibrations drive the abrasive against the material which is to be cut and form the desired shape in it.

Putting magnetostriction to work in this way wasn't easy. Before the inventor perfected a commercial model, he experimented for twelve years.

He worked with a number of materials, searching for the magnetostrictive qualities he needed for the transducer. He found them in "A" Nickel.

Then he had to find an alloy for the tool holder with suitable high strength and acoustical properties. Most materials he tried heated up rapidly and cracked at stress points. Again, he discovered the very qualities he needed in another Inco Nickel Alloy — Monel®.

The inventor of the Cavitron found Inco ready to help in supplying information on magnetostriction, fabrication and metal stress at all times.

That same service is available to you. Call on us for help in solving your problems. And write for your revised copy of "Magnetostriction" and the booklet "Inco Nickel Alloys for Electronic Uses."

Consult your regular supplier of Inco Nickel Alloy forms for latest information regarding their availability. Remember, too — it always helps to anticipate your requirements well in advance.

THE INTERNATIONAL NICKEL COMPANY, INC.
67 Wall Street New York 5, N. Y.

Inco Nickel Alloys

MONEL® • "R"® MONEL • "K"® MONEL • "KR"® MONEL • "S"® MONEL
INCONEL® • INCONEL "X"® • INCONEL "W"® • INCOLOY®
NIMONIC® ALLOYS • NICKEL • LOW CARBON NICKEL • DURANICKEL®

TUNG-SOL

6U8

miniature

{ triode-
pentode

PROVIDES NEW FLEXIBILITY IN TV RECEIVER CIRCUIT DESIGN



see other side for additional informatio

TUNG-SOL

6U8



miniature

triode-pentode

Tung-Sol Designed and Developed

- ✓ ***Completely independent sections***
- ✓ ***Versatility in circuit application***
- ✓ ***Improved circuit performance***

This tube has two electrically independent sections—a triode and a pentode and is intended as a local oscillator mixer for FM and TV receivers. Each section is adequately shielded, and both are capable of exceptionally good performance at the higher frequencies.

Because the two sections are completely independent, a high degree of flexibility of circuit design is available—especially valuable in TV tuner oscillator use. Performance of the 6U8 triode at low voltages is superior to that of many types previously used for this service. It has sufficient reserve emission to operate efficiently under widely varying supply voltage conditions.

The pentode provides excellent gain with low local oscillator voltage injection resulting in low oscillator radiation from TV receivers. Use of the pentode section as the mixer permits the high (40 m. c.) I. F. so desirable to reduce interference and increase stability.

The construction and characteristics of the 6U8 provide designers with extremely desirable flexibility in combining circuit functions. The pentode section of the tube may be used as an I. F. amplifier, video amplifier, sound limiter or synchronizing separator. The triode performs satisfactorily as a horizontal or vertical oscillator, or sync clipper.

Wherever there is need for a triode and a pentode in a receiver, they can be combined in the 6U8.

MECHANICAL DATA

Coated unipotential cathodes—2			
Outline drawing	RTMA 6—2	Bulb	T—6-1/2
Base	RTMA E9—1	Miniature button	9-pin
Maximum diameter			7/8"
Maximum overall length			2-3/16"
Maximum seated height			1-15/16"
Base pin connections		RTMA basing	9 AE
Pin 1—triode plate		Pin 6—pentode plate	
Pin 2—pentode grid #1		Pin 7—pentode cathode grid #3, shield	
Pin 3—pentode grid #2		Pin 8—triode cathode	
Pin 4—heater		Pin 9—triode grid	
Pin 5—heater			
Mounting position			Any

ELECTRICAL DATA

Interelectrode Capacitances	With Shield #315	Without Shield	
Pentode grid #1 to pentode plate	0.006	0.010 max.	μμf.
Pentode input	5.0	5.0	μμf.
Pentode output	3.5	2.6	μμf.
Triode grid to triode plate	1.8	1.8	μμf.
Triode grid to cathode	2.5	2.5	μμf.
Triode plate to cathode	1.0	0.4	μμf.
Cathode to heater (either section) approx.	3.0	3.0	μμf.

ELECTRICAL DATA

Ratings

Heater voltage (ac or dc)	6.3	VOLTS
Maximum heater-cathode voltage	90.0	VOLTS
Maximum plate voltage (pentode)	300.0	VOLTS
Maximum plate voltage (triode)	300.0	VOLTS
Maximum grid #2 supply voltage	300.0	VOLTS
Maximum plate dissipation (pentode)	2.8	WATTS
Maximum grid #2 dissipation	0.5	WATTS
Maximum positive dc grid #1 voltage	0	VOLTS
Maximum positive dc grid voltage (triode)	0	VOLTS
Maximum plate dissipation (triode)	2.5	WATTS

Typical Operating Conditions and Characteristics

	Triode	Pentode	
Heater voltage	6.3		VOLTS
Heater current	450		MA.
Plate voltage	150	250	VOLTS
Grid #2 voltage	...	110	VOLTS
Cathode resistor	56	68	OHMS
Transconductance	8500	5200	μMHOS
Grid #1 voltage (approx.) for Ib=10 ua.	-12	-10	VOLTS
Plate current	18	10	MA.
Grid #2 current	...	3.5	MA.
Plate resistance (approx.)	.005	0.40	MEG.
Amplification factor	40	...	

TUNG-SOL
ELECTRON TUBES

The TUNG-SOL engineering which has produced the 6U8 is constantly at work on a multitude of special electron tube developments for industry. Many exceptionally efficient general and special purpose tubes have resulted. Information about these and other types is available on request to TUNG-SOL Commercial Engineering Department.

TUNG-SOL ELECTRIC INC., NEWARK 4, NEW JERSEY

SALES OFFICES: ATLANTA, CHICAGO, COLUMBUS, CULVER CITY (LOS ANGELES), DALLAS, DENVER, DETROIT, NEWARK, SEATTLE

TUNG-SOL MAKES ALL-GLASS SEALED BEAM LAMPS, MINIATURE LAMPS, SIGNAL FLASHERS, PICTURE TUBES, RADIO, TV AND SPECIAL PURPOSE ELECTRON TUBES AND SEMICONDUCTOR PRODUCTS

it makes SENSE to SAVE DOLLARS with Heldor

IF YOU manufacture electronic or nuclear components requiring the use of hermetic-seal terminals and cans, Heldor's *proven* quality-control volume production methods makes possible substantial dollar savings for you.

It will pay you to get the facts about Heldor's cans, hermetic-seal bushings and complete assemblies made to meet MIL-T-27 or commercial specifications. Send your specifications or prints today for a "quote" that tells its own money-saving story.

HERMETIC SEAL BUSHINGS

CANS & COVERS



COMPLETE ASSEMBLY SERVICE

HELDOR MANUFACTURING CORPORATION

HELDOR BUSHING & TERMINAL CO., INC.

238 Lewis Street • Paterson, N. J.

fast starts! with an assist from SELETRON



Seletron
SELENIUM RECTIFIERS

Here's why Heyer Industries chose and *reorders* SELETRON for their new portable fast chargers

There's nothing like a good charge to wake up your car battery and Heyer Industries, Inc., Belleville, N.J., find SELETRON Selenium Rectifiers assure efficient and certain action in their "Safe-Fast" portable battery chargers.

Purchasing Agent Walter Mack says, "The selenium rectifier is a major component in our product, and extensive field tests show we are safe on all counts with SELETRON. Your rectifiers give excellent performance under heavy current load."

Arduous duty in fast chargers is only one of many uses for versatile SELETRON Selenium Rectifiers. There are innumerable applications. Besides radio, TV and other audio-visual equipment normally requiring miniatures, they are components in industrial electronic circuits calling for big power stacks of all sizes.

Our engineers can guide you to a solution of your problem in rectification. Why not outline it to us today, and study our catalog in Sweet's Product Design File. *We also manufacture germanium diodes and transistors.*

For complete dependability Heyer's fast charger utilizes one Model 6T0730 SELETRON Selenium rectifier.

Seletron and Germanium Division

RADIO RECEPTOR COMPANY, Inc.

Since 1922 in Radio and Electronics

SALES OFFICE: 251 WEST 19th STREET, NEW YORK 11 • FACTORIES IN BROOKLYN, N. Y.

TAYLOR ***Commercial Grade Vulcanized Fibre***
is tough, lightweight, abrasion resistant . . .
excellent for bending, punching, stamping and forming . . .
resistant to organic solvents, oil and gasoline . . .
has excellent electrical characteristics.

Want to make something of it?

Make it into insulating plates, upset washers, arc barriers, terminal blocks, switch and appliance insulation, cases, face plates for golf clubs . . . or any other electrical or mechanical component that can benefit from the unique properties of this versatile material.

Make it in red, gray, black, or special colors.

Make it from sheets or rolls with these specifications:



SPECIFICATIONS

Thickness Range:	.005" to 1"
Finish:	Pressed and calendered
Punching:	To 3/16" thick
Sheet Size:	56" x 90"
Roll Width:	56" for thicknesses of .005" through .060". Coils to 3/16" for thicknesses of .005" through .090".

PROPERTIES

Mechanical	
Flexural Strength	
(Lengthwise)	14000 psi min.
(Crosswise)	12000 psi min.
Tensile Strength	
(Lengthwise)	7500 psi min.
(Crosswise)	5500 psi min.
Compressive Strength	
(Flatwise)	20000 psi min.
Izod Impact Strength	
(Lengthwise)	3.5 Ft.-Lbs./inch
(Crosswise)	2.9 Ft.-Lbs./inch
Electrical	
Dielectric Strength	
(1/32" thick)	250 min.
Short Time Test	
(1/8" thick)	175 min.
Arc resistance, seconds	100

Make it from turned rods. Diameters from 1/8" to 1" with ground or buffed finish.

Make it easy for yourself when you're buying vulcanized fibre. Call your Taylor engineer . . . he will be glad to work with you . . . help select the correct grades to fit your needs —Commercial, Bone, Super White, Abrasive and Built-up. Also ask him for samples of Taylor Laminated Plastics . . . *Phenol, Silicone and Melamine Laminates* . . . suited for a variety of your product requirements.

Taylor Fibre Company, Norristown, Pennsylvania — La Verne, Calif.

TAYLOR
Laminated Plastics
Vulcanized Fibre

Want more information? Use post card on last page.

FASTEST THING IN FASTENINGS®

alliance TENNA-ROTOR "TURNS" TO TINNERMAN

...BEAMS-IN 50% ASSEMBLY SAVINGS!

Engineers at Alliance Manufacturing Company, Alliance, Ohio, knew from experience how SPEED NUT brand fasteners change fastening problems into production savings. That's why they "turned" to Tinnerman for a clear savings picture in designing the Tenna-Rotor! Push-On SPEED NUTS were selected right from the Tinnerman catalog for tremendous time and engineering savings at the design stage! 16 Push-Ons, zipped over integrally molded studs, attach the electronic mechanism to the plastic control panel and box! They eliminated metal inserts, nuts, and lockwashers — reduced materials handling — stepped-up production, and netted a 50% savings in assembly costs.

A call will bring your Tinnerman representative with complete, detailed information to help solve your fastening problems . . . and maybe find savings like this!

PUSH-ON SPEED NUTS®



. . . zip over integral studs, rivets, tubing, or other unthreaded parts; bite into smoothest, hardest surfaces — lock with firm spring tension on metal, plastic or wood. Eliminate costly inserts in plastics; save machining of die castings!

Write today for your copy of SPEED NUT "Savings Stories" a booklet of amazing examples of Tinnerman savings to industry:

TINNERMAN PRODUCTS, INC., Dept. 12, Box 6688, Cleveland 1, Ohio. *In Canada:* Dominion Fasteners, Ltd., Hamilton, Ontario. *In Great Britain:* Simmonds Aerocessories, Ltd., Treforest, Wales. *In France:* Aerocessoires Simmonds, S. A. — 7 rue Henri Barbusse, Levallois (Seine).



TINNERMAN Speed Nuts®



MORE THAN 8000 SHAPES AND SIZES

WIDE RANGE FAST-PULSE GENERATOR

PG-200A
Pulse Generator
PGA-210
Range Extenders



SPECIFICATIONS

PULSE POWER

- Amplitude 100 volts open circuit
- Continuously variable over a range of -10 db
- 50 db attenuation in steps of approx. 10 db
- Driving impedance 50 ohms or less
- Max. average current (50 ohms load) 0.1 amp. for pos. pulses, 0.07 amp. for neg. pulses
- Max. recurrence rate at least 20,000 pps
- Max. duty cycle 50%, min. pulse interval (trailing edge to leading edge) approx. 40 μs

PULSE WAVEFORM

- Rise and decay times 0.03 μs or less (10% to 90% amplitude)
- Crest and base line overshoots and ripple less than 5% of average pulse amplitude
- Duration calibrated 0.1 to 50 μs, accuracy below 5000 pps within 5% or 0.1 μs whichever is greater, accuracy above 5000 pps subject to additional 0.3 μs error, min. pulse width less than 0.05 μs (50% amplitude)

PULSE POSITION

- Delay after external sync signal fixed at approx. 10 μs or adjustable from approx. 20 to 70 μs
- Advance or delay with respect to sync out trigger calibrated 0.1 to 50 μs, accuracy below 5000 pps within 5% or 0.1 μs whichever is greater, accuracy above 5000 pps subject to additional 0.3 μs error

features

- DURATION AND POSITION .05 TO 1000 μs
- RISE AND DECAY TIMES CONSTANT .03 μs
- SINGLE PULSES TO 20,000 PER SECOND
- 100 VOLTS, 50 OHMS DRIVING IMPEDANCE
- CALIBRATED WIDTH, POSITION AND RATE
- TRIGGER OR SINE WAVE SYNCHRONIZATION
- NEGLIGIBLE INTERACTION OF CONTROLS

RANGE EXTENDER

- 19 additional time increments of 50 μs each
- Continuous calibrated coverage from 0.1 to 1000 μs, accuracy within 5%
- Plugs into top of Pulse Generator directly above position or duration control

SYNCHRONIZATION

- Externally by almost any 5 volt waveform from essentially 0 to 20,000 per sec.
- Internal single pulses, power line freq. or adjustable from 20 to 20,000 pps
- Recurrence rate meter, accuracy within 5%
- Sync out trigger 50 volts, 1 μs duration

TELETRONICS LABORATORY INC.

54 KINKEL STREET, WESTBURY, LONG ISLAND, NEW YORK

"O.K. But what's your price for performance?"

Here's a purchasing agent buying resistors on a price basis. But doing it the *right* way.

Some day we may even be able to quote resistor prices in terms of performance—so many cents per thousand hours of trouble-free operation. Then we'll be able to tell you exactly how much *less* Ward Leonard resistors really cost than the so-called "bargain" resistors now on the market.

But until then, remember, it's *performance* you pay for when you're buying resistors. There's a lot more than just a few cents difference in the performance you'll get from the two resistors above.

The one made by Ward Leonard will perform at its rated value for the life of the product it goes into. There's a chance the so-called "bargain" resistor will too. But you can't afford to take *any* chances on your product's failure—even once out of a hundred times. Not when you consider the actual cost of such failure, figured in terms of returned merchandise, replacement cost, customer and dealer dissatisfaction.

That's why, even on a price basis, the accuracy, dependability and uniformity of Ward Leonard resistors make them far better buys than any of the questionable bargains you'll find on the market. Send for *new* Resistor Catalog No. 15. Ward Leonard Electric Co., 31 South Street, Mount Vernon, N. Y.

3•18

WARD LEONARD

WARD LEONARD ELECTRIC COMPANY

MOUNT VERNON, NEW YORK

Result-Engineered Controls Since 1892

This check list shows you how to get the most for your money in terms of resistor performance

COATING. Vitrohm enamel coating of all Ward Leonard resistors provides a complete hermetic seal highly resistant to shock, high humidity, extreme temperatures, acids, alkalies, and electrolysis. Unlike most resistor manufacturers, we manufacture our own vitreous enamel.





RESISTANCE WIRE. The resistance wire is drawn to Ward Leonard's own specifications for each particular resistor type. It is capable of withstanding heavy overloads, has a uniformly low coefficient of resistivity. Many of the "bargain" resistors are wound with resistance wire of ordinary grade.



RESISTOR CORE. Ward Leonard's own manufactured cores upon which the resistance elements are wound consist of a perfectly cylindrical ceramic body of high density, low porosity, and high dielectric strength, with a thermal coefficient of expansion correlated to the expansion of the enamel.



TERMINALS. In Ward Leonard resistors, special alloy terminals insure proper expansion and adherence to the enamel, are designed to provide strong anchorage. Every wire-to-terminal junction is joined mechanically first, then specially silver-brazed for lasting contact.

Ward Leonard's complete engineering textbook, "Handbook of Power Resistors," $3. per copy.

Want more information? Use post card on last page.

A NEW CTS FAMILY

Of Variable Resistors



FOR PRINTED CIRCUIT APPLICATIONS

Note these unique design features:

- Protection against breaking during handling is achieved by recessing each blade-type terminal in a slot in the bakelite base of the control.
- Valuable mounting space is conserved on the printed circuit panel by placing the terminals close in to the mounting bushing.
- Adequate clearance for circuit paths is provided by ample spacing between terminals.
- Available in miniaturized ¾" diameter (U70) and in ⁹⁄₁₆" diameter (U45, GC-U45, WT-U45).

For your printed circuit applications, CTS offers consultation without obligation.

SLOTS WILL RECEIVE STANDARD .094 x 7/16" RADIUS LOCATING LUG AS WELL AS MOUNTING EARS ON CTS TYPE U45 TWISTED EAR MOUNTED CONTROL
GENERAL TOLERANCE — DECIMALS ±.005"

Ample spacing between printed circuit terminal openings for the miniature Type U70 assures adequate clearance for circuit paths.

Ample spacing between printed circuit terminal openings for Types U45, GC-U45 and WT-U45 provides adequate clearance for circuit paths.

Type U70, 3/4" diameter *miniaturized* variable composition resistor with special printed circuit terminals. Wattage rating: .3 watt for resistances through 10,000 ohms, .2 watt with 350 volts maximum across end terminals for resistances over 10,000 ohms.



Type U45, 15/16" diameter, variable composition resistor with blade-type printed circuit terminals. Wattage rating: 1/2 watt for resistances through 10,000 ohms, 1/3 watt for resistances over 10,000 ohms through 100,000 ohms and 1/4 watt with 500 volts maximum across end terminals for resistances over 100,000 ohms.

Type GC-U45, 15/16" diameter, variable composition resistor with blade-type printed circuit terminals same as U45 except with attached SPST, 3 ampere, 125 volt "GC" type switch. Also available with type "WF", DPST, 3 ampere, 125 volt switch. (Variable resistor type WF-U45.)

CHICAGO TELEPHONE SUPPLY
Corporation

Specialists in Precision Mass Production of Variable Resistors

Need ceramic coil forms?

Look to CTC!

Nine different types to choose from — each meeting strict government specifications.

Wind these CTC ceramic coil forms to your specifications — then let us make them up for you in quantity. Forms are made of grade L-5 silicone impregnated ceramic varying in winding diameters from .205" to ½" and in mounted heights from 19/32" to 1 11/16" (see table below). Forms LST, LS5, LS6 and LS7 are also available with silicone fibreglas terminal retaining collars permitting 2 to 4 terminals. Designated as Type C, these latter forms are excellent for bifilar windings and are advantageous for single pie windings, permitting terminals to be located above or below winding thus shortening wiring to circuit elements. These forms also afford twice as many soldering spaces.

CERAMIC COIL FORM SPECIFICATIONS

Coil Form	Mounting Stud Thread Size	Form O.D.	Mounted O.A. Height
*LST	8-32	.205"	19/32"
*LS6	10-32	¼"	21/32"
*LS5	¼-28	⅜"	1 1/16"
LS8	¼-28	21/64"	23/32"
*LS7	¼-28	½"	1 11/16"

*ALSO AVAILABLE as Type C, described above.

For your convenience, a kit (X1897) containing 3 each of the forms listed above is available for developing prototypes and pilot models. Also, a new Coil Kit (X2060) containing 10 slug-tuned LS6 Type C coils is available — ranging from 2 Microhenries to 800 Microhenries.

Ceramic coils wound to your specifications can be furnished in quantity. Cambridge Thermionic Corporation, 437 Concord Avenue, Cambridge 38, Mass. West coast manufacturers contact E. V. Roberts, 5068 West Washington Blvd., Los Angeles, and 988 Market Street, San Francisco, California.

Shown approximately full size.



Color-Coded Chart on inside cover of the CTC Ceramic Coil Form Kit lists data of interest to designer and enables designer to order in quantity after specifications are determined.

CAMBRIDGE THERMIONIC CORPORATION

custom or standard . . . the guaranteed components

CTC

Write for Free Catalog #400 containing complete data on the entire CTC line.

Want more information? Use post card on last page.


PRINTED CIRCUITS
do a BETTER JOB at LOWER COST
printed . . . stamped . . . etched
Everyone in electronics today knows that printed circuits are the real answer to production speed-ups . lower costs . . . greater profits. Printed circuits can help you in numerous ways — regardless of the product you manufacture.
Davelle invites you to write today and learn how this latest scientific development can reduce costs and solve your production problems. Send us a sketch or print of your product and our engineering staff will design a printed circuit layout for your application. In addition, if you desire price quotations, let us know the quantities involved.
You will find Davelle's printed circuits are priced lower while maintaining highest precision standards of workmanship.
DAVELLE
LABORATORIES, INC.
SPRINGFIELD GARDENS 13, L. I., N. Y.

Armco Simplifies Its Electrical Steel Grade-Names

Nearly 25 years ago Armco introduced a system of electrical steel nomenclature based on numbers indicative of standard core loss limits at 10 kilogausses. At that time all rolling was by the hot reduction method. Since then, cold reduced electrical steels have been introduced, oriented grades developed, and core loss limits have been set at 10 and 15 kilogausses.

Armco now takes another constructive step to help simplify its electrical steel nomenclature. Armco grade names now conform closely to the AISI type number system. The new Armco trade-names along with the ones they replace are:

The New Armco Trade-Names	The Obsolete Armco Trade-Names
TRAN-COR M-43	Armature
TRAN-COR M-36	Electric
TRAN-COR M-27	TRAN-COR 101
TRAN-COR M-22	TRAN-COR 82
TRAN-COR M-19	TRAN-COR 72
TRAN-COR M-17	TRAN-COR 65
TRAN-COR M-15	TRAN-COR 58
TRAN-COR M-14	TRAN-COR 52
TRAN-COR A-5	Radio 5
TRAN-COR A-6	Radio 6
TRAN-COR T	TRAN-COR T
ORIENTED M-8X	TRAN-COR 2X-O
ORIENTED M-7X	TRAN-COR 3X-O
ORIENTED M-7W	TRAN-COR 3W-O
ORIENTED M-6W	TRAN-COR 4W-O
ORIENTED T	TRAN-COR T-O
ORIENTED T-S	TRAN-COR T-O-S

Note the simple and clear differentiation between non-oriented and oriented grades. The non-oriented are known by the familiar name TRAN-COR. The oriented types are called ORIENTED, and their numbering system is patterned after AISI practice also. As before, "X" indicates the oriented grade suitable for either wound or stacked cores, "W" the grade made for wound cores only.

Differentiation between hot- and cold-reduced grades will be made by adding "hot-rolled" or cold-rolled" to the new trade names.

Radio 5 and Radio 6 become TRAN-COR A-5 and A-6, the "A" standing for "audio."

ARMCO STEEL CORPORATION
4713 Curtis Street, Middletown, Ohio
Export: The Armco International Corporation

IS POWER...SIZE...OR WEIGHT

YOUR ELECTRONIC DESIGN PROBLEM?

DIFFUSED JUNCTION GERMANIUM RECTIFIERS

Not only is the complete G-E rectifier line an umbrella which covers virtually every power requirement imaginable but individual types also apply to a broad base of power circuit functions. The 1N91 is an excellent example. Utilizing its low voltage...high current characteristics our engineers pin point new applications every day. A machine involving small dc relays...a calculator...model train control...appliances...a pinball machine are typical discoveries. Quite possibly the equipment design you are presently at work on will be the next addition to this list.

Why not send your specifications to General Electric application engineers for a complete recommendation!

G-E HAS A COMPLETE LINE

Type	Peak Inverse	D.C. Output
1N91	100 v	150 ma
1N92	200 v	100 ma
1N93	300 v	75 ma
1N151	100 v	500 ma
1N152	200 v	500 ma
1N153	300 v	500 ma
1N158	380 v	500 ma

DESIGN FEATURES

- **VERY LOW LOSSES.**
- **HERMETICALLY SEALED** against deteriorating elements.
- **MINIATURE SIZE** made possible by low internal losses.
- **DESIGNED** to meet all military humidity tests and shock and vibration requirements.
- **MULTIPLE ARRANGEMENTS** for full wave or bridge circuits up to tens of amperes.

LET G-E APPLICATION ENGINEERS ADVISE YOU!

1878 75 1953 YEARS OF ELECTRICAL PROGRESS

General Electric Company, Section 4113
Electronics Park, Syracuse, N. Y.
Here are my circuit requirements. Please send me your recommendation.

NAME.....

COMPANY.....

ADDRESS.....

CITY..... STATE.....

GENERAL ELECTRIC

slip ring assemblies-

we specialize in all sizes

Your slip ring requirements may necessitate a very large assembly, equipped to carry 500 or more circuits, and operable for long periods of time under severe conditions. Or you may require a miniature unit which can be produced inexpensively in high volume and still function to precision specifications. . . . PM Industries can fulfill either type of requirement because we are experienced in designing, developing, and producing Slip Ring Assemblies at both ends of the scale.

FOR EXAMPLE —



REQUIREMENT: S. R. A. for gun fire control. **CUSTOMER:** U. S. Navy, Bureau of Ordnance. The specifications on this unit called for 531 circuits, including high voltage and RF. Also included in the specifications were easy servicing, long operating life, and ability to withstand vibration and severe shock.

The completed assembly, which met all specifications, was 8′ 1″ high, 40″ in diam., and weighed 4300 lbs. Subsequently the customer specified greatly reduced weight, increased electrical capabilities from fewer rings, additional RF circuits, and decreased space allotment. These have been achieved in a unit 9″ x 12″ x 59″ weighing 450 lbs.



REQUIREMENT: S. R. A. for selsyn motors. **CUSTOMER:** Bendix Aviation Corp. This unit, which is being produced to meet special military specifications, is .450″ long, with rings .250″ in diam. The rings are silver alloy not less than #70 Vickers in hardness, and are molded in mineral filled Melamine with a central mounting shaft of stainless steel. The molded units are 100% tested at 900 volts RMS, 60 cycles. Production rates, even though high initially, have recently had to be increased in order to meet Bendix Aviation's demand for this PMI assembly.

For further information on how PMI might be of assistance to you, write for our Facilities Report and our new brochure "Slip Ring Assemblies to Your Specs."

PMI

DESIGN • DEVELOPMENT • PRODUCTION

Industries Inc., Stamford, Conn.

Electro-mechanical devices • Engineered plastic-metal assemblies



We shot for the moon

. . . on a clear night

We set our sights on developing a new electron gun . . . one whose finer beam would establish an all-time high in resolution for electrostatic-focus picture tubes.

We shot for a gun that would produce a smaller, sharper spot . . . a spot free from the effects of excessive "starring" which causes an outline blur similar to the haze around the moon on a cloudy night.

Smaller spot size, and cleaner, more uniform spot shape are the secrets of the Du Mont Hi-R Teletron. These are the features which have made possible a more vivid presentation of the television picture.

They are the reasons why, in just a few months, the Hi-R Teletron has become the performance standard of the television industry.

DU MONT®

*Teletrons**

Hi-R—A new high in resolution — now being incorporated in all DuMont Electrostatic Focus Teletrons

*TRADE MARK

CATHODE-RAY TUBE DIVISION • ALLEN B. DU MONT LABORATORIES INC., CLIFTON, N. J.

By testing motors under desert conditions G.E. gives you more for your motor dollar

This motor is being removed from the dust chamber at Fort Wayne, Indiana, for inspection by G.E. Specialty Motor Dept. Engineers. Operated for many gruelling hours in hot, wind-driven sand, it has endured conditions tougher than any it will be expected to meet in service.

Used to detect the particular problems of desert operation, the dust chamber typifies the engineering thoroughness and precision at General Electric —the resourcefulness that helps build better quality fractional-horsepower motors—of all kinds—for you.

Whatever your aircraft motor problem, remember that G.E. Engineers have both the testing facilities and skill to solve it. General Electric will design and build precisely the motor you need to meet your most demanding requirements . . . solve your toughest problems.

For more information or engineering assistance, contact your nearby G-E Apparatus Sales Office. General Electric Company, Schenectady 5, N. Y.

704-18

You can put your confidence in—

GENERAL ELECTRIC

TV PURCHASING AGENTS:

Cut Production Line Rejects

with *Federal* "BEST-IN-SIGHT" PICTURE TUBES

OVER 99%* hit the bull's-eye for quality

Thousands of famous-name TV picture tubes were quality-tested by a famous-name manufacturer* of sets. When the scoring was over, Federal led all the brands tested . . . with an O. K. on over 99% of its tubes!

Here's proof of picture performance, Mr. Purchasing Agent . . . proof that you can cut your production line rejects with "Best-in-Sight" picture tubes.

Federal dependability is based on Federal's years of experience in producing *power* tubes . . . up to 500 KW . . . for hundreds of broadcast stations . . . for rectifying, industrial, military and general purpose applications.

Talk over *your* TV tube requirements with Federal . . . get the facts about the tube with *picture* quality to match the finest *chassis* quality.

For full information on types and sizes, write today to Dept. N-413.

Federal Telephone and Radio Company

VACUUM TUBE DEPARTMENT — 100 KINGSLAND ROAD, CLIFTON, N. J.

In Canada: Federal Electric Manufacturing Company, Ltd., Montreal, P. Q.
Export Distributors: International Standard Electric Corp., 67 Broad St., N. Y.

"Federal always has made better tubes"

DIRECT READING, MULTI-PURPOSE

SIGNAL GENERATORS



new!

-hp- 620A
SHF SIGNAL GENERATOR
7,000 to 11,000 mc

Now *-hp-* offers precisely accurate, easily obtained, *direct reading* test signals at any frequency from 10 to 11,000 mc!

New Model 620A SHF Signal Generator extends coverage of the *-hp-* generator group through the 7,000 to 11,000 mc range. Like other *-hp-* VHF, UHF and SHF Signal Generators, Model 620A provides the utmost in accuracy, pulsing capabilities, wide range, broad usefulness, and convenience. Frequency and output are directly set and read—no charts or interpolation are necessary.

Within its range, this new instrument simplifies all types of measurements including sensitivity, selectivity and rejection, signal-to-noise ratio, conversion gain, SWR, antenna gain and transmission line characteristics. It is also highly useful for slotted lines or waveguide networks, filter networks, etc.

Versatile *-hp-* 620A provides internal or external pulse modulation, internal square wave modulation, FM or CW output. On internal FM, the instrument provides a sawtooth sweep variable between 40 and 4,000 cps (deviation variable to ±3 mc). For external frequency modulation, capacitive coupling is provided to the repeller of the klystron oscillator. Repeller voltage is tracked automatically, and no adjustment is needed to select the correct frequency.

Output of the instrument is 0.1 mw or 0.071 v to 0.1 μv (—10 dbm to —127 dbm) into 50 ohms. Frequency calibration accuracy is better than 1%, and attenuator accuracy is within ±2 db.

Repetition rate is 40 to 4,000 pps, and pulse width is variable from 0.5 to 10 μsec. Sync-out signals may be simultaneous with the rf pulse, or in advance by any period from 3 to 300 μsec. Model 620A may be synchronized with external sine waves, or with positive or negative pulse signals. The instrument is compactly and sturdily constructed of highest quality components, weighs 90 pounds, and measures approximately 17" wide x 14" high by 16" deep. Power source is 115 v ±10%, 50/60 cps, 250 watts. Price: $2,250.00.

COMPLETE COVERAGE | **HEWLETT-PACKARD**

FOR ALL FREQUENCIES

10 to 11,000 mc



-hp- 608A VHF SIGNAL GENERATOR

-hp- 614A UHF SIGNAL GENERATOR

Only Hewlett-Packard offers this broad selection of direct-reading signal generators

Instrument	Frequency Range	Characteristics	Price
-hp- 608A	10 to 500 mc	Output 0.1 μv to 1 v into 50 ohm load. Pulse or CW modulation. Direct calibration.	$ 850.00
-hp- 612A	450 to 1,200 mc	Output 0.1 μv to 0.5 v into 50 ohm load. Pulse, CW or amplitude modulation to 5 mc. Direct calibration.	1,200.00
-hp- 614A	800 to 2,100 mc	Output 0.1 μv to 0.223 v into 50 ohm load. Pulse, CW or FM modulation. Direct calibration.	1,950.00
-hp- 616A	1,800 to 4,000 mc	Output 0.1 μv to 0.223 v into 50 ohm load. Pulse, CW or FM modulation. Direct calibration.	1,950.00
-hp- 618B	3,800 to 7,600 mc	Output 0.1 μv to 0.223 v into 50 ohm load. Pulse, CW, FM or Square wave modulation. Direct calibration.	2,250.00
-hp- 620A	7,000 to 11,000 mc	Output 0.1 μv to 0.071 v into 50 ohm load. Pulse, CW, FM or Square wave modulation. Direct calibration.	2,250.00

-hp- 612A UHF-TV SIGNAL GENERATOR

Model 612A is a new master oscillator—power amplifier generator especially designed for TV measurements including receiver and amplifier gain, selectivity, sensitivity and image rejection. Like other *-hp-* generators, it is also a convenient *direct-reading* power source for driving bridges, slotted lines, antennas and filter networks.

-hp- 612A covers all frequencies from 450 to 1,200 mc, and provides 0.5 volt output into 50 ohms throughout range. It has low incidental FM and broad band video modulation to 5 mc. It may be modulated internally or externally, amplitude modulated, or pulse modulated (good rf pulses 0.2 μsec or longer). Pulse modulation may be applied to the amplifier, or direct to the oscillator for high on-off signal ratios. Price: $1,200.00.

Data subject to change without notice. Prices f. o. b. factory.
For complete details, see your -hp- field representative or write direct

HEWLETT-PACKARD COMPANY
2853-A PAGE MILL ROAD • PALO ALTO, CALIFORNIA, U.S.A.
SALES REPRESENTATIVES IN PRINCIPAL CITIES



-hp- 616A UHF SIGNAL GENERATOR



-hp- 618B SHF SIGNAL GENERATOR

hp INSTRUMENTS | COMPLETE COVERAGE

The most versatile test data recorder you've ever seen!

Check these features:

SPAN:
adjustable from 1 to 50 millivolts. Arbitrary dial markings, readily converted to millivolt range by means of calibration supplied with recorder.

ZERO SUPPRESSION:
coarse and fine dials permit movement of zero by ±100% of max. span.

DAMPING:
adjustable to obtain optimum balancing action for almost any span or source impedance.

SENSITIVITY:
automatically adjusts measuring circuit response as span is changed.

SPEED:
full scale pen travel as fast as one second.

WIDE CHART:
11-inch calibrated width gives high resolution.

STANDARDIZING:
manual.



If you need to record results of a variety of tests, this new *ElectroniK* instrument is just what you've been looking for. A simple turn of its dials converts it to practically any range your tests require.

Especially useful with strain gauges, accelerometers, tachometers, differential thermocouples—or any other voltage-producing transducer—it is like having a hundred instruments in one. You can vary its full scale span over a wide range, to spread out test curves in exceptionally readable form. You can move its zero point up and down at will, until the portion of the test curve in which you're most interested is spread across the recorder chart. And you can change its sensitivity and damping to give the recording characteristics that best fit your test. Span and zero adjustments are completely independent.

Our local engineering representative will be glad to discuss how this new instrument can bring new convenience to your test work. Call him today . . . he is as near as your phone.

MINNEAPOLIS-HONEYWELL REGULATOR CO., *Industrial Division*, 4428 Wayne Ave., Philadelphia 44, Pa.

● **REFERENCE DATA:**
Write for Data Sheet No. 10.0-10 "Adjustable Span *ElectroniK* Recorder."

MINNEAPOLIS
Honeywell
BROWN INSTRUMENTS
First in Controls

You Can Depend on COMMUNICATION ACCESSORIES for

ADVANCED DESIGN

THROW AWAY the special washers and tubings used in your present mechanical mountings of toroids. C-A-C Advanced Design provides a molded-in brass bushing with center hole sizes to clear (type A) or tapped (type B) for a 6/32 screw.

PRESSURE ENCAPSULATION in low loss plastic provides a dense molding of extremely uniform dimension. We've cycled them from —73° C to 150° C—boiled them for hours in salt water—without any significant change.

TERMINALS are brass, silver-plated. Located for ease of connection. Any reasonable number of terminals may be provided. Units may be stacked and mounted with a single screw.



AN EXCLUSIVE C-A-C DEVELOPMENT

Compression MOLDED PLASTIC TOROIDS

THE C-A-C MP (molded plastic) Toroid is the result of years of development and exhaustive tests to determine the most suitable materials and method of manufacture. The small, extra cost of the molded unit is more than justified by the superior protection of the unit from damage in assembly and operation—and the elimination of complicated mounting arrangements. The assemblies are compact (see table for dimensions). Complete data available on request; samples will be furnished for your evaluation.



TOROIDAL INDUCTORS
Data For Standard Types

	Type	Normal Lmax.	Appr. Size O.D. x H	Useful Freq. Range	Qmax @ Freq.			T.C.	Inc. ma
★	206	3.0 Hy	.90x .40	Up to 15 KC	140 @	9	KC	1	23
★★	930	17.5 Hy	1.20x .60	Up to 15 KC	170 @	7.5	KC	1	42
	254	35 Hy	1.85x .85	Up to 15 KC	220 @	5	KC	1	67
	466	60 Hy	2.15x1.00	Up to 15 KC	260 @	5	KC	3	95
★	848	1.4 Hy	.90x .40	10- 50 KC	170 @	20	KC	1	33
★★	395	8.0 Hy	1.20x .60	10- 50 KC	220 @	20	KC	1	61
	381	17.0 Hy	1.55x .65	10- 50 KC	260 @	17.5	KC	3	71
★	608	600 Mh	.90x .40	30- 75 KC	165 @	60	KC	3	50
	579	7.5 Hy	1.55x .65	30- 75 KC	185 @	30	KC	2	110
★	041	320 Mh	.90x .40	50-200 KC	115 @	120	KC	3	68
	013	4.0 Hy	1.55x .65	50-200 KC	145 @	70	KC	3	150

REMARKS

Qmax—Values taken at approx. .01 Iac. Q decreases with increasing current to about .50 Qmax at 1.0 Iac—higher inductance values have lower Qmax at lower frequency due to dielectric losses of winding distributed capacity. All values are for inductors wound with Heavy Formex wire.

T.C.—Temperature characteristics as follows:
1—approx. 100 ppm/°F
2— = .1% 55 to 90°F
3— = .1% 30 to 130°F
(most types with temp. characteristic 1 are available with characteristic 3 at no sacrifice in performance)

Iac—r.m.s. current which raises 0.1 Hy inductor to max. (2% above initial) inductance — (1% increase occurs at approx 0.35 Iac.

★ FINISHED SIZE—1-1/10" O. D. x 1/2" THICK
★★ FINISHED SIZE—1-5/16" O. D. x 11/16" THICK

COMMUNICATION ACCESSORIES Company
HICKMAN MILLS MISSOURI

Want more information? Use post card on last page.

A NEW TERMINATION TECHNIQUE FOR . . .

- COMPUTERS
- SWITCHBOARDS AND INSIDE PLANT EQUIPMENT
- RELAYS, SWITCHES, AND MULTI-CIRCUIT COMPONENTS



AMP FLAT* TAPER

If you are concerned with the wiring of close spaced equipment, investigate the new AMP Solderless TAPER TAB RECEPTACLE for flat relay or switch tabs shown at right. It is self locking when installed on a male tab with matching 3½° taper, yet can be removed and reconnected any number of times without solder or special tools. These terminals are supplied on reels in continuous strip. Customer crimps them on wires using AMP automatic machines at speeds up to 4,000 per hour!

Performance of these miniature connectors meets exacting requirements for millivolt drop, corrosion resistance, and vibration. They are suited for critical low level circuits or power circuits up to several amperes.

Write to AMP Electronics Division for complete information concerning AMP TAPER TAB RECEPTACLES . . . you will receive data and samples by return mail.

An example of the savings possible with Taper Tabs and Receptacles. This disconnect block in Remington Rand's new electronic computer had more than 1,000 wires soldered to tabs in a space approximately 5" x 9"—an assembly operation requiring two weeks' time. After tabs were modified to taper shape (See picture insert), the same operator can now assemble two blocks per day—a 20 to 1 increase—using A-MP's Taper Tab Receptacle No. 41355. There are neither loose wire ends nor drops of solder in the assembly to cause shorts nor cold or rosin joints to open up in the field. Installation is simply a mechanical operation requiring little operator skill, resulting in greater uniformity.

*For connector plugs and other applications where a round pin is more adaptable, see AMP taper pins.

PHOTO AT RIGHT SHOWS AMP SELF LOCKING TAPER TAB RECEPTACLES BEING APPLIED TO MATING TABS ON A STEPPING SWITCH. LOCKING ACTION GIVES MAXIMUM ELECTRICAL AND MECHANICAL SECURITY . . . CONNECTIONS ARE SUITABLE FOR CRITICAL LOW LEVEL CIRCUITS.



© AMP AMP Trade-Mark Reg. U. S. Pat. Off.



AIRCRAFT-MARINE PRODUCTS, INC.
2100 Paxton Street, Harrisburg, Pa.
Aircraft-Marine Products of Canada, Ltd.
1764 Avenue Rd., Toronto 12, Ontario, Canada

Want more information? Use post card on last page.

For a complete range of compositions solving every important design problem

Specify GENERAL CERAMICS

ELECTRICAL CERAMICS

-including

TEMPERATURE EXTREMES
SHOCK AND VIBRATION
LOW ELECTRICAL LOSS
HIGH DIELECTRIC STRENGTH
MECHANICAL ADAPTABILITY



General Ceramics has specialized in the manufacture of high quality technical ceramic materials for the electrical and electronic industries for over 25 years. The many compositions now supplied were developed over the years to solve specific problems of these industries. Most of these compositions have been standardized by General Ceramics and are available to solve your problems quickly and economically. Why not call, wire or write today for information.

GENERAL STEATITE INSULATORS

General CERAMICS and STEATITE CORP.

General Offices and Plant: KEASBEY, NEW JERSEY

MAKERS OF STEATITE, ALUMINA, ZIRCON, PORCELAIN, SOLDER-SEAL TERMINALS, LIGHT DUTY REFRACTORIES, CHEMICAL STONEWARE, IMPERVIOUS GRAPHITE & FERRAMIC MAGNETIC CORES



Westinghouse Fosterite® Transformers must pass this 4-hour underwater test

If you're looking for a small, open-type transformer, fully protected against moisture, check the line of Westinghouse Fosterite impregnated transformers. This four-hour underwater test proves the point:

All Fosterite-treated transformers are completely submerged in hot water at 60° Centigrade for two hours, after which they are "thermal-shocked" in cold tap water, and soaked there for an additional two hours. An electrical test is then applied, in which each transformer must show an insulation resistance reading of at least 2000 megohms. Fosterite has to be good!

This is just one of many severe tests to which Westinghouse specialty transformers are subjected. They assure you of quality that will meet your requirements exactly . . . quality that stands up under extreme conditions.

Fosterite impregnated and coated transformers can be made available to meet your most stringent specifications. In addition to moisture protection, Fosterite makes drastic weight reductions possible . . . as much as 30 to 50%, when compared to enclosed types.

Call your Westinghouse representative for further information, or write Westinghouse Electric Corporation, P. O. Box 868, Pittsburgh 30, Pa. J-70678

YOU CAN BE SURE... IF IT'S

Westinghouse

T&S

5.70 x 10^6 Bd Hd energy product nominal

NEW ALNI

Thomas & Skinner Alnico 5Cb Typical Demagnetization and Energy Product Curve



SPECIALISTS IN MAGNETIC MATERIALS . . .

Permanent Magnets *Laminations* *and Wound Cores*

Highest energy product of ANY Alnico!

CO 5Cb*

From the Thomas & Skinner Research & Development Laboratories . . . first to develop Shell-Molded Alnico . . . comes the announcement of new Alnico 5Cb, with an energy product offering new concepts in permanent magnet applications.

By incorporating the use of new alloy elements with special heat-treating procedures, Thomas & Skinner has developed Alnico 5Cb. Ready for use as an advanced permanent magnet material, Alnico 5Cb is the result of years of intensive work by Thomas & Skinner Research & Development engineers.

New Alnico 5Cb is similar in physical characteristics to Alnico 5, but offers considerably higher external energy and residual induction . . . an average energy product of 5.70 million nominal.

For electrical, electronic and industrial applications, Alnico 5Cb opens new possibilities for weight and space reductions in product design.

There may be a definite need within your own product development for the extremely high energy product offered by this new magnetic material. Write Thomas & Skinner today for specific information on Alnico 5Cb. For complete assistance on permanent magnet designs, call on Thomas & Skinner engineers.

* Patent applied for.

THOMAS & SKINNER Steel Products Company, Inc.

1122 East 23rd Street, Indianapolis, Indiana



let EDO house your electronic equipment

Housing intricate electronic equipment for airborne or shipboard use to withstand shocks and forces which might cause malfunction often presents problems as difficult as the design of electronic systems themselves.

Tackling such problems for electronic manufacturers, ship and aircraft builders is a specialty of the Edo Corporation. Whether your equipment must operate properly on jet aircraft or on board ship under battle conditions, its reliability is improved if mounted in Edo-designed and built cabinets or housings.

If you have a housing problem, why not talk it over with our versatile engineering staff whose three-fold experience in the marine, aviation and electronics fields is unique *and at your disposal.*

to withstand...

SHOCK
MACH 1 SPEED
VIBRATION
CONCUSSION
SPRAY
ENVIRONMENTAL

TWO TYPICAL HOUSING PROBLEMS SOLVED BY EDO

1. AIRBORNE HOUSING. A volume producer of airborne radar nacelles, Edo was asked to design a pressurized external store housing capable of being flown in the trans-sonic speed range. From wind tunnel tests to completed tooling and production, Edo relieved the electronics manufacturer and the aircraft builder of these design problems.

2. SEABORNE INSTALLATIONS. To house its own electronic equipment developed and manufactured for the Navy, Edo engineers have perfected a series of *standard* electronic cabinets admirably suited to naval electronic equipment. Capable of housing all standard electronic units, the Edo cabinets are vibration-proof and spray-proof.

Edo CORPORATION College Point, L. I., N. Y. SINCE 1925

FOR IMPROVED EFFICIENCY... LOWERED COSTS... INVESTIGATE THESE KEY TELEVISION COMPONENTS

MAGNADUR®

FERROXCUBE®



first in ferrites... and first in mass production

of this basic group of TV components! Ferroxcube and Magnadur parts are the products of 16 years of extensive research and manufacturing experience. The new design requirements of the television industry are being supplied successfully by Ferroxcube Corporation—providing TV set makers with the new ferrite and permanent magnet components with which improved television designs are created.

SEND US PRINTS OF YOUR MAGNETIC CORE PIECES FOR QUOTATION

FERROXCUBE CORPORATION OF AMERICA

• A Joint Affiliate of Sprague Electric Co. and Philips Industries, Managed by Sprague •

35 EAST BRIDGE STREET • SAUGERTIES, NEW YORK

NEW GUN

Tests made under standard conditions in fringe areas and in laboratories show better definition in Westinghouse picture tubes

In the Westinghouse engineering laboratories, tests were made of the performance of the new Westinghouse electrostatic gun in a 21-inch tube. Comparable tests were made on the Westinghouse FM-6 gun—which has been recognized as being among the best in the industry. The results of these tests show that the new gun gives a decidedly superior performance.

To substantiate this laboratory data a series of field tests was made in a residence in Bath, New York. A Westinghouse 21YP4 electrostatic focus picture tube was selected at random from cartoned stock. The 21YP4's of three other leading manufacturers were purchased from distributor stock. Identical test conditions were maintained.

The results of these tests:

1. The smaller spot size produced in the Westinghouse tube gave greater picture resolution, finer definition, than that of any other tube tested.
2. The Westinghouse tube showed more detail in highlights and smaller snow particles than any other tubes tested.
3. Subsequent laboratory tests showed that the Westinghouse tube maintained far better focus over a wide range of focus voltage than any other tubes tested, as follows:

Westinghouse: Sharp focus from —50 V to +150 V.
Brand "X": Sharp focus from —30 V to —60 V only.
Brand "Y": Sharp focus from —80 V to —100 V only.
Brand "Z": Sharp focus from +160 V to +200 V only.



This curve relates center resolution to beam current over a range of anode voltages — depicting the ability of the gun to maintain sharp definition despite changes in current.

YOU CAN BE SURE... IF IT'S Westinghouse

WESTINGHOUSE ELECTRIC

In Westinghouse Electrostatic Picture Tube Gives Better Resolution in Fringe Areas





Check Comparative Resolutions Shown in These Photographs

The greater resolution, finer definition, and better contrast of the Westinghouse tube is obvious on the unretouched photographs on the left. Each photograph shows a Westinghouse tube operating next to a competitive tube in an adjacent chassis. Each pair of pictures is the result of a single photograph with each tube operating under identical conditions.

Westinghouse invites you to perform this or similar tests in any chassis you may choose. Complete data resulting from the Bath, New York, tests on Aug. 15, and Westinghouse laboratory tests is available upon request to Dept. A-211, Westinghouse Electric Corp., Elmira, N. Y.

The following test conditions were maintained throughout all field tests:

Date: August 15, 1953
Location: Bath, New York
Signal: Test pattern from station WHAM-TV, Rochester, N. Y., 70 miles distant.

Tubes Tested: Westinghouse 21YP4 with new electrostatic focus gun and 21YP4's of three other leading manufacturers. All tubes selected at random.

Beam Current: 200 μa
Anode Voltage: 13.5 KV
Screen Voltage: 400 V

ET-95039

RELIATRON™ TUBES

CORPORATION, ELECTRONIC TUBE DIVISION, ELMIRA, N. Y.

Want more information? Use post card on last page.

You know you can count on his help

When the need was grim and the time was short, this man somehow always got there to see things through. You called him, *knowing* he would come.

And this "old-fashioned" idea of responsibility and service still lives today, in those individuals and enterprises that have been fortunate enough to inherit it. It governs *this* enterprise, for one, in its relationships with all those who depend on it for knowledge, integrity, and willing acceptance of full responsibility in time of need. We honor these *men with missions,* because we understand them well.

• • •

The BRISTOL BRASS CORPORATION, makers of Brass since 1850 in Bristol, Conn. Offices or warehouses in Boston, Chicago, Cleveland, Dayton, Detroit, Los Angeles, Milwaukee, New York, Philadelphia, Pittsburgh, Providence, Rochester.

"Bristol-Fashion" means **Brass at its Best**

GOLD PLATED CONTACTS
AMPHENOL
GOLD PLATED CONTACTS
GOLD PLATED CONTACTS
GOLD PLATED CONTACTS



AMPHENOL has long been the leading manufacturer of approved A N connectors—and every AMPHENOL A N connector is made to government specifications. Under these specifications, however, many alternate processes in manufacture are allowed. Where this choice is given, AMPHENOL has *always* gone to the highest quality interpretation. Thus, many features of AMPHENOL A N connectors exceed the basic requirements of the specifications and are unique with AMPHENOL.

AMPHENOL's pioneer work in improving A N connectors has often been recognized by the inclusion of AMPHENOL-developed changes in government specifications. The 1-501 blue dielectric and gold-plated contacts are examples of how AMPHENOL initiative has resulted in *better* A N connectors.

CADMIUM SHELLS The connector shells on all AMPHENOL A N's are cadmium plated with a chromate conversion coating. The shell finish is available in either bright cadmium or olive drab. The cadmium plate with chromate conversion coating has excellent conductivity and surpasses all military specifications for corrosion resistance. In the olive drab finish the connectors are non-reflecting.

1-501 BLUE DIELECTRIC AMPHENOL A N connectors use as dielectric the new 1-501 diallyl phthalate resin-based molding compound. Developed by AMPHENOL, this material combines the specific requirements of nearly perfect dimensional stability, high insulation resistance in the presence of high temperatures and high humidity combined, and high arc resistance. 1-501 has a lifetime shrinkage of less than 0.3%.

GOLD PLATED CONTACTS The newest improvement on AMPHENOL A N connectors, and one of the most significant, is the conversion to gold-plated contacts. Now standard on all AMPHENOL A N connectors, gold-plated contacts have many advantages, including superior contact surfaces, an end to the problem of oxidation and easier, faster soldering. Gold-plated contacts on A N connectors are unique with AMPHENOL and may be obtained only by the specification of AMPHENOL.

AMPHENOL CATALOGING Because of the diversity of the AMPHENOL line, there is a variety of catalogs and allied literature published by AMPHENOL.

For general information about the AMPHENOL line, *Catalog* B will prove most useful. Where more specific information is required, *Catalog* A, A N connectors and fittings, and *Catalog* D, R F cables and connectors, should be requested. *Catalog* C is an "OK Methods Manual" of instructions for proper assembly of cables and connectors. As these four catalogs are being continually revised and brought up to date, a new suffix number is attached to the catalog letter for each issue. In all cases, a request for catalogs will produce only the latest issue.

Among the special literature published by AMPHENOL are the *Engineering News*, new products listings, RF Cable and Connector *Selector* Slide Rule and miscellaneous bulletins on new AMPHENOL components.

AMPHENOL

AMERICAN PHENOLIC CORPORATION Chicago 50, Illinois

Amform 2288-103325 Printed in U.S.A.

your easiest reach

to over 80,000 industrial electronic parts

the prices...
the specifications...
the reference information...

Industrial Electronic Catalog Contents

Product Service Reply Index	
Tubes	40 pages
Recording and Phono Equipment	65 pages
Rectifiers, Fuses, and Dial Lights	25 pages
Amplifiers, Sound Systems, & Intercoms	35 pages
Speakers, Horns	45 pages
Mikes, Earphones	40 pages
Test Equipment	120 pages
Books, Manuals	20 pages
Industrial Transmitting Equipment	100 pages
TV Accessories and Crystals	40 pages
Switches, Jacks, and Relays	35 pages
Power Conversion Equipment, Batteries	55 pages
Transformers, Chokes	115 pages
Capacitors, Filters	130 pages
Resistors, controls	50 pages
Wire, Antennas, Accessories	105 pages
Connectors, Sockets, Receptacles	40 pages
Service Aids, Tools, Hardware	115 pages

FREE! SEND FOR THE BIGGEST INDUSTRIAL ELECTRONIC CATALOG EVER PRINTED

Join the increasing number of Electronic Engineers and Purchasing Executives who have discovered that specification design-data and prices can be obtained and compared from one catalog in seconds!

Investigate for yourself the 1954 Electronic Expediters INDUSTRIAL ELECTRONIC CATALOG of over 1300 plus pages showing more than 90% of all electronic manufacturers.

SPECIAL INFORMATION and QUANTITY QUOTATION SERVICE

Take advantage of our SALES SERVICE DEPARTMENT. Use the Product Service Reply Cards attached to the Product Information Index Section. Simply circle corresponding product numbers and mail. The same day your card is received special information and prices will be on their way.

INDUSTRIAL ELECTRONICS
RADIO & TELEVISION PARTS

Electronic Expediters
2909 West Devon Avenue • Chicago 45, Illinois
Phone ROgers Park 4-8640

Electronic Expediters DEPT. 11CE
2909 W. Devon Ave.
Chicago 45, Illinois

☐ Send your new 1954 Catalog
We'd like to easily reach prices and information on over 80,000 Industrial Electronic Parts.

☐ Please enter us on your regular mailing list for special equipment buys and current trade information.

Name _____ Title _____
Company _____
Address _____
City _____ Zone _____ State _____

Want more information? Use post card on last page.

NATVAR *in* NORWAY

This secondary coil shows the rugged construction used to insure proper operation under all service conditions. Natvar Varnished Fiberglas Tape and Sleeving are used to insulate and protect coils and leads from moisture and heat.

This UNITOR AC Arcwelder provides a welding current of 600 amperes at 40 volts load voltage on a 50% duty cycle. Heat range can be controlled either at the unit or from the operator's stand, from maximum down to 100 amperes at 25 volts. The unit can be moved close to the job so that long ground and electrode cables are not required.

UNITOR A. S., Oslo, Norway, manufactures a complete line of AC Arcwelders which can be easily moved from job to job. Since service conditions vary widely, these units are designed and built to operate in spite of severe moisture, corrosion, heat, and vibration.

Transformer coils and leads are insulated and protected with Natvar Varnished Fiberglas Tape and Sleeving because of its uniformly high performance under adverse conditions. Natvar agent and distributor for Norway is C. Bagges Asbestkompani A.S., Radhusgt 6, Oslo.

If you need insulating materials with good physical and electrical properties, and exceptional uniformity, it will pay you to get in touch with your distributor, or with us direct.

NATVAR CORPORATION

FORMERLY THE NATIONAL VARNISHED PRODUCTS CORPORATION

TELEPHONE RAHWAY 7-8800 — CABLE ADDRESS NATVAR: RAHWAY, N. J.

201 RANDOLPH AVENUE • WOODBRIDGE, NEW JERSEY

Natvar

Natvar Products

- Varnished cambric—cloth and tape
- Varnished canvas and duck
- Varnished silk and special rayon
- Varnished—Silicone coated Fiberglas
- Varnished papers—rope and kraft
- Slot cell combinations, Aboglas®
- Varnished-lacquered tubing and sleeving
- Extruded vinyl tubing and tape
- Styroflex® flexible polystyrene tape
- Extruded identification markers

Ask for Catalog No. 22



Series SM-20.....Sub-Miniature Rectangular Connectors
Series 20.....Miniature Rectangular Connectors
Series H-20 .....Hermetical Seal Miniature Rectangular Connectors
Series C-20.....Miniature Hexagonal Connectors (Vibration Proof)
Series EZ-16.....Easy Release Power Connectors (Spring Loaded contacts)
Series 16.....Rectangular Power Connectors
Series 14.....Rectangular Power Connectors
Series PC.....Printed Circuit Connectors
Miniature Precision Stand-offs
SPECIAL DESIGNS—submit your connector problems to our engineering department.

Continental Connectors

ELECTRONIC SALES DIVISION DeJUR-AMSCO CORPORATION

Write Dept. EC-11, DeJur-Amsco Corporation
45-01 Northern Blvd., Long Island City 1, N. Y.

Want more information? Use post card on last page.

PLASKON ALKYD

Here's How...

Plaskon Fiber Glass Alkyd Meets Specific Electronic Equipment Requirements

—*says* DEJUR-AMSCO CORPORATION,
Exclusive Sales Agents for Continental Connectors,
45-01 Northern Blvd., Long Island City 1, N. Y.

Continental has kept pace with the electronics industry in miniaturization, sub-miniaturization and printed circuit connector development. The DeJur-Amsco Corporation's "Continental Precision Connectors" catalog says:—

"We have introduced new molding materials, such as Plaskon Fiber Glass Reinforced Alkyd . . . to meet specific electronic equipment requirements."

Among the reasons Continental went to Plaskon Alkyd are—customer demand for greater dimensional stability; greater arc resistance; superior mechanical strength; greater resistance to moisture absorption; and products with clean, sharp-molded edges, highly resistant to chipping.

Virtually No Shrinkage with Plaskon Alkyd,

—*says* CAL-CONNECTOR,
7414 Varna Avenue, North Hollywood, California

"Shrinkage of insulating inserts in electrical connectors presents a serious problem to the user—especially when a *pressurized* connector is required. In many plastics used for inserts, after-shrinkage from cold-molded dimensions continues for months. However, parts molded with Plaskon Alkyd 422 display no such effect. Quick to recognize the advantages of dimensional stability in electrical connectors, the Cal-Connector Co. now molds inserts of Alkyd 422 for the products it manufactures. As a result—*Cal-Con inserts have virtually no shrinkage!*"

Miniature VARICONS are molded of Plaskon Alkyd for dielectric properties—*plus.*

ELCO CORPORATION,
190 W. Glenwood Avenue, Philadelphia, Pa.

These pygmy parts are miniature connectors that do the work of giants and now, utilizing Plaskon Alkyd, carry even heavier loads. Elco Varicons have a wide acceptance in the electrical and electronics fields. They require electrical insulating material with a very high degree of arc resistance, to assure withstanding a maximum of 4000 volts between closest terminals. Like all Plaskon Alkyd parts, they possess superior dimensional stability, so there is no measurable after-shrinkage from cold-molded dimensions. Dimensional stability is highly important to Varicons, for there must be perfect fit between these miniature matched pairs. And the high-speed, low-pressure molding characteristics of Plaskon Alkyd contribute to Elco's production speed and low costs.

You can give your product superior arc resistance; make it stronger, more compact; assure its freedom from after-shrinkage; mold it faster—by using either Plaskon Alkyd or Plaskon Fiber Glass Reinforced Alkyd.

Solves Vital Problems for Electronics Manufacturers







Here's Why...

- **High dimensional stability (low after-shrinkage)**
- **Superior mechanical strength**
- **Fast, clean-edge moldings**
- **Extremely high arc resistance**
- **High heat resistance**
- **Greater compactness with safety**

—Because of their superior dielectric properties, Plaskon Alkyd parts can provide greater safety, with reduced over-all dimensions.

- **Molds easily, cleanly and rapidly, at low pressures**

Plaskon Mineral Filled and Plaskon Fiber Glass Reinforced Alkyd possess similar characteristics. In addition, Plaskon Fiber Glass Reinforced Alkyd has exceptionally high impact strength. Tough and rugged, it has three times the resistance of commonly used impact molding materials.

Write today!

FOR COMPLETE INFORMATION

BARRETT DIVISION

ALLIED CHEMICAL & DYE CORPORATION
2112 SYLVAN AVENUE, TOLEDO 6, OHIO

District Offices: Boston • Charlotte, N. C. • Chicago • Cincinnati • Cleveland • Detroit • Los Angeles • New York • Philadelphia • St. Louis • Washington, D. C.

Manufacturers of Molding Compounds, Resin Glues, Coating Resins, Paper and Foundry Resins, Phenolic and Polyester Resins

In Canada:
Barrett Company Ltd. (Resins)
Canadian Industries, Ltd. (Molding Compounds)

INSIST ON

PLASKON.

ALKYD

FOR SUPERIOR ELECTRICAL PARTS

Barrett



POTTER DECADE AND GLOW LAMPS—One of six decade units used in Potter Model 850 Megacycle Frequency-Time Counter shown below. Twenty-five Bradleyunits are used in each decade.

POTTER ELECTRONIC PLUG-IN COUNTER DECADES

are equipped with ½-1-2 watts BRADLEYUNITS



Model 850 Frequency-Time Counter
A versatile production counter for handling very short or rapidly recurring count pulses as in package conveyor applications. Also used for rapid inventory counts.

Electronic counters . . . like this Potter unit which has a counting speed up to 1,600,000 counts per second . . . are used for controlling manufacturing processes with high precision. Therefore their component parts must be stable in characteristics and accurate in rating.

The fixed resistors selected for this Potter precision counter are Bradleyunits in the ½, 1, and 2 watt ratings. Being conservatively rated at 70C instead of 40C, Bradleyunits have stable resistance values. Under continuous full load for 1000 hours, their resistance change is less than 5 per cent.

The leads of Bradleyunits are differentially tempered. This graduated softness of the leads near the resistor body prevents sharp bends and avoids damage to the resistor.

Bradleyunits are encased in a plastic insulating shell. Hence, they need no wax impregnation to pass salt water immersion tests. They are available in three tolerances—plus or minus 5%, 10%, and 20%. Let us send the Allen-Bradley resistor chart.

Allen-Bradley Co., 110 W. Greenfield Ave., Milwaukee 4, Wis.

Sectional View of BRADLEYUNIT
showing plastic insulating shell surrounding the resistor unit, permitting these units to be closely grouped with safety. Available up to 22 megohms in all ratings.

ALLEN-BRADLEY

FIXED & ADJUSTABLE RADIO RESISTORS

QUALITY

Sold exclusively to manufacturers of radio and electronic equipment



Electronic

WESTERN GEAR WORKS



Illustrated are a few typical examples of electronic gearing designed for customer requirements.

WESTERN GEAR WORKS

Manufacturers of PACIFIC-WESTERN Gear Products

Pacific Gear & Tool Works

Plants: Seattle
San Francisco
Belmont
Lynwood
(Los Angeles County)
Houston

SLANT your requirements to

INSTRUMENT CORP. OF AMERICA

for miniature

SLIP RING AND COMMUTATOR ASSEMBLIES

This Instrument Corporation of America plant contains the most modern and complete facilities available anywhere in the world for the exclusive production of Miniature Slip-Ring and Commutator Assemblies to precision standards. It is now in full scale production to meet your requirements in the fastest possible time at the lowest possible cost.

COMPLETE ENGINEERING AND PRODUCTION FACILITIES AVAILABLE

Our assemblies can be supplied at low cost. Quality is the highest in the industry. Dimensional accuracy and other characteristics are excellent and these units are highly recommended for instruments such as synchros, etc.

ONE PIECE ELECTRO-PLATED TYPES FOR EXTREME ACCURACY

Wherever extreme dimensional precision, accurate concentricity and high dielectric qualities are required, the electro-deposition method is recommended . . . the production of which is licensed under an exclusive arrangement with the Electro Tec Corporation.

TYPICAL SPECIFICATIONS:

Sizes: .035" to 24" Cylindrical or Flat

Cross-sections: .005 to .060" or more

Finish: Polish to 4 Micro-Inches or Better

Breakdown: 1000 V or More Hi-Pot Inter-Circuit

Ring Hardness: 75 to 90 Brinell

Rotation Speeds: To Over 12000 RPM

Surface Protection: Palladium and Rhodium or Gold Prevent Tarnish, Minimize Wear

Our engineering staff is at your service at all times for consultation

INSTRUMENT CORPORATION OF AMERICA

BLACKSBURG • VIRGINIA

UNDER EXCLUSIVE LICENSE OF ELECTRO TEC CORPORATION


ELECTRONS, INCORPORATED
127 SUSSEX AVENUE
NEWARK 3, N. J.
We offer more inert gas-filled tube types to choose from than any other manufacturer.



—spelt backwards is just another name for quality

HUDSON

STANDARD CASES and COVERS... SPECIAL SHAPES and FEATURES!

PRECISION DRAWN CLOSURES AND QUALITY METAL STAMPINGS—Designers and production engineers can draw on the Hudson line of standard cases and covers to solve "hurry up" closure problems. Several hundred stock shapes and sizes, with numerous variations possible due to optional features available, assure prompt service at mass-production prices. Hudson stock parts can usually meet all but the most unusual requirements.

All components Hudson-produced of selected metal stocks using Hudson-built tool and dies. Available in brass, copper, aluminum and steel. Check with Hudson first! Quotations supplied promptly on receipt of your specifications.

PRECISION DRAWN CASES AND COVERS AND QUALITY METAL STAMPINGS FOR ELECTRONICS

HUDSON TOOL and DIE COMPANY • Inc

118-122 SO. FOURTEENTH STREET, NEWARK 7, NEW JERSEY

HUNDREDS OF STANDARDIZED DESIGN ASSURE FASTEST POSSIBLE DELIVERY! When time is short, consult the Hudson Catalog of stock shapes and sizes. If you have not yet received your copy of this file folder, request yours, today. Keep a copy handy in engineering, production and purchasing departments. Just call or write.



G-E MIDGET AND G-E LIGHTWEIGHT IMPROVE SOLDERING EFFICIENCY AND SPEED IN TIGHT PLACES.

Now—2 G-E Irons for Hard-to-solder Places

FAST PRODUCTION WITH THE G-E LIGHTWEIGHT

Quick heat recovery and easy handling combine to give you quality production at high speed. The thin, $\frac{5}{16}$-inch diameter shank allows easy soldering where a bulkier iron can't reach or would cause damage to insulation and surrounding parts.

PINPOINT ACCURACY WITH THE G-E MIDGET

Soldering difficult joints is as easy as writing with a pencil when you use the slender, 1¾-ounce, 6-volt midget iron. Power costs are cut to one-fourth those of a regular iron, and tip heat can be closely controlled with the optional four-tap transformer.

BOTH LIGHTWEIGHT AND MIDGET IRONS OFFER YOU:

Longer Service, Lower Maintenance—Extra long wearing Ironclad tips resist pitting and corrosion, giving you longer service for both high-speed repetitive production line soldering and intermittent work. General Electric Calrod* heaters provide dependable, efficient operation throughout their long life. The tip and heater unit is easily replaced by unscrewing it from the handle.

Reduced Operator Fatigue—Both irons are light in weight, well balanced, and have comfortable handles. Easy handling helps cut rejects and increase operator speed and efficiency.

SOLVE YOUR SOLDERING PROBLEMS TODAY

For the complete story on the G-E Lightweight and Midget soldering irons contact your G-E Apparatus Sales Office or Distributor. Additional information is yours by mailing the coupon below.

*Reg. Trade-mark of General Electric Company

Section D720-115
General Electric Co.
Schenectady 5, N. Y.

Please send me the following bulletins:

☐ For immediate project ☐ For reference

☐ GED-1583, G-E Lightweight Soldering Iron.

☐ GEA-4519D, G-E Industrial Soldering Irons.

Name.....

Company.....

Address.....

City..... State.....

You can put your confidence in—

GENERAL ELECTRIC

RMC DISCAPS®

APPROVED AND USED BY LEADING MANUFACTURERS

"Heavy Duty" By-Pass DISCAPS

TYPE B



.00047 .00068 .0008 .001	.0015 .002 2x.001	.003 .004* .005* 2x.0015 2x.002*	.0047 .005 2x.002	.01* ±20% .02* +80%−20%	.01* .02*	.01 .02 2x.004

*Rated 600 V.D.C.W. Flash test 1200 V.D.C.

SPECIFICATIONS

TYPE B BY-PASS SERIES—GUARANTEED MINIMUM VALUE

POWER FACTOR: 1.5% Max. @ 1 KC (initial)
POWER FACTOR: 2.5% Max. @ 1 KC (after humidity)
WORKING VOLTAGE: 1000 V.D.C.
TEST VOLTAGE (FLASH): 2000 V.D.C.
LEADS: No. 22 tinned copper (.026 dia.)
INSULATION: Durez phenolic—vacuum waxed
INITIAL LEAKAGE RESISTANCE: Guaranteed higher than 7500 megohms
AFTER HUMIDITY LEAKAGE RESISTANCE: Guaranteed higher than 1000 megohms

HIGH VOLTAGE DISCAPS—*Designed for Deflection Yokes*

NOW AVAILABLE IN ANY CAPACITY BETWEEN 15 MMF AND 240 MMF

SPECIFICATIONS

POWER FACTOR: .1% Max. @ 1 M C (initial)
POWER FACTOR: 2.5% Max. @ 1 M C, after humidity
WORKING VOLTAGE: 2000, 3000, 4000, 5000 V.D.C.
TEST VOLTAGE: 4000, 6000, 8000, 10,000 V.D.C.
LEADS: No. 22 tinned copper (.026 dia.)
INSULATION: Durez phenolic—vacuum waxed
INITIAL RESISTANCE: Guaranteed higher than 7500 megohms
AFTER HUMIDITY LEAKAGE RESISTANCE: Guaranteed higher than 1000 megohms
AVAILABLE TOLERANCE: ±5% ±10% ±20%

SEND FOR SAMPLES AND TECHNICAL DATA

DISCAP CERAMIC CONDENSERS

RADIO MATERIALS CORPORATION

GENERAL OFFICE: 3325 N. California Ave., Chicago 18, Ill.

FACTORIES AT CHICAGO, ILL. AND ATTICA, IND.

DISTRIBUTORS: *Contact* Jobber Sales Co., 146 Broadway, Paterson 1, N. J.

Wrap up your circuitry in these tremendously flexible plug-ins to get these vital advantages!

1. **GET "1-SHOT ENGINEERING"** — you pre-solve Parts Design, Production Layout and Procurement all in "one shot".
2. **SLASH ASSEMBLY COSTS** — manufacture goes fast at low cost, because subdivided into units on which operations are simple and out-in-the-open.
3. **YOUR CUSTOMERS SAY "WONDERFUL!"** — Installation simplified to non-technical push-in connects done in the field as fast as unloaded. Reliability of service provided by 30-second plug in of replacement spares when tell-tales warn.

To move circuitry from layout to completed equipment — IT'S AS SIMPLE AS THIS . . .

ALDEN PLUG-IN PACKAGE

4 SIZES OF PLUG-IN PACKAGES

Alden standard Bases, Lids, Handles, Cans, Sockets for 7, 9, 11 and 20-pin packages house Terminal Card Circuitry with tremendous flexibility for endless variety of open and shielded packags . . . making it easy and inexpensive to give your equipment reliability in service with instantly replaceable plug-ins for all sub-units.



Package components and matching sockets.

4 SIZES OF ALDEN BASIC CHASSIS



Your circuitry on Terminal Card strips snaps right into Alden Basic Chassis. Vertical mounting and hinged front panel give beautiful accessibility and space saving. Chasses can be plugged interchangeably into Standard Racks, Alden Uni-Racks, Alden Portable Cases. Alden Rack Adapter mates Standard Rack to Chassis.

Plugged into Standard Rack with Rack Adapter

Mount in Alden Uni-Racks

Plugged into Portable Cases

Subdivided function by function, your circuitry drops naturally onto Alden Terminal Mounting Cards —



ALDEN PREPUNCHED TERMINAL MOUNTING CARDS cut to proper sizes for 7-pin, 9-pin, 11-pin and 20-pin packages. Or in 3' strips for chassis — cut it off as you require.



ALDEN MINIATURE STAKING TERMINALS Lay out in any pattern on Terminal Mounting Cards; ratchet slots hold elements for soldering without plliering or wrap-around.



ALDEN JUMPER STRIP snakes right under Terminals providing common circuit without soldering.

ALDEN CARD-MTG. TUBE SOCKETS for min. 7-pin, 9-pin and octal tubes.

CIRCUITRY TO MOUNT IN PACKAGE AND CHASSIS

Your chassis circuitry is easily organized with 1 point of check and 30-second replacement —



Alden's new concept in Rack-and-Panel Connectors, eliminates congested rat's nest of blind wiring and provides —


3. Critical voltages isolated by wide spacing.
4. Possible to jump contacts because both sides are instantly accessible.
1. Connectors are spread out in an orderly row, giving a central point of check.
2. All leads are instantly accessible, identified by number and color-coding.

All you need is this Kit —

It's as simple as this —

Arrange Alden Side Rails (1) and Alden Lock Frame (2) to suit your chassis. Alden Serve-A-Unit Locks (3) mount in your chassis to engage prepunched holes in Alden Lock Frame (2) to pilot, draw in, lock or eject.

Tiny tell-tales assigned unit by unit spot trouble instantly —

See how compact front panel easily mounts six tiny Alden Sensing Elements—specifically designed to lick the problem of having only a small amount of space. Assembled by simplest methods.

ALDEN MINI-TEST POINT JACK

For checking critical voltages from front of panel.

ALDEN "PAN-I-LITE"

Miniature indicator light with unbreakable 1-piece light-lens unit replaceable from front.

ALDEN "FUSE-LITE"

Fuse blows — Lite glows. Simple unscrew 1-piece light-lens unit and blown fuse comes out with it.

GET THE COMPLETE STORY — REQUEST "ALDEN HANDBOOK" — SENT FREE



NA-ALD

ALDEN PRODUCTS CO. 127 N. Main St., Brockton 64, Mass.

IRVINGTON
INSULATING VARNISH DIGEST

Finishing Enamel Oilproofs Windings Quickly and Easily

The insulation on electrical windings exposed to contact with oil can easily be given an added degree of protection by application of a coating of Irvington No. 32 Red Enamel over the previous insulation treatment.

This enamel can be readily applied by brushing and air dries to the point where the parts can be handled within half an hour at room temperature. Additional baking and long drying periods are eliminated.

In addition to oilproofing windings, No. 32 Red Enamel protects them against moisture, chemicals, dust and water. It forms a very tough, adhesive film on most surfaces. The enamel is low in initial cost and has the advantage of long storage life.

No. 32 Red Enamel is brushed on windings to protect them from oil

Preheating of Parts Improves Impregnation

Units that are to be impregnated with insulating varnish by dipping should be preheated before being placed in the dip tank.

The preheating aids in expelling any moisture from the parts and also causes the surrounding varnish to decrease in viscosity. This results in more thorough penetration of the windings.

Correct Baking Procedures Essential In Performance of Insulating Varnishes

Design of Ovens and Control of Baking Cycles Play Major Part in Satisfactory Curing

It is generally accepted that baking varnishes provide greater all-around qualities than air drying varnishes. Air drying varnishes are used mainly for maintenance purposes or where baking facilities are unavailable.



After vacuum impregnation with a clear baking varnish, heavy transformer coils are baked in an oven like the one shown

Spray Method Can Be Used on Large Pieces

While the two recommended methods of applying insulating varnish are dipping and vacuum-and-pressure impregnation, there are instances where the unit is too large for the capacity of existing shop equipment.

In such cases, the varnish may be applied by spraying. It is usually necessary to apply the varnish at a lower viscosity than is customary with other methods. Air pressure and consistency of varnish should be adjusted to produce a smooth, uniform coating.

When baking varnishes are applied by spraying, the standard baking schedules should be followed to assure a complete cure. Spray application is also frequently used for Irvington air drying varnishes, which are recommended chiefly for emergency repair and maintenance work.

Baking varnishes are made in a variety of types specially formulated to provide high dielectric strength, resistance to high temperatures, vibration, moisture, oils, chemicals, dust and fumes. These qualities can be achieved only by proper varnish curing.

Design of Oven

A well-designed baking oven should provide dry heat at controlled temperatures which are uniform throughout the entire oven. Any variations between the temperatures in different parts of the oven may result in faster curing of the varnish on some insulated windings than on others. Service performance of the varnish will then tend to be non-uniform.

The oven should be provided with a ventilating system to remove solvent fumes released from the varnish. Otherwise the solvent fumes continue to circulate through the oven, washing over the windings that are being baked and preventing them from drying thoroughly.

Baking Schedules

Baking temperatures and times should conform to the recommendations of the varnish manufacturer. In any cases where unusual conditions are involved — such as in the case of deep-seated windings or multiple coats of varnish — it is desirable to consult a representative of the varnish manufacturer on the specific procedures that will give most effective results.

For further information, write the Sales Manager, Varnish Department, Irvington Varnish & Insulator, Division Minnesota Mining & Manufacturing Company, 11 Argyle Terrace, Irvington, New Jersey



Look closely at the picture below. This spotlessly clean and orderly paint spray room is but one of the outstanding facilities available to you at Karp. And this "good housekeeping" is reflected by the gleaming hammertone enamel finish of the marine radio cabinet at left—typical of the uniformly high quality finish we give your cabinets, chassis, housings and enclosures.

Another Karp facility: Where our finish is the beginning of lower enclosure costs for you.

Because this entire spray room is air conditioned—completely dirt and dust free, and because it is manned with specialists in surface preparation and finishing who work with the most modern equipment, we are able to assure you of the finest quality finish for any type service or exposure.

And to make sure that the finish lasts for the life of your enclosure it is carefully baked in our electro-mechanically timed ovens. Result: your perfect finish is a lasting finish. Attractive but tough—and always economical.

Like the Finishing Department, our entire plant is dedicated to the principle of producing the finest sheet metal cabinets, chassis, housings and enclosures *at the lowest possible price*. How well we live up to this principle is easily proved: simply send us your prints. We'll promptly quote prices and delivery.

KARP

MOST COMPLETE FACILITIES FOR ENGINEERED SHEET METAL FABRICATION

KARP METAL PRODUCTS CO. *Division of H & B American Machine Company*
215 63RD STREET, BROOKLYN 20, N. Y.

FACILITIES FOR ENGINEERED SHEET METAL FABRICATIONS: in aluminum or steel • long run or short • spot, arc, gas or heliarc welding • any type finish.

- Modern plant—3 city blocks long
- Thousands of dies available
- Most modern of sheet metal fabricating equipment
- U. S. Air Force Certified Welding Facilities
- Air-conditioned spray room... complete baking facilities
- Complete sub-assembly facilities

Want more information? Use post card on last page.

Can you see the BIG difference?

On the face of it, Avien's Two-Unit Fuel Gage looks like previous systems, but there's a big and important difference behind it all.

Behind this Avien dial face (shown here three times actual size) is Avien's brand-new concept of fuel gage system "packaging."

Previously, you'd find these units behind a dial: an indicator case, motor and balancing potentiometer; and elsewhere a bridge-amplifier, a shockmount and a tank unit.

Now, in the Avien Two-Unit Gage, the necessary components for the bridge and amplifier functions have been built right into the indicator case.

The result: a fuel gage system of "plug-in, plug-out" simplicity, which weighs 50% less and eliminates the need for any field calibration.

What a BIG difference this makes in money!

First of all, the basic system costs less. Less time is spent in installation. Less wiring and connectors are needed. Less maintenance is required, because there are fewer components to maintain. Trouble-shooting time is cut for the same reason. And fewer parts must be stocked for maintenance and repairs.

Because of this new package, Avien gages are now "shelf items." They're completely interchangeable in the aircraft for which they are designed.

Additional functions for fuel management can be easily integrated into the basic Two-Unit system.

The Avien Two-Unit Fuel Gage is now available to meet your production programs. The indicator is available in either large or small sizes, with all varieties of dial configurations.

Every month, Avien produces over ten thousand major instrument components for the aviation industry.

The Avien Two-Unit Fuel Gage will make such a BIG difference in your cost sheet, we suggest that you write or call for more information today.

Avien

AVIATION ENGINEERING DIVISION
AVIEN-KNICKERBOCKER, INC.
58-15 NORTHERN BOULEVARD, WOODSIDE, L. I., N. Y.

The first of two articles on profits

PROFITS... How High Are They?


SHARE OF THE NATIONAL INCOME GOING TO PROFITS*
Percent of National Income
10
9
8
7
6
5
4
1939 '40 '41 '42 '43 '44 '45 '46 '47 '48 '49 '50 '51 '52 '53†
*Net Profits After All Federal and State Taxes
†Annual Rate in First 6 Months
Source: U.S. Dept. of Commerce

How high are profits? What is being done with them? This is the first of two articles designed solely to throw some factual light on these key economic questions.

One of the important economic developments of 1953 has been a substantial increase in the dollar volume of corporation profits from the level of 1952. But to answer the question "How high are profits?" we must also measure them: 1) by comparison with the record of previous years, and 2) as a share of the total national income. The term "profits," as used here, refers to profits *after taxes*. These are the only profits that can be paid to stockholders or retained for use in the business.

In the first six months of 1953, corporate profits *after taxes* were at an annual rate of $20.4 billion. This was higher than in the first half of 1952, but lower than in the full years 1948 or 1950, or in the first half of 1951. If allowance is made for the declining value of the dollar, this year's net profits for all corporations represent less purchasing power than those made five or six years ago.

Here is the record of profits over the years:

	Net Profits After Taxes of All U. S. Corporations	
	Billions of Dollars	
	Actual	In 1953 Prices
1929	8.4	14.6
1939	5.0	9.8
1947	18.5	22.1
1948	20.7	22.7
1949	16.3	18.3
1950	22.7	24.6
1951	20.1	19.7
1952	18.6	18.7
1953*	20.4	20.4

*Annual rate, first six months

The record shows that real profits have a little more than doubled since 1939. This increase, however, does not mean that corporations are doing exceptionally well. The entire national income has doubled since 1939. And our industrial plant is more than twice as large as it was in 1939. Therefore, profits have just about kept pace with industrial growth.

Return on Investment

How high are profits compared with sales, or compared with the stockholders' investment?

What is the rate of return to the people who have invested their savings in corporate business?

The table below shows that for the past three years the rate of return on both sales and investment has been substantially below the return achieved in earlier postwar years. The rate of return on stockholders' investment is higher now than it was in 1939. But this is primarily because today's profits are reported in terms of today's prices, whereas much of the investment in plant facilities is still carried on the books at prewar prices, which are substantially below the cost of replacement. The current rate of return, measured as a percentage of total corporate sales, is below prewar levels.

	Corporate Profits After Taxes	
	Per Cent of Total Sales	Per Cent of Stockholders' Equity *
1929	6.1	NA
1939	4.1	4.0
1947	5.3	
1948	5.3	
1949	4.4	14.8 average
1950	5.3	
1951	4.1	11.8
1952	3.6	10.3
1953#	3.7	10.8

* Manufacturing corporations only
NA Not available
Annual rate, first six months

In considering these figures, it should be remembered that they are averages for all corporations. Some companies make more than the average, and many make no profit at all. In every year since 1915 at least 25% of all corporations have operated at a loss. In 1939, 58% of all corporations were losing money. This year the figure will probably be at least 30%. The improvement since 1939 shows a much healthier economy. But it does not indicate that profits are easy to make.

How Big a Share of the Pie?

The most important single fact about profits is that they now represent a *smaller* share of national income than they have in past years of normal prosperity. For the past three years, profits have taken a smaller share of the pie than in 1939, and considerably smaller than in the early postwar years. Here, as the chart at the beginning shows, is the record:

	Corporate Profits After Taxes as a Percentage of National Income
1929	9.6
1939	6.9
1947	9.3
1948	9.3
1949	7.5
1950	9.4
1951	7.2
1952	6.4
1953*	6.6

*Annual rate, first six months

The main reason for the declining corporate share of national income is, of course, the increasing share taken by the federal government in the form of taxes. The wage earners' share is also higher than in 1939. But the really startling increase is in federal taxes. Taxes on profits now equal almost 8% of the national income, compared to only 2% in 1939.

Why This Is Important

It is important that these facts about profits and taxes be widely understood. At its next session, Congress must consider what to do about the emergency taxes on profits enacted after the outbreak of the Korean War. The so-called excess profits tax is scheduled to die on January 1, 1954. In the absence of new legislation, the rate of the corporate income tax will drop from 52% to 47% on April 1. Many factors, including the revenue needs of the government, must enter into the decision whether or not to reduce taxes. But one fact stands out clearly: By comparison either with past years or with the total national income, corporate profits today are relatively low.

* * *

The second article in this series will discuss what corporations do with their profits.

McGraw-Hill Publishing Company, Inc.



Special 136 conductor cable carefully engineered by Rome for use with IBM electric accounting machines, Types 402 and 403; IBM Reproducing Punch, Type 514; IBM Summary Punch, Type 523; and IBM Accumulating Reproducer, Type 528.

Spools of Rome hook-up wire set up on multiple spool racks used in making cables for practically all IBM electric accounting machines.



Carefully engineered wires and cables help keep IBM equipment "on the beam"

Equipment manufactured by International Business Machines Corporation has established a record for accuracy and service that's hard to beat.

Much of the reason for this record is the fact that IBM uses only the finest components in their equipment.

This is one of the reasons IBM often comes to Rome Cable for top quality, specially engineered wires and cables. One of these is the 136 conductor cable (pictured top center) which is used in several IBM machines.

Others are various types of hook-up wire, a few of which are shown on the multiple spool rack (top left). Millions of feet of this Rome hook-up wire, manufactured to exacting specifications, are used by IBM every year.

In addition to the constructions shown, Rome manufactures a wide range of military and commercial type hook-up wires, intercommunication cables, coaxial cables, R. F. transmission line, television camera cables and other special constructions, engineered to the application involved.

Commercial type HOOK-UP WIRES

Rome offers commercial hook-up wires with three standard insulations.

Rome Hi-Temp—a rubber insulation with exceptionally high resistance to heat. Underwriters' approved for 75° C.

Rome Synthinol—a polyvinyl chloride thermoplastic compound, highly resistant to acids, oils, alkalies, moisture and flame. Underwriters' approved for 80° C.

Rome Synthinol 901—offers all the advantages of Synthinol plus higher resistance to heat deformation, shrinkage and cracking, also improved solderability. Underwriters' approved up to 105° C.

MILITARY HOOK-UP WIRES

Rome manufactures military type SRIR, SRHV and WL, complying with Army-Navy Joint Specification JAN-C-76, as well as shipboard types SRI and SRIB conforming to Specification MIL-C-915. Insulated with Rome Synthinol, these wires are made in a complete range of specification sizes.

ROME CABLE Corporation
ROME · NEW YORK
and
TORRANCE · CALIFORNIA

ROME CABLE CORPORATION, Dept. EL-11, Rome, N. Y.
Please send me information on Electronic Wiring

Name.....

Company.....

Address.....

City..... Zone..... State.....

Want more information? Use post card on last page.

The Superior anode family is on the air



When you meet anyone in radio or television circles named Anode, the chances are favorable that he was born in Norristown, Pa., at Superior Tube Company.

Millions of Anodes have started life at Superior—all types and sizes—stainless steel, nickel, Monel*, Inconel*, straight cut, angle cut, rolled—one or both ends, flattened, bent—and for all types of vacuum tubes.

If the anode you want isn't pictured, tell us about it.

A—Weldrawn†, 304 Stainless Steel, Double angle cut. .520" O.D. x .500" I.D. x 1.321" long.

B—Weldrawn, 305 Stainless Steel, Single angle cut. .520" O.D. x .500" I.D. x 1.102" long.

C—Weldrawn, 305 Stainless Steel, Straight cut. .520" O.D. x .500" I.D. x 1.750" long.

D—Weldrawn, 305 Stainless Steel, Rolled and bent 10°. .449" I.D. x .010" Wall x 1.050" long.

E—Seamless Nickel, Flattened one end. .500" O.D. x .025" Wall x 1.625" long.

F—Weldrawn, 305 Stainless Steel, Rolled one end. .500" I.D. x .010" Wall x 1.182" long.

GUN ASSEMBLY FOR ELECTRO-STATIC TYPE TELEVISION PICTURE TUBE

All of the anode elements (as well as the disc cathode) are fabricated from Superior Tubing. A critical part of this assembly is the "focusing anode" or "focusing ring", produced from Superior Stainless Steel ⅝" O.D. x .028" wall, cut to ½" lengths. It is of extreme importance that the finish of the focusing ring be smooth, and that the I.D. be burr-free else corona would occur and the flow of electrons to screen would be distorted. Superior achieves its degree of smoothness and freedom from burrs by a special and exclusive process.



Seamless Nickel Cathode. Round, flanged one end, .070"/.072" I.D. x .0025" Wall, .295" long.

Disc Cathode .121" O.D., .312" long.

Lockseam†† Nickel Cathode Round, tabbed, single bead, .045" O.D. x .0021" Wall. 27 mm long.

No. 1 Grid Cup, 305 Stainless Steel. .499" I.D. x .010" Wall x .438" long.

Superior
THE BIG NAME IN SMALL TUBING

SUPERIOR TUBE COMPANY
Electronics Division
2500 Germantown Ave., Norristown, Pa.

All analyses .010" to ⅝" O.D. Certain Analyses (.035" max. wall up to 1⅜" O.D.)

*Registered U. S. Trademark, International Nickel Company

†Manufactured under U. S. Patents

††Trademark Reg. U.S. Pat. Off.

Want more information? Use post card on last page.

New Waldes Truarc GRIP Ring requires no groove, holds fast by friction, can be used over and over again



Ring # 5555		5555-12	5555-13½	5555-18	5555-25	5555-31	5555-37
SHAFT DIAMETER	Fract. Equiv. S	1/8"	—	3/16"	1/4"	5/16"	3/8"
	Dec. Equiv. S	.125	.136	.187	.250	.312	.375
	TOL.	±.002	±.002	±.002	±.002	±.003	±.003
RING DIMENSIONS	Thickness T	.025	.025	.035	.035	.042	.042
	TOL.	±.0015	±.0015	±.002	±.002	±.002	±.002
	Length A	.268	.285	.364	.437	.553	.626
	Lug B	.078	.078	.097	.097	.141	.141
	Hole P	.042	.042	.042	.042	.078	.078
	Min. Ring Clear C	.33	.34	.44	.50	.67	.73
Approx. Ultim. Thrust Load (Lbs)		20	20	25	35	50	60

The Waldes Truarc Grip Ring is a new, low cost fastener that provides a positioning shoulder secure against moderate thrusts or vibration. Installed on a straight ungrooved shaft, the Truarc Grip Ring can be assembled and disassembled in either direction with Truarc pliers.

The Grip Ring can be installed tightly against a machine part in order to take up end-play. The basic Truarc design principle assuring complete circularity around periphery of the shaft and the ring's unusually large radial width combine to exert considerable frictional hold against axial displacement. The ring can be used again and again.

Find out what Waldes Truarc Retaining Rings can do for you. Send us your drawings. Waldes Truarc engineers will give your problems individual attention without obligation.

SEND FOR NEW CATALOG

WALDES

TRUARC

REG. U. S. PAT. OFF.

RETAINING RINGS

WALDES KOHINOOR, INC., LONG ISLAND CITY 1, NEW YORK

WALDES TRUARC RETAINING RINGS AND PLIERS ARE PROTECTED BY ONE OR MORE OF THE FOLLOWING U. S. PATENTS: 2,382,947; 2,382,949; 2,410,953; 2,420,321; 2,420,341; 2,439,705; 2,441,866; 2,455,165; 2,483,300; 2,483,383; 2,487,802; 2,487,803; 2,491,308; 2,500,081 AND OTHER PATENTS PENDING.

Waldes Kohinoor, Inc., E 115
47-16 Austel Place, L.I.C. 1, N. Y.

☐ Please send me sample Grip-Rings (please specify shaft size _____)

☐ Please send me the complete Waldes Truarc catalog.

(PLEASE PRINT)

Name_____

Title_____

Company_____

Business Address_____

City_____ Zone____ State_____



ED SCHWERSKE, skilled inspector at Anaconda, checks enamel magnet wire for surface quality. This wire will be used in automatic multiple-head coil-winding machines where high quality, uniformity, greater spool lengths are important.

He keeps harping . . . on quality

LET'S START by being frank. Today the only practical way to make magnet wire that is perfect for commercial applications is under strict quality-control procedures.

At Anaconda, quality is determined by statistical limits—or fences—beyond which no phase of production may stray. Charts of each process are kept to guide machine operators and foremen on their road to higher quality. The narrower the control limits, the better the wire. These limits—at Anaconda—are the most exacting in the industry today.

MANY TESTS ARE MADE

Ed Schwerske's sensitive fingers check wire smoothness. But—thorough as Ed's inspection is—it is only one of 30 tests the wire must pass.

Want more information? Use post card on last page.

DRAWING FINE WIRE demands close tolerances. Wire is "miked" in the process to make sure it's within acceptable limits. If not, the reel is rejected. Anaconda's reject rate is low—all the more impressive because of rigid standards—the most exacting in the industry.

REGULAR AS CLOCKWORK. This inspector thoroughly checks wire on large enameling machines. Every 1½ hours he makes a record of his inspections on the card which hangs beside each machine. This card becomes part of the permanent quality-control record.

Each test is recorded. And in that complete record is the final proof of the quality of ANACONDA Wire.

TYPICAL CUSTOMER EXPERIENCE

Listen to Head Inspector, Merrill Bailey: "When I hear how one customer now winds 11 sticks of 20 coils with ANACONDA Wire where he could wind only 7 sticks before, I know our painstaking inspection pays off. His coil-winders say our wire winds faster, easier, and longer without breaks."

ANOTHER PROOF OF QUALITY

The list of customers who have depended on ANACONDA Magnet Wire for 25 years or more is long . . . and many buy 80-90% of their wire from Anaconda. Many have further expressed their confidence by eliminating incoming inspection of the wire . . . at considerable savings.

Would you like to see how Anaconda Quality Control actually works? Ask your Anaconda Representative to arrange for a plant visit. There you will see typical Anaconda thoroughness at work—the legacy of over a half century of experience and leadership. *Anaconda Wire & Cable Company, 25 Broadway, New York 4, N. Y.* 53360

ANACONDA®

TODAY'S HEADQUARTERS FOR MAGNET WIRE

BREAKDOWN TEST FOR FORMVAR. A sample from every reel is given this test. The wire is first put under tension by twisting. Then a gradually built-up potential is applied until the wire breaks down. This makes sure that the dielectric strength is ample.

FINGER ON QUALITY CONTROL. Every Anaconda Operator is concerned with the performance of his machine. Here foreman and operator go over control chart which graphs reject rate—in this case close to nominal. If it should stray, machine is shut down.

*Reg. U.S. Pat. Off.

A COMPLETE LINE:
ANY TYPE, SIZE OR SHAPE
—round, square, rectangular—

Your *special* needs will be given *special* attention.

Write for complete pocketsize catalog C69A and handy reference wall chart for shop use (gives dimensions of popular wire sizes).



EQUIFLEX
metal Vibration Isolators...

. . . ensure long life, resistance to temperature extremes and absence of drift or permanent set.

Each unit consists of a tubular core attached by springs either to a square mounting plate or to a circular mounting cup. The springs are arranged to form two opposed cones. Within these cones of springs, are two floating metal stampings held apart by an internal compression spring. This damper keeps amplitude within safe limits at resonant frequencies. Overload and shock conditions are met by heavy, rebound washers securely fastened to each end of the tubular core.

The mountings withstand 100 hour salt spray tests, take 15G shocks without damage and will keep equipment captive up to 30G's.

Extra-damped mountings are available in which each multiple coil spring is shrouded with polyethylene tubing.

For further details, write for illustrated, descriptive folder.

ELECTRICAL ASSEMBLIES Ucinite RADIO AND AUTOMOTIVE

The UCINITE CO.

Newtonville 60, Mass.

Division of United-Carr Fastener Corp.

Specialists in

ELECTRICAL ASSEMBLIES, RADIO AND AUTOMOTIVE

NEW Quickey FASTENER



- **FACILITATES NESTING of sheet metal stampings**
- **ELIMINATES DAMAGE due to welded or staked studs**



Not this

Welded or staked studs are easily damaged in transit from one department to the next or during processing, painting, polishing, etc. The bolts themselves can cause serious damage, denting, scratching or chipping painted or polished surfaces.

But this

QUICKEY SNAPS IN just before final assembly . . . allows finished parts to be nested for economical transportation *without* protruding studs of any kind. Installed at the last moment, every Quickey is perfect. If damaged during later assembly operations, any Quickey can be removed and replaced easily and quickly, even in blind assemblies.

•

Like thousands of other fasteners and allied devices, designed and manufactured by United-Carr, Quickey helps speed assembly and cut costs. Available in a complete range of sizes and in volume quantities; further details on request.

UNITED-CARR

MAKERS OF DOT FASTENERS

UNITED-CARR FASTENER CORPORATION, CAMBRIDGE 42, MASSACHUSETTS

BRAND-NEW TUBES FOR COLOR TV....



Developmental color-TV chassis

G.E. WILL HAVE THEM FOR YOU!



TRI-COLOR PICTURE TUBES
Aluminized glass, in the needed sizes

***New* receiving tubes to improve color-TV circuit efficiency and economy, such as:**

SYNCHRONOUS DETECTOR

HIGH-VOLTAGE REGULATOR

TRIPLE DIODE

HIGH-CURRENT FULL-WAVE RECTIFIER

HIGH-VOLTAGE RECTIFIER

HIGH-CURRENT DAMPING DIODE

THE first color-TV sets will be expensive to build. For one thing, their large tube complements will be made up of types not designed for color-circuit applications.

From the start, designers and builders will strive to cut color-chassis costs, in order to bring down receiver prices and profit from the wider market these reductions will create.

G-E tube designers already are working toward that end! At left are some of the tubes in development. Each will help give you one, or both, of these benefits:
(1) a more efficient, simpler color circuit,
(2) fewer tube sockets to be filled.

Make the most of tomorrow's massive opportunity in color TV by planning ahead for lower set prices! Get in touch *now* with your G-E tube commercial engineer!

Phone, wire, or write the General Electric tube engineer nearest you!

CHICAGO
R. E. BERRY
C. J. BIVER
H. W. A. CHALBERG
●
Tube Department
General Electric Company
3800 North Milwaukee Ave.
Chicago 41, Ill.
●
Phone: SPring 7-1600

CLIFTON, N. J.
W. E. CRONBURG
W. R. RATE
F. W. TIETSWORTH
●
Tube Department
General Electric Company
200 Main Avenue
Clifton, N. J.
●
Phone: GRegory 3-6387

LOS ANGELES
R. R. W. LACY
●
Tube Department
General Electric Company
11840 West Olympic Blvd.
Los Angeles, Calif.
●
Phone: BRadshaw 2-8566
or ARizona 9-7765

GENERAL ELECTRIC

162-1A3

"WALKIEPHONE" PTC 122/123

PORTABLE RADIO-TELEPHONE FOR CIVIL ENGINEERING COMMUNICATIONS









For purposes of routine inspection and maintenance the Pye V.H.F. Walkiephone makes a valuable but inexpensive addition to any V.H.F. Scheme. Armed with this lightweight equipment one man becomes, unimpeded, a source of information and when required, a centre of control. In places both unexpected and inaccessible the Pye "Walkiephone" ensures the smooth control of emergency operations. Robust, reliable, and economical in use, the complete equipment weighs only 10½ lbs with batteries.

Telecommunications

PYE LIMITED CAMBRIDGE ENGLAND

Burton browne advertising

Barton browne advertising



things are NOT as they seem . . .

This is a perfect square within the circle —it is an optical illusion that the sides bend.



Things are not as they seem . . .
These two fuses look alike . . .
But they are not.

This fuse may burn out anywhere along the length of the filament even in the cap—this blown fuse is impossible to detect visually.



This Littelfuse has a controlled blowing point—the filament is plated throughout its length except in the very center—the fuse will always blow here. A blown Littelfuse can be detected immediately—a Littelfuse feature.

Littelfuse holds more design patents on fuses than all other manufacturers combined.

LITTELFUSE

DES PLAINES, ILLINOIS

This is the . . . K-TRAN*

. . . the original permeability tuned 3/4" I.F. transformer introduced by Automatic in 1945. Since then, many have tried to imitate and copy it, but failed, due to Automatic's patents and manufacturing know-how.



Many long threads under steel spring tension maintain core torque accurately. Core is not supported by coil form.

Iron cores supported by side frames. Coils supported by core. Differing thermal expansion rates of coil form and side frames give thermal stability correction. *Only* K-TRANS have this feature.

Powdered iron core designed and manufactured by Automatic has center tongue for permanent adjustment and an integral shell giving complete magnetic shielding except for coupling flux.

Holes to seat the patented K-TRAN mounting clip, which assures perfect grounding.

Silvered mica capacitors manufactured entirely by Automatic.

High temperature plastic supports. Safe for use up to 90°C. Made in Automatic's molding plant.

Special *thin* wall coil form manufactured by Automatic.

Shield manufactured in Automatic's aluminum department.

All leads located exactly by threading into side frames. Capacity coupling is absolutely uniform.

Heavy spring pressure plate guarantees capacitor stability.

Automatic also manufactures the K-CAP the finest ceramic capacitor available.

AUTOMATIC MANUFACTURING CORPORATION

MASS PRODUCERS OF ELECTRONIC COMPONENTS

65 GOUVERNEUR ST. NEWARK 4, N. J.

*Manufactured under U. S. Patents 2429468, 2547085, 2435630, 2483919



Everlock's alternating chisel edges actually BITE into both surfaces—into the face of the work and the nut—and are held in place permanently by powerful spring tension.

Available in four standard types or special to your exact specifications.

When ordering screw-washer assemblies from screw manufacturers specify EVERLOCK washers for quality and fast service.

WRITE FOR LATEST CATALOG AND PRICES

THOMPSON-BREMER & COMPANY • 520 N. DEARBORN STREET, CHICAGO 10, ILLINOIS

SUBSIDIARY OF AMERICAN MACHINE AND FOUNDRY COMPANY • NEW YORK, N. Y.

Want more information? Use post card on last page.

CAPACITORS

G.E. ANNOUNCES a new line of

Micro-miniature Tantalytic Capacitors

Smallest electrolytic capacitors commercially available— permit new design flexibility for low-voltage d-c applications

General Electric's new *Micro-miniature* Tantalytic capacitors combine *smaller-than-subminiature* size, large capacitance and low leakage current. They permit new design flexibility in low-voltage, d-c circuits . . . particularly transistorized subminiature assemblies where space is at a premium, such as hearing aids.

SUPERIOR PERFORMANCE. *Micro-miniature* Tantalytic capacitors outperform aluminum electrolytics in electrical stability, operating and shelf life, because of the inert characteristics of tantalum metal and the stability of its oxide. They gain added reliability from the use of silver cases, a non-acid electrolyte, and complete sealing that prevents leaking and contamination of the interior.

WIDE TEMPERATURE RANGE. *Micro-miniature* Tantalytics can operate over a −20 C to +50 C range—may be stored at −65 C. With some capacitance derating, they can operate well below −20 C. At −55 C, units rated 10 volts and above will maintain at least 65% of their 25 C value. They also perform satisfactorily above +50 C with some life limitations.

AVAILABILITY. Designed especially for non-resonant, non-critical applications such as coupling, by-pass and filtering, *Micro-miniature* Tantalytics can be obtained in sample lots 2 to 3 weeks after your order is received at the factory. Production lots can be shipped 6 to 8 weeks after your order is received. For more information, see your G-E Apparatus Sales Representative or write for bulletin GEA-6065 to General Electric Company, Section 442-13, Schenectady 5, N. Y.

Progress is our most important product

GENERAL ELECTRIC

AVAILABLE RATINGS

Working volts d-c	Maximum muf	
	5/16" Length	1/2" Length
2	3.0	6.0
4	2.0	4.0
6	1.5	3.0
8	1.2	2.5
10	1.0	2.0
16	.7	1.5

These ratings are based on known muf X volt capabilities. They meet the −15% to +75% capacitance tolerance. Other ratings, particularly whole muf values, can be supplied if the muf X volt rating is not exceeded for the voltage involved.



LARGE CAPACITANCE and small size make Micro-miniature Tantalytics valuable where space is at a premium. Diameters are .125 in.

IDEAL COMPANIONS. Transistors and Micro-miniature Tantalytics make ideal companions in low-voltage d-c miniaturized assemblies.

1,000,000 Capacitors . . .

and Not a Defective One in the Lot

(so a customer told us)

Whenever you have a problem involving capacitors or related circuits, get in touch with us. Our engineers will be glad to work with you. If you want complete data on any of the following types of capacitors, write us for literature.

Dry Electrolytic Capacitors
- Normal applications
- Temperature extremes
- Sub-miniature size

Paper Dielectric Capacitors
- Metal tubulars
- Bathtubs
- Noise suppression

A customer who buys Mallory Capacitors at the rate of a million or more per year, reported their records showed not a single field reject during the past twelve months.

Actually there may have been some defective units during that time. It hardly seems possible to make a million of anything with a perfect score.

But, the significant point is that this customer . . . like many others . . . has found by experience that the reject ratio on Mallory Capacitors is lower than that of any other supplier they deal with.

Unusual story? Not at all. This kind of dependability is the natural result of the exacting standards for manufacturing and quality control you find at Mallory. You are assured of absolute uniformity when you buy Mallory Capacitors . . . whether it is a hundred or a million.

Expect more . . . Get more from **MALLORY**

Parts distributors in all major cities stock Mallory standard components for your convenience

P. R. MALLORY & CO. Inc.

MALLORY

SERVING INDUSTRY WITH THESE PRODUCTS:

Electromechanical — Resistors • Switches • Television Tuners • Vibrators
Electrochemical — Capacitors • Rectifiers • Mercury Batteries
Metallurgical — Contacts • Special Metals and Ceramics • Welding Materials

P. R. MALLORY & CO. INC., INDIANAPOLIS 6, INDIANA

Want more information? Use post card on last page.

electronics

W. W. MacDONALD, Editor

NOVEMBER • 1953

CROSS TALK

▶**BUSINESS** . . . Conversations with men in many fields during the past month reflect a rather widespread belief that American business may drop as much as 10 percent in 1954. It is not seriously expected to dip lower than that because people have money in the bank and jobs. McGraw-Hill's economist describes the prospect as a not unhealthy decline "from super-boom to prosperity."

In our travels it seems that pessimism is found largely in businesses not accustomed to frequent introduction of new products. Optimism, on the other hand, is found in businesses that expect to grow with new products. Electronics is one such business, and this is why so many people look to us for compensating increases.

Electronics could go up in 1954, might hold level. If it drops the drop will be less than in most other businesses.

▶**MECHANIZATION** . . . In June we said "this might be the first commercially significant year for circuit mechanization." Several things have happened since to strengthen that conviction.

More small radios utilizing machine-made wiring have come on the market. Many television sets now utilize subassemblies employing such wiring. We've heard about an experimental tv set in which not only wiring but virtually all interconnection of component parts is accomplished without the aid of human hands. A system of complete military circuit mechanization, including automatic testing, has been demonstrated. Top management in many companies has issued what amounts to an edict that engineers down the line must develop still better labor-saving systems, and do it soon. An active industry engineering committee studying mechanization methods is becoming even more active, now with an eye on the calender.

Mechanized wiring is well along, although many engineers think ideal materials and methods are just barely within sight. Mechanization of complete circuits, on the other hand, is still in the early experimental stage; machine inflexibility continues to be a problem but it is one that will eventually be solved.

▶**MANPOWER** . . . The technical-personnel market is still tight, but not as tight as it was six months ago. The cost of finding men nevertheless remains high. A chief engineer of our acquaintance has kept score on help-wanted-ad costs over the years. He tells us that it cost him $700 to find a man he wanted back in 1951. Now it costs $1,100.

▶**SCANNER** . . . In July we put in a personal, boat-owner's plea for a depth finder that would tell us what was *ahead* rather than under. On the market today is a unit that not only does this but scans and also tracks if you want it to.

▶**TRANSISTOR** . . . Don't sell glass, vacuum pumps or rare gases short. There are signs that all three may be very useful in the manufacture of transistors. For special applications, at least, it is now known that germanium dislikes contact with most solids and liquids; put it in a bottle, pump the air out and admit the right kind of gas, and temperature and humidity as well as mechanical troubles decline.

▶**TRANSITOR** . . . Proofreaders will please curb an understandable urge to put another S in this word, because we do mean transitor. It is a word used by some tv-station engineers to describe the devices upon which the camera is focused when making transitions between scenes. A whirling spiral disc may be used, for example, to denote shifting of action to the thought, dream or spirit world.

▶**COVER** . . . Several contemporary magazines have used 3-D front-cover pictures, supplying subscribers with the necessary glasses. Not to be outdone, it seems, ELECTRONICS mailed out a couple of copies last month with faulty front-cover registry. One of them just bounced back from the field along with a kidding letter and a pair of plastic specs. Darned if it doesn't look like deliberate 3-D!

By J. E. BINNS
Associate Engineer
Brookhaven National Laboratory
Upton, N. Y.



West face of reactor at Brookhaven. N. Y. Research workers on balcony are performing experiments with neutron beams emerging from the reactor

Electronic Control

Safe operation of Brookhaven's nuclear reactor requires use of several types of electronic instruments for neutron sensing over the wide range of levels encountered. Servo system is provided for automatic operation of the reactor at constant level

BROOKHAVEN'S NUCLEAR reactor consists of a 25-ft cube of graphite that contains rods of uranium, the fuel, and rods of boron steel for control. Although this reactor was designed to afford a maximum of experimental facilities and is quite different from the power-producing and fuel-breeding reactors of the future, it presents many of the same instrumentation problems.

The major problem is control of neutron production in the reactor. Neutron production ranges between 10^6 and 10^{10} neutrons per second. A neutron is commonly detected by allowing it to be absorbed by some nucleus that then becomes unstable and splits into charged fragments that produce copious ionization in passing through a gas. These gas ions are collected on a charged electrode and cause a current to flow in the external signal circuit.

At high neutron levels the average signal current is great enough to provide a usable d-c signal; at low neutron levels this d-c component is below the noise level, and it becomes necessary to count individual pulses of current.

Starting Up

When the reactor is shut down, all the neutron-absorbing control rods are in the reactor and the neutron level is so low that it has to be observed by an ion chamber that utilizes the fission of U^{235}. The signal consists of discrete pulses that average about one per second. The circuit rejects low-energy noise pulses, equalizes the signal pulses as to energy content and takes a time average, which is proportional to the average pulse rate. The counting rate meter is illustrated in Fig. 1A.

The operator now withdraws one of the boron-steel control rods. Since fewer neutrons are being absorbed, the reactor is now a better multiplier of neutrons and the counting rate rises on an exponential curve, leveling off at a slightly higher value.

Withdrawal of each successive rod causes an increase in counting rate, the increments becoming larger and larger. These are analogous to the output increments obtained from an amplifier with some positive feedback and a constant small input signal when the gain is increased in equal steps. These phases of the reactor startup are shown in Fig. 2.

By the time the counting rate meter goes off scale with an increase in level of a factor of 104, the next instrument begins to respond. This is the period meter. See Fig. 1B. It uses a boron-lined ion chamber to sense neutrons. Here the d-c level is high enough to be used as the signal for a d-c amplifier whose output is proportional to the time derivative of the logarithm of the input, that is, to



FIG. 1—Counting rate meter used to measure low neutron levels (A) and period meter used to measure higher levels (B)



FIG. 2—Phases in starting up a nuclear reactor

# of a Nuclear Reactor

the percentage rate of rise of the neutron level or to the reciprocal of the reactor period. At this stage of startup the response is in the form of a transient deflection that becomes larger with each successive rod withdrawal.

The reactor is still subcritical, that is, the neutron level is a function of control-rod positions. Eventually the reactor becomes supercritical, which means that the neutron level rises exponentially without apparent limit. This is analogous to the building up of amplitude of self-sustained oscillation in an amplifier after critical gain has been exceeded.

The farther the rod has been pulled past the critical position the greater is the rate of rise of the neutron level. The period meter now shows a steady reading. The operator adjusts the rod to give a safe rate of rise. If he brought up the neutron level on too short a period there would be danger of overshooting the safe maximum level and damaging the fuel assemblies by excessive temperature.

At some time during the exponential rise of neutron level the d-c signal from another boron-lined chamber becomes large enough to deflect a sensitive galvanometer. The operator can follow the rise by means of the galvanometer.

As the desired level is approached, the operator slows down the rise by inserting a control rod. The trick is to bring the rod to such a position that the reactor is just critical at the desired level, that is, so that the level neither rises nor falls.

Operation at Constant Level

In practice the reactor is always either slightly subcritical or slightly supercritical, so that the level is either slowly falling or slowly rising. To maintain a constant average level it is necessary to keep moving the rod slightly about the critical position. This may be done by the operator or by a servo that uses a boron-lined chamber to sense neutron level.



FIG. 3—Typical operating cycle of a nuclear reactor

Safety Provisions

During high-level operation, the plant is constantly monitored to detect excessive neutron level or temperature inside the reactor, excessive gamma radiation or the presence of radioactive dust in personnel areas, excessive output of radioactive cooling air from the stack or failure of the cooling system. Certain of these conditions will cause immediate shutdown of the reactor, while others will sound an alarm.

Shutting Down

The reactor may be shut down in a few seconds by inserting all control rods simultaneously, either by the operator or by an instrument. When all control rods are in, the reactor is highly subcritical and the neutron level decays with a short time constant. Figure 3 shows typical operation of a nuclear reactor.

Design and construction of the Brookhaven reactor was carried out under the auspices of the Atomic Energy Commission.

Color-Television Converter

Chrominance detail is heterodyned into the pass band of transmission medium to produce good color reception, since programs sent via coaxial circuits with 2.7-mc bandwidth would otherwise drop out color information from television signal. Technique produces results comparable to those encountered in cable-carried monochrome

By J. G. REDDECK and H. C. GRONBERG

RCA Laboratories Div.
Princeton, N. J.

National Broadcasting Co.
New York, N. Y.

AN IMPORTANT requirement to be met by any color television standards proposed for commercial adoption is that the signal be capable of satisfactory transmission over intercity network facilities.

This article describes a method of passing NTSC color signals over existing facilities that do not pass the full range of frequencies of the proposed specifications.

Two principal types of facilities are currently available for long distance transmission of monochrome television programs. One is a radio relay designated by the Bell System as TD-2, capable of passing the full video range. The other is a coaxial cable system designated L-1, capable of passing video frequencies up to about 2.7 megacycles.



FIG. 1—Video spectrum of the NTSC field-test signal, showing band-sharing obtained by chrominance subcarrier



FIG. 2—Typical signal from burst-frequency generator (A), frequency response over a microwave transmission system (B) and frequency limitation imposed by coaxial-cable transmission (C)

In monochrome television transmission, the energy content of the higher-frequency components of the picture signal is relatively small compared to that of the lower-frequency components. A loss of the higher-frequency components results in a picture of reduced detail, but the picture is generally considered acceptable. However, a color television signal made up of a luminance portion and a color subcarrier has all the chrominance information at the high end of the video spectrum.

A loss of these components results in a picture with little or no color information.

Thus, transmission of the high-frequency end of the video band becomes a matter of major importance.

Figure 1 shows the video spectrum of the NTSC field-test signal. Band sharing is accomplished by adding to the luminance information a subcarrier that is modulated by chrominance information. The subcarrier frequency is chosen to be an odd multiple of half the line frequency (and consequently an odd multiple of half the frame frequency) for frequency interleaving of luminance and chrominance information. In practice, the subcarrier frequency is determined by a crystal and the line-sync generator is locked to this crystal by frequency divider and multiplier circuits.

The following description assumes a subcarrier frequency of 3.579545 mc. What follows would generally apply to any subcarrier frequency chosen.

for Cable Networks



FIG. 3—Composite signal separated (A); heterodyning upper band down (B)



FIG. 4—Transmitter terminal equipment alters NTSC color signal for narrow-band transmission

The bandwidth of the common-carrier microwave system, as used for television transmission, extends beyond 4 mc; the color signal represented by Fig. 1 may be transmitted without modification. Because color reception depends critically on the frequency response of the transmission path, it is essential that the microwave circuits give a flat frequency response up to 4 mc.

The pass band of the coaxial-cable system limits the total spectrum of the signal to about 2.7 mc. Transmission of the signal of Fig. 1 results in complete loss of the chrominance information.

Facilities Tests

Late in 1951, color demonstrations were given in Washington, D. C. Color signals originating in New York, were sent over both the microwave and the coaxial-cable systems. To check the performance of the network paths, extensive use was made of a burst-frequency generator.[1]

Figure 2A shows a photograph of the signal obtained from this generator. The simulated composite video signal is made up of horizontal sync and blanking pulses, with discrete bursts of various frequencies during picture time. This unit was initially designed to provide a quick check of terminal and interconnecting facilities for monochrome television. Its use is equally applicable to color transmission.

A frequency-response over the microwave system and associated local channels is shown in Fig. 2B. Such a test must be made using

Although at the present time the use of the heterodyne conversion equipment is necessary when using the L-1 cable carrier system, the Bell System has recently developed a new wide-band cable system known as the L-3. This system is nominally 8-mc wide, of which about 4 mc may be used for television and the remainder for other services. At present one of these new L-3 systems is in operation between New York and Philadelphia with telephone circuits operating over it. Tests of the system have included transmission of the proposed compatible color tv signal.

It is the hope of the broadcasting networks that certain sections of the country now served only by the L-1 systems will be the first to be benefited by L-3 installations, although the Bell System has made no announcement of its plans in this regard. Wherever this is done, the use of conversion equipment for color will no longer be necessary.

The foregoing does not imply that good compatible color pictures will not be available by network except where the L-3 system is available. Color pictures transmitted over the L-1 coaxial cable system using the telephone company's heterodyne conversion equipment compare favorably with the transmission afforded by the newly developed L-3 system and with that of radio relay facilities.

The Editors



FIG. 5—Receiver terminal equipment translates 2.4-mc subcarrier back to 3.6 mc using filters and heterodyne principle

oscilloscopes of bandwidth greater than that of the circuit being tested. The response is fairly well down at 4.3 mc, as shown by the last burst.

Figure 2C shows a frequency-response check made over the coaxial-cable system including associated facilities. Amplitude of the last burst indicates that the response is still good at 2.4 mc.

Color Conversions

When narrow-band coaxial-cable transmission is used, retention of much of the chrominance information in the NTSC color signal may be accomplished by suitable conversion equipment at the transmitting and receiving cable terminals. This equipment operates on the composite color signal so that frequency components around the subcarrier frequency are translated into the pass band of the coaxial-cable system.

As an alternative method[2], the color studio can employ an encoder operating at 2.4 mc, which receives information from the color cameras directly. The advantage of the conversion method to be described lies in its flexibility. Circuit complexities of a color encoder are avoided. Also, the conversion equipment can be remote from the studio, allowing full-band transmission to a point such as Toledo, with restricted-band transmission over coaxial cable to some other point, such as Dayton.

The translating equipment is designed to provide approximately 2 mc of luminance detail, and 0.3 mc of chrominance detail. By means of filters the transmitting terminal equipment divides the composite color signal into two bands of frequencies as indicated in Fig. 3A. The first band contains frequency components of the signal extending from 0 to 2 mc. The second band contains components whose frequencies extend 0.3 mc on each side of the subcarrier frequency f_s, 3.579545 mc.

This second band is moved down in frequency by heterodyning so that it is adjacent to the 0-to-2 mc band. The new spectrum of the signal is thus limited to 2.7 mc, as shown in Fig. 3B. This signal is sent over the coaxial cable to the receiving terminal equipment. Here the two bands are separated and the upper band moved back to its original position by heterodyning.

The transmitter terminal equipment that alters the NTSC color signal for narrow-band transmission is indicated in the block diagram of Fig. 4. First, a linear-phase-shift low-pass filter selects the luminance components extending out to 2 mc. An *m*-derived band-pass filter selects the components that extend 0.3 mc on each side of the subcarrier frequency f_s, 3.579545 mc. This band is then lowered by heterodyning in a mixer with a sine-wave voltage whose frequency is 5/3 times the color subcarrier frequency, or 5.965909 mc.

A second *m*-derived band-pass filter follows the mixer. This filter selects only the difference frequency components that extend 0.3 mc on each side of $\frac{3}{5} f_s$, or 2.386364 mc. This band around 2.4 mc is then added to the low-pass band to give a spectrum shown in Fig. 3B. All components originally near 3.6 mc are now near 2.4 mc. In effect, the subcarrier has been lowered. The synchronizing burst is now a burst of 2.386364 mc. This new spectrum can now be transmitted over a system limited to about 2.7 mc.

Terminal Inverter

The receiver terminal equipment to translate the 2.4-mc subcarrier back to 3.6 mc is shown in Fig. 6. Another linear-phase-shift low-pass filter selects the luminance components extending out to 2 mc. An *m*-derived band-pass filter selects the components extending 0.3 mc on each side of 2.386364 mc. This band is then heterodyned in a mixer with a signal whose frequency is again 5/3 f_s, as in the transmitting terminal.

Another *m*-derived band-pass filter following the mixer selects only the difference-frequency components, which extend 0.3 mc on each side of f_s. Thus the color subcarrier is moved back to its original value. The band around 3.579545 mc is added to the low-pass band. The spectrum of Fig. 3A is recovered and the signal is ready for transmission as an NTSC color signal of reduced detail.

It is noteworthy that the heterodyning signals at both the transmitting and receiving ends of the terminals must be locked to the original subcarrier, f_s, in order to maintain the 455/2 ratio between the subcarrier and line frequency. This condition is established by automatic-frequency-control circuits in both the transmitter and receiver terminal equipment.

An oscillator in each is locked to the color synchronizing burst of its input signal. Thus the heterodyning signals and the lower subcarrier are locked to the original subcarrier f_s. The final subcarrier is thus identical in frequency to the original subcarrier. Band-pass filters at both terminals must be carefully designed to eliminate any undesired components introduced by the mixers.

REFERENCES

(1) H. Borkan, W. C. Morrison and J. G. Reddeck, Video Test Signal Generator, ELECTRONICS, p 139, Sept. 1953.

(2) An Analysis of the Sampling Principles of the Dot-Sequential Color Television System, *RCA Review*, Sept. 1950.

Air photo taken with camera controlled by automatic film-speed synchronizer. Sharp, detailed photographs require that film and projected ground image move through camera at same speed

By **HERBERT E. MEINEMA**
Lake Forest, Ill.

Film Synchronizer for Aerial Cameras

Phototube-controlled servo system measures aircraft ground speed and adjusts camera film transport to keep film and image moving at same rate, regardless of speed and altitude changes. Controls compensate for camera angle and focal length of lenses

SHARPNESS of the photographic image obtained with moving-filmstrip aerial cameras is largely dependent on accurate correlation between the ground speed of the plane and the speed of the film moving past the lens. Ground speed data obtained from usual aircraft indicators, although accurate over longer periods, are not sufficiently accurate for short-time variation.

To provide a means of continuously measuring ground speed, and use this information to maintain proper film speed, the instrument shown in the block diagram, Fig. 1, was developed.

The system uses a phototube scanning unit to measure the angular ground speed by reflected light. A limiting amplifier and a frequency-responsive detector put the phototube output into a square-wave form for controlling a servo system that adjusts the film speed to follow a function of the signal voltage.

Scanner Unit

Operation of the scanning head is shown in Fig. 2. Two parallel gratings are mounted one above the other. Each grating is composed of alternate transparent and opaque bands lying in a direction across the line of flight of the aircraft. A ray of light reflected from a single point on the ground will be alternately transmitted or cut off, as the point moves through positions A, B and C. The light transmitted through the grating will be pulsating in character; its frequency will depend upon the pitch of the grating and the ratio of the grating separation to the altitude and ground speed of the plane. This frequency will be $f = sd/ap$ where f is the frequency in cycles per second, s is the ground speed in feet per second, a is the altitude of the plane in feet, d is the grating separation in inches and p is the pitch of grating lines in inches. The light pulsations are converted into electrical pulsations by phototubes above the top grating.

The surface of the earth is not uniform in appearance, but consists generally of terrain having many light and dark areas of varying size and shape. Light pulses transmitted through the gratings from light reflecting points on the ground will be identical in frequency at any given instant since all points are moving at the same speed relative to the plane. The relative phase of the pulses, however, will be purely random.

Since the total amount of light received by the gratings is directly proportional to the number of re-



FIG. 1—Block diagram of film-speed synchronizer. Error signal from differential amplifier operates variable-speed transmission to balance error

flecting points in the field of view, percentage modulation of the light received will be proportional to $1/\sqrt{n}$, where n is the number of light-reflecting points. The magnitude of the pulsating component of the modulated light will also be directly proportional to the brightness of ground illumination and the average degree of contrast between light and dark areas. Also, if we assume a constant size for the reflecting areas on the ground, the amplitude of the modulated component of light will be inversely proportional to altitude.

Design Factor

In the practical design of the scanner, several factors had to be taken into account. Grating area had to be kept reasonably small because of restrictions on the size of the hole in the fuselage of the aircraft. Included angle of view had to be as large as possible to include the greatest number of reflecting points, and the frequency generated by the gratings had to be kept within reasonable limits for convenience in amplifying and converting.

A single slit instead of a grating would not have been suitable. When flying over a row of regularly spaced reflections, such as waves, the frequency of the signal would be a function of the number of such reflections passed over per second, rather than their angular velocity. As many lines as possible should be provided in the gratings, but due to diffraction and the difficulty of aligning the gratings the minimum practical spacing is about 0.020 inch, with a separation of 3 inches between the gratings. With flight limits of 600 mph at 100 ft altitude and 250 mph at 3,000 ft, the signal frequency covers a range from 1,320 to 18 cycles per second.

The top grating is separated into two equal areas in which the pattern in one is displaced from the other by the width of one opaque line. A lens assembly above each area concentrates most of the light passing through the gratings on the cathode surfaces of the phototubes. The two phototubes are connected in series, the signal voltage being taken from the common junction. The phototubes thus receive the same amount of ambient light, but a reflecting point on the ground will cause light to fall first on one tube and then on the other. Ambient light is, therefore, balanced out and only the modulated light component generates a signal.



FIG. 2—Gratings of scanner unit modulate reflected light to produce frequency variations in phototube output

The phototubes used are sensitive in the red region as it has been found that the greatest terrain contrast lies in this band. The phototubes must be well matched in current for identical light values and must remain thus, irrespective of light level, temperature and aging. They must also be rigidly constructed, otherwise vibration will cause the generation of spurious frequencies.

Because the modulated light is very low in level it is important that the phototube output be as high as possible for a given light input. The impedance of the tubes is on the order of 1,000 megohms so the input impedance of the amplifier must be at least this high. This is accomplished by feeding the phototube signal into a cathode-follower circuit, Fig. 3.

When operated at high speeds and low altitudes the large areas of reflection on the ground produce a low-frequency component which will blanket the signal unless removed. The constants of the cathode-follower input are proportioned to attenuate these low-frequency signals and an additional two-section high-pass filter network provides additional attenuation. A high-gain amplifier stage and a cathode follower to drive a shielded line complete the unit. The complete scanner is shock mounted with the mounts in the same horizontal plane as the center of mass to prevent rotational vibration.

Main Control Unit

In the main control unit, Fig. 4, the signal from the scanner is clipped in several stages to produce a constant amplitude square wave of the same fundamental frequency as the original. The square wave is then used to trigger a multivibrator. The multivibrator output is rectified to obtain a d-c potential directly proportional to the original scanner-signal frequency.

The signals from the scanner are usually intermittent, arriving in bursts and disappearing when over low-contrast areas such as freshly plowed fields or still water. The d-c output from the rectifier is used as the reference voltage for the



FIG. 3—Scanner-unit circuit has cathode-follower input to provide high impedance for phototubes. Amplified signal is fed to main control unit through shielded line

servo system, and therefore, must remain steady, changing only as the frequency of the signal varies. To provide this constant reference, the d-c current from the rectifier charges a capacitor, and the voltage across this capacitor is used as the reference. When the scanner signal drops below a threshold value a relay drops out, disconnecting the charging circuit from the capacitor. Because no energy is removed from the capacitor, other than by stray insulation leakage, the voltage across it remains steady until the subsequent signal burst arrives. The servo system during the no signal interval, continues to act as though the last signal were still present.

The reference signal is a function of the relative angular velocity of the ground image with respect to the aircraft, whereas the actual speed of the moving film in the camera is a function of the focal length of the lens system and the angle at which the camera points toward the ground. To correlate the relative speeds of the scanner ground image and the lens ground image a d-c tachometer is mechanically coupled to the film drive roller. The tachometer output, which is directly proportional to film speed, is modified by means of attenuator switches so that for a particular focal-length lens and camera angle, the film speed and ground-image speed are the same. One attenuator switch is set up so that each step represents a lens focal length, and the other attenuator is calibrated for various camera angles.

The d-c signal after passing through the lens and camera-angle attenuators is compared to the scanner signal. The differential or error signal, is applied to a phase-sensing modulator having an output frequency of four-hundred cycles. This output is amplified and used to energize one phase of the two-phase servo motor. The servo motor drives the speed-control shaft of the variable-speed transmission until the reference and tachometer signals are in balance, at which time the film velocity is synchronized with the ground-image velocity.

Bibliography

D. Hancock, Jr. and H. E. Meinema, Cameras for Aerial Photography, U. S. Patent No. 2,413,349, Dec. 31, 1946.



FIG. 4—Circuit of main control unit. Relay opens differential amplifier input when scanner signal drops below specified level. Charged capacitor maintains previous signal on grid, holding film speed constant while passing over nonreflecting areas

Polycathode Counter

By J. H. L. McASULAN and K. J. BRIMLEY

Research Dept., Nobel Division
Imperial Chemical Industries Ltd.
Stevenston, Ayrshire, Scotland



Millisecond timer (top unit) being used with regulated current source to measure delay time of blasting caps. Count is started by application of firing voltage and ended by sound of explosion picked up by microphone



Internal arrangement of millisecond timer. Plug-in unit at upper left contains counter and driver tubes



Batching counter with cover open. Position of glow on counter tubes at top indicate number being set

TECHNIQUES using tubes to count and indicate by the successive movement of a localized glow between a number of cathodes in a gas-filled multi-electrode cold-cathode tube have been described at various times[1,2,3,4]. Such tubes can greatly simplify existing methods of scaling and indicating pulses, permitting digital methods to be applied in fields where such methods would normally be too expensive or insufficiently reliable.

A single decade scaler using these tubes involves one counter tube and one coupling tube. These scalers cost less than conventional circuits using neon indicators. Besides being simpler, less critical of adjustment and more reliable, they are more economical in power consumption and require less space.

The fastest Ericsson Dekatron tube[3] is the GC10/D which will count up to 20 kc. Another model, the GC10/B, will count reliably up to 2 kc.

Operating Principle

The counter tubes operate on the principle that the ionization of the gas around the cathode of a gas-discharge tube will lower the striking potential to an adjacent cathode.

The counter tube has a central anode connected through a load resistor to B+, with ten counter cathodes arranged symmetrically around it as in Fig. 1 and connected independently to ground. Between counter cathodes are two guide electrodes, $1G_1$ and $2G_1$. Since the ten cathodes have similar characteristics, the burning potential to a glowing cathode will be lower than the striking potential to any other cathode.

Because of the partially ionized gas in the region, the striking potential from the anode to the two

Tube Applications

Millisecond timer, batching counter and oscilloscope time marker use polycathode counter tubes in low-cost, dependable circuits. The basic decade scaler units used in these instruments are capable of counting at rates up to 20,000 per second

cathodes adjacent to the glowing one will be less than to the more distant ones. In Fig. 1, if the glow is on K_1 and the 1G rail is negative relative to ground by an amount greater than the burning-striking differential of $1G_1$, the glow will move to $1G_3$ since it has the smallest burning-striking differential because of the glow on K_1. While 1G is negative, the tube current will rise, causing the anode potential to fall by an amount approximately equal to this negative swing. This extinguishes the glow on K_1. If the



FIG. 1—Arrangement of cathodes around anode of counter tube. Guide cathodes 2G and 1G are used to transfer glow in proper direction from counting cathodes K_1 and K_2

driving potential to the 1G rail is removed, the glow will remain on $1G_1$ since the striking potential to any other cathode must be greater than the burning potential to $1G_1$. Similar manipulation of the 2G rail and the K rail will put the glow on K_2.

In practice it is not necessary to manipulate all three rails. The K-cathodes are kept at ground potential and the guide electrodes are biased relative to ground, so when there is no signal the glow is stable only on one of the K-rail cathodes.

Basic Counter-Unit

In the basic counter unit a pulse shaper in the form of a trigger circuit is used to supply the counter tube with a standard negative signal having uniform amplitude and good edges.

With this method of operation, bias rails for the guides can be eliminated, providing the coupling time constant is reduced so that when 1G draws current, the self-bias produced on the coupling capacitor extinguishes the glow on the guides after the integrating capacitor has been charged through 2G. Bias for the output cathode can also be dispensed with if the resistance in the guide circuits is kept high enough to prevent guide current from lowering the output current to a point where insufficient output is available to drive the next stage. This presents little difficulty since resistances of 100 to 200K can be used in the guide returns, and 10K is the minimum output-cathode load resistor needed to drive the coupling trigger circuit.

The trigger circuit is a variation of the Schmitt circuit, modified to operate from positive signals and give good negative signals. This circuit is straightforward, designed to operate from a minimum input of 5 volts positive and give a uniform output of 100 volts and about 0.3-millisecond duration. Repetition rate is limited by grid-current paralysis of the coupling capacitor. For high repetition rates diode clamping can be used to eliminate paralysis.

Millisecond Timer

The driver and counter stage is designed as a unit to plug into a plug-panel, with the end of the tube showing through a front panel. A timer built up from these units is



FIG. 2—Millisecond timer circuit. Thyratron gating circuit is used to connect crystal oscillator to counter units. Basic driver and counter unit, at top left, is repeated in other two counting stages



FIG. 3—Batching counter circuit. Counter tube V_5 is used as flip-flop switching unit. Concentric dials in each selector stage are used for setting up the two numbers for count

shown in Fig. 2 and the photo.

The circuit is straightforward, using a 1-kc crystal gated by a conventional gating circuit and triggered from lock-on 2D21 gastetrode trigger tubes.

The instrument is used for routine determination of delay times of electric-delay blasting caps and has also been adapted to operate as a Geiger scaler by substituting a suitable pulse shaper for the oscillator unit.

Batching Counter

Application of polycathode counter tubes has been made to the alternate batching of two three-digit numbers. The specification for the unit described here was that the machine should be engaged for a preselected number of revolutions and disengaged for a second preselected number.

To avoid the use of triple gates to indicate when counting of a three-digit number has been completed, the number is subtracted from 1,000 and this complementary number is set up on the counter tubes. The count is then completed to 1,000, with the output pulse from the last stage indicating the end of count. This pulse operates a bistable circuit in the reset unit which sets up the new number for the second counting cycle.

A number is set up by forcing the glow to the selected cathode with a 100-volt negative pulse applied to that cathode through a ten-position selector switch. A separate switch is used for setting up each of the two numbers. The two switches for each counter are mounted concentrically beneath the visible end of the counter tube. When the numbers are being set up, the glow moves to the cathode corresponding to the position of the switch to give a visual indication of the number selected.

The input amplifier stage of the batcher, shown in Fig. 3, amplifies and shapes the signal from a reluctance pick-up attached to a moving member of the machine being controlled. The output is differentiated and the positive pulse used to drive V_3 of the first selector unit.

Selector Units

Three selector units are connected in series. Tube V_3 is a driver stage like that used in the millisecond timer and V_4 is a GS10/B counter tube. Each cathode of the counter tube has its own resistor and is also connected to the appropriate position on each of the two concentric selector switches. These switches, set to the preselected numbers, receive the resetting pulse through blocking diodes as shown.

Reset Unit

The reset unit consists of driver V_8, bistable counter V_6, and reset-pulse amplifier V_7. The unit is fed from the output of the third counter.

Bistable counter V_6 is a counter-tube with alternate cathodes joined. As the glow moves from cathode to cathode the tube acts as a flip-flop, providing positive signals alternately to the two grids of dual-triode amplifier V_7. These amplified signals are a-c coupled to the counter units via stopping-diodes 6D2 and the selector switches. The diodes only pass the negative resetting pulses and prevent feedback in the resetting chain when the two numbers have a common digit in the same position.

Each position of the flip-flop corresponds to one position of the two-position control coupling to the machine. On the completion of the preset number of revolutions the



FIG. 4—Oscillograms of cro timing marks produced by counter-tube marker. Output from counter tube (A) is clipped and differentiated (B). With a superimposed one-second pulse (C) the wave is integrated to obtain output (D)

flip-flop operates and the machine is switched to its alternative position. At the same time, the second preset number is set up.

Control Switch

The control switch has five positions. In the RUN position the machine is coupled to the input and the batching action is as described.

In the CHECK position, repeated operation of the TEST-RESET pushbutton operates the flip-flop and resetting circuits by injecting pulses into V_8, causing the two preset numbers to appear alternately.

The SET positions, one for each number to be set, operate as described above. Rotation of the switch to the selected number is indicated by rotation of the glow to the cathode corresponding to the number set.

The 50-CPS position of the control switch allows the whole instrument to be tested, without running the controlled machine, by injecting a power-line signal to simulate pulses from the pickup unit.

The clutch controlling the batching operation of the machine is operated by signals from the plates of V_7.

Although V_8 has been coupled as a bistable stage to cover two required conditions of the machine to be controlled, the use of the 12-cathode GS12/B would allow multistable circuits to cover 2, 3, 4, 6 or more different conditions.

CRO Time Marker

A further application of counter tubes utilizes the waveform appearing at the anode to provide timing marks on oscilloscope traces, as shown in Fig. 4. In the circuit of Fig. 5, the output of a 1-kc crystal oscillator is stepped down to 100 cps by the first counter stage. This output is used to drive the second counter stage through an amplifying and inverting triode.

The output from the anode of the second counter is shown in Fig. 4A. The large positive square pulses correspond to the tenth counts and the thickening of the trailing edges of the other pulses correspond to the movement of the glow from a cathode to the following guide electrodes.

By cutting off the negative part of the pulses just above where this thickening occurs, the effect can be eliminated. This clipping is carried out by diode V_7, bias being obtained through a 20K potentiometer. When this waveform is differentiated by the *R-C* circuit in the output of V_7, it appears as in Fig. 4B. The tenth pulse corresponds to the trailing edge of the large positive pulse of Fig. 4A, and is consequently larger than the other nine, the relative sizes being dependent on the bias setting of the 20K potentiometer.

To provide a straight base line from which measurements of displacement might be made, this output is passed through diode V_9 which has its anode biased positively. The diode cuts off the erratic base line of Fig. 4B and refers the pulses to a potential determined by the 330K and 5K divider.

The third counter unit is driven through triode V_{11} from the output cathode of the second counter. The output from this counter consists of a 100-millisecond positive square wave with a repetition rate of one per second. As this pulse is too long for the purpose of time marking, it is differentiated and the negative pulse from the trailing edge rejected by V_9. The 220K and 68K divider control the size of this positive pulse, so as to reject the small variations due to the intervening nine counts of the second counter.

This pulse, recurring at intervals of one second, is superimposed on the signal output from V_8 by feeding it to the common 150K load resistor. The resultant waveform is shown in Fig. 4C. This photograph was obtained by brightening the beam with the differential of this signal. Without brightening, the pulses are too sharp to register without over-exposing the base line. For practical purposes this is not convenient. Instead, the output is integrated; the result being as shown in Fig. 4D. This was obtained by using a drum camera having a time sweep of approximately 6 inches per second, and using a steady beam brightness.

References

(1) Ericsson Telephones Ltd., Beeston, Nottingham.
(2) J. J. Lamb and J. A. Brustman. ELECTRONICS, 22, p 92. Nov. 1949.
(3) R. C. Bacon and J. R. Pollard, The Dekatron, *Electronic Engineering*, May 1950.
(4) J. R. Acton, The Single-Pulse Dekatron, *Electronic Engineering*, Feb. 1952.
(5) G. H. Hough and D. S. Ridler, *Electrical Communication*, Sept. 1950.
(6) J. McAuslan and K. J. Brimley, *Electronic Engineering*, Sept. 1952.
(7) J. McAuslan, *Electronic Engineering*, Dec. 1952.



FIG. 5—Time marker circuit for cathode-ray oscilloscope. Crystal-controlled oscillator supplies 1,000-cycle signal to three counter stages and variations of voltage at anode of counter tube are used to indicate tenth and hundredth second marks

Antenna-Matching

By R. L. TANNER
Stanford Research Institute
Stanford, Calif.

FREQUENTLY it is necessary to estimate the transfer efficiencies of networks used to match arbitrary load impedances to feed cables or transmission lines.

Such a problem arises when making a choice between two possible antennas for use in a particular application.

The approach to be described is to calculate the matching efficiency for all possible antenna impedances based upon some idealized network capable of matching all impedances likely to be encountered.

Equivalent Circuits

The basic circuits of Fig. 1 permit an infinite variety of impedance transformations. Each particular combination yields a different value of efficiency. If the combination yielding the highest efficiency is chosen, the circuits reduce to the simple L-type networks shown in Fig. 2. These circuits are the idealized networks on which the matching efficiency will be based. The region of the impedance plane that each of the circuits matches is also shown.



FIG. 1—Basic ladder-type matching networks



FIG. 2—Two L-type matching networks. Shaded areas show region in impedance plane matched by network

Calculations

Using the circuits of Fig. 2 and assigning specific loss values to the elements, it is possible to calculate matching efficiency for every value of R and X and to present the information as contours of constant efficiency in the R-X plane. Nor-



FIG. 3—Antenna-matching-efficiency chart for coil Q equal to 100

Network Efficiency

Charts used to estimate transfer efficiencies of networks matching load impedances to transmission lines and feed cables. Typical use is in choosing between two possible types of liaison antennas for installation in a particular aircraft

malized antenna reactance $X = X_a/Z_o$ as a function of normalized antenna resistance $R = R_a/Z_o$ for a certain matching efficiency is given by the expression

$$X = -[QR(1-\eta)/\eta] \pm \sqrt{R/\eta - (R^2/\eta^2)} \quad (1)$$

and

$$X = \frac{\rho R/(\rho^2 - \eta\alpha^2 R)}{(1 \pm \sqrt{\eta\alpha^2 R[1+(1-\eta\alpha^2 R)/\rho^2]})} \quad (2)$$



FIG. 4—Antenna-matching-efficiency chart for coil Q equal to 50

where Q = Q of the network inductors, D = dissipation factor of the network capacitor, η = efficiency, $\rho = D\eta/(1-\eta)$ and $\alpha = [(1/Q) + D]/(1-\eta)$.

Equation 1 applies to the region in the impedance plane matched by the circuit of Fig. 2A, while Eq. 2 applies to the region matched by the circuit of Fig. 2B. For the circuit of Fig. 2A the loss in the capacitor is almost always negligible compared to the loss in the inductor. Thus D does not appear in Eq. 1. For the circuit of Fig. 2B it is not possible to ignore the loss in the capacitor.

Efficiency Charts

The charts show contours of constant efficiency in the R-X plane. Logarithmic impedance scales are used. The slight discontinuities that appear in two of the higher-efficiency contours result from an approximation made in deriving Eq. 2. Maximum error occurs at the boundary between the domain of Eq. 1 and that of Eq. 2. This error is not large, however.

Use of Charts

To use the chart, the impedance to be matched is first normalized with respect to the feed-cable impedance. The normalized impedance is then found on the chart and the efficiency of match determined by interpolation between the two contours enclosing the point. It has been found that for a coil Q equal to 100 the chart gives a good approximation for frequencies below 15 mc, while for a coil Q equal to 50 the chart gives a better approximation at frequencies between 15 and 24 megacycles.

Bridges Measure

Junction transistors operating at moderately high frequencies possess many of the complexities of vacuum tubes operating at very high frequencies. Special bridge circuits measure admittance parameters to specify transistor small-signal operation

SMALL-SIGNAL operation of a transistor is accurately specified by means of four complex parameters having both real and reactive components. Eight quantities must be measured, and since these quantities in a fixed environment are potentially a function of operating voltage, current and frequency, the measurement equipment must have considerable flexibility.

The bridge equipments to be described operate in the frequency range of approximately one kilocycle to one megacycle although by suitable modifications the range can be extended. These bridges use a multifrequency test signal such as a square-wave, pulse, or swept-frequency test signal. Multielement equivalent circuit representations can thus be obtained which are valid over a wide range of frequencies so that an ordinarily complex measurement task is considerably simplified.

Small-Signal Operation

The small-signal, and therefore linear, operation of a transistor is accurately determined by means of four independent parameters. These are generally chosen as the coefficients in equations associated with the input and output terminals. These terminal equations may be written in either a loop or nodal form; the resulting independent parameters are impedances or admittances respectively.

The bridges described here have been designed to measure the admittance parameters. This choice of admittance rather than impedance parameters was dictated by several factors;[1] the most important of these factors is the greater ease with which the admittance parameters can be measured as compared with the impedance parameters.



FIG. 1—Two-generator (A) and one-generator (B) equivalent transistor circuits



FIG. 2—Block form (A) and detailed circuit (B) of y_{bbe} admittance bridge

Since many circuit applications for a junction transistor will use a common-emitter connection (emitter element common to both input and output circuits), this paper will consider the measurement of the admittance parameters associated with a common-emitter circuit. The appropriate nodal or loop parameters associated with other circuits can be obtained by suitable transformations.[2]

The four admittance parameters are indicated in Eq. 1 and 2.[3] These equations are Kirchhoff's nodal equations for the base and collector respectively when the a-c base-to-emitter voltage and a-c collector-to-emitter voltage are V_{be} and V_{ce} respectively and the a-c base current and a-c collector current are I_b and I_c respectively. The admittance parameters are further defined by means of Eq. 3, 4, 5 and 6, which equations also serve as a basis for the admittance measurements to be described

$$I_b = y_{bbe} V_{be} + y_{bce} V_{ce} \quad (1)$$

$$I_c = y_{cbe} V_{be} + y_{cce} V_{ce} \quad (2)$$

$y_{bbe} = g_{bbe} + jb_{bbe}$
= input admittance with output short-circuited (3)

$y_{bce} = g_{bce} + jb_{bce}$
= reverse transfer (feedback) admittance with input short-circuited (4)

$y_{cbe} = g_{cbe} + jb_{cbe}$
= forward transfer admittance with output short-circuited. (5)

$y_{cce} = g_{cce} + jb_{cce}$
= output admittance with input short-circuited. (6)

The nodal equations 1 and 2 can be depicted most directly by means of the two-generator equivalent

Transistor Parameters

By L. J. GIACOLETTO
RCA Laboratories Division
Princeton, N. J.



Photograph of y_{bb} bridge panel is typical of other test sets described



Under chassis view shows arrangement of components and generous use of shielding

circuit shown in Fig. 1A. The more familiar one-generator π equivalent circuit is shown in Fig. 1B.

The small-signal circuit operation of a transistor can be completely determined after the admittance parameters have been measured.[3]

If the measurement frequency is low enough, the admittance parameters are essentially conductance parameters. These conductance parameters are very useful throughout the audio frequencies and can be measured on a General Radio Type 561 vacuum-tube bridge. This bridge is useful because g_{cbo}, $1/g_{cc}$ and μ_{cb} for a transistor are the same as g_m, r_p and μ for a vacuum tube and g_{bco}, $1/g_{bb}$ and μ_{bo} are the same quantities measured on the grid side of the vacuum tube. The bridge balances out reactive effects.

The vacuum-tube bridge can be used to measure d-c conductance coefficients[4] of junction transistors. The method of measurement is the same as for small-signal parameters, but the d-c terminal voltages and currents are zero. The bridge can also be used to measure open-circuited self-impedance loop parameters by using a current bias rather than the usual voltage bias.

Since the bridge balances out the reactive component, measurement of either reactive or susceptive parameters at 1,000 cps can be made. The simplest method of doing this is by substitution. First, balance the bridge with the transistor; second, remove the transistor and connect an adjustable passive network between appropriate terminals of the bridge; third, rebalance the bridge by adjustment of the passive network. The value of the passive network is the desired result.

To determine performance of a transistor as a function of frequency, both conductance and susceptance components of the admittance parameters must be known. These parameters can be measured using the four admittance bridges to be described, at any frequency desired from approximately 1 kc to 1 mc. These admittance bridges are for measuring *pnp* junction transistors. It is only necessary to reverse the various voltage polarities to measure *npn* junction transistors.

The y_{bb} admittance bridge is shown in block form in Fig. 2A. A test signal of suitable amplitude and frequency is connected to a bridge arrangement of R_1-y_{bb} network and R_2-transistor. It is usually convenient to make $R_1 = R_2$ in which case the bridge will be balanced when the y_{bb} network has the same admittance as is present between the transistor base and emitter.

The presence of R_2 can be compensated for by connecting an identical resistor across the y_{bb} network. A detailed circuit of the y_{bb} test set is shown in Fig. 2B.

Battery Operation

Consider first the d-c operation of the transistor. The collector-to-emitter voltage is supplied by means of a 10-position selector switch and nine R-M cells. This arrangement permits nominal 1.3-volt steps in V_{cb}. The base-to-emitter voltage is established with



FIG. 3—Operation of y_{bb} test set using square-wave, pulse and swept-frequency test signals

the aid of a potentiometer and an external V_{BB} bias battery.

Normally, only two elements are required in the y_{bb} network for point-by-point measurements. Experience has indicated that if $_eg_{b'e}$ is small, to a fairly good approximation y_{bb} can be represented as a pure conductor $g_{bb'}$, associated with base lead conductance in series with a parallel conductor, $_eg_{b'e}$, and capacitor $_eC_{b'e}$. Here, b' denotes an internal base point connected to the external base b through an ohmic resistor $1/g_{bb'}$.

This network arrangement of y_{bb} is very useful since it yields directly elements of some physical importance and elements that are to a good approximation independent of frequency. However, since there are three elements to be balanced, the correct balance can be obtained only by multifrequency testing. Multifrequency testing is achieved by using a square-wave, pulse, or a swept-frequency test signal that contains multiple frequencies. The bridge equipment and null indicator must be wide band in its frequency response. The operation of the y_{bb} test set for the three types of multifrequency test signals mentioned is indicated in Fig. 3.

The top tracing is the input test signal. The second tracing is the test signal applied to the transistor. The third tracing indicates the null (zero) signal when all three elements of the y_{bb} network are properly adjusted.

The fourth tracing indicates the null signal when $g_{bb'}$ is unbalanced. The fifth tracing indicates the null signal when $_eg_{b'e}$ is unbalanced. The sixth tracing indicates the null signal when $_eC_{b'e}$ is unbalanced. From the shape of the null signal the cause of the unbalance is ascertainable so that a complete balance can be easily and rapidly obtained.

A multifrequency test signal has considerable merit over a single-frequency test signal even when only a resistive and reactive element are to be balanced because the cumulative effect of small phase shifts of individual component frequencies provides a comparatively large net unbalanced null signal.

Output Admittance

The y_{cc} test set is similar to the y_{bb} test set and is shown in block form in Fig. 4A. Assuming $R_1 = R_2$ when the bridge is balanced, the admittance of the y_{cc} network is equal to the y_{cc} admittance of the transistor shunted by R_3.

It is not possible to make R_1 large enough to be negligible. Accordingly R_3 is made as large as possible and then compensated for by connecting a resistor of equal value across the y_{cc} network. The detailed circuit arrangement for the y_{cc} test set is shown in Fig. 4B. A variable (0 to 300 volt) regulated power supply can be used to provide collector bias.

The arrangement of the nine 1.3-volt R-M cells together with the selector switch and pushbutton switch is essentially an infinite resistance voltmeter for setting V_{CE}. A vacuum-tube voltmeter may be used instead.

Transfer Admittance

The y_{eb} test set is somewhat different from the preceding two tests since it measures transfer admittance rather than self admittance. The block diagram for the bridge arrangement of the y_{eb} test set is shown in Fig. 5A. The operation of this bridge circuit[4] can be better understood by referring to Fig. 1A and Fig. 6A.

When the bridge is balanced, y_{eb} is given by the value of the y_{eb} network elements. Also, when the bridge is balanced, the collector is short-circuited to the emitter as is required for the measurement of y_{eb}. A null balance can be obtained with the circuit of Fig. 5A only because of the phase reversal that takes place in the transistor.

Measurements of junction transistors have indicated that the y_{eb} network can be constructed most simply by means of a conductor g in series with an inductor L. It is difficult to make a continuously variable inductor, and the inductors invariably have appreciable



FIG. 4—Block form (A) and detailed circuit (B) of y_{cc} admittance bridge



FIG. 5—Block form (A) and detailed circuit (B) of y_{cbe} admittance bridge



FIG. 6—Equivalent circuit of y_{cbe} bridge and arrangement of y_{cbe} network



FIG. 7—Block form (A) and detailed circuit (B) of y_{bce} admittance bridge



FIG. 8—Vacuum tube provides balanced signal from unbalanced source

resistance. To circumvent these difficulties, a y_{cbe} network of resistors and capacitors was devised as shown in Fig. 6B. Although the y_{cbe} network now contains three elements, single-frequency measurements are possible since r_1 and r_2 are not independent elements. However null adjustment is more difficult than with a two-element network.

The detailed circuit of the y_{cbe} test set using the y_{cbe} network of Fig. 6B is shown in Fig. 5B.

The operation of the y_{bce} test set shown in block form in Fig. 7A is similar to the operation of the y_{cbe} test set. The important difference is that there is no phase reversal associated with y_{bce}. Consequently, an accurately-balanced test signal is necessary to produce a null across R_1. The detailed circuit of the y_{bce} test set is shown in Fig. 7B.

A switch is used to multiply the $-1/g_{bce}$ values in the $-y_{bce}$ network by 10. This was done to accommodate the large range of values encountered in this parameter. Since $-C_{bce}$ does not vary over as large a range as $-1/g_{bce}$, the multiplier has been wired to be effective only for $-1/g_{bce}$.

The circuit used to provide a balanced signal from an unbalanced source is shown in Fig. 8. Although simple, its operation should be carefully checked to insure that the two outputs are accurately balanced at all frequencies used.

Associated Equipment

A suitable null indicator is required for the operation of the four admittance test sets. A wide-band untuned null indicator simplifies measurement work considerably. A Tektronix type 512 cathode-ray oscilloscope has been found generally suitable as either a balanced or unbalanced null indicator. The oscilloscope is normally operated with maximum gain. Somewhat greater gain may be desirable particularly for the y_{bbe} and y_{bce} test sets.

The network component values used in the four test sets were chosen to cover a range of typical transistor parameters. For measurements beyond the range provided, or for special transistors, it will be necessary to change the network component values. Another method of providing a larger range of values is to switch in different values of R_1 and R_2 in the y_{bbe} and y_{ece} test sets or to divide the test signal as was done in the y_{bce} test set. By careful design a large range of values may be measured.

The accuracy of a bridge is dependent to a considerable degree upon the extent and effectiveness of shielding. The shielding indicated should be considered as a minimum requirement.

The apparatus may be used for measuring point-contact transistors provided the point-contact transistor is short-circuit stable. The y_{bbe} and y_{ece} test sets may also be used for measurement of junction diodes in either the forward or reverse direction.

REFERENCES

(1) Paper presented "Junction Transistor Characteristics at Low and Medium Frequencies", *Proc. Nat'l Electronics Conf.*, Chicago, Sept. 1952.

(2) L. J. Giacoletto, Terminology and Equations for Linear Active Four-Terminal Networks Including Transistors, *RCA Review*, p 28, March 1953.

(3) W. Shockley, M. Sparks and G. K. Teal, *P-N* Junction Transistors, *Physical Review*, **83**, p 151, Jul. 1951.

(4) F. B. Llewellyn, Phase Angle of Vacuum Tube Transconductance at Very High Frequencies, *Proc. IRE*, **22**, p 947, Aug. 1934.



FIG. 1—Circuit of complete amplifier. Value of feedback resistor *R* depends on impedance of speaker used. Output tubes can be 1614, 6L6, 5881 or KT66

Multiple-Feedback

Plate-to-grid feedback in tetrode output stage of amplifier gives double the power output of triode Williamson circuit. Low distortion and high stability characteristics of triode stage are retained with reduced power supply requirements

IMPROVING the power output and stability of the Williamson amplifier circuit without increasing distortion and plate-power consumption involves special design considerations.

Obtaining 15 to 20 watts output without using four output tubes and a large power supply, and without operating the power tubes beyond ratings, rules out a triode output stage. A tetrode output stage, besides requiring considerably more feedback to equal the distortion performance of a triode stage, raises a stability problem that has not been discussed before. The voltage gain of a tetrode output stage is proportional to its load impedance, and this load impedance is highly variable with frequency in the case of a speaker load.

Since the voltage gain of the output stage is part of the gain of the overall feedback loop (whether taken from the primary or secondary of the output transformer), stabilization of the feedback loop is made more difficult. It is therefore necessary to obtain a low output impedance in the output stage itself, before overall feedback is applied, to make the gain of this stage relatively independent of loading. This may be done in only three ways: by using triodes, with their numerous disadvantages; by loading the stage with resistance in addition to the speaker, and thus wasting a good part of the increased power output obtained from tetrodes; and finally by using local feedback in the amplifier output stage.

An example of 100-percent local feedback is found in the cathode-follower output stage. An extremely low output impedance is realized in this way, but the driving requirements are severe, and high plate-supply voltages are required in the



FIG. 2—Distortion compared to power output at 1,000 cps. Curve is substantially the same at 50 cps



FIG. 3—Maximum undistorted power output over frequency range of amplifiers



FIG. 4—Variation of response with frequency at 1-watt output with 8-ohm load

Audio Amplifier

By JOSEPH M. DIAMOND

Development Engineer
United Transformer Co.
New York, New York

drivers. A more practical device is plate-grid feedback, since any degree of feedback may be selected.

Local feedback may also be obtained by driving the screens with a fraction of output voltage, but since the relationship between control grid and screen grid is not linear, it is preferable to feed back to the control grids[1].

Local Feedback

In this case the 480,000-ohm local-feedback resistors, together with the 100,000-ohm 6AU6 plate loads, provide about 12 db of local feedback, and make the output impedance of the power stage in itself about 1,200 ohms at each plate. This figure compares favorably with the 1,700-ohm plate resistance of the 6L6 as a triode.

This driver and power stage combination is similar to the triode equivalent in both output impedance and distortion, but power output is doubled and the B+ requirement is somewhat reduced. It only remains to add a phase inverter, a gain stage and the overall feedback.

The phase inverter used is of the paraphase or anode follower type, and is difficult to surpass. For high frequency applications this circuit has given excellent balance to 1 mc.

The other half of the 6SL7 functions as a voltage amplifier. Overall feedback, as seen from Fig. 1, is split into push-pull feedback from the output-transformer primary, and a single-ended feedback loop from the secondary which encloses the first loop. Each of these loops contributes about 12 db, making the total feedback around the output stage 36 db, including local feedback. This procedure avoids using a very large amount of push-pull feedback, requiring critical control of balance[2], and also avoids using 20 db or more of feedback from the secondary with the questionable stability that often results.

With the present design, including the 10,000 ohm — 150 μμf and 1 meg — 0.02 μf phase-control networks, complete stability is obtained on open circuit, speaker load, or with any degree of capacitive loading. There is no tendency toward oscillation under conditions of heavy overload and recovery from such overload is immediate. The resultant freedom from instability under all dynamic conditions is of far greater practical interest than a perfectly flat frequency response beyond the audible range.

REFERENCES

(1) D. T. N. Williamson, Amplifiers and Superlatives, *Wireless World*, 58, No. 9, p 357, Sept. 1952.

(2) B. B. Drisko and R. D. Farrell, 40-DB Feedback Amplifier, ELECTRONICS, 25, p 130, March 1952. Also, letter to the editor by E. F. Good, Oct. 1952, p 420 and reply by B. B. Drisko and R. D. Farrell, p 362, Jan. 1953.

Radiation Monitor

By R. H. DELGADO
Nuclear Instrument and Chemical Corp.
Chicago, Illinois



Monitor checks contamination on soles of feet, backs and palms of hands. Operation is simple and fail safe

SAFETY OF PERSONNEL in radioisotope laboratories is enhanced by a completely automatic radiation monitor that measures, evaluates and indicates the amount of beta and gamma radioactive contamination on the worker's hand surfaces and the soles of his shoes. Called the hand-and-foot monitor, the device combines laboratory precision with the operational simplicity of a pinball machine.

The instrument is normally in ready condition and an illuminated green legend says READY FOR USE. Meanwhile the counting channels are pulsed from an internal signal generator and the contamination indicators cycle continuously to indicate that the counting channels are operating properly.

Operation

The worker stands on the platform with feet on paper-covered grills. Radiation detectors for the shoe soles are under the grills. When the hands are inserted in the counting chambers, where another set of radiation detectors is located, switches are operated to start automatic operation.

The indicators are reset and the legend changes to a white COUNTER-IN-OPERATION sign. If either or both hands are withdrawn before the predetermined monitoring time has elapsed, the indication changes to a yellow CHECK-INCOMPLETE, RESET-AND-REPEAT warning. At the end of the monitoring time an illuminated legend either reads CHECK OK or DECONTAMINATION REQUIRED.

Each counting channel provides a single illuminated number proportional to the amount of radioactivity measured by that channel. If decontamination is required, an additional set of indicators shows in which channel or channels the tolerance has been exceeded.

System

Figure 1 is a block diagram of the instrument. It consists of five detecting and counting channels, a regulated low-voltage power supply for the electronic circuits, a regulated high-voltage power supply for the radiation detectors and an automatic control circuit that programs and times the operations.

The trigger circuits, binary scaling stage and decade scaling stages are all plug-in units. This simplifies servicing and permits easy change of the scaling factor of any or all channels. To convert a unit from beta and gamma monitoring to alpha monitoring it is only necessary to replace the detectors and use appropriate scaling factors in the counting channels.

G-M Counters

The radiation detectors are thin-wall (30 to 40 mg per square cen-

Protects Lab Workers

Automatic fail-safe radiation counter measures radioactive contamination on workers' hands and feet. Changeable scaling factor permits conversion from beta and gamma to alpha monitoring. Plug-in units facilitate rapid servicing

timeter), stainless-steel, halogen-quenched Geiger-Mueller counters. This counter combines long life, ruggedness and high output with good sensitivity. The inorganic, halogen-quenching vapor does not gradually decompose with use as do organic vapors. Guaranteed minimum life of the counter is greater than 10^{10} counts. This allows the counters to be left connected to their rated operating voltages with no worry about their life. The walls of the counter are thin enough to allow beta particles with energies as low as 200,000 electron volts to be detected. The counters develop pulses of approximately 18 volts.

In the hand-monitoring section two counters are connected in parallel in each channel and the output is fed through RG-11/U coaxial cable to the trigger circuits on the scaler chassis. In the foot monitoring platform eight counters are connected in parallel to a single output. The counters are shielded individually by a minimum of ½ in. of lead around back and sides to reduce background from stray and natural radiation.

Trigger Pairs

The trigger circuit shown in Fig. 2 is built as a plug-in unit and is complete except for the grid-bias potentiometer on the scaler chassis. The diode in parallel with the nonconducting tube's grid resistor sharpens the pulse and helps restore the grid quickly. Thus, even if the bias of the first section is adjusted for high sensitivity, long pulses will not cause the circuit to double pulse.

The 6BK7 dual triode gives the large output pulses required to drive the scaling stages while retaining good resolution. The input sensitivity can be set between 0.2 and 2 volts for negative pulses. However, the permissible range of input pulse is better than 0.2 to 20 volts. Output is a 100-volt negative-going pulse with a 90-percent duration of 2 μsec with the circuit



FIG. 1—Complete monitor comprises five detecting and monitoring channels employing 16 G-M counters, single-channel and overall warning indicators



FIG. 2—Trigger circuit includes crystal diode to sharpen pulse



FIG. 3—Scaling stage uses computer-type dual triode to enhance reliability

constants shown. Output pulses of better than 150 volts can easily be obtained.

Scalers

The binary scaling stage shown in Fig. 3 is conventional. The 5963 dual triode is used for high reliability although any stock 12AU7 will work satisfactorily. The 5963 is a computer-type tube in which the emissions of the two sections are matched and the cathode specially designed to avoid the sleeping sickness that occurs when tubes are cut off for long periods.

The decade scaling stages are of the scale-of-sixteen-minus-six variety. The binary stages making up the scale of sixteen are the same as those shown in Fig. 3. This circuit also uses 5963 dual triodes. However tests have been made using 12AU7's too mismatched for use even in ring-type scalers. The scaling action was perfect over a B+ range of over 80 volts. Figure 4 shows the feedback loops for adding six pulses per cycle to provide decade operation with a scale of sixteen counter.



FIG. 4—Feedback loops produce decade counting by adding six counts per cycle to scale-of-sixteen binary scaler

Warning Circuits

Each scaling channel terminates in a thyratron circuit operated from the carry pulse of the last decade. The five thyratrons operate from a common plate load and a signal from any or all of the circuits is fed to a common thyratron circuit. The individual circuits provide single-channel indications while the common circuit operates relay RE_5 that changes the final indication from CHECK OK to DECONTAMINATION REQUIRED. Figure 5 shows these circuits.

Thyratrons are preferred for this application because once a thyratron has fired it will continue to conduct and does not depend on any critical design as would be encountered in special flip-flops; also, if there is the slightest possibility of spurious operation, the circuit will fail safe. It is better to say that decontamination is necessary than take the chance of missing a person with radioactive material on his body.

Control Section

The control circuit is shown in Fig. 6. There are actually two hand switches, one for each hand.

With the power turned on, the READY-FOR-USE lamp is lit and the scaler-reset line is closed so the decades can scale. The trigger-circuit stop-count line is grounded so they can operate and the stop-test line is ungrounded so pulses from the test signal generator will drive the trigger circuits. The thyratron-reset line is held open so the decontaminate-signal circuits will not function.

When hand switch S_1 is operated, a circuit is completed to the COUNTER-IN-OPERATION light and counting timer TI_1 which determines the monitoring time. Another circuit is completed to RE_1, which then operates and locks.

Relay RE_1 turns off the READY-FOR-USE light and prepares a circuit to be used if the hands are removed too soon. The stop-test line is now grounded through RE_{1d} to shunt out the pulses from the test signal generator. Relay RE_1 also operates RE_2.



FIG. 5—Thyratron warning circuits are fail safe to prevent incorrect indication

Relay RE_2 resets all of the scaling stages by momentarily opening the reset line through RE_{2B}. This relay also grounds the thyratron-reset line so the individual channel warning circuits can operate.

At the end of the monitoring time counting timer TI_1 turns off the COUNTER-IN-OPERATION lamp, energizes RE_3 and turns on either the CHECK-OK or DECONTAMINATION-REQUIRED lamp. This choice is determined by RE_5 (Fig. 5), which is operated by the master warning circuit.

When RE_3 operates it locks and breaks the partial circuit to the CHECK-INCOMPLETE lamp so that it will not light when the hands are removed. The trigger-circuit stop-count line is now opened so that no further counts from the Geiger counters will be registered until the monitor is reset.

When the hands are removed, the hand switches restore and complete a circuit through contacts of RE_1 to operate the reset timer TI_2 and energize RE_4. Relay RE_4 locks itself and the reset timer while opening the circuit, already broken by the hand switches, to counting timer TI_1. This prevents the counting timer from restarting until the monitor has been reset. The display remains on the counting channels until the reset timer operates or until the reset button S_2 is pushed. Resetting opens one side of the 115-volt line. This restores relays 1 to 4 and the reset timer TI_2, returning the monitor to the ready-for-use condition.

Interlock

The under-voltage interlock system, shown in Fig. 7, consists of a thermal time-delay switch S_3 and high-resistance relay RE_6. If the high voltage falls below a predetermined value, the contact-type meter applies 150 volts through its contacts and locking coil and S_3 to RE_6. When the relay operates, it opens one side of the 115-volt line to the control section turning off the READY-FOR-USE light. This

interlock prevents use of the radiation monitor if the voltage on the detectors has fallen below their operating point.

The BACKGROUND switch in parallel with contacts RE_{1D} of relay RE_1 is key operated and can be used to shunt out the pulses from the test signal generator to allow service personnel to check the radiation background while the monitor is in the ready-for-use condition without running through the timed cycle. Shielded hermetically-sealed relays are used along with 0.01-μf disc-ceramic capacitors placed directly at the coil terminals, to eliminate a-c pickup in the counting circuits.

Tolerance and Background

In body monitoring, it is desirable that the personnel have no radioactive contamination on their person. If the monitor were set to signal for decontamination when it detected the slightest amount of radioactivity, the signal would operate every time a person was checked since radioactivity is present to some extent all of the time, from cosmic rays, minute amounts of natural radioactivity and the radioactive materials used in the lab.

The radioactive background or noise level for the monitor must be determined for the specific location in which it is to be used. This can be done by taking a long measurement or a number of short ones and taking the average. However, since the background fluctuates in a random manner it is necessary to apply statistical methods to determine the maximum probable amount of background activity that will be measured per unit time.

The counting timer TI_1 is adjustable from 5 to 60 seconds. With a scaling factor of 100, tolerance can be adjusted anywhere between 100 and 1,200 counts per minute. If the background is extremely low, the first decade can be replaced with a binary stage or even bypassed completely to give a tolerance as low as 10 counts per minute.

Power Supplies

The power supply for the electronic circuits employs a 5U4G rectifier, capacitor input filter, 6AS7G regulator and 6SJ7 difference amplifier. A single OD3/VR-150 serves as voltage standard for both the high- and low-voltage power supplies.

The high-voltage supply must provide voltage continuously adjustable between 600 and 3,000 volts at 1 ma with 0.5-percent stabilization over a line voltage range of 95 to 135 volts. In addition, the supply must have very low noise. The supply has been designed not only to operate Geiger counters, but also air-proportional counters or scintillation detectors employing multiplier phototubes.

The high-voltage supply uses a transformer having a 2,800-volt secondary in a voltage doubler circuit. This provides adequate voltage for a series-shunt regulator and permits operating the regulator tubes in more favorable regions than is usually possible. The high voltage supply is shown in Fig. 7. The high-voltage metering system uses electronic depression to provide a meter scale of 600 to 3,000 volts.



FIG. 6—Automatic control circuit simplifies monitoring operation. Warning lamp signals if worker withdraws hand before check is complete



FIG. 7—High-voltage supply for Geiger-Muller tubes incorporates under-voltage interlock as additional safety feature

Universal Medical Timer

By ROBERT G. ROUSH and EDMUND T. URBANSKI

Research Associate *Research Technician*

Engineering Laboratory
The Johns Hopkins University
Baltimore, Md.

Timing units above researcher's hand give start and stop signals to stimulus units below. Cross connections are made on jack field

PULSE-TYPE electronic stimulators described in the literature have varied little in principle, differing mainly in the type and number of output circuits required for aural, visual and electrical stimuli. Despite basic similarities, these devices have been restricted in application.

In the equipment to be described, the design has been directed towards simple and reliable circuits that can be easiiy adapted to virtually any stimulation problem in the fields of psychological and medical research.

Basic Considerations

The factors by which one stimuli-generating equipment differs from another are essentially two: the type and number of stimulus output circuits and the timing patterns associated with these outputs. The most flexible stimulator design should therefore consist of an adequate number of standardized timing subassemblies and a sufficiently large variety of stimulus output subassemblies to meet the requirements of most of the stimulation problems encountered. The processes of timing and stimulus generation can therefore be functionally separated and all interconnections between these two functions made available to the experimenter in a patch panel arrangement. The conversion of the equipment from one problem to another can then simply consist of an exchange of stimulus-generating subassemblies and a reconnection of the timing subassemblies to provide the required display patterns.

Unit Assemblies

The photograph shows an equipment based upon these considerations. The upper chassis is the timing unit. It has five plug-in subassemblies. Four of these are delay circuits. The fifth is an astable circuit that can also function as a fifth delay unit if required. In general, the delay circuits are of the monostable variety, although in some applications—for example, flicker-fusion frequency studies—a pick-off type of delay unit is desirable in order that adjustable duty ratios may be provided.

Each monostable delay unit has been provided with a trigger-input and a delayed-trigger-output pin-jack. By interconnecting the output and input jacks of successive units in the desired manner, delay periods can be added in any sequence. Two or more delay units can be cross-coupled to establish a second or even a third pulse recurrence frequency if required.

The lower chassis has four plug-in stimulus subassemblies, although for most problems no more than two are required. Each of these units possesses two trigger input jacks; one to initiate the stimulus and the other to terminate it. A row of five pin jacks is located in the main panel directly above each of these units. The pin jacks are connected internally to the respective trigger-output lines of the units in the timing chassis.

A choice of any two of five trigger pulses to start and stop each stimulus can therefore be made at each stimulus subassembly location. The temporal relationships of these pulses is determined by the delay unit interconnections and, by the respective delay adjustments. This arrangement permits almost any conceivable timing pattern for two stimuli to be arranged quickly by the experimenter. The interconnections required for a specific problem are shown in Fig. 1, which illustrates the flexibility of this system.

The circuit of the monostable delay unit designed for the timing section is shown in Fig. 2. Tubes V_1 and V_2 and associated com-

and Pulse Stimulator

Flexible control of timing intervals from two or more units using phantastron circuits is basis of equipment for medical and psychological research. Several types of stimulus generators driven by the timers produce audible, visual or electrical signals as desired

ponents constitute a conventional screen-coupled phantastron circuit that can be triggered into its quasistable condition by applying a positive pulse to the input of trigger-injection amplifier V_{4B}.

Delay Circuit

A delayed positive pulse is obtained at the termination of the quasistable period of the circuit in the following manner: the positive excursion of the suppressor-grid potential of V_1 during the interval is limited to a few volts above ground potential by positive grid current flow in V_{2B}. The termination of the period is regenerative and the circuit has been designed so the plate currents of both V_1 and V_{2B} are interrupted at this instant.

The resulting negative step function of current in R_8 is shaped into a positive pulse at the grid of cathode follower V_{4A} by the R-C peaker action of R_9, C_3 and R_4. An additional output voltage useful for gating or monitoring is obtained from the suppressor grid of V_1 through buffer cathode follower V_{3A}. The output is a rectangular waveform having an upper level slightly above ground potential and a duration equal to that of the quasistable interval of the circuit.

This interval is adjustable from approximately 150 microseconds to 3 seconds by controls S_1 and R_2. Adjustment is accomplished by increasing the value of the timing capacitor in the second position of S_1 and lowering the positive grid-return potential of V_1 in the third position of this switch. The ten-turn helical potentiometer R_2 gives essentially linear control of delay over each of these ranges.

Pattern recurrence frequencies are established by a circuit identical to the delay circuit, except for the addition of switches S_{1C}, S_2 and S_3 and associated components shown by dashed lines in Fig. 2. With these switches in the position shown, the circuit will function as a delay unit. When S_2 is thrown to the opposite position, the screen is capacitively coupled to the suppressor grid, and the normal quasistable interval of the circuit is followed by a second such period during which multivibrator action between the screen and suppressor grids takes place.

Grid Cutoff

This period of grid cutoff is established by the capacitance values selected by S_{1C}. They have been chosen to permit the charge recovery period of C_1 or C_2 to be complete before permitting the normal action of the circuit again to take place. The recovery period has been made small by using a



FIG. 1—Interconnections of timers and stimulus generators for a problem



FIG. 2—Monostable delay unit used in timing section of the universal stimulus generator

large value of R_1 and correspondingly low values of C_1 and C_2. Switch S_3 therefore functions to give monostable or astable operation of the circuit.

Sawtooth Voltage

When S_3 is in the position shown in Fig. 2, the quasistable interval of the circuit and the amplitude of the sawtooth voltage output are both linearly dependent upon the setting of R_2. In the opposite position, the initial plate voltage of V_1 is fixed and its grid-return voltage controlled by R_2. Consequently, this position of S_3 provides a fixed amplitude sawtooth voltage that has a period inversely proportional to the setting of R_2.

The first position of S_3 is employed in monostable applications where linear control of delay is most often required and also for the linear control of recurrence period in astable operation. The latter position of S_3 gives linear frequency control in the astable position of S_3 over a wide range, although a control ratio of greater than 10 to 1 on a given range setting is not recommended if good timing stability is desired.

The modified phantastron delay unit was chosen instead of the astable multivibrator not from any consideration of linearity of control or stability but because of the additional output that is available. The constant-amplitude variable-frequency sawtooth of voltage can be used as a time base for displaying all the equipment waveforms on a cathode-ray oscilloscope. It can also be utilized when the duty ratio of the stimulus is to be controlled in preference to its duration.



Monostable delay unit illustrates type of construction employed in timers

The simple multivibrator amplitude comparator shown in Fig. 3 will produce trigger output pulse delayed from the start of the negative-going waveform by an interval, $t_d = \alpha\, t_R$, where t_R is the repetition period of the sawtooth, and α an adjustable factor controlled by R_1. This pulse is produced by differentiating the positive jump in the plate potential of V_{1A} that occurs at the instant of conduction of V_{1B}. Range switch S_1 has no control over this delayed pulse, but does permit a sufficient amount of control of the multivibrator period to prevent the occurrence of additional pulses due to the restoration of the grid potential of V_{1B} before the input waveform has crossed the grid base of V_{1A}. This switch setting corresponds to the range-switch setting of the astable circuit if the multiple burst is to be prevented.

Actually, the delayed pulse is usually employed to turn off a stimulus, so in this case the multiple burst would be of no consequence. The constant-current cathode load V_{2A} has been provided to insure a constant trigger-pulse amplitude over the range of control of R_1. This control range will provide a duty ratio α of from 0.05 to approximately 0.95.



FIG. 3—Multivibrator amplitude comparator produces delayed output pulse



FIG. 4—Tone-burst stimulus generator

Stimulator Circuit

At present, only three basic stimulus subassemblies have been designed. Each of these is a bistable system having two trigger-pulse input circuits; one for initiating and the other for terminating the stimulus.

One unit for the production of auditory tone bursts is shown in Fig. 4. In this circuit, amplifier V_{3A} is keyed on, and V_{3B} is keyed off for the period between start and stop pulses. The keying voltages are obtained from the bistable multivibrator V_{2A}, and are applied to V_3 through buffer cathode followers V_4.

An audio signal applied to the input of V_{3A} will appear in the output circuit for the period between timing pulses to provide a tone burst. Conversely, a signal applied to V_{3B} will provide a tone blank for this same period. By connecting the same trigger pulse to both pulse-input circuits, the on-off periods will be equal and the circuit can then be used as a conventional electronic switch if desired.

A portion of the voltage appearing across the common load impedance V_{3A} and V_{3B} is transferred to the output circuit through a two-stage resistance-capacitance coupled feedback amplifier. A feedback factor of approximately unity is employed in this circuit to give a midfrequency gain of one and an output impedance of 15 ohms. This circuit will deliver approximately 5 volts to a 500-ohm resistive load with negligible distortion over a



FIG. 5—Visual-stimulus generator turns on preset current in glow-modulator tube. Light intensity is function of tube current. Circuit can also be used to operate solenoid



FIG. 6—Current stimuli adjustable from 2 to 20 ma are keyed on and off by triggers

wide frequency range. Series resistance may be added between the output and the load if load-impedance matching is required.

Another type of subassembly used for the production of visual stimuli is shown in Fig. 5. Here the rectangular output of the bistable circuit is employed to turn on a preset current in a Sylvania R1131C glow-modulator tube V_1. The intensity of the light pulse obtained from this tube is essentially a function of the current through it and thus a reasonably large amount of degeneration in the gating tube circuit is desirable for stabilizing this current. The flash intensity can be preset by simply triggering the circuit with a start pulse and adjusting R_1 until the current measured at J_1 has the desired value. This circuit can also function to operate a relay or a solenoid in lieu of the glow-modulator tube for problems requiring an electromechanical operation to take place at some instant during the stimuli pattern.

Current Stimulus

The circuit of a third unit tentatively designed for the production of current stimuli, adjustable from 2 to 20 milliamperes, is shown in Fig. 6. The load impedance through which this current must flow is connected by a suitable electrode system in series with two cathode followers V_3 and V_4. These tubes are biased beyond plate-current cutoff at all times, except during the stimulation period. The lower cathode follower serves as an adjustable constant-current load in series with the external load. The upper circuit provides a low-impedance path to chassis ground only during the stimulation period.

The bistable multivibrator V_1 is employed here to apply a constant-voltage rectangle to V_3 and to the resistance-capacitance network in the grid circuit of the lower cathode follower. If the external load impedance is low enough to prevent grid-current flow in V_4 owing to reduced plate voltage on this tube, the current in the load circuit will be determined almost entirely by the setting of R_1. The resistive component of this impedance must be 6 kilohms or less, and any reactive component must be capacitive for this condition to be realized.

The impedances generally realized with a suitable electrode system will easily meet these requirements.

Dual capacitive coupling in the grid circuit of V_4 provides an additional measure of safety. The substitution of beam power tubes for V_3 and V_4 with attendant circuit modifications will permit constant-current pulses up to 0.1 ampere to be obtained from this unit. A further modification may be made by utilizing the gating pulse from the monostable delay units to key V_3 and V_4 directly in lieu of bistable multivibrator V_1. This may be done in any stimulus subunit that is to be used only for short-duration stimuli.

Auxiliary Circuits

The excellent stability of the phantastron circuit in the presence of supply-voltage variations has eliminated the necessity for using regulated voltages for the timing chassis. The positive 300-volt supply for this chassis has been obtained from a simple full-wave rectifier circuit with L-section filtering.

The power supplies provide regulated supply voltages of +300, −300 and −150 volts.

The development described is an outgrowth of Contract N5ori-166, Task Order I between the Office of Naval Research and The Johns Hopkins University for Cooperative Research.

Current-Slope Control

Simple six-tube control circuit for resistance welders permits independent control of buildup and decay rates of welding current. Gives longer electrode tip life and more uniform welds on aluminum and magnesium



Up-down slope control unit with separate control station



FIG. 1—Welding-current waveform

CONTROL of rise and fall of the current envelope in resistance welding is of aid in increasing weld quality and uniformity.

A gradual rate of increase is helpful in reducing sticking in spot welding of aluminum materials, magnesium and their alloys. From a production point of view this means fewer interruptions for dressing electrode tips. Tests show that the number of welds made before sticking occurred could be increased 20 to 25 times by controlling the up slope of the welding current envelope.

Control of the down slope, or rate of decay of welding current, has an annealing effect that helps to relieve stresses, reducing the possibility of shrinking, cracks and porosity in the welding of temper types of aluminum. Also, the application of forging pressures is less critical when controlled down slope is used.

To assist in obtaining and maintaining high-quality welds, the combination up-down slope control shown in the photograph has been developed.

The control unit employs a relatively simple electronic circuit having a short reset time, capable of resetting in one cycle when interconnected to a seam-welding control. The unit is completely electronic in operation, with no relays or moving parts requiring maintenance.

Welding-Current Waveform

When connected in the welder circuit, the up-down slope control produces the welding-current waveform shown in Fig. 1. The up and down slope adjustments control the rate of current increase and decrease. Control of initial and maximum current is provided to establish the current range through which the slope will operate.

The down-slope delay determines the point where the down slope will start. This delay requires a precision timing circuit since it effectively determines the end of actual weld time. If this timing is not accurate, the amount of heat energy supplied to the weld will vary, causing inconsistent results. This is one of the main features of this control, from a welding viewpoint.

Basically the control may be considered as a variable resistance inserted in the phase-shift circuit of the main welding control as shown in Fig. 2. The phase of the voltage developed across the output transformer is used to control the point on the supply-voltage wave at which the welding ignitron tubes fire.

Circuits

In this phase-shift circuit, increasing the resistance will decrease welding current. An increase in resistance shifts the phase of the voltage across T_a, making it more lagging, and retarding the firing point of the welding ignitron tubes.

The two sections of the low-mu twin-triode V_a are connected to present a variable resistance across the secondary of T_a. This resistance is reflected to the primary, which is connected in the phase-shift circuit. This reflected resistance will control the welding current.

The variable resistance is controlled by the current conducted by V_a, which will be dependent on the grid bias values. During standby, bias is supplied by V_4 which charges capacitor C_1 during each

for Resistance Welders

By R. O. JOHNSEN
Control Department
General Electric Co.
Schenectady, N. Y.



FIG. 2—Circuit of current-slope control unit

half-cycle of supply voltage. The voltage across the capacitor is applied through half of V_4 to the initial-heat potentiometer. A portion of this voltage is applied to the control grids of V_4, setting the initial current.

Up-Slope Control

Tube V_3 isolates the up-slope timing circuit from the down-slope circuit. The up-slope control determines the rate at which C_1 discharges after V_4 stops conducting. The bias voltage for V_4 will then vary from the initial bias value, as selected by the up-slope control potentiometer, to zero. Zero bias is reached in the time it takes C_1 to discharge through the control potentiometer.

The voltage developed across the secondary of transformer T_2 at the beginning of each weld is rectified and the resulting negative d-c voltage is used as a bias to turn tubes V_2 and V_4 off, thus initiating the up-slope time by allowing C_1 to discharge.

Down-Slope Control

The down-slope starts at the instant V_2 begins to conduct. Tube V_3 is normally held off by the precision timing circuit consisting of tube V_1, capacitors C_2 and C_3, the down-slope delay control and the secondary of T_1. During standby, C_2 and C_3 are charged to equal d-c voltages by T_1 through each section of twin-diode V_1. At the instant that welding current starts to flow, V_4 is cut off by the same negative d-c voltage that cuts off V_4. This removes the supply voltage of T_1 from the timing circuit and permits C_2 and C_3 to discharge through the down-slope delay control. The manner in which these capacitors discharge, including the bias voltage for V_2, is shown in Fig. 3.

This timing circuit is self-regulating. With a 60-cycle line frequency, timing will not vary over the range of 1 to 15 cycles.

In the 16-to-30-cycle range, variation will be ±1 cycle or less. These values will hold true with a ±10 percent supply voltage regulation.

In Fig. 3, the bias voltage for V_2 (between circuit points D and E in Fig. 2) crosses the value of D at Y, reducing the bias voltage to zero and permitting V_2 to conduct. Should the supply voltage decrease, as indicated by dotted line in Fig. 3, the discharge rate will decrease because of the lower differential in the d-c charge on C_2 and C_3. Because of this lower discharge rate, E will again cross D at Y, permitting the down-slope delay time to remain constant.



FIG. 3—Effect of voltage change on bias level

The down-slope begins when V_3 starts conducting. The down-slope is determined by the rate at which C_4 charges through the down-slope control. The voltage developed across C_4 is applied through V_3 to the initial-heat potentiometer. A portion of this voltage is once again applied to the grid of V_4. Thus, the bias voltage on V_4 is increased from zero to the bias originally selected by the potentiometer, at a rate determined by C_4 and the down-slope potentiometer.

To reset the control at the end of each weld, tubes V_3 and V_4 must refire. These tubes will refire in the time it takes C_3 to discharge, removing the hold-off bias. This reset time is about 8 cycles. In control combinations where a sine-wave voltage appears at the start of each weld, it is possible to obtain a one-cycle reset time. This available voltage could then be applied to T_2 in such a way that the plate voltage of tubes V_3 and V_4 would be 180 degrees out of phase with the grid voltage obtained from T_2. With this sine-wave hold-off during the weld, and with C_3 removed, the reset time can be reduced to one cycle.

Microphones Measure

Designed for measurement of sound pressure level in the range 40 to 220 db referred to 0.0002 dyne per square centimeter, three different types of microphones are used to cover the frequency range from 3 to 30,000 cps required to record industrial noise, explosions and jet or rocket noise



High-intensity microphone is mounted on base containing cathode follower. Power supply and output circuits are contained in remote case. Probe is at right

RESEARCH in medicine requires microphones capable of reproducing low-intensity sound, whereas modern aircraft and new industrial apparatus produce sounds different in range and intensity from those encountered in speech and music. The condenser microphone is adaptable to the needs of each of these fields, embodying sturdiness and stability as well as least phase shift over a wide range of levels and frequencies.

This paper describes microphone systems designed for measurement of sounds in the range 40 to 220 db referred to 0.0002 dyne per square centimeter. The frequency range encountered in these measurements is so great that it is necessary to use several types of sound generators as calibration source. From 3 to 300 cps the pistonphone produces good-waveform sound pressure levels in small cavities and provides levels up to approximately 130 db.

In the range from 50 to 2,000 cps loudspeakers of the cone type are used. From 500 to 10,000 cps, loudspeakers with a thin metallic or plastic diaphragm provide good sources. From 5,000 up to 30,000 or more cps, a microphone of the Altec 633 type is used as a loudspeaker. It produces sound pressure levels on the order of 120 db at a distance of 12 inches, with an electrical input of approximately 10 watts.

Microphones encountered in speech and music work have a noise floor of 20 to 30 db and a maximum undistorted range of approximately 140 db. For abnormally high sound-intensity ranges microphones having a noise floor of approximately 65 db are used in the range from 140 to 200 db. Recording of acoustic shock waves and explosions require a usable range from 160 up to 220 db or more. Suitable modifications of a small condenser type microphone can provide the core of a measurement system that meets all of the requirements outlined above.

Microphone Construction

The shock-wave microphones are in principle and size the same as certain standard microphones. A diaphragm of increased stiffness is used, depending upon the sound pressure levels encountered. The diaphragm is clamped tightly around the edges. It is laminated with a molecular coating of gold on the exposed surface to make the conductor. This structure allows full excursion of the diaphragm without possibility of shorting or arc-over since the dielectric material that forms the diaphragm insulates the conducting surface from the back plate even when large amplitudes cause the diaphragm to touch the back plate.

Figure 1 is a schematic of the cathode follower and its associated power supply, as used with type 21BR microphones. The base housing the cathode follower is connected to the power supply with a five-conductor shielded cable. The cathode follower uses a type 5840 subminiature pentode having a shock rating of 500 g. A switch on the output provides either direct cathode-follower output or transformer coupling. The transformer is uniform to 5 cps.

High-Intensity Sound

By JOHN K. HILLIARD
Altec Lansing Corp.
Beverly Hills, Calif.



Probe that can be attached to high-intensity microphone creates little disturbance in cavity and allows use at temperatures above 700 F

Recorded shock wave corresponds to pressure change of 27 psi or sound pressure level of 200 db above 0.0002 dyne per sq cm

The microphone diaphragm may be exposed directly to the shock wave or where desirable a probe may be attached. A probe tube, shown in the illustration, is available for sampling minute sound-pressure fields without upsetting the physical dimensions of the cavity.

Pistonphone Calibration

A pistonphone is used for the calibration of pressure microphones in the region where there is no deviation between the free field and pressure calibration. It consists essentially of the dynamic system having a 2-in. voice coil, mounted on a metal V cone diaphragm, a cloth spider and permanent magnet. A small piston 5 millimeters in diameter is attached to the apex of the cone. This piston operates into an entirely enclosed pressure chamber.

The chamber has a removable cover with provision for the insertion of a microphone. A microscope with an eyepiece micrometer, graduated in tenths of millimeters is mounted between the voice coil and the pressure chamber. It permits the measurement of the piston stroke in the range from 0.02 to 0.8 mm.

The pressure chamber proper is bounded by a laminated plastic cup that has a cylindrical bore of 90 mm and a depth of 75 mm. The rubber sealed piston assembly extends into this bore. Various insert cylinders are used to reduce the cavity, depending upon the types of microphones to be calibrated and the special range of frequencies to be used.

The largest chamber is approximately 475 cubic centimeters and shows no measurable standing waves up to approximately 300 cycles. A smaller chamber of approximately 18 cubic centimeters is used for higher frequencies and to develop higher sound pressure levels. The maximum sound pressure that can be developed with 475 cubic centimeters is approximately 16 dynes per square centimeter. With the 18 cubic centimeter chamber a sound pressure level of 124 dynes is available.

The pressure developed in the cylinder is a function of the piston diameter, the barometric pressure, the piston stroke and the pressure chamber volume. Sound pressure level is computed according to the following equation:

$$P = 0.52 \frac{D^2 H B}{V}$$

Where P = effective sound pressure in μb
D = piston diameter in mm
B = barometric pressure in mm of Hg
H = piston stroke in mm
V = pressure chamber volume in cc



FIG. 1—Cathode follower and power supply used with sound pressure level microphones

Jet Noise Levels

Aircraft propulsion systems presently used, and those planned for the future include turbojet engines, rockets, supersonic pro-

pellers and ram jets. Presently the turbojet engine is the most common and potent source of noise. It is anticipated that unless quieter engines can be designed, the radius of disturbance from an airport may be as great as 30 miles.

The origin of the noise in jet engines is probably due to the formation of eddy currents at the nozzle, irregularities of fuel combustion and to some extent intake noise. Since these sources are not accurately defined, progress in providing a muffler to reduce this noise has been delayed and it is not expected that within the immediate future these sounds can be attenuated at a rate sufficiently fast to cope with the increase in power.

The noise of jet engines is a more continuous spectrum than that of propeller-driven aircraft. In the latter case the noise is concentrated in the lower frequencies having a maximum amplitude at the propeller blade frequency, which is in the range of 75 to 150 cps. The energy falls off rapidly at the harmonic frequencies. The jet engine, however, has almost a uniform spectrum up to 1,000 cps and above 4,000 cps appreciable energy is radiated. Since a propeller is principally a low-frequency generator, the noise is nondirectional and is at a maximum near the pilot's position. For this reason the rear part of the cabin is considerably quieter than the forward part.

Jet Noise

In a jet plane the source of noise is well to the rear. However, since the jet spectrum is extended, the noise-distribution pattern varies with frequency. In the first octave the noise is nondirectional. The sound radiator is a dipole antenna and the pattern shifts progressively so that the radiation at medium and higher frequencies is at right angles to the airplane. At very high frequencies the radiation is directed forward.

Attenuation of low frequencies by the wall of the plane requires increased thickness or mass, but the high frequencies are easily attenuated by present-day construction. Because of the varying directions of the noise, passengers in such planes as the English Comet are seated as far forward as practical.

Table I—Microphone Characteristics

Type	Open-circuit sensitivity in db ref to 1 volt	Maximum sound pressure level (spl)	Frequency range in kc
21C	− 46	140	0.005-17
21BR-180	− 66 ± 5	180	0.005-17
21BR-200	− 86 ± 5	200	0.005-17
21BR-220	− 106 ± 4	220	0.005-17

The manufacture, testing and use of turbojet and ram jet engines have created many problems in connection with the intense noise produced by the operation. The present-day turbojet engine burns approximately 5,000 to 8,000 pounds of fuel an hour. The acoustic power increase is approximately proportional to the fourth power of the fuel consumption, and this corresponds to approximately 70 kw at its highest speed. The sound pressure level is approximately 160 db at a distance of 1 nozzle diameter from the engine.

The spl developed by an engine is a precise value depending upon the fuel consumption. Measurements on a number of engine test cells have shown that the sound output is within a few tenths of a decibel when the fuel is correctly metered. There are three noise-level situations that cause concern with operation of jets:

(1) A short full-power check of the engine before taking off.

(2) Adjustments in plane after installations.

(3) Finally, what is probably the most potent source of interference, factory testing of jet engines.

At the present time objections come principally from adjustments in the plane and factory testing. The latter represents the major source of annoyance to nearby office workers and residential areas. This testing also constitutes a hazard in that a certain partial or permanent impairment of hearing can be produced by operations' personnel being exposed to this noise.

In the research and design on engines, high ambient pressures and temperatures are involved when a microphone is used to obtain data within or near the combustion chamber. Types of burner instabilities occur and the role of flame-driven standing waves in burners is being studied. The names given to these instabilities are: (in rockets) "chugging" and "screaming;" (in afterburners) "rumbling" and "queaking;" (in ram jets) "resonance", "rough burning," "pulsing" and "whistling."

High Temperatures

The condenser microphone can be operated at higher temperatures than conventional microphones, since the materials used are Mycalex, glass and stainless steel. The Mycalex becomes unstable above 1,000 degrees F and other parts are stable up to 1,600 degrees F. For short periods of time, such as an interval of less than one minute, the microphone can be directly exposed to 1,600 F.

Where continued temperatures above 700 degrees are encountered in the measurements, the microphone is used with a probe tube. The probe tube usually has a bore of 1 to 3 mm and a length to provide the necessary temperature gradient. The probe tube also provides more of a point-source pickup and reduces diffraction of sound around it allowing end of the tube to be mounted in a wall of a pipe or engine. The length of the probe tube varies from 3 in. up to experimental units measuring 14 in. in length.

The walls of the probe can be cooled by liquid, air or covered with heat resistant insulation so that the temperature at the microphone end is within accepted limits. Usually stainless steel is used to resist the corrosive action of heat and the various types of liquid fuels and propellants. The wall of the probe tube is sufficiently thick so that an attenuation of at least 50 db is provided.

Where the ambient barometric pressure exceeds 30 psi, it may be necessary to provide a bypass from the front of the diaphragm or the chamber to the housing at the rear of the microphone to equalize the static pressure. When the tempera-

ture at the diaphragm is elevated beyond 200 degrees, the voltage between cathode and ground drops, and it is advisable to provide means for maintaining a constant potential of 200 volts.

Plant Noise Control

Noise control of jet engine testing cells has become compulsory. Factories are usually located in areas somewhat remote from residential sections, but progressively these areas are built up and complaints by the residents bring preventive measures. Present acceptable daytime sound levels can approach a value of 72 to 75 db and nighttime levels, a value of 60 to 65 db before complaints will be received.

An engine at 5 feet will develop approximately 160 db spl at full power. Some engine plants have as many as 50 individual testing cells in operation simultaneously and the spl is raised to 177 db. Exhaust stack treatment, tunnels, ducts and resonators are used to provide various degrees of attenuation. The cost of providing the attenuation is between $500 and $1,000 per db. At least 50 db of attenuation at 100 cycles is required. Higher powered engines are being developed and it is anticipated that in the near future the initial noise will be increased by a factor of 5 to 10 db.

Noise Monitoring

The management of factories must provide means of continuously monitoring the noise interference in a neighborhood and take appropriate measures to keep it within acceptable limits to avoid legal action. Facilities for this monitoring are now in use experimentally and are also being planned for several areas that include office and residential areas.

The procedure consists in mounting microphones in an open structure such as a tower, church or school belfry in the residential area. The output of the microphone is amplified to a level of approximately + 10 vu and transmitted over private or leased telephone circuits to the plant receiving terminal. The telephone circuits are equalized for uniform response up to 8,000 cycles and selection of cable pairs can provide a signal-to-noise ratio of 50 db. The threshhold of residential ambient noise is seldom less than 40 db, and this allows a range up to 90 db.

At the receiving terminal, line amplifiers provide sufficient gain to compensate for the loss in the telephone cable. (The equalized 1,000-cycle gain is equivalent to the loss of 4 db per circuit mile.) In addition to monitoring the noise, equipment is available to operate a warning light when the sound pressure level in the region of this microphone exceeds the specified interference level and to record noise on tape or sound-level recorders.

Equipment used at the pickup point is the type 21 condenser microphone, having a dynamic range of 30 to 140 db spl and a 100-db gain amplifier capable of + 10 vu output. The gain of the system is adjusted so that the maximum expected level in the area will develop + 10 vu and maintain the highest possible signal-to-noise ratio without producing crosstalk in adjacent cable circuits.



Calibration chart for representative microphone at 124 db spl input

Calibration of the microphone, amplifiers, telephone cables, line terminal equipment and recording facilities may be provided by mounting a small stable loudspeaker near the microphone. This loudspeaker is energized by a calibrated reference tone transmitted over a separate outgoing telephone line.

The monitoring at the exhaust stack or within a few diameters of the engine is accomplished with the 21BR-200 microphone. Experimental tests over a period of several months in a midwestern jet-engine factory indicate that the microphone system can be exposed to conditions of weather, including 100-percent humidity and temperature ranges from −20 F to 100 F. Overall change in sensitivity of microphone, amplifier and telephone cables was less than 2 db over a period of one month.

When the aircraft engine noise exceeds the predetermined complaint level in the residential areas, the procedure is to reduce the fuel consumption temporarily or shut down the required number of engines to keep within the specified level.

Hearing Loss

Loss of hearing to personnel operating and testing equipment in factories today is a factor that management must evaluate to protect the worker. It is estimated that a large sum is involved in legal action today resulting from claims on loss of hearing. Drop forges, trip hammers, riveting and the like develop peak sound pressure levels in excess of 150 db. Employees working in these high noise fields without ear protectors may suffer permanent loss of hearing at frequencies above 1,000 cycles.

Other Applications

Condenser microphones are being used to determine the vibration of fuel lines, tanks and other parts in rockets. Safe-risk distances for operating personnel adjacent to rocket launching apparatus is determined by measuring the spl at the launching platform.

Motor car engine timing chain noise is measured by mounting a probe tube close to the individual links of the chain around the sprockets.

In the medical field, small animals are used for experimental purposes to study the effects of exposure to blast. By inserting a probe tube in the animal at the point of interest, the internal pressure can be accurately measured.

In the field of vibration, the microphone may be used to trace the nodal pattern of vibrating turbine buckets, as well as recording the axial modes of a vibrating turbine wheel.

Step-Switch Converter

Amplifier-controlled telephone-type stepping switches convert analog voltage to digital information. Converter is particularly useful when results of engineering computations performed on analog computers must be analyzed statistically

By R. R. BENNETT and H. LOW

Hughes Research and Development Laboratories
Culver City, Calif.



FIG. 1—Principal features of analog-to-digital converter: standard telephone-type stepping switches are used



FIG. 2—Amplifiers used in absolute-value circuit

APPLICATION of analog computers to statistical studies[1] requires gathering numerous discrete statistical results and reducing them to useful engineering data. Output devices generally associated with analog computers present the desired results as curves. Measuring discrete points from these curves introduces human error and time lag. The device to be described automatically converts an analog voltage into digital form. Figure 1 illustrates its operation.

Voltage X in the range of $\pm$ 100 volts is connected to the input of the absolute-value circuit. The output of the absolute-value circuit, $|X|$, then becomes an input to the summing networks of the tens and units relay amplifiers.

The tens relay amplifier energizes the tens-digit stepping switch S_1 as long as the sum of its inputs is positive while the units relay amplifier energizes the units-digit stepping switch S_2 as long as the sum of its inputs is negative. Hence, S_1 operates as long as the absolute voltage on its feedback arm is less than $|X|$.

While S_1 operates, the sum of the inputs to the units amplifier is positive and S_2 does not operate. As soon as S_1 feeds back the appropriate voltage to the tens amplifier and stops, S_2 steps until a voltage is fed back sufficient to make the sum of the inputs to the units amplifier positive, at which time S_2

Digitizes Analog Data



Analog-to-digital converter with associated tabulator. Keys are operated by solenoids energized by converter

stops. The shaft position of the two stepping switches represents the two-digit answer. Additional banks of contacts are used to energize keyboard solenoids on a tabulator and to light the visual indicators shown in the photograph.

The conversion and tabulation operation takes place in less than one second and is actuated by either a pushbutton on the unit or automatically by an external switch.

The same shaft position may be used to obtain any function of X by adding enough banks to the stepping switches, essentially providing a table of values of $f(X)$ for each X. The function $f(X) = X^2$ is of particular value in statistical studies. The mean square of the variable X is obtained by recording X^2 and computing the sum of the X^2's at the end of a sample of runs. The addition of the X^2's may be accomplished within the accompanying tabulator.

More Digits

The system can be extended to more than two digits by adding one more relay amplifier and stepping switch for each additional digit. The limitation to the number of digits depends upon the accuracy of the reference voltages, the accuracy of the feedback divider resistors and the resolution of the relay amplifiers.

The two-digit system converts an analog voltage to the nearest unit. Figure 1 shows the position of the stepping switches for $24.5 > |X| \geqq 23.5$ volts. The tabulator would record 24 for this value of X. The statistical problems for which the converter was built did not warrant greater accuracies. The divider resistors for S_1 and S_2 are ± 0.1-percent and ± 1.0-percent wire-wound resistors, respectively.

Absolute-Value Circuit

Figure 2 shows a relay amplifier and an inverting amplifier connected to form an output that is equal to the absolute value of the input. The relay selects the input if the input is positive or the negative of the input if the input is negative. A second pair of contacts provides the contact closure to energize appropriately the plus or minus solenoid of the tabulator. The relay amplifier is a conventional chopper amplifier using a 60-cps synchronous converter. It energizes its relay on a negative 10-millivolt input and has inherently negligible drift.



FIG. 3—Relay amplifier used to position stepping switch

The inverting amplifier is a high-gain d-c feedback amplifier connected to give an overall gain of minus one. It is linear over the range of ± 120 volts. Cathode resistor R_1 is for zero balancing the amplifier.

Figure 3 is a schematic of a stepping-switch actuating amplifier. The slight differences between the tens and units amplifiers are indicated on the schematic. Balancing an amplifier consists of adjusting cathode resistor R_1 to give the proper relay-contact closure with all inputs grounded. Two neon lights on the front panel indicate the desired relay-contact position.

Amplifier Drift

Direct-current amplifier drift in the inverting amplifier and the two stepping-switch actuating amplifiers is reduced to a negligible amount by using regulated power supplies, differential-amplifier input stages[2] and deposited-carbon resistors throughout. The amplifiers would be chopper stabilized in applications where more accuracy is required from the converter.

References

(1) R. R. Bennett and A. S. Fulton, Automatic REAC Operation for Statistical Studies, Symposium II on Simulation and Computing Techniques, Reeves Inst. Corp., Apr.-May 1952.

(2) G. E. Valley, Jr. and Henry Wallman, "Vacuum Tube Amplifiers", p 441, MIT Rad. Lab. Series, McGraw-Hill Book Co., Inc., N. Y., 1948.

TRANSISTORS: Theory and Application

Grounded Emitter

Part IX

By ABRAHAM COBLENZ and HARRY L. OWENS

Signal Corps Engineering Laboratories
Fort Monmouth, New Jersey

IN PREVIOUS ARTICLES of this series, discussions have been restricted to the grounded-base connection for transistors. One of the main reasons for introduction of the grounded-base connection first is because it appears that in the testing and evaluation of transistors, this connection will be used. In general, the values of parameters obtained and the interpretation to be placed on the measurements depend on the method of connection.

Grounded emitter and collector circuits have advantages over the grounded-base circuit in certain applications. The significance of the method of connection will become apparent in the ensuing discussion.

Grounded-Emitter Connection

The parameters which describe the grounded-emitter connection most adequately for design and analysis purposes are the input and output resistances, and the voltage and power gains. To find these, it is necessary to obtain the loop currents.

Table I—Typical Values of Transistor Parameters

	Point Contact	Junction
r_e	150 ohms	25 ohms
r_b	120 ohms	500 ohms
r_m	35 kilohms	0.96 meg
r_c	15 kilohms	1.0 meg
R_g	500 ohms	500 ohms
R_L	20 kilohms	0.1 meg
alpha	2.3	0.96
e_g	0.01 volt	0.001 volt



FIG. 1—Equivalent and schematic circuit diagrams for grounded-emitter connection

Following the rules in the previous article, Kirchhoff law equations for the two loops in Fig. 1 will be set up to find these currents as a function of known transistor parameters.

Figure 1 shows the essentials of the grounded-emitter connection. Note that d-c biases are omitted, the r's are shown instead of Z's for simplicity, and that arbitrary current directions, toward the imaginary junction point J, are assumed.[1]

Following the rules in Part VII the loop equations are

$$(R_g + r_b + r_e)\, i_1 + r_e\, i_2 = e_g \qquad (1)$$

$$-r_m\,(i_1 + i_2) + r_e\, i_1 + (R_L + r_e + r_c)\, i_2 = 0 \qquad (2)$$

Note that $(i_1 + i_2) = -i_e$ and that i_e = current through r_e toward J. Ordinarily, with the direction of currents as selected, $r_m i_e$ would have a minus sign since it is a generator; since i_e flows from plus to minus with respect to it, it requires another minus sign, so that $r_m i_e$ is now plus. However, $i_e = -(i_1 + i_2)$, and therefore the term appears as $-r_m\,(i_1 + i_2)$ in the equation. Rewritten in standard form, Eq. 1 and 2 become

$$(R_g + r_b + r_e)\, i_1 + r_e i_2 = e_g \qquad (3)$$

$$(r_e - r_m)\, i_1 + (R_L + r_e + r_c - r_m)\, i_2 = 0 \qquad (4)$$

Solving for i_1

$$i_1 = \frac{e_g\,(R_L + r_e - r_m + r_c)}{[(R_g + r_e + r_b)\,(R_L + r_e + r_c - r_m) + r_e\,(r_m - r_e)]} \qquad (5)$$

Input Resistance

The input resistance for the rounded-emitter connection is

$$R_{ic} = \frac{e_g}{i_1} - R_g$$

$$= r_e + r_b + \frac{r_e\,(r_m - r_e)}{R_L + r_e + r_c - r_m} \qquad (6)$$

Since one can normally neglect r_e compared to r_m

$$R_{ic} = r_e + r_b + \frac{r_e\, r_m}{R_L + r_e + r_c - r_m} \qquad (7)$$

For comparison, the equivalent relation for the grounded-base connection is

$$R_i = r_e + r_b - \frac{r_b\, r_m}{R_L + r_c} \qquad (8)$$

A study of these equations reveals the following:

(1) The subscript convention adopted is as follows: If only one subscript is used (for example, R_i), the value refers to the grounded-base connection; R_{i_c} re-

and Collector Circuits

Design equations for additional transistor circuit configurations are derived and average values inserted to show typical performance. Relative advantages of various circuits for both junction and point-contact transistors are discussed in detail

Table II—Formulas and Typical Values for Transistor Circuit Parameters

	Grounded Base	Grounded Emitter	Grounded Collector
Input Resistance	$r_b + r_e - \frac{r_b (r_b + r_m)}{R_L + r_b + r_c}$	$r_b + r_e + \frac{r_e (r_m - r_e)}{R_L + r_b + r_c - r_m}$	$r_b + r_c - \frac{r_c (r_e - r_m)}{R_L + r_b + r_c - r_m}$
P.C.	≈ 150 ohms**	≈ 35,000 ohms	≈ 2,000,000 ohms
Junction	≈ 90 ohms	≈ 700 ohms	≈ 700,000 ohms
Output Resistance	$r_b + r_c - \frac{r_b (r_b + r_m)}{R_g + r_b + r_c}$	$r_c + r_e - r_m + \frac{r_e (r_m - r_e)}{R_g + r_e + r_b}$	$r_c + r_e - r_m - \frac{r_e (r_e - r_m)}{R_g + r_e + r_b}$
P.C.	≈ 9,500 ohms	≈ −13,000 ohms	≈ −650 ohms
Junction	≈ 530,000 ohms	≈ 63,000 ohms	≈ 25 ohms
Voltage Gain	$\frac{(r_b + r_m) R_L}{(R_g + r_b + r_e)(R_L + r_b + r_c) - r_b (r_b + r_m)}$	$\frac{(r_e - r_m) R_L}{(R_g + r_b + r_e)(R_L + r_e + r_c - r_m) + r_e (r_m - r_e)}$	$\frac{r_e R_L}{(R_g + r_b + r_e)(R_L + r_e + r_c - r_m) + r_e (r_m - r_e)}$
P.C.	≈ 30	≈ −130	<1
Junction	≈ 150**	≈ −575	<1
Power Gain	$\frac{4 R_L R_g (r_b + r_m)^2}{[(R_g + r_b + r_e)(R_L + r_b + r_c) - r_b (r_b + r_m)]^2}$	$\frac{4 R_L R_g (r_m - r_e)^2}{[(R_g + r_b + r_e)(R_L + r_e + r_c - r_m) + r_e (r_m - r_e)]^2}$	$\frac{4 R_g R_L r_e^2}{[(R_g + r_b + r_e)(R_L + r_e + r_c - r_m) + r_e (r_m - r_e)]^2}$
P.C.	≈ 100 (20 db)	≈ 1700 (32 db)	≈ 0.1
Junction	≈ 440 (26 db)	≈ 6600 (38 db)	≈ 0.02
Current Gain	$\alpha_{cc} = \frac{i_2}{i_1}$	$\alpha_{ec} = \frac{\alpha_{cc}}{1 - \alpha_{cc}}$	$\alpha_{cb} = \frac{-1}{1 - \alpha_{cc}}$
P.C.	≈ 2.3	≈ −1.66	≈ 0.77
Junction	≈ 0.96	≈ 24	≈ −25
Stability P.C.	Stable unless $R_L = 0$*	Unstable	Unstable
Stability Junction	Stable	Stable	Stable
Phase P.C.	No reversal unless R_L low or α high	Voltage and current phase reversal	No phase reversal usually
Phase Junction	No phase reversal	Voltage phase reversal	Current phase reversal
Advantages	High R_c	High R_i and gain; single voltage supply; high Z levels for junc.	Cathode follower action; high current gain; good freq. resp.
Disadvantages	Low R_i; low gain for point-contact types	Unstable	Voltage and power gain poor; may be unstable

* Point-contact transistors are available which are short-circuit stable.
** These are revised values, slightly higher then were given in Part VII.



FIG. 2—Biasing connections for grounded-base connection



FIG. 3—Grounded-emitter circuit for pnp and point-contact transistors



FIG. 4—Same as Fig. 3 except for npn transistor instead of pnp

fers to grounded-emitter connection, and similarly R_{i_c} refers to the grounded-collector connection.

(2) In Eq. 8, since r_b, r_m, r_c and R_L are in general positive numbers, R_i will always be less than $r_e + r_b$ by the quantity $r_b r_m/(R_L + r_c)$.

(3) In contrast, in Eq. 7, the input resistance will in general be greater than $r_e + r_b$, by the quantity $r_c r_m/(R_L + r_c + r_e - r_m)$. As this latter quantity may be negative, two possibilities occur: (a) Junction transistors: As alpha is less than unity, and as alpha $= r_m/r_c$, $(r_c - r_m)$ is always positive. Hence, $r_c r_m/(R_L + r_c + r_e - r_m)$ is always positive and R_{i_c} is always greater than $r_e + r_b$. (b) Point-contact transistors: In this case alpha is greater than 1; therefore, r_m is greater than r_c and $r_c - r_m$ is negative. However, by making R_L greater than $r_c - r_m$, $r_c r_m/(R_L + r_c + r_e - r_m)$ can still be made positive and an input resistance greater than $r_e + r_b$ obtained.

Typical Values

Using the typical values from Table I, $R_{i_c} = 35{,}000$ ohms for the point-contact transistor and 700 ohms for the junction unit. These values should be compared with 150 ohms and 90 ohms respectively, obtained for the grounded-base connection.

High Input Resistance

As can be seen from Eq. 6, it is possible, in the grounded-emitter circuit, to make the input resistance quite high by proper choice of R_L. This is not, in general, possible with the grounded-base connection (see Eq. 8). When $R_L + r_c + r_e = r_m$, the denominator of the second term right-hand side, Eq. 6, becomes infinite, and the input resistance becomes, theoretically, also infinite. It is profitable to consider two cases:

(a) Junction: As alpha is less than 1, and r_c is greater than r_m, the second term right-hand side can be made very large only if R_L is very small, and alpha is very near unity, say 0.997. Further, if R_L is made small, the possible voltage and power gain will be small.

(b) Point contact: Making $R_L + r_e + r_c = r_m$ is entirely feasible, and high input resistances are readily achievable in practice.

In Eq. 6 it is very possible that r_m is greater than $(R_L + r_e + r_c)$ if R_L is sufficiently small, and this may easily lead to a negative value of R_{i_c}. This leads to a condition of instability wherein the circuit sings or oscillates parasitically. The subject of instability will be treated later in this series.

Voltage Gain

Returning to Eq. 3 and 4, and solving for i_2

$$i_2 = \frac{e_g\,(r_m - r_c)}{[(R_g + r_e + r_b)(R_L + r_c + r_e - r_m) + r_c\,(r_m - r_c)]} \qquad (9)$$

The voltage gain VG_c is then given by

$$VG_c = \frac{-i_2 R_L}{e_g} = \frac{-(r_m - r_c)\,R_L}{[(R_g + r_e + r_b)(R_L + r_c + r_e - r_m) + r_c\,(r_m - r_c)]} \qquad (10)$$

Using typical values, $VG_c = -130$ for point-contact units, and $VG_c = -575$ for junction units.

These values should be compared with 30 and 150 respectively for the grounded-base connection. The negative sign shows that the voltage across R_L and the input voltage e_g are 180 degrees out of phase. Thus it is seen that the grounded-emitter connection produces a phase change of 180 degrees. It will be recalled that the grounded-base connection does not produce phase inversion.

To find the theoretically maximum value of VG_c, one assumes, as was done for the grounded-base connection, that $R_L = \infty$, and $R_g = 0$. Numerator and denominator of Eq. 10 are divided by R_L. Multiplying and dividing numerator by r_c

$$VG_c\ (\max) = -\left[\alpha - \frac{r_c}{r_c}\right]\frac{r_{22}}{r_{11}} \qquad (11)$$

Equation 11 should be compared with Eq. 12 below, which is the corresponding expression for the grounded-base connection of a transistor.

$$VG\ (\max) = \alpha\,\frac{r_{21}}{r_{11}} \qquad (12)$$

The maximum theoretical voltage gain for the grounded-emitter connection is somewhat less than that for the grounded-base connection; however, since for most transistors r_c/r_c is negligible compared to alpha, there is in practice no appreciable difference between these two gains. As the numerical values obtained indicate for specific values of transistor and circuit parameters, the grounded-emitter connection need not always show a smaller gain than the grounded-base connection. The reason follows from the difference in the way the voltage gain varies with R_L and r_c in the two expressions for voltage gain.

Power Gain

Power gain is obtained from the formula

$$PG_c = \frac{I_2^2 R_L}{e_g^2/4R_g} = \frac{4R_g R_L i_2^2}{e_g^2} \qquad (13)$$

$$= \frac{4R_g R_L\,(r_m - r_c)^2}{[(R_g + r_e + r_b)(R_L + r_c + r_e - r_m) + r_c\,(r_m - r_c)]^2} \qquad (14)$$

Using typical values, $PG_c = 1{,}700$ for point-contact units and 6,600



FIG. 5—Curves of α_{cc} vs frequency for grounded-base connection



FIG. 6—Curves of α_{eb} vs frequency for grounded-emitter connection



FIG. 7—Equivalent circuit of grounded-base circuit shows loop currents

for junction transistors.

By comparison, for the grounded-base connection, corresponding values are 100 and 440 respectively. The grounded-emitter connection is inherently capable of power gains greater than those for the grounded-base connection.

Output Impedance

To find the output impedance, e_g is set equal to 0 in Eq. 3, and Eq. 4 is set equal to e_g instead of to 0. This is equivalent to removing the signal from loop 1 of Fig. 1, and inserting it in loop 2.

The resulting equations are

$$(R_g + r_b + r_e)\, i_1' + r_e i_2' = 0 \qquad (15)$$

$$(r_e - r_m)\, i_1' + (R_L + r_c + r_e - r_m)\, i_2' = e_g \qquad (16)$$

Solving for i_2'

$$i_2' = \frac{(R_g + r_b + r_e)\, e_g}{[(R_g + r_b + r_e)(R_L + r_c + r_e - r_m) - r_e (r_e - r_m)]} \qquad (17)$$

$$R_{oo} = \frac{e_g}{i_2'} - R_L$$

$$= r_c + r_e - r_m + \frac{r_e r_m - r_e^2}{R_g + r_e + r_b} \qquad (18)$$

Using typical values $R_{oo} = -13{,}000$ ohms for point-contact units and 63,000 ohms for junction units.

The fact that the output resistance is negative for the point-contact transistor indicates that, under average operating conditions, the point-contact transistor tends to be unstable when used in the grounded-emitter connection. Because this type of connection has some very worthwhile features, however, it is sometimes profitable to alter the circuit slightly to make it stable. For a given transistor, r_m, r_c, r_b and r_e are fixed. Adding series resistance to r_e will bring the output resistance into the range of positive values. A resistance of approximately 750 ohms placed in series with the emitter will make R_o plus for the point contact. This is a common artifice to stabilize a transistor circuit.

Because r_e is greater than r_m for junction types, the output resistance is always positive for the junction transistor and it may be inferred that, collating Eq. 18 with Eq. 7, the grounded-emitter connection is unconditionally stable for this type of transistor.

Regarding magnitudes, an inspection of Eq. 18 will show that the very high values of resistance possible for R_t, Eq. 7, are, even theoretically, not feasible for R_o. Since adding a high resistance to r_e to make R_o positive introduces prohibitive losses, just enough resistance is usually added to make R_o slightly positive, for the point-contact unit. Accordingly, the grounded-emitter connection for this type usually results in a high-input, low-output impedance arrangement. For the junction transistors, low-input, high-output impedance arrangements are possible; but, with the proper α_{cc} and R_L, both high input and output impedances are attainable.

Other Advantages

From a biasing standpoint, the grounded emitter has a particular advantage over the grounded base. Figure 2 shows the elementary biasing arrangement for the grounded-base connection.

Speaking generally, since the emitter and collector currents in the base are in opposite directions, it would be difficult to use a single battery, in the base, to bias emitter and collector simultaneously. The directions of current shown in Fig. 2 are electronic; those in Fig. 1 are arbitrary.

In Fig. 3 a possible biasing arrangement for the grounded-emitter connection is shown. Note the use of a single battery for the bias supply. The d-c collector-to-emitter path biases the emitter with respect to the junction point by an amount $I_2 r_c$. Point B is negative with respect to point E by an amount $I_b R_g$, and the correct bias polarities are achieved using only one power supply. The polarity in Fig. 3 is for point-contact and *pnp* transistors.

The sketch in Fig. 4 shows the same type of connection for the *npn* transistor. Here, point B is positive with respect to E by an amount $I_b R_b$, and the correct polarities are observed.

One interesting but unfortunate aspect of the grounded-emitter connection is its poor frequency response compared to the grounded-base connection. In transistor work, frequency response usually means α versus frequency. Figure 5 shows two typical curves for α versus frequency for a point-contact unit and the junction unit, both measurements having been made using a grounded-base connection. Figure 6 shows frequency response curves for the same units in the grounded-emitter connection.

Current Gain

In general, alpha is a measure of the current gain in the transistor, and is defined as $-i_c/i_e$. For the grounded-base connection, it can be verified from Fig. 7 that $i_e = i_1$ and $i_c = i_2$, and that for this connection only

$$\alpha = -\frac{i_c}{i_e} = -\frac{i_2}{i_1} \qquad (19)$$

A notation frequently used in the literature is to use the small letter a for the ratio of output to input current, that is

$$a = \frac{i_2}{i_1} \qquad (20)$$

and from Eq. 19, for the grounded-base connection

$$\alpha = -a \qquad (21)$$

In the case of the grounded-emitter connection, it is not so much the ratio of collector current to emitter current that is of interest, as the ratio of output to input current, a. The ratio of collector to emitter current is invariant with the method of connection. Except for stray capacitance, the transistor does not know how it is hooked up; but the ratio of output to input current differs quite widely for the three possible connections. The grounded emitter current gain varies with α_{ee}. In practical transistor measurements it is common to measure the grounded-base alpha, α_{cc}, and to compute from this data the grounded-emitter current gain.

In specifying alpha, it is convenient to use the letters c, b, and e as subscripts and by their sequence to indicate the method of connection. In practice, the letters in the subscript state first the output current terminal, and then the input current terminal—the letter omitted implies the common or grounded terminal. Thus, α_{cc} is the grounded-base α, α_{eb} the grounded-emitter α, and α_{cb} the grounded-collector α. When speaking of the frequency response curves, the ratio of output to input current versus frequency is taken, not the ratio of collector current to emitter current.

From Eq. 5 and 9, the value of a for the grounded-emitter connection is

$$\frac{i_2}{i_1} = \alpha_{eb} = \frac{r_m - r_c}{R_L + r_e + r_c - r_m} \qquad (22)$$

While this is true mathematically, from the physical standpoint this relation has limited use as a comparison number for transistors because the gain shown may differ over a very wide range depending on the value selected for R_L. It will be recalled that alpha for the grounded-base connection is measured with the collector shorted. Consider the equations of the grounded-base connection:

$$v_1 = (R_g + r_{11})\, i_1 + r_{12} i_2 \qquad (23)$$

$$v_2 = r_{12} i_1 + i_2\,(R_L + r_{22}) \qquad (24)$$

If v_2 is set equal to 0, (short-circuit the collector and put R_L equal to 0)

$$-\frac{i_2}{i_1} = \frac{r_{12}}{r_{22}} \qquad (25)$$

which is α_{cc} by definition.

Hence, to get a comparable figure of merit, and render the result independent of R_L, α_{eb}, the current gain for the grounded-emitter connection, is defined by putting $R_L = 0$ in Eq. 22.

$$\alpha_{eb} = \frac{r_m - r_c}{r_e + r_c - r_m} = \frac{\frac{r_m}{r_c} - \frac{r_c}{r_c}}{\frac{r_e}{r_c} + 1 - \frac{r_m}{r_c}} \qquad (26)$$

Neglecting r_c/r_c compared to r_m/r_c and to unity and using the grounded-base alpha definition, $\alpha_{cc} = r_{12}/r_{22} \approx r_m/r_c$

$$\alpha_{eb} = \frac{\alpha_{cc}}{1 - \alpha_{cc}} \qquad (27)$$

Equation 27 does not depend on the load resistance, and shows how the current gain for the grounded-emitter connection varies with the grounded-base current gain, α_{cc}. A significant aspect of the grounded-emitter connection is that current gains greater than unity are entirely possible, using junction transistors. Typical values are

$\alpha_{eb} = -1.66$ for point-contact unit (28)
(the minus sign indicates phase reversal)

and $\alpha_{eb} = 24$ for junction units. (29)



FIG. 8—Equivalent circuit of grounded-collector connection

Frequency Response

The ordinate in Fig. 6 is α_{eb} of Eq. 27. The reason for the relatively poor frequency response of the grounded-emitter connection compared to the grounded-base arrangement may be seen.

Due to the capacitance, both stray and internal, and to the transient time dispersion effects[8], at some frequency below cutoff, α_{cc} falls off by 10 percent. This would be point X of Fig. 5. When α_{cc}' is 0.9 α_{cc}

$$\alpha_{eb}' = \frac{0.9\,\alpha_{cc}}{1 - 0.9\,\alpha_{cc}}$$

(using Eq. 27) and for the junction type $\alpha_{eb}' = 6.34$.

Comparing this value with $\alpha_{eb} = 24$ (Eq. 29) when α_{cc} was 0.96, it is seen that, due to the nature of the $\alpha_{cc}/(1 - \alpha_{cc})$ function, when α_{cc} falls off by 10 percent, the grounded-emitter alpha, α_{eb}, falls off by almost 75 percent. The frequency response of the grounded-emitter connection falls off much more rapidly than the inherent frequency response of the transistor as measured by α_{cc}.

These effects are illustrated by Fig. 5 and 6. Both curves are for the same transistors, but Fig. 5 was obtained using the grounded-base arrangement, and Fig. 6 using the grounded-emitter arrangement. A rule of thumb sometimes useful is to consider that the frequency of alpha cutoff, using the grounded-emitter connection, may be a fifth or less of the response using the grounded-base arrangement.



FIG. 9—Grounded-collector connection using electron flow

As the numerical example shows (see Eq. 28) for point-contact transistors the grounded-emitter current gain will usually be negative. From Eq. 27, if α_{cc} is greater than unity, as in the case of point-contact units, α_{eb} is negative, representing an 180-degree phase reversal in current.

It is desirable to bear in mind that:

(1) When the signal is fed into the emitter, and the output taken from the collector, the transistor will introduce no significant phase change, regardless of the method of connection. Under special conditions of loading and frequency dependence of parameters, changes in phase may be observed, but these will in general be less than 180 degrees. The significant point is that phase change is essentially associated with the method of feeding the signal into the transistor;

the method of connection introduces a phase change only because it determines the method of feeding the signal. The grounded-base connection is an illustration of feeding the signal into the emitter and taking the output from the collector—no significant phase change is observed.

(2) A phase change is usually observed in the grounded-emitter connection because the signal is fed into the base. A similar effect will be observed for the grounded-collector connection, where the signal is also fed into the base.

Unlike the vacuum tube, which is usually considered to be essentially a voltage amplifier, the transistor usually amplifies both voltage and current concomitantly. For the grounded-emitter connection, where both current gain and voltage gain are usually greater than unity for both point-contact and junction units, the transistor is a power amplifying device. As



FIG. 10—Grounded-emitter connection using electron flow

an illustration, in transistor equipments using several stages in cascade, or in a typical superheterodyne arrangement beginning with the very first r-f stage, one computes power gain stage by stage, so that there is a successive power build-up. This method of computation should be compared with the vacuum-tube analog, where voltage gains only are normally computed, up to the one or two last power gain stages.

Grounded Collector

The third principal method of connection of transistors is in the grounded-collector or common-collector connection. An equivalent circuit diagram is given in Fig. 8.

In writing the circuit equations, bearing in mind the rules previously laid down in Part VII of this series[1], the following must be considered for the grounded-collector equivalent circuit:

(1) Current i_e = current through r_e which flows toward junction J, and is in this case given by i_2, that is $i_2 = i_e$.

(2) The polarity of $r_m i_2$, consistent with the usage for the grounded-emitter and grounded-base connections, is chosen minus toward junction J, and plus toward the collector terminal.

(3) For the grounded-collector connection, i_c = current through $r_c = i_1 + i_2$.

The current-determining equations are

$$(R_g+r_b+r_e)\, i_1+(r_e-r_m)\, i_2=e_g \qquad (30)$$

$$r_e\, i_1+(R_L+r_e+r_e-r_m)\, i_2=0 \qquad (31)$$

$$i_1=\frac{e_g\,(R_L+r_e+r_e-r_m)}{[(R_g+r_b+r_e)\,(R_L+r_e+r_e-r_m)-r_e\,(r_e-r_m)]} \qquad (32)$$

$$i_2=\frac{-e_g\,r_e}{[(R_g+r_b+r_e)\,(R_L+r_e+r_e-r_m)-r_e\,(r_e-r_m)]} \qquad (33)$$

The value of i_2 when e_g is considered to be in series with R_L is



FIG. 11—Grounded-base connection using electron flow

$$i_2'=\frac{+e_g\,(R_g+r_b+r_e)}{[(R_g+r_b+r_e)\,(R_L+r_e+r_e-r_m)-r_e\,(r_e-r_m)]} \qquad (34)$$

Input Resistance

The input resistance of the grounded-collector circuit is

$$R_{ic}=\frac{e_g}{i_1}-R_g$$

$$=r_b+r_e-\frac{r_e\,(r_e-r_m)}{R_L+r_e+r_e-r_m} \qquad (35)$$

Typical values are R_{ic} = 2 megohms for point-contact units and + 0.7 megohm for junction units.

The high input resistance obtainable from the grounded-collector connection is in sharp contrast to the input resistance of a few hundred ohms for the grounded-base connection.

Thus it is seen that the grounded-base connection exhibits a low input resistance, while the grounded-emitter and grounded-collector connections show quite a high input resistance. Redrawing Fig. 8, using this time instantaneous electron current flow paths, instead of the arbitrarily-selected current directions, Fig. 9 is obtained.

R_L Equals Zero

If a unit change of current occurs through r_e, since the current gain is α_{cc}, a current change of $\alpha_{cc} \times 1$ will occur through r_c. At the junction point J, since the sum of the currents at a junction must be zero, a current of $1 - \alpha_{cc}$ units will flow through r_b. This is the condition for $R_L = 0$, that is, output shorted, for the current through r_c is not exactly α_{cc} times the current in r_e unless $R_L = 0$, by definition. When α_{cc} is very near unity, $1-\alpha_{cc}$ is very near zero, and therefore a very small current flows in loop 1, and the circuit to the right of points X-Y (Fig. 9) presents a high impedance to generator. The current gain for the grounded-collector connection is given by the equation

$$\alpha_{cb}=\frac{i_1}{i_1}=\frac{-1}{1-\alpha_{cc}} \qquad (36)$$

Typical values are 0.77 for point-contact units and −25 for junction units.[3]

In Fig. 10 for the grounded-emitter case, a unit change in current through r_e results in α_{cc} times that change in current through r_c, for $R_L = 0$. The net current change through r_b is $1 - \alpha_{cc}$ and tends to make i_1 very nearly equal to 0 and the input impedance high, as alpha approaches unity. Note also how the current gain is now $i_2/i_1 = \alpha_{cc}/(1 - \alpha_{cc})$ in agreement with Eq. 27.

In Fig. 11 for the grounded-base connection, unit current change through r_e produces $\alpha_{cc} \times 1$ current change through r_c, and therefore $1 - \alpha_{cc}$ current change in r_b. Hence the input current through r_e does not approach 0 as α_{cc} approaches 1. Thus the input resistance for the grounded-base connection will never become very high.

R_L Not Zero

When R_L is not zero, a slightly different approach will provide the physical interpretation for the high input resistance. In Fig. 9 for the grounded-collector connection when

R_L and i_2 have values such that

$$e_g \cong i_2 (r_e + R_L) \qquad (37)$$

or when

$$e_g \cong i_1 (r_m - r_e) \qquad (37')$$

a very small drop in $r_b + R_g$ only is involved, that is $i_1 = 0$, and the input impedance is high. If Eq. 37 and 37′ are valid, then

$$r_e + R_L = r_m - r_e \qquad (38)$$

The significance of Eq. 38 can be seen by considering Eq. 32. Since none of the terms in the denominator can ever be infinite for finite values of load resistance, the only way for i_1 to be close to zero is for the numerator to be very nearly zero, that is

$$R_L + r_e + r_e - r_m \cong 0 \qquad (39)$$

When a value of R_L is used which makes Eq. 39 true, then R_i may become very high, see Eq. 35, and the physical interpretation is that an insignificant amount of current is drawn from the source generator e_g. The condition expressed by Eq. 39 is identical to that in Eq. 38, verifying the conditions for high input resistance.

Similar remarks apply to the grounded-emitter connection. (See Fig. 10). When

$$e_g \cong (i_1 + i_1)\, r_e = (R_L + r_e - r_m)\, i_2 \qquad (40)$$

i_1 is approximately zero, and the drop across $R_g + r_b$ is negligible. When $i_1 \cong 0$, from Eq. 40

$$i_2 r_e \cong (R_L + r_e - r_m)\, i_2 \qquad (41)$$

Transposing Eq. 41, R_L must be selected so that

$$R_L + r_e + r_e - r_m = 0 \qquad (42)$$

exactly as in Eq. 39. This is confirmed by Eq. 5, where it may be seen that if Eq. 42 is true, loop 1 current is negligible. From Eq. 6 one can then observe that if Eq. 42 is valid, the input resistance may be quite high.

But these remarks do not apply to the grounded-base connection. For the grounded base case,

$$i_1 = \frac{e_s (R_L + r_b + r_c)}{[(R_g + r_b + r_e)(R_L + r_b + r_c) - r_b (r_b + r_m)]}$$

and by inspection this cannot be made to approach 0 by any choice of R_g and R_L, and therefore a high input resistance is impossible.

Returning now to the analysis of the grounded-collector connection,

$$VG = \frac{-i_2 R_L}{e_g}$$

and, using Eq. 33

$$VG = \frac{r_e R_L}{[(R_g + r_b + r_e)(R_L + r_e + r_e - r_m) - r_e (r_e - r_m)]} \qquad (43)$$

Typical values for VG are slightly less than unity, but positive, for point-contact and junction transistors.

Output Resistance

Since $R_o = (e_g / i_2') - R_L$, using Eq. 34

$$R_o = r_e + r_e - r_m - \frac{r_e (r_e - r_m)}{R_g + r_b + r_e} \qquad (44)$$

Typical values for R_o are −650 for point-contact units and 65 for junction units.

The grounded-collector connection is a low-resistance output connection. While the negative sign of R_o for the point-contact connection is generally undesirable, producing an unstable condition, nonetheless, proper operation is possible. If a stabilizing resistance of about 1,000 ohms is added in series with the output, (in series with r_e at the emitter) the net output resistance becomes positive.

Cathode Follower

Considering the high input resistance and low output resistance levels of the grounded-collector connection, and bearing in mind the low voltage gain figures obtained, a close analogy between this method of connection and the cathode follower of vacuum tube practice is observed. The current gain for the junction type (Eq. 36) is 25, further improving the analogy.

For the point-contact type, the current gain is rather poor, + 0.768, and combined with the negative output indicates that, in general, the applications of point-contact transistors connected in this way are rather limited. For the junction transistors, both input and output resistances are positive, and the relative magnitudes suggest strongly the transformer step-down effect obtainable in the cathode follower.

A disadvantage of the grounded-collector connection arises from the fact that the output is taken from the emitter terminal, see Fig. 8. Because the output is taken from the emitter terminal, large output voltage swings are not feasible. In general, emitter biases are of the order of 1 volt, and collector biases up to 50 volts. Excessive voltage swings in the emitter will move it into regions where the transistor is either entirely inoperative as a transistor, or has reached saturation as evidenced by clipping.

Regarding the power capabilities, using Eq. 33

$$PG = \frac{4 R_g R_L i_2^2}{e_g^2} = \frac{4 R_g R_L r_e^2}{[(R_g + r_b + r_e)(R_L + r_e + r_e - r_m) - r_e (r_e - r_m)]^2}$$

Typical values for power gain in the grounded-collector connection are 0.1 for point contact units and 0.02 for junction units.

The power gain of the grounded-collector connection may be made somewhat higher by suitable choice of R_L and R_g, but in general tends to be unimpressive. In practice, the grounded-collector connection is used principally as a coupling device for impedance matching and, using the junction transistor, for current gain. It is clearly not suited for voltage or power amplification. There is experimental evidence that the frequency response of this connection holds some promise.

Summary

This article has pointed out the pertinent operating characteristics of transistors in grounded-emitter and grounded-collector connections, as compared to the grounded-base connection explained in the previous part of this series.

These characteristics are summarized in Table II, which appears on page 167 of this issue.

References

(1) Abraham Coblenz and Harry L. Owens, Equivalent Transistor Circuits and Equations, ELECTRONICS, p 156, Sept. 1953.

(2) Abraham Coblenz and Harry L. Owens, Point-Contact Transistor Operation, ELECTRONICS, p 158, July 1953.

(3) R. L. Wallace and W. J. Pietenpol, Some Circuit Properties and Applications of npn Transistors, *BSTJ*, p 530, July 1951.

(4) R. M. Ryder and R. J. Kircher, Some Circuit Aspects of the Transistor, *BSTJ*, p 367, May 1949.

PCM Coding System Uses Special Tubes

Multielectrode selector and coding tubes translate voltages sampled from signal into pulse-code impulses. Circuit is more simple and compact than present pulse-code modulators. Basic system can be used for analog-to-digital data conversion, speech scrambling, statistical tabulation and pulse-height analysis

By ARTHUR G. FITZPATRICK

Research Activity
Electronic Instruments Division
Burroughs Corporation
Philadelphia, Pa.

USE OF PULSE-CODE modulation has been restricted, especially in airborne telemetering, by the weight, size and complexity of the modulating equipment.

The basic pulse-coding system to be described achieves a reduction in weight, size, complexity and power consumption over present pulse-code modulation methods. Two special tube types, incorporated in a circuit requiring a minimum of additional components, perform the functions of sampling, quantizing and coding. Sampling is achieved in the selector tube, a ribbon-beam cathode-ray tube having ten separate targets. Quantizing and coding are done in the coding tube, which has ten stable electron-beam positions produced by crossed electric and magnetic fields. In addition to simplifying pcm circuits, the method described may be useful in related techniques such as analog-to-digital data conversion, statistical tabulation and pulse-height analysis.

The Selector Tube

The beam-deflection selector tube is shown in cross section in Fig. 1A. The electron gun produces an efficient ribbon beam that comprises over 90 percent of the cathode current. The tube delivers high beam current at low accelerating voltage, 1 ma at 250 volts. This low voltage permits a deflection sensitivity of 12 volts per target.

Use of a ribbon beam allows short, sharp focusing in a small bulb size. The tube fits in a bulb 1¼ in. in diameter and 1¾ in. high. The ten targets are 0.060-in. wires with suitable suppressors. Each target is brought out individually through the stem. The electrical characteristics of the gun and three targets are given in Fig. 2. Reliability is provided by a low-power heater (2 watts), low cathode-current density, absence of critical element spacing and simple construction requiring a minimum of control elements and external circuits.



Exploded view of coding tube shows four stacked collector rings that surround anode. Apertures in anode determine which ring receives current

The Coding Tube

The coding tube is shown in cross section in Fig. 1B. An electric field and an axial magnetic field within the tube produce ten stable beam positions of which no more than one is possible at a given time. While the beam is holding in any position, portions of it are permitted to pass through coded apertures in the anode to the four rings comprising the parallel binary digits; 300-400 microamperes may pass through each aperture. The tube and its associated permanent magnet occupy a space 1¾ in. in



Basic elements of selector tube. Ribbon-shaped electron beam strikes one of ten targets as determined by deflection voltage derived from signal source. All connections are brought through the base of the tube

diameter and 1¼ in. high.

With a uniform magnetic field of 300 to 350 gausses within the tube and all electrodes 100 volts positive with respect to the cathode few electrons leaving the cathode reach any of the positive electrodes. However, if the potential of one of the spades is lowered and the current to this spade monitored, the characteristic of Fig. 3 will result. If a 100,000-ohm load resistor is placed in this circuit, two stable operating points will be produced: one near +100 volts and the other near cathode potential

With resistors in all the spades, and a spade and anode supply of 100 volts, assume the tube to be initially cut off. If the potential of one of the spades is lowered beyond the point of unstable equilibrium, usually 40 volts positive with respect to cathode, that spade will operate at its lower stable point, 1 ma, with the anode and collector rings receiving a total of 8 ma. Holding action will continue until operating conditions are changed externally, thus providing a simple memory device.

Circuit Operation

A partial coding circuit is shown in Fig. 4. Only three of the ten connections are completed. Assume that the coding tube is cut off and the selector-tube beam is cut off by bias on its focus electrode. If the deflection-plate voltage is of the proper amplitude and the beam is turned on for a short time, the beam will fall on one of the targets, thus lowering its potential. As this potential passes the point of unstable equilibrium on the spade characteristic, the spade will take over and assume its stable position near cathode potential. It will make no difference if the selector-tube beam is turned off; the coding tube will remember the selected target.

Only one spade will assume its low operating potential when the beam falls equally on two targets. The spade that holds is determined by the direction of the magnetic field applied to the coding tube. This choice remains constant once the apparatus is set up. The coding tube is cleared before each sample is taken; thus only the new level will be stored.

A complete pcm circuit is shown in Fig. 5. If one of the spades in the coding tube is holding, the cathode current for the tube is approximately 9 ma. The cathode resistor for the triode control tube is adjusted until the voltage at its plate is about 100 volts below the coding tube spade-anode supply, about 150 volts above ground.

Next, the voltage on the selector-tube focus electrode is made sufficiently negative with respect to ground and its own cathode that the selector beam is cut off and no current reaches the targets. Any voltage applied to the deflection plates produces no output. However, if the beam is turned on momentarily, current will strike a target corresponding to the amplitude of the deflection voltage at the instant of sampling.

The signal to be sampled and coded is applied to the selector-tube deflection plates. If a negative sampling pulse is applied to the input the control triode and coding tube will be cut off. Simultaneously, the same sampling pulse turns the selector-tube beam on and the beam falls on a target corresponding to the instantaneous deflection-plate voltage.

During the sampling pulse the R-C network comprising the load



FIG. 2—Selector-tube deflection characteristics of three adjacent targets



FIG. 1—Cross-section views of special tubes used in pulse-code modulation system

resistance and stray capacitance of the previously-holding spade discharges and the R-C network in the new position charges through the selector-tube beam. The sampling pulse must be long enough for both these actions to be completed, approximately 3 microseconds. Since 1 ma of beam current is available, the final potential across the new R-C combination will be close to 100 volts.

At the end of the sampling pulse, the selector tube is turned off and the coding tube turned on with the selected spade held at or near coding-tube cathode potential as a

result of charge stored in its stray capacitance. With low potential on one spade, the coding tube locks on it. Coding-tube current goes to this electrode and to the anode and proper collector-ring outputs. This condition will be maintained until the next sampling pulse causes the action to be repeated.

Outputs

The output of the coding tube is determined by monitoring the current to the four collector rings. Each ring either receives current or does not, depending upon the relative location of the beam and the coding of the anode apertures.



FIG. 5—Coding system for pulse-code modulation



FIG. 3—Spade characteristic for coding tube



FIG. 4—Basic coding circuit for pulse-code modulation

The output is in straight decimal-to-binary notation. Use of the rings as output permits a wide range of voltage and impedance levels to be delivered to the load.

The output may be derived alternatively from the spades, with a low potential indicating the presence of the beam at that level. However, this method is limited by loading effects on the spades, and does not provide the desired binary-coded output.

Increasing Sampling Levels

Where greater definition is required, the use of these tubes may be extended by interconnecting two systems of the type described. As many as twenty levels may be obtained.

To specify completely the increased number of sampling levels, a fifth binary digit is necessary that is obtained from one of the spades, selected so that its output is high when the positive half of the input signal is sampled and low when the negative part of the signal is sampled. The coded output then consists of a four-digit binary code representing signal amplitudes from 0 to 9, with the fifth digit indicating plus or minus.

One hundred levels may be obtained by arranging one pair of tubes to read the tens digit, with a feedback network to the second pair where the units digit can be read.

Other Applications

In an analog-to-digital converter, the analog voltage to be converted can be applied to the selector-tube deflection plates, with the digital output taken in decimal form from the coding-tube spades or in binary form from the collector rings. The required output accuracy determines whether 10, 20 or 100 levels are to be sampled.

The tubes may also be used in enciphering or speech scrambling. Instead of wiring a 1-to-1 correspondence between targets and spades, the leads from both targets and spades are brought to a plug-board, and the relationships changed by rearranging the wiring.

This pcm system may also be adapted for use in statistical tabulation. A multi-output tube has been developed for this purpose. Instead of coded holes and collector rings, the anode has a slot in each of ten possible positions with an individual target outside each slot. These targets receive appreciable currents, and are electrically isolated from the spades and anode. If a voltage proportional to the data to be tabulated is applied to the deflection plates, a single output is created that operates the counter to tabulate the data.

Another possible application is that of a pulse-height analyzer. Pulses, the height of which are to be analyzed, are applied to the selector-tube deflection plates. Turning the beam on at the peak amplitude of the pulse initiates the sampling and quantizing action.

Bibliography

S. Fedida, A System of Pulse-Code Modulation Using Circulated Pulses, *Electronic Eng.*, 24, No. 294, p 356, Aug. 1952.

W. M. Goodall, Telephony by Pulse-Code Modulation, *Bell System Tech. Jour.*, 26, No. 3, p 395, Jul. 1947.

L. A. Meacham, and E. Peterson, An Experimental Pulse-Code Modulation System of Toll Quality, *Bell System Tech. Jour.*, 27, No. 1, p 1, Jan. 1948.

M. Langevin, and G. Allart, Ten-Channel Impulse Analyzer, *Minutes of Meeting of Academie des Sciences*, p 515, Jan. 28, 1952.

W. E. Glenn, A Pulse-Height Distribution Analyzer, *Nucleonics*, 9, No. 6, p 26, Dec. 1951.

S. Kuchinsky, Multi-output Beam-Switching Tubes for Computers and General-Purpose Use, Natl Conv IRE, March 25, 1953.

Wide-Range Vacuum Gage

Linear cold-cathode radium-type gage measures gas pressures from 1,000 to 0.0001 millimeters of mercury absolute with consistent accuracy. Collection of ions is made in a low-voltage field to minimize contamination of electrodes

By CLIFTON B. SIBLEY and JONATHAN R. ROEHRIG

National Research Corporation
Cambridge, Mass.

AN OUTGROWTH of the radium-type vacuum gage invented by Downing and described by Mellen[1], the gage to be described has six linear ranges to cover pressure measurements from 1,000 to 0.0001 millimeters of mercury.

The response of the gage is practically instantaneous, and the output signal to the meter is linear and proportional to the gas pressure. The signal is determined by the collection of gas ions produced by a constant flux of alpha particles emitted from a small nonhazardous sealed radium source. Essentially, all of the ions produced are collected in either of the two ionization chambers, one for the high ranges: 1,000, 100 and 10 mm, and one for the low ranges: 1, 0.1 and 0.01 mm. The ion current is amplified by a factor of 10^7 and is indicated by a panel meter or a recorder. A low-voltage collection field is used, thereby eliminating the problems of contamination of the electrodes.

The use of a special small chamber built into the measuring head excludes the possibility of nonlinearity due to recombination of the ions in the high-pressure ranges, a factor which limited the use of the previous gage. This has been done without sacrificing any of the inherent advantages of the previous gage, which included rugged construction, no filament, operation at the temperature of the gas being measured and the absence of mercury introduced into the system. The gage is normally calibrated for air but may recalibrated for other gases.

The volume of the sensing element has been kept small so that the pressure in the element will follow more closely sudden pressure changes in small-vacuum systems. The entire sensing element, including the radium source, range resistors, thermal relays, preamplifier and collector electrodes is mounted in a shell similar to that of a metal 6L6, which has a volume of about 50 cc as compared with 450 cc for the previous gage.



FIG. 1—Input circuit of vacuum gage. Relay RE_1 is closed for low-pressure-chamber operation. For high-pressure operation, RE_2 is closed

Sensing Element

As shown in the photograph, the sensing element consists of the ionization chamber and the preamplifier enclosed in a metal envelope. Separating them is a thin brass disk that is used to mount the radium source and the special small high-pressure chamber.

Below the disk is mounted the electrometer tube, the various input resistors and the range-changing relays. Since these components are located in the vacuum to be meas-



FIG. 2—Complete circuit of wide-range vacuum gage



Chamber volume of present vacuum gage is 50 cc against previous model's 450 cc

Exploded sensing element shows radium source, high-pressure chamber, collector electrode, electrometer tube, range relays, resistors and vacuum seal

ured, no special feedthrough insulators are necessary. The positive-ion collectors are merely the resistor leads extending into the ionization chambers. A Neoprene O ring seals the tube-envelope flange to the header flange and is compressed with a ring clamp around the flanges. For special applications, this joint may be made using solder.

D-C Amplifier

The Roberts[3] d-c amplifier circuit with the improvements developed by N. F. Moody[4] is essentially the basic circuit. A CK-571AX (5886) electrometer pentode is used in the input stage and a CK-546DX pentode in the cathode follower.

The low filament currents assure a long life for the filament batteries. Since the input resistor to the amplifier is 100,000 megohms on the lowest pressure range, it is necessary to connect the amplifier directly to the chamber. Therefore, the sensing element includes the first stage of the two-stage amplifier as well as the input switching circuits for range changing.

The six ranges are selected by means of three thermal relays. These relays are made specifically for switching very-high-impedance circuits and are available only in a single-pole, single-throw arrangement in which the arm of the relay is directly connected to one heater lead. Switching of the two high-impedance collector electrodes with one relay is impossible. To provide six ranges, it is necessary to connect the large chamber for the three low-pressure ranges and the small chamber for three high-pressure ranges to the electrometer grid.

The input circuit shown in Fig. 1 was developed to provide the necessary switching with the relays available. In each case the relay connects the unused collector to the feedback line. In order to zero set, both relays are closed, thereby simulating zero pressure in the ionization chamber. A third relay changes the input resistance to give two ranges for each chamber.

The remainder of the circuit is similar to that developed by Moody with the addition of the switching circuits. In the original Roberts circuit, the order of stability achieved was dependent on the gain of the feedback loop. Vacuum-tube electrometers are inherently low-gain tubes due to the low plate voltages and currents required for minimum grid current. To improve the loop gain and zero stability, positive feedback is added around the cathode-follower stage from the cathode to the plate of the electrometer tube.

In the previous gage, the ionization chamber produced a constant output current at all pressures below one micron. The current was the equivalent of that produced by 4.5 microns of air pressure. This dark current was found to be caused by the direct collection of alpha particles (positively charged He atoms) that hit the collector.

To balance out this current, the zero of the amplifier was displaced downscale so that at zero pressure the meter read zero. However, when the range was extended to 10 microns full scale, this dark current zero correction amounted to 45 percent of full scale and would have required a meter-reversing switch. In the new gage a shield prevents the alpha particles from striking the collector, eliminates the dark current and allows the sensitivity to be increased even further into the low-pressure range.

The minimum pressure that can be measured is limited by several factors. Among these are the grid current of the electrometer tube, the response time constant and the permissible contamination without loss of accuracy. The grid current of the electrometer tube sets an ultimate limit of about 10^{-6} mm as the lowest measurable pressure. This would require an input resistor of ten-million megohms giving a response time constant of well over one minute.

With an input resistor of only 100,000 megohms the input time constant is about 5 seconds and the negative feedback of the amplifier reduces the meter response to less than one second. Contamination that causes shunting of the input resistor also becomes a real problem if the resistor is increased above this value. These practical considerations limit the input resistance to 100,000 megohms, which corresponds to a minimum pressure reading of 10^{-4} mm.

References

(1) G. L. Mellen, Radium-Type Vacuum Gage, Electronics, Apr., 1946.
(2) R. B. Lawrance, paper presented at AIChE meeting, May 12, 1952.
(3) S. Roberts, A Feedback Micro-Microammeter, *Rev. Sci. Instr.*, p 181, June, 1939.
(4) N. F. Moody, Improved D-C Amplifier for Portable Ionization Chamber Instrument, *Rev. Sci. Instr.*, p 336, Apr. 1951.

Zero-Intercept

Phase meter uses new comparator circuits to determine zero-axis intercept of waveforms. Measures phase angle between two symmetrical or unsymmetrical waves at frequencies from 100 kc down to practically zero. Phase lead or lag is also indicated

By Y. P. YU *Chief Engineer, Advance Electronics Co., Passaic, N. J.*

INSTRUMENTS for measuring phase angle usually require the generation of two square waves from two input signals by successive processes of amplifying and clipping. The square waves are fed to a summing amplifier. The plate current of the sum amplifier is directly proportional to the phase angle between the two alternating voltages.

A direct current meter measuring the plate current can be used to indicate the phase angle between the two signals. However, phase lead or lag cannot be identified when this method is used.

Another method employs two differentiating circuits and a bistable multivibrator. The two square waves are fed to separate differentiating circuits, and the output pulses of both circuits are used to trigger the bistable multivibrator.

Averaging Effect

The chief difficulty of these methods lies in making the phase angles of the resultant square waves equal to those of the applied signal. Any variation in supply voltages, or in the d-c potentials across various coupling capacitors due to the harmonic contents of the applied signals, may change the levels at which clipping takes place. As a result the period of the positive loops of the resultant square waves will no longer equal that of the negative loops.

Since the zero axis of an alternating waveform moves to the line representing the average value of the waveform after an R-C coupling network, the phase angle of the resultant square wave would be very different from that of the original signal wave if a slightly



FIG. 1—Block diagram of phase meter. Peak to peak voltmeter measures amplitude of sawtooth wave generated between pulses from comparator circuits



FIG. 2—Basic comparator circuit uses amplifier with regenerative feedback to control flip-flop turn-off stage



FIG. 3—Complete phase meter circuit uses cathode follower inputs with or without phase inverters. Pulses from comparators control operation of sawtooth generator through multivibrator

Phase Comparison Meter

Front panel of type 404A Advancetron phase meter. Input jacks for waveforms being compared are at either end of panel. Controls next to each input provide for inserting 20-db attenuation and 180-degree phase shift. Indicator is 200-μa meter movement with 0-36, 0-90, 0-180 and 0-360 deg ranges

unequal change in clipping level occurs at an early stage.

The phase meter to be described here is shown in Fig. 1. Two comparator circuits are used, each producing a pulse when its input wave crosses the zero axis. The first pulse initiates generation of a sawtooth pulse, and the second pulse cuts off the sawtooth generator. The amplitude of the sawtooth wave generator varies with the time between the two pulses. This peak amplitude is measured with a vacuum-tube voltmeter calibrated to indicate phase angle directly. This method overcomes the previously mentioned difficulties, and has the additional advantage of allowing phase angle to be determined within one period of the waveform.

Comparator Circuit

The pulse-producing comparator circuit defines the instant when a given voltage or current waveform passes through a certain critical point on its negative or positive slope by the stable and sharp break characteristic of a nonlinear element, such as a germanium diode. This circuit will generate a narrow pulse, or a definite number of pulses, when a given voltage or current waveform reaches a critical point, then return immediately to its normal quiescent state.

The circuit diagram of the comparator circuit is shown in Fig. 2. The feedback network consists of a three-winding transformer. The amplifier is a single pentode V_1. Windings 1 and 2 are arranged so that mutual coupling between these two windings will produce regenerative feedback for the amplifier. Diodes V_2 and V_3 are connected so the first is cut off and the latter is conducting when the potential of the input waveform is above reference potential, and the condition will be reversed when the potential of the input waveform is below the reference potential.

The turn-off unit consists of triodes V_4 and V_5 connected as a bistable multivibrator. When the input is above the reference potential diode V_2 is cut off, diode V_3 is conducting and the loop gain of the amplifier and feedback network is less than one. Thus no oscillation can take place. As soon as the negative slope of the input waveform reaches a potential E_r, diode V_2 conducts, the regenerative feedback loop closes, and a positive pulse is produced at the output terminal.

This positive pulse also causes triode V_5 of the turn-off unit to conduct. The potential at the plate of V_5 drops, and a switching action occurs. At the end of the switching action, V_4 is cut off and V_5 conducts. Thus a positive step voltage appears at the plate of V_4 and a negative step voltage appears at the plate of V_5. This negative step voltage decreases the screen potential of V_1 and terminates the oscillation of the amplifier and feedback transformer.

As soon as the potential of the input waveform rises above the reference potential E_r, V_4 conducts and V_5 is cut off, and the screen potential of V_1 becomes high enough to allow the amplifier to function. However, since diode V_2 is cut off and the regenerative feedback is opened no oscillation can take place.

As soon as the input waveform decreases to a potential equal to that of the reference voltage, V_2 again conducts, oscillation takes place, and the switching action is repeated again. In this way the circuit will produce one pulse each time the waveform crosses the reference potential level.

Since no coupling capacitor is needed in the input, the low end of frequency response can be extended to less than one cycle per second without relaxation oscillation or bouncing, and the high end is limited only by the stray capacitances of the tubes employed.

Another advantage resulting from the absence of coupling capacitors is that the accuracy and function of the circuit are not affected by the harmonic contents, shape or the degree of symmetry of the input signal.

Complete Phase Meter Circuit

In Fig. 3, diodes D_1 to D_4 and tubes V_1 to V_5 are connected as an amplitude comparator circuit for input signal E_1. As soon as E_1 intersects with the zero axis, diode D_1 conducts and V_1 oscillates through grid-plate coupling of the transformer. One positive pulse is delivered to V_7 when E_1 intersects with the zero axis.

In a similar manner, diodes D_4 to D_8 and tubes V_4 to V_6 deliver one positive pulse to V_8 whenever input

signal E_2 intersects with the zero axis. Carbon-film ceramic resistors R_3 and R_6 serve for temperature compensation in turn-off units V_2 to V_3 and V_4 to V_5 respectively.

Pentodes V_7 and V_8 are used as amplifiers to isolate the comparator circuits. Tubes V_9 and V_{10} are arranged as a bistable multivibrator. Diode V_{16} feeds the trigger pulse through the plate of V_9 to the grid of V_{10} from amplifier V_7 only when V_9 is cut off, because the cathode of V_{16} is biased through R_1 with a positive potential of 200 volts.

Similarly, diode V_{17} feeds the trigger pulse through the plate of V_{10} to the grid of V_9 from amplifier V_8 only when V_{10} is cut off. Therefore, the operation of the instrument is not affected when signals E_1 and E_2 are in phase.

Action With Distorted Waveforms

Diodes V_{16} and V_{17} also serve to prevent the bistable multivibrator from switching to the reverse direction on arrival of the following pulse from the same channel, without awaiting for completion of the switching action initiated by the next pulse from the other channel. This feature is very desirable when one of the input signals contains so much distortion that its waveform intersects with the zero axis more than once during a half-cycle. For example, in Fig. 4, signal E_2 has so much distortion that its waveform intersects with its zero axis within a half-cycle. The comparator circuit would then generate an additional undesirable pulse b_1' after the desired pulse b_1 within the same half-cycle. Pulse a_1 of the E_1 channel passes through amplifier V_7 and diode V_{16} to the plate of V_9 and the grid of V_{10}, after which a switching action takes place with the result that V_{10} cuts off and V_9 conducts.

As soon as pulse b_1 of the E_2 channel reaches the plate of V_{10} and the grid of V_9 through diode V_{17}, a reverse switching action takes place with the result that V_9 cuts off and V_{10} conducts. Since the potential at the plate of V_{10} is below 200 volts, V_{17} cuts off because its cathode is biased at + 200 volts through R_{20}. Thus pulse b_1 cannot pass through V_{17}. Therefore, no switching action will take place in multivibrator tubes V_9 and V_{10} until the arrival of pulse a_2. As a result, the phase angle reading will be confined in the interval between pulses a_1 and b_1 and not be affected by the undesirable pulse b_1'.

In a case where the distortion occurs during the interval between a_1 and b_1, phase measurement has to be transferred to the interval between b_1 and a_2 in order to avoid errors due to undesirable pulses such as b_1'.

Sawtooth Generator

Tubes V_{11}, V_{12} and the NE-2 neon diode are connected as a direct-coupled sawtooth generator. Its operating principle is somewhat similar to a boostrap sawtooth generator. Pentode V_{11} is used as a clamp tube for terminating the sawtooth waves. When V_{11} is cut off by the negative pulse of the multivibrator, C_9 charges through variable resistor R_9 and fixed resistor R_{10}. Since R_9 is isolated from +400 volts by R_7 and coupled to the cathode of cathode follower V_{12} through capacitor C_9 and the constant-voltage-drop neon diode, the charging current to C_9 is constant. Thus the grid of cathode follower V_{12} rises linearly with a slope equal to the time constant of C_9 and the series resistors R_9 and R_{10}.



FIG. 4—Trigger pulses that could be developed when comparing sine wave with wave that intersects zero axis four times in every period

As soon as the negative pulse at the grid of V_{11} passes, the bias potential returns to zero, the plate current begins to flow, and C_9 discharges immediately. By careful arrangement of the values of R_9, R_{10} and the values of the capacitors on switch S_4, it is possible to set the peak amplitude of the sawtooth wave to a predetermined value with S_4 and variable resistor R_9 when both input signals E_1 and E_2 are 360 deg apart throughout a wide frequency range, probably from 100 kc down to 0.001 cps with commercially available components.

Cathode follower V_{13} isolates the sawtooth generator from the peak-reading voltmeter. Diode V_{18} is used in order that C_{10} and C_{11} can be charged by V_{13} through a low-impedance path. The capacitors are charged to the positive peak amplitude of the sawtooth wave, and store the charge for a long period because diode V_{18} is cut off during discharge. Capacitor C_{10} can be switched in or out of the circuit by switch S_5 so that a longer or shorter period of discharge can be chosen to suit the frequency of applied signals. Diode V_{19} is used in a similar manner to couple the negative peak amplitude of the sawtooth wave to the grid of V_{20}. A peak-to-peak voltmeter is used instead of a simple peak voltmeter to obtain higher accuracy when the phase angle to be measured is near 360 deg.

Tubes V_{14} and V_{15} are arranged as a balanced cathode follower. High stability can be obtained in this circuit since it is essentially a balanced bridge and a large amount of degeneration against common-mode fluctuation is established by R_{23}. Good accuracy can also be obtained because the output meter current can be made independent of tube factors by increasing the load resistance connected between the two cathodes. Switch S_6 is used to select the various ranges on the output meter.

Accuracy

The accuracy of this instrument is within 1 percent from zero to 10 kc. The error then increases slowly to 4 percent at 100 kc. These values are with an external indicator; an additional error of 1.5 percent is added when the panel meter is used.

Readings can be reproduced with a deviation of less than 0.5 percent after 500 hours of operation.

By JOSEPH B. BIDWELL
Asst. Head, Mechanical Development Department
Research Laboratories Division
General Motors Corp.
Detroit, Mich.



Cross-section of pickup head showing suspension of parts

Movable-Anode Tube Gages Surface Roughness

Pickup stylus coupled to movable plate of transducer tube measures roughness on a wide range of surface shapes. High electrical output of tube reduces complexity of amplifying and indicating circuits

MEASUREMENT of roughness requires a means of comparing minute surface deviations with the nominal surface of the material being measured. In the unit to be described, a pickup head incorporating a movable-anode tube and a diamond stylus is used to measure the deviations. The movable-anode tube feeds a highly stable vacuum-tube voltmeter through a two-stage triode amplifier.

Stylus

As a means of sensing the irregularities, a diamond stylus with a 0.0005-inch tip radius is used. This stylus radius permits greatest penetration of fine irregularities without scratching the surface being measured.

The reference surface from which stylus deflections are measured is established by two large-radius skids arranged in line with, and at either side of the stylus. These skids ride over fine scratches following the nominal surface contour. The skids are mounted on a tubular case that houses the pickup element. A transducer is attached to the housing and the stylus is fastened to its input thus producing a mechanical displacement which is the deviation of the actual surface from the nominal.

Pickup

Mechanical displacement is converted into electrical signal by an RCA 5734 electro-mechanical transducer. This device is a three element, all-metal vacuum tube constructed as shown in Fig. 1. The plate rod can be moved with respect to other tube elements by an extension through a thin metal diaphragm that seals one end of the tube. This relative motion changes the tube characteristics so that variation of output voltage can be used to indicate mechanical displacements. Average mechanical-electrical conversion characteristics for a circuit having a 75,000-ohm load resistance and a 250-volt plate supply are shown in Fig. 2. The relation between displacement and voltage is not linear and the electrical output for a given dynamic displacement range is greater if the mean deflection is positive rather than negative.

Several features make this transducer useful for measuring surface roughness and other small displacements. It has a high ratio of electrical output to mechanical input, reducing the complexity of the indicating circuits. The size and weight of the tube are small and the force required to deflect the plate rod from its neutral position is moderate. The principal drawback is the limited allowable movement of the plate rod. Movement of more than ½ deg. either side of neutral may result in permanent deformation of



FIG. 1—Type 5734 tube used as transducer



FIG. 2—Variation in movable-anode tube output voltage with displacement of anode

the diaphragm or in damage to tube elements. This angular restriction amounts to ± 0.008-inch movement on the end of a 1-inch extension to the plate rod.

To permit use of the pickup on a wide variety of surface shapes a total allowable stylus travel of about 0.040 inch is provided. The need for this range of travel can be seen from Fig. 3A, which shows the relative positions of the stylus and skid on different surfaces. Although the nominal extension of the stylus from the housing varies considerably, the motion required after engagement with the surface ranges from only a few microinches to 0.001 inch. The use of a long extension of the plate rod to provide for sufficient travel is undesirable since the sensitivity would be reduced and the high-frequency response of the assembly impaired.

Viscous Coupling

The nonlinear response of the tube requires that some means be provided so that dynamic deflections always take place about its undeflected neutral position regardless of the nominal stylus position.

A viscous coupling was developed to limit anode movement without restricting position of the stylus. The construction of this device is shown in Fig. 3B. A plate attached to the stylus is suspended within a U-shaped driven plate. Space between plates is filled with a viscous fluid. Displacement of the driving plate transmits force through the viscous material to the driven plate. The spacing of the plates is such that the fluid is kept in the clearance space by capillary attraction eliminating the need for seals and permitting use of the coupling in any position without loss of fluid. It is essential that the material used between the plates be a true liquid and not a grease, in order that the plate rod may always return to its neutral position.

The viscous coupler performs in a manner analogous to an electrical filter. The force between the plates is proportional to their relative velocity. The movement of the elastically-restrained output plate for a sinusoidal displacement of the stylus can be shown to be

$$\delta_{out} = \delta_{in} \frac{k}{\sqrt{k^2+1}} \text{ where } k = \frac{\mu A \omega}{Ch}$$

δ_{out} is the output displacement amplitude, δ_{in} the input displacement amplitude, μ the absolute fluid viscosity, A the total shear area of plates, ω the frequency of displacement, C the spring rate of driven plates and h the separation of plates.

Phase angle can be determined to be: $\beta = \tan^{-1} 1/k$

The performance of the coupler can then be described in terms of k. Figure 4 shows percent transmission and phase angle as a function of k. For values of k less than about 0.1 the coupler acts as a differentiator and the output is proportional to the derivative of the input. For values of k greater than 5, transmission is greater than 98 percent and the coupler serves essentially as a solid connection.

As utilized in the surface-roughness gage, the cutoff of the coupler is well below that of the amplifier so as not to influence the performance of the overall instrument. The particular geometry and viscosity used in this pickup results in $k=5$ at a frequency of 3 cps.

Since k is affected by temperature, a silicone fluid having a small change in viscosity with temperature is used in the coupler. This is especially important in this pickup since the tube heater raises the ambient temperature of the coupler.

Suspension System

The stylus and driving vane mounting are shown in Fig. 5. A parallelogram spring suspension locates the stylus rigidly along the pickup axis eliminating the need for sliding bearings that might intro-



Roughness gage provides five roughness ranges and three cutoff frequencies



Pickup head with cover removed to show arrangement of parts



FIG. 4—Characteristics of viscous coupler. For k less than 0.1 coupler acts as a differentiator



FIG. 3—Range of surface contours (A) requires variable stylus position. Viscous coupling (B) permits this variation while limiting travel of plate rod



FIG. 5—Circuit of surface-roughness gage. Signal from movable-anode tube mounted in probe, is measured by a-c VTVM

duce friction. The driving plate is also located in its properly spaced relationship to the driven plate by these spring supports. Positive stops on the plate rod prevent mechanical displacements that would damage the tube.

As the stylus is deflected when the pickup first engages a surface, the plate rod is restrained by the stop screw and the coupling slips until the riders contact the surface. The elastic force of the tube diaphragm then causes additional slip in the coupling bringing the plate rod to its neutral position. Traversing the pickup over the surface, the high-frequency displacements of the stylus are transmitted undiminished through the coupling to the transducer tube.

The static force of the stylus on the surface is reduced since it is determined by the stylus suspension which has a spring rate of only 30 milligrams per 0.001-inch deflection as compared to 300 milligrams per 0.001 inch for the tube diaphragm itself with a one-inch extension.

Measuring Circuit

The electronic circuit used with the pickup described above for measurement of surface roughness is shown schematically in Fig. 5. It is essentially a stable a-c vacuum-tube voltmeter with provision for selecting low-frequency response characteristics. A three-position switch allows a choice of 5, 15, or 50 cps cutoff frequency by switching a single R-C filter circuit. This provision permits separation of short wave-length roughness from the longer-wavelength characteristics of the surface. The above frequencies correspond to wavelength cutoffs of 0.030, 0.010, and 0.003 inch respectively at the recommended traversing speed of 0.150 inch per second. The most generally used wavelength cutoff is 0.030 inch. Shorter wavelengths are called roughness and longer are called waviness.

The remainder of the circuit consists of two triode amplifier stages and a bridge output. Negative feedback is used to stabilize the gain. The power supply is well filtered and voltage stabilized to permit operation from a-c lines varying widely in voltage. The meter is a rectifier type with relatively long period and large damping to permit easier reading of average current. This is necessary since the input is not periodic but consists of a series of irregular fluctuations that may occur at relatively low frequency.

High Input Impedance

By E. W. HOGUE
Bethesda, Maryland

HIGH INPUT impedance amplifier circuits are of extreme importance to engineers faced with the problem of coupling signal-generating transducers to control circuits.

One technique widely used in the past for providing high input impedance to a vacuum-tube amplifier (the order of several hundreds of megohms) is the cathode-follower with cathode-connected shield[1,2] illustrated in Fig. 1A. This setup suffers from several disadvantages, in particular, the double-shielded wire with its attendant mechanical, electrical and economic drawbacks.

Figure 1B shows an improved circuit offering several unique and important features. By grounding the cathode and using the shielding arrangement illustrated, all the disadvantages of the cathode-connected shield circuit are overcome, and the new circuit presents to the transducer an impedance whose value is not limited by stray capacitive and resistive leakage[3].

In the circuit of Fig. 1A it was necessary to shield a set of conductors from ground by means of an off-ground shield. In the new circuit it is necessary to shield one set of conductors from another set of conductors by means of a grounded shield.

In the new circuit grounded shields S_1 and S_2 perform the double function of impedance raising and electrostatic interference prevention.

In the removal of strays directly shunting the source, the shielding in the new circuit can easily be made almost perfect, raising Z_t to an enormous value. The impedance presented to the transducer then becomes

$$Z_{in} = (M + 1)Z_t$$

where Z_t is the parallel resultant of R_g and z, which includes the entire capacitance and resistance to ground of the shielded cable connecting transducer to grid; and where M is the undegenerated voltage gain of the tube. In the new circuit a multistage amplifier can be used instead of the single tube to give very large values of M. This permits the use of large lengths of shielded cable between transducer and input stage because, in effect, the cable capacitance is divided by M.

As a result of the impedance-raising shield in the new circuit, the impedance presented to the transducer in practical circuits becomes many thousands of megohms. Paradoxically, while feedback serves to raise the impedance presented to the transducer terminals, it serves at the same time to lower the impedance from each of these terminals to ground in the new circuit. Both of these effects are brought about by feedback through the internal impedance Z_t of the transducer.

Other properties resulting from the highly degenerative nature of the circuit are low microphonism, reduced sensitivity to magnetic hum, high linearity, and low voltage gain. As in the cathode-follower, the voltage gain of the new circuit is very nearly equal to unity, its upper limit.

Practical Circuits

Figure 2 shows a practical high-input-impedance preamplifier in which a constant-current tube serves as the plate load for a 6J7 pentode to provide a voltage loop-gain approaching that of the pen-



FIG. 1—Basic circuits of double-shield (A) and new (B) preamplifier circuits



FIG. 2—Circuit having input of impedance 1,500 meg shunted by 0.005 $\mu\mu$f



FIG. 3—Single-tube version of preamplifier has shunt capacitance of 2 $\mu\mu$f

Preamplifier Circuit

Reduced noise level and distortion are fortunate byproducts of raising amplifier input impedance to several thousand megohms by connecting transducer in feedback loop of a two-stage preamplifier. Circuit has numerous industrial applications and makes possible the use of charged parallel-plate capacitors as transducers

tode amplification factor.[4] A cathode-follower serves to couple the high-impedance plate to the output load. The input impedance of this circuit is 1,500 megohms paralleled by the gride-plate capacitance of the 6J7—approximately 0.005 μμf.

If shielded cable having a total capacitance C is used to connect the grid to the signal source, and the voltage gain of the amplifier is 1,500, an additional capacitance $C/1{,}500$ will then parallel the grid-plate capacitance.

The second preamplifier in Fig. 3 uses a double triode (12AX7) of which the first half is a voltage amplifier and the second half is a cathode follower. Positive feedback between the cathode-follower and the cathode of the voltage amplifier can be adjusted to give stable gains of up to 3,000 in accordance with the relation

$$M' = \frac{M}{1 - \beta M}$$

where M is the normal voltage gain of the first stage without feedback, and where β is the fraction of the output voltage impressed on the input cathode. Since β is positive, as βM approaches unity, M approaches infinity. For $\beta M > 1$ the amplifier is unstable. With an input grid resistor of several megohms this preamplifier presents an input impedance of many thousands of megohms in parallel with the grid-plate capacitance of a triode—approximately 2 μμf for the 12AX7. A pentode would give a much lower input capacitance, but because its gain depends upon g_m, which is highly variable, rather than on μ, which is



Two versions of preamplifiers that present input impedance of several thousand megohms to the transducer

reasonably constant, the pentode is unsuitable for use with positive feedback. As βM approaches 1 both β and M must be highly stable to avoid self-oscillation.

The ideal tube for use in this application would be a triode-tetrode. The tetrode half, used as the voltage amplifier, would be provided with a grounded screen-grid carefully aligned behind the control-grid wires to provide good screening of the grid from the plate to give low grid-plate capacitance, but poor screening of the cathode from the plate to retain the stable gain characteristic of the triode.

Transducers

The circuit makes the use of tiny electrostatic mechanoelectrical transducers practical. The inherent virtues of the polarized variable capacitor as a transducer have long been known, but its one defect, an extremely high internal impedance at audio and subaudio frequencies, has restricted its use to a few laboratory and professional applications.

In all these applications the transducer is kept close to the input stage, and in most cases its capacitance is kept above 50 μμf. Using the new circuit, an electrostatic phonograph pickup having a total internal capacitance of 5 μμf has been operated with complete success when connected to the preamplifier by three feet of ordinary fine shielded wire running from each terminal. Full output of several volts was obtained over the range from 40 cps to over 10,000 cps.

The charged parallel-plate variable capacitor comes close to being the ideal mechanoelectrical transducer when operating into the new circuit. It then behaves as a voltage source whose output is a linear function of the capacitor plate separation. Using a typical closely spaced parallel-plate capacitor the total noise level of the input stage can easily be held to 14 millivolts rms for a 140-volt signal. Since the transducer itself generates no noise, the linear dynamic range of this transducer when coupled to the new circuit is around 10,000 to 1 in voltage, or 80 decibels.

REFERENCES

(1) A. D. Blumlein, British Patent 448,421, June 4, 1936.
(2) J. F. Keithley, Stabilized Decade-Gain Isolation Amplifier, ELECTRONICS, p 98, Apr. 1949.
(3) E. W. Hogue, United States Patent 2,598,259, May 27, 1952.
(4) Valley & Wallman et al., "Vacuum Tube Amplifiers", p 439, 18, M.I.T. Radiation Laboratory Series, McGraw-Hill Book Co., New York, 1948.

Switching System Speeds

Punch-card controlled bridge being used to measure interelectrode capacitances in subminiature tubes. Variety of adapter units permit measurements on all types of tubes

ACCURATE MEASUREMENT of interelectrode capacitance becomes increasingly important as tubes are used at higher frequencies.

Conventional methods of measuring tube capacitances, although accurate, require time-consuming changes in coaxial cable connections for each capacitance measured. Grounded-sheath coaxial cables are necessary for connections to tube elements because of the stringent limitations placed on the amount of stray capacitance that can be tolerated. In testing the eight different capacitance values of a dual-triode tube, nine coaxial cables must be rearranged eight times.

Where large groups of a single tube type are to be tested, it is possible to decrease set-up time by connecting the adapter only once for each desired capacitance measurement, and running all tubes through before changing to the next set-up. Although this reduces the number of connector changes, it requires that each tube be inserted into the adapter once for each measurement.

Multiple tube insertion is undesirable, particularly for subminiature tubes where long flexible leads are used. It was this problem that was largely responsible for the development of the new automatic switching equipment described here.

Automatic System

In the equipment shown in the photograph, the coaxial cables have been replaced by relays actuated from a punched card. This change has resulted in simplification of operation with increased speed of testing. The possibility of incorrect cable arrangement is completely eliminated. The switching relays are housed in shielded compartments and are connected so that the stray capacitance paralleling the tube under test is negligible.

A large-diameter cylinder on top of the bridge contains the relays used to make proper tube connections. A smaller cylinder is one of a set of adapters used to make connection from the switching unit to the tube under test. An adapter for any type of tube base may be plugged into the front of the switching unit.

A punched card is run through the control box at the right of the bridge, making connections for the series of capacitance measurements. Switches on the front of the box may be used for experimental measurements or for tube types for which no card is available.

The direct-capacitance measuring bridge permits measurement of capacitance between any two elements or groups of elements of an electron tube independently of other capacitances within the tube.

The bridge circuit may be represented by the three-terminal network shown in Fig. 1A. Points *B* and *C* are the terminals between which the desired capacitance is placed for measurement, and *G* is the shield or ground terminal. The bridge is designed so that the indicated capacitance value is proportional to C_1, and is independent of C_2 and C_3. If terminals *B* and *C* are connected to the tube elements under test by means of individual, grounded-sheath coaxial-cable connections, only capacitances from *B* and *C* to *G* (ground) are added to the bridge.

Tube connections can be ar-

Tube Capacitance Tests

Interelectrode capacitance measurements are simplified by punch-card controlled switching system that permits checking tube capacitances without manual changing of tube connections. Stray capacitances are eliminated by relay grounding system

By R. E. GRAHAM

Product Development Laboratory
Sylvania Electric Products Inc.
Kew Gardens, N. Y.



FIG. 1—Capacitances existing in three-terminal bridge circuit (A). Relay switching system (B) grounds all capacitance except that between terminals being measured

ranged to place the desired capacitance between *B* and *C*, and all other capacitances between *B* and *G* or *C* and *G*. Since the bridge is insensitive to capacitances from *B* and *C* to ground, it is possible to obtain a direct interelectrode-capacitance measurement between the elements connected to *B* and *C*. For example the grid-to-plate capacitance of a triode may be measured independently of the grid-to-cathode or plate-to-cathode capacitances simply by connecting the grid to terminal *B*, the plate to terminal *C*, and the cathode to to terminal *G*. In this manner, grid-to-cathode and plate-to-cathode capacitances will be applied from *B* to *G* and from *C* to *G*, respectively, and will have no effect on the measurement of the grid-to-plate capacitance from *B* to *C*. It is for this reason that the resulting measured value is termed the direct grid-to-plate capacitance.

Switching Unit

The principle of operation of the automatic relay system is illustrated in Fig. 1B for one tube terminal. The entire system consists of a repetition of this arrangement for each tube terminal. The letters *B*, *C* and *G* refer to bridge terminal connections, as in Fig. 1A. Three relays are used for each tube terminal. Relays *Y* and *Z* are ganged, and *X* is a single relay.



FIG. 2—Card reader unit and relay arrangement for one tube terminal. Relay group XYZ is repeated in each section of switching unit. Power supply, capacitor in card reader and inductor serve the entire device. Cross-section shows placement of relays within circular housing

With the contacts in the position shown in the diagram, the tube terminal is connected to bridge terminal *C*. The stray capacitance across *Y* is from *B* to ground, and that across *X* and *Z* is from *C* to ground. These capacitances are not objectionable from the standpoint of accurate measurement.

The only opportunity for stray capacitance between *B* and *C* is from the *B* wiring in the *Y* cavity to the *C* wiring in the *X* cavity by way of the connecting wiring hole *R*. This undesirable capacitance can be held to an acceptable minimum provided the hole is effec-

tively plugged by the grounded conductor running through it. To attain maximum shielding between cavities the hole must be small, the conductor must be almost as large as the hole and the insulation on the conductor must be thin. These conditions are met by using plastic-covered radio hook-up wire of a diameter equal to that of the hole.

When relay *X* is changed from the position shown in Fig. 1B the tube terminal is connected to ground. This can also be accomplished by throwing *Y* and *Z* without changing *X*. When all the contacts are changed from the positions shown, the tube terminal is connected to bridge terminal *B*. In no case is there a possibility for stray capacitance to occur between terminals *B* and *C*.

Figure 2 shows the cross-section of the switching unit with its arrangement of miniature relays and associated equipment. The three relays are arranged similar to Fig. 1B and perform the switching function for one tube terminal. This relay arrangement is repeated ten times making it possible to measure the capacitance of tubes with up to nine terminals, with one set of relays connected to an external shield.

The switching unit uses thirty relays operating electrically as ten sets of three relays each. The three relay categories are labeled *X*, *Y* and *Z* as in Fig. 1B. One terminal of each *Y* and *Z* relay is connected to the *B* and *C* terminals of the bridge, respectively. It is not necessary for *X* and *Y* relays to be shielded from other relays in the same category since all contacts in each instance are connected either to ground or to their respective bridge terminals. In category *X*, however, different relays may be connected to different bridge terminals, and therefore, the relays are shielded from each other in ten pie-shaped cavities. The switching unit can thus be pictured as ten relays in ten cavities, and two groups of ten relays each in two separate cavities.

Stray Capacitances

It was mentioned earlier that a direct-capacitance bridge measures the capacitance between terminals *B* and *C* and is insensitive to capacitances from *B* and *C* to ground. There are, however, practical limitations on the values of these grounded capacitances. For the direct-capacitance bridge, used here, capacitances from *B* to ground should be kept below 25 μμf. Capacitance from *C* to ground should be less than 300 μμf for accurate measurements in the order of thousandths of a micromicrofarad, such as grid-to-plate values. However, the total capacitance from *C* to ground may be considerably higher when the values to be measured are greater.

If the limitations of total capacitance to ground are exceeded, the bridge-balance null will become too broad to permit accurate readings, and the bridge zero-balance point (no capacitance between terminals *B* and *C*) will be shifted away from the zero calibration on the dial.

Measurements on the switching unit determined that the capacitance from *B* to ground is (61 + 12 *t*) μμf, where *t* equals the total number of connections made from terminal *B* to the front of the unit. The capacitance from *C* to ground is (165 + 4 t_c — 8 t_s) where t_c and t_s represent the total number of terminals connected to *C* and *B* respectively.

The adapter for connecting subminiature tube leads to the switching system adds about 5 μμf to ground per terminal. Thus, in connecting one tube terminal to the *B* bridge terminal, a total capacitance to ground of 78 μμf is encountered in the switching unit and adapter. In connecting one tube terminal to the *C* bridge terminal and one to the *B* bridge terminal, as is done for the measurement of grid-to-plate capacitance, a capacitance of 166 μμf from *C* to ground is encountered. If seven tube terminals are connected to the *C* bridge terminal, and one is connected to the *B* bridge terminal there is a total capacitance of 220 μμf from *C* to ground. Since the capacitance from *B* to ground is too high, a 1.23-mh inductance is used to resonate out part of it. Thus, bridge accuracy is not impaired and the null balance remains sharp. The value of the inductance is picked to resonate with 95 μμf at 465 kc.



FIG. 3—Punch card for 6021, 6111 and 6112 tube types. Boxes at center indicate capacitance being measured

The 0.003-μf capacitor in series with the inductance provides 60-cycle isolation necessary for correct operation of a continuity checker used for relay maintenance. A switch in the card reader prevents over-heating of the switching unit when no card is in the reader.

Measurements indicate that the residual capacitance between the circuits of any two adjacent output terminals of the switching unit is less than 0.00005 μμf.

Control Box

The control box consists of a card reader and a set of manual switches, either of which may be used to control the switching unit. When using the card reader, correct connnections are made automatically. Contacts are made through the holes of a card moved through the reader. Each position corresponds to a desired capacitance measurement. The card, shown in Fig. 3, may be punched for as many as eight different measurement positions, the number depending upon the tube type. Symbols indicating the capacitances to be measured are written on the card in boxes, each in turn being visible through a window in the card reader as the card is moved to the next position.

REFERENCES

(1) C. H. Young, Measuring Interelectrode Capacitances, *Tele-Tech*, 6, No. 2, p 68, Feb. 1947.

Transient Analysis of Transistor Amplifiers

Response of junction-transistor amplifiers to steep-front pulses can be calculated using equivalent circuit described. Grounded-base circuits with *npn* junctions are seen to give best transient performance. Response times of 0.5 μsec have been observed

By W. F. CHOW and J. J. SURAN

Electronics Division, General Electric Company
Electronics Park, Syracuse, New York

APPLICATION of transistors to pulse amplifiers, computers and servo amplifiers requires an understanding of transient behavior. All physically-realizeable mechanisms, whether electrical, mechanical or acoustical, are subject to energy-storage effects. Thus, the response of a physical system to a suddenly applied force will never be instantaneous.

Transient behavior of lumped-parameter R-L-C networks is well known.[1] Whenever lumped-parameter electrical analogies are possible, the study of transient and frequency response is comparatively simple. Even when the analogies lead to highly complex circuits, a solution of transient response problems may still be attained by use of an analog computer. For example, in vacuum tubes, the interelectrode energy-storage properties are dealt with in design problems by assuming physical capacitors to exist between the electrodes.

When more complex phenomena are involved, such as electron bunching due to space charge, the lumped-parameter equivalent circuit becomes inadequate as a representation of the physical case. This does not invalidate the use of the simple equivalent circuit, providing its limitations are kept in mind.

Theory Review

To understand better the basis for a transient study of transistors, consideration of the physical phenomena involved in transistor action is helpful. Figure 1A illustrates the potential energy profile of a *pnp* junction transistor biased in the usual manner.



FIG. 1—Potential profile for *pnp* junction transistor is shown in A. Low-frequency diode equivalent circuit of a grounded-base amplifier is shown in B. Emitter and collector resistances are included in the diode symbols

The low-frequency diode-equivalent circuit of a *pnp* junction-transistor amplifier is shown in Fig. 1B.

There is very little potential drop across the emitter-base barrier of the transistor, and current will flow freely from the emitter to the base. Practically no potential gradient exists in the base region. The base-collector barrier is biased in the inverse diode direction, and practically all of the potential drop between the external base and collector leads occurs across the base-collector barrier.

A positive signal current, applied to the emitter of a *pnp* transistor, will cause holes to migrate from the emitter to the base. For an *npn* transistor, a negative current applied to the emitter will cause electrons to migrate from the emitter to the base. In order that the emitter signal may cause a change in collector current, holes that have migrated from the emitter to the base must traverse the base region and appear at the base-collector barrier. Since there is virtually no electric potential gradient in the base region, the process of hole travel through the base is essentially one of diffusion. This diffusion is motivated by a concentration gradient rather than an electric-field gradient, the concentration of holes being much higher in the base region near the emitter than in the base region near the collector.

If all the holes that enter the base from the emitter due to a signal current in the emitter were to do so with equal momentum vectors and if, in the process of traveling through the base region from the emitter to the collector, the holes were to experience no collisions or nonuniform field effects, the only re-



FIG. 2—Drawing shows ideal (A) and actual (B) movement of carriers across base region. Due to dispersion effect, carriers leaving emitter junction at same time arrive at collector junction at slightly different times



FIG. 3—Thermal analogy of diffusion of holes or electrons in base region of a junction transistor. A thermal conducting rod is placed between points of fixed temperature. Resulting distribution of temperature is shown in (B)



FIG. 4—Dispersion and time-delay effects are clearly evident from curves showing collector current (B) resulting from steep-front emitter current rise. Best transient response is obtained with shortest base region

sult of hole diffusion through the base region would be a time delay between collector and emitter signals. Such a hypothetical diffusion is illustrated in Fig. 2A.

In practice, carriers moving through the base region of a transistor are subject to many effects that cause individual carrier paths to differ greatly. The initial carrier momentum vectors are randomly distributed; this alone would cause path variations in the diffusion of the carriers through the base. Furthermore, the carriers are subject to collision among themselves as well as to collision with fixed atoms, and are also subject to nonuniform space-charge forces.

A more realistic picture of carrier diffusion would therefore look like that illustrated in Fig. 2B. A current pulse at the emitter gives rise to an instantaneous influx of carriers in the base region, but the arrival of these carriers at the collector is spread out over a period of time.

This dispersion effect in the transistor is analogous to the dispersion of a pulse as it is propagated along a transmission line. In the transmission line, the dispersion effect is treated by considering the line to have distributed capacitance, inductance and resistance.

Thermal Analogy

The diffusion of holes or electrons in the base region of a junction transistor bears a striking physical analogy to the diffusion of heat in a thermal conductor. For example, consider the phenomena involved if a massive hot plate were suddenly applied to the end of a metal rod with the other end maintained at 0 C as illustrated in Fig. 3A. The transition of the temperature distribution along the rod from a short time (solid line) after the hot plate is applied to a time when a steady-state distribution of temperature has been reached is illustrated in Fig. 3B.



FIG. 5—Equivalent circuit used to calculate transient response

The fundamental physical conditions of the thermal problem are: (a) A constant temperature T is suddenly applied to one end of the metal rod, (b) heat diffusion through the length of the rod occurs as a result of the temperature gradient, (c) a uniform radiation of heat, proportional to the temperature, accounts for some heat loss from the rod to the surrounding medium, and (d) zero temperature is maintained at the far end of the rod.

For the base region of the *pnp* junction transistor, the corresponding physical conditions are: (a) a sudden excess concentration (concentration above the thermal equilibrium value) of carriers is injected into the base region at the base-emitter barrier, (b) carrier diffusion through the length of the base region occurs as a result of the carrier concentration gradient, (c) a uniform loss of carriers exists, due to the recombination of holes with electrons, and the loss is proportional to the carrier concentration, and (d) zero excess concentration of carriers at the base-collector barrier is maintained, implying that all carriers which arrive at the base-collector barrier are immediately swept into the collector.

Transient response of the collector current to a step in emitter current can be shown[3] to be of the form illustrated in Fig. 4. Both the dispersion and time-delay effects are clearly evident. In terms of the transistor construction, the time delay may be related to the length of the base region; the dispersion is related to the length of the base region and the collector-base barrier thickness. Other effects, such as surface phenomena and barrier-thickness modulation by applied voltages[4] also affect the transient response of transistors, but these may often be neglected in transient considerations, especially for small-signal analysis.

A simple small-signal equivalent circuit of a grounded-base junction-transistor amplifier, which has been found useful in transient analysis calculations, is illustrated in Fig. 5. The delay line is assumed to have the current transfer characteristic given by

$$\frac{i_c}{i_e} = e^{-K/\omega}$$

The time constant RC is adjusted so that it corresponds to the α cutoff frequency f_{α_e} of the transistor. Thus

$$\frac{i_y}{i_s} = \frac{\alpha_o}{1+j\omega RC} = \frac{\alpha_o}{1+j\frac{\omega}{2\pi f_{\alpha_e}}}$$

where α_o is the low-frequency current amplification factor of the transistor and f_{α_e} is the α cutoff (3 db down) frequency of the transistor. In Fig. 5, the signal source e_i is assumed to have an internal impedance of R_g. Resistances r_e, r_b, r_c and R_L are, respectively, the a-c emitter resistance, base resistance, collector resistance and load resistance. The collector capacitance of the transistor is represented by C_c.

Comparison of the experimental and theoretical frequency-response characteristics for a *pnp* junction transistor amplifier is illustrated in Fig. 6. The circuit parameters for the transistor used in the experiment are listed on the diagram.

Knowing the frequency response characteristics of the transistor network, and restricting the input signal to a magnitude sufficiently small so that the equivalent circuit may be assumed linear, transient-response calculations may be made.[1] Calculations based upon the equivalent circuit of Fig. 5 are found to be in good agreement with results obtained experimentally.



FIG. 6—Comparison of experimental and theoretical phase and attenuation characteristics for transistor amplifier show close correlation

Contributing Factors

The transient response of transistor amplifiers depends upon essentially three factors: the connection of the transistor (grounded-base, grounded-emitter or grounded-collector), the operating point of the transistor emitter and collector biases, and the circuits external to the transistor.

Figures 7A and 7B illustrate the transient response of two grounded-base *npn* junction transistor amplifiers. In each case the input signal was a square-wave of 10 μsec duration, 0.05 μsec rise and decay times and 60 mv magnitude (positive). The circuit of Fig. 7A exhibited a response time of 2 μsec. Maintaining the bias currents of the circuit constant, but reducing the load resistance by a factor of two, caused a 100-percent improvement in response time, but at the expense of a voltage amplification reduction of 43 percent as illustrated in Fig. 7B.

Grounded-emitter amplifiers were (Fig. 7C) found to have somewhat poorer response times, in general, than the grounded-base circuits. Figure 7D illustrates a grounded-collector stage with a load resistance of 500 ohms. The grounded-collector amplifier has no voltage amplification, but nevertheless exhibits power gain. The apparent rapid transient response of the grounded-collector circuit (0.07 μsec) is due to the direct transmission of the input signal through the low-resistance path between the base input and emitter output leads ($r_b + r_e$). However, it should be remembered that this rapid response is only apparent, and that the actual power response is approximately similar to that of the grounded-emitter circuit.



FIG. 7—Circuits, parameters and curves showing transient response of different transistor amplifier circuits

In conclusion, it has been shown that the frequency and transient response of junction transistor amplifiers may be calculated with good accuracy from the equivalent circuit of Fig. 5. Experimental tests indicate that the grounded-base amplifier gives the fastest transient responses, but in general, this is dependent upon the external circuit connections. For *pnp* junction transistors presently available, response times of the order of 1 μsec have been obtained, whereas for *npn* junction types, responses ranging from 0.5 to 1 μsec have been observed.

This work has been supported, wholly or in part, under Contract AF 33 (600)-17793, which is sponsored jointly by the U. S. Air Force, U. S. Army and U. S. Navy.

References

(1) M. F. Gardner and J. L. Barnes, "Transients in Linear Systems", Wiley & Sons, Inc., New York, 1942.
(2) R. B. Adler, "A Large Signal Equivalent Circuit for Transistor Static Characteristics", R.L.E., M.I.T. Transistor Group, Oct. 2, 1951.
(3) R. F. Shea, *et. al*, "Principles of Transistor Circuits", to be published by John Wiley & Sons Inc., N. Y., 1953.
(4) J. M. Early, Effects of Space-Charge Layer Widening in Junction Transistors, *Proc. of the IRE*, Nov. 1952.

Matching Nonstandard

Experimental procedure determines matching parameters for junctions between standard waveguide and guide having constant but unusual cross section. Method is applicable to dielectric-filled guides and junction of waveguide and traveling-wave-tube helix

By A. CHLAVIN
Microwave Laboratory
Hughes Research and Development Laboratories
Culver City, Calif.

MATCHING A JUNCTION between standard guide and nonstandard guide is a problem often encountered in waveguide circuits. Nonstandard guides may be thought of as guides of constant but unusual cross sectional characteristics such as elliptical, triangular or ridged guides. They may also be more conventionally shaped guides carrying higher-order modes. Standard guides may be thought of as the rectangular or coaxial guides for which slotted sections, detectors and loads may readily be obtained. Since most junctions of the type considered here present complicated boundary conditions, mathematical analysis is tedious and often impossible.

A well known experimental method for determination of junction-matching parameters is the moving-short method.[1] However, this method is limited in that it is often not possible to move a short-circuit plunger in the nonstandard guide. For example, a moving-short method could not be easily applied to a dielectric-filled guide or a junction between the helix of a traveling-wave tube and a guide. The method suggested here is an experimental procedure that does not involve moving terminations in the nonstandard guide.

Procedure for Matching

The first problem encountered in matching the junction between standard and nonstandard guide is that of terminating the nonstandard guide. Since no loads or detectors are available and moving terminations are not to be used, it is necessary to make an additional junction back to the standard line for a termination. This arrangement is shown schematically in Fig. 1: Y_i is the admittance looking into the entire test section; Y_y is the admittance just to the right of junction 1 and Y_x is the admittance just to the left of junction 2. The distance between Y_x and Y_y is ψ, the length of nonstandard guide; Y_L is the load admittance transformed to the output of junction 2.

Three test sections like those shown in Fig. 1 must be fabricated. The nonstandard waveguide in each test section should differ in electrical length by an amount $\Delta\psi$, which is not 180 degrees. The dimensions of the junctions should be held closely from one test section to the next. One end of a test section is attached to a microwave test-bench setup consisting of an oscillator, pad and slotted section. To the other end of the test section a variable susceptance unit such as a single-post tuner is fastened, together with a flat termination. The test setup is shown in Fig. 2.

If the depth and position of the probe in the tuner are adjusted to arbitrary values b and θ an admittance looking into the test piece can be measured with the slotted section. If depth b is kept fixed and the position of the post in the line changed by increments in θ, the admittance at each of these incremental points can be determined with the slotted section. The locus of such points when plotted on an admittance chart will be a circle. The diameter of this circle is a function of the junction involved, the length of nonstandard guide ψ and the depth b of the post in the tuner.

For a particular test piece, the length of nonstandard guide is fixed and the diameter of the circle is directly a function of the depth of the post in the tuner. If the second and third test pieces are substituted for the first, keeping the same b in the post tuner and repeating the impedance measurements for incremental values of post position θ, a second and third circle will be obtained on the admittance chart. Because the length of guide ψ of the second and third test pieces is different from that of the first, the resulting circles will be of different diameters and not concentric with each other. Since the diameters of these circles depend upon b, the depth of post, they may or may not intersect depending upon how deep the post was initially placed



FIG. 1—Test section used to determine waveguide-junction parameters

Waveguide Sections



FIG. 2—Microwave test-bench setup used to make impedance measurements

in the guide. A single point of intersection of the three circles is desired. This is illustrated in Fig. 3.

When the post depth b_0 and its position θ_0 are found that give a single admittance point at the input independent of the length of nonstandard guide ψ, the second junction has been matched with the tuner.

Validity of Procedure

Moving a fixed susceptance along an otherwise matched transmission line causes the input admittance at a fixed reference plane to move along a circle in the *G-B* plane.[2] The horizontal diameter of this circle coincides with the *G*-axis. For a different susceptance a different circle is obtained that does not cross any other circle so generated. The whole right-hand plane can, in principle, be filled with such circles: that is, to any point in the right-hand half plane there corresponds a value of susceptance and its position along the matched line. The post tuner and flat load described in the experimental procedure represent just such a variable susceptance and matched line and are capable of filling nearly all of the righthand plane with circles.

The test piece can be thought of as three transducers: junction 1, the length of nonstandard guide and junction 2. Each transducer may be represented by a linear fractional transformation.[3] Since repeated transformations still result in a linear fractional transformation the entire test piece may be thought of as the transducer. The circles generated by the variable susceptance at the output are transformed through the transducer and appear as circles at the input since circles transform into circles. These circles may be magnified, rotated and translated by the transformation but still do not cross each other, since the transformations are conformal.



FIG. 3—Junction measurements plotted on admittance chart

Graphic Solution

If the length of nonstandard guide is changed, the whole family of circles shifts position, since the transformation parameters are different. However, they still remain a family of nonintersecting circles. Each of these transformed families of circles corresponding to a particular value of ψ will cover the right-hand plane since the transducer is considered lossless.[4] One circle in each family therefore, passes through an admittance point that will make Y_s in Fig. 1 equal to Y_0. Since there is only one value of Y_L that when transformed can make $Y_s = Y_0$, there is a definite value for the post depth and post position. If $Y_s = Y_0$ the length of nonstandard guide will have no effect on the input admittance since Y_0 always transforms into Y_0. The point of intersection of the three circles at the input represents a point where the admittance does not vary with the length of nonstandard guide. This indicates that the post tuner has matched junction 2 and $Y_s = Y_0$. The point of intersection is therefore the admittance of junction 1.

It is clear that junction 2 need not be constructed identical to junction 1. The only requirement is that junction 2 be matched by the tuner so that the input admittance be independent of ψ. By measuring the admittance of the tuner, the complex conjugate of junction 2 is obtained and the admittance of the intersection point is the admittance of junction 1. This property may be useful in speeding up measurements of complicated junctions.

References

(1) John C. Slater, "Microwave Electronics", p 109, D. Van Nostrand Co. Inc., New York, 1950.

(2) Theodore Moreno, "Microwave Transmission Design Data", p 41, McGraw-Hill Book Co. Inc., New York, 1948.

(3) W. H. Watson, Matrix Methods in Transmission-Line and Impedance Calculations, *Journ IEE*, p 737, 1946.

(4) Reference (1), p 104.

Microphone Sensitivity Conversion

Chart gives quick interchange of values for three common systems of rating microphone sensitivity. Change in open-circuit voltage sensitivity during impedance transformation can also be determined

By LEO ROSENMAN

Shure Brothers, Inc.
Chicago, Ill.


RETMA RATING IMPEDANCE – R_{RR}
NOMINAL IMPEDANCE IN OHMS
RETMA RATING – S_R
OPEN CIRCUIT VOLTAGE RESPONSE
$S_V = 20 \log_{10} \frac{E}{p}$ DB
E = OPEN CIRCUIT VOLTAGE
p = SOUND PRESSURE IN DB REFERRED TO 1 MICROBAR
OPEN CIRCUIT POWER RESPONSE
$S_P = S_V - 10 \log R + 44$ DB
R = NOMINAL IMPEDANCE
RETMA SENSITIVITY RATING
$S_R = S_V - 10 \log_{10} R_{RR} - 30$ DB
R_{RR} = CENTER VALUE OF NOMINAL IMPEDANCE RANGE

MICROPHONE sensitivities are often specified in different systems, making comparison difficult. The accompanying nomograph gives the relationship between open-circuit voltage response, open-circuit power response, and the RETMA sensitivity rating.

The voltage response value, S_v, is in db referred to 1 volt per microbar, and the power response, S_p, is in db referred to 1 milliwatt for 10 microbars sound pressure. A microbar is 1 dyne per sq cm.

The RETMA sensitivity rating is the power available in db relative to 1 milliwatt for 0.0002 dyne per sq cm. It is not defined for values below 19 ohms. For a given nominal impedance, R_{NR}, the microphone rating impedance, is the center value of the range of impedance values covered by the triangular sections on the nomograph.

Use of the nomograph to convert sensitivities is illustrated for a microphone having an open-circuit voltage sensitivity of −60 db and a nominal impedance of 15,000 ohms. Connecting these points as indicated by the solid line gives a power sensitivity of −58 db.

In finding the RETMA rating the microphone rating impedance of 9,600 ohms is used, since 15,000 ohms falls within that area on the R_{NR} scale. The dashed line indicates that the rating is −150 db.

Open-circuit voltage sensitivity of microphones undergoing impedance transformation can be found by determining the power sensitivity for the original impedance and then pivoting about this point until aligned with the new impedance. The new open-circuit voltage may then be read on the S_v scale.

References

RETMA Standard SE-105, "Microphones for Sound Equipment".
ASA Standard 224.1, "Acoustical Terminology".



MOLDED... LAMINATED

METAL PLASTIC ASSEMBLIES



ANY SIZE...
ANY TYPE...
FOR ANY USE...

CONSULT CINCH

The wide demand and long use of Cinch components is testimony to engineering vision and design . . . to the exactitude demanded in the manufacture and the appropriateness and durability of the materials. Whatever the requirement for metal plastic assemblies, Consult CINCH.

Cinch Electronic Components are available at leading jobbers — *everywhere*

CINCH MANUFACTURING CORPORATION

1026 South Homan Ave., Chicago 24, Illinois

Subsidiary of United-Carr Fastener Corporation, Cambridge, Mass.

Magnetic Drum Design

Nomograph relates drum diameter, spot density, frequency, angular velocity, access time and number of spots stored, to speed determination of design having optimum compromise of cost, storage volume and access time for modern computing machines

By D. G. O'CONNOR

Endicott Engineering Laboratory
International Business Machines Corp.
Endicott, N. Y.

THE SINGLE NOMOGRAPH below suffices for all quantities involved in the design of magnetic drums.

Example 1. It is required that 1,200 spots be stored on the full track. Assuming an operating frequency of 70 kc, a straight line through $N = 1{,}200$ and $f = 70$ kc gives $\omega = 3{,}500$ rpm and access time $T = 17$ milliseconds. Next, assume a reasonable value for spot density such as $d = 50$ and project from $N = 1{,}200$ through this to read $D = 7.6$ inches for required drum diameter.

Example 2. An access time of $T = 8$ milliseconds is required when using a revolver section having $N = 720$ spots. Extending a line through these values gives $f = 90$ kc. Assuming 4,000 rpm as a reasonable angular velocity for a revolver, a line through this value and $f = 90$ kc gives $N = 1{,}350$ spots. This means that 720/1,350 or 8/15 of the complete track is used for the revolved information. Assuming $d = 40$ for spot density, project through this value from $N = 1{,}350$ to read $D = 10.7$ inches as drum diameter.



Nomograph for parameter relations on magnetic information-storing drums. In revolver-type drum applications, each bit of information is read by one head, erased by the next head, and rerecorded by the third head a short distance ahead. The recorded information thus revolves around the drum concurrently with rotation of the drum to reduce access time to a fraction of a revolution

Stop Vibrator Power Supply Troubles Before They Start

The best time to do this is while your equipment is still on the drawing board. Each element . . . the vibrator, transformer and buffer capacitor . . . must be carefully selected for balanced electrical characteristics if your power supply unit is going to do the right job when it gets in service.

The best way to avoid vibrator power supply trouble is to call on the specialized knowledge and experience of Mallory engineers. Let us analyze the power requirements of your equipment and help you translate them into a power circuit that will give the performance you need.

Why call on Mallory? There are a lot of reasons . . . good ones. In the first place our experience in this field is backed by an unmatched fund of engineering knowledge that started over 20 years ago . . . when we produced the first commercial vibrator. Our experience includes supplying more vibrators for original equipment than all other makes combined.

That's not all. We are equipped to design and manufacture complete power supply units . . . to your exact requirements . . . to meet your production schedules. If you want to save engineering time and reduce production costs, write us today. It is a good way to stop your troubles before they begin.

Expect more . . . Get more from MALLORY

Parts distributors in all major cities stock Mallory standard components for your convenience

P.R. MALLORY & CO. Inc.
MALLORY

SERVING INDUSTRY WITH THESE PRODUCTS:
Electromechanical—Resistors • Switches • Television Tuners • Vibrators
Electrochemical—Capacitors • Rectifiers • Mercury Dry Batteries
Metallurgical—Contacts • Special Metals and Ceramics • Welding Materials

P. R. MALLORY & CO., INC., INDIANAPOLIS 6, INDIANA

Want more information? Use post card on last page.

ELECTRONS AT WORK

Including INDUSTRIAL CONTROL

Edited by ALEXANDER A. McKENZIE

Thyratron-Vacuum Tube Counter.....198
Stereovectorcardiograph 198
Pentode Gain Stabilizing Circuit.....200
Diode-Capacitor Memory.....200
Front Cover 202
Microwave Absorption Mats.....206
Bulb Puncture in Gas Tubes.....208
TV Field-Strength Indicator.....214
Low-Distortion Detector 214
Pertinent Patents 216

OTHER DEPARTMENTS featured in this issue:

Page

Production Techniques ..244
New Products 298
Plants and People.....412
New Books 453
Backtalk 464

Thyratron-Vacuum Tube Counter

By Richard W. Hopheimer

Staff Member
Lincoln Lab., M. I. T.
Cambridge, Mass.

LOW-FREQUENCY COUNTING operations in which low-impedance output is required can be accomplished in a circuit derived from a thyratron counter described in the MIT Radiation Laboratory book, "Waveforms". This circuit is reproduced in Fig. 1.



FIG. 1—Thyratron counter circuit

If it is assumed that V_1 is conducting and V_2 is off, a positive pulse of suitable amplitude, applied at + TRIG will cause V_2 to conduct. The plate voltage of V_2 decreases rapidly and because of the capacitor C the plate voltage of V_1 is decreased by an approximately equal amount causing it to fall substantially below ground. This extinguishes V_1. Another pulse will cause the counter to assume its original state.

Within its frequency limits this counter operates reliably unless something happens to cause the two thyratrons to conduct simultaneously. If this occurs the circuit ceases to function, and additional measures must be taken to extinguish one of the thyratrons.

This difficulty can be avoided by making V_1 a vacuum tube instead of a thyratron. In this case, if it is assumed that V_2 is off, a positive pulse will cause V_2 to conduct and to remain in conduction. Another applied pulse will cause the plate voltage of V_1 to decrease. As in



FIG. 2—Modified counter circuit

the original circuit, this will cause the plate voltage of V_2 to decrease, extinguishing the tube.

A practical form of this circuit is shown in Figure 2.

Research described in this document was supported jointly by the Army, Navy, and Air Force under contract with the Massachusetts Institute of Technology.

Stereovectorcardiograph

UNIPLANE VECTORCARDIOGRAMS showing current distribution around the heart have been used during the last 15 years. For more detailed studies three-dimensional wire models have been constructed from photographs of two plane vectorcardiograms displayed on a c-r tube screen. Three or more electrocardiograph leads are appropriately connected to the deflection plates for this purpose.

Recently, two-gun c-r tubes have been employed for simultaneous display of information that can be re-

Two stereovectorcardiograms recorded from a normal individual. A third-dimensional effect is obtained by fusing each pair of images at a distance of 8 inches from the eyes. Older viewers may require corrective lenses of plus 3 to 5 diopters. Practice in fusing images may require as much as 15 minutes initially

Accurately Tests and Calibrates Omni-Range and ILS Receiving Equipment

SIGNAL GENERATOR

Type 211-A

Frequency Range 88-140 mc.

Output Frequency Crystal Monitored
Amplitude Modulation 0-100%
Modulation Fidelity ±0.5 db
30 cycles to 11 kilocycles
Negligible Spurious FM

The Type 211-A Signal Generator was designed by Boonton Radio Corporation in cooperation with the CAA and leading manufacturers of aircraft navigation and landing receivers. It was designed for specific application to the calibration of these receivers to the high accuracy characteristics required. The CAA system requiring these receivers guides aircraft from one location to another and assists in landing under marginal weather conditions. The Signal Generator is also useful in testing accurately tuned communications receivers.

SPECIFICATIONS

FREQUENCY RANGE: 88 to 140 mc. in one Range. Vernier Dial marked to 10 Kc. division. Accuracy ± 0.25%.

R. F. OUTPUT: 0.1 to 200,000 microvolts. Output resistance looking into output terminals 26.5 ohms.

AMPLITUDE MODULATION: AM 0-30% and 0-100% with internal or external oscillator. Distortion below 5% at 95% modulation.

INTERNAL AUDIO OSCILLATOR: 400 and 1000 cps.

MODULATION AMPLIFIER: Uniform response within ± 0.1 db 90 to 150 cps. and 9.5 to 10.5 Kc. within ± 0.5 db 30 cps. to 11 Kc.

PHASE DISTORTION: Up to 60% modulation less than 0.25 degrees at 30 cps and 10 degrees at 11 Kc.

SPURIOUS FM: Less than 1 Kc. at 60% FM.

CRYSTAL CALIBRATING FREQUENCIES: 110.100 and 114.900 mc. ± 0.0035%. Calibrations can be made at these and other frequencies by slipping dial vs condenser shaft position.

PRICE: $1800.00 FOB Boonton, N. J. (Relay Rack not included).

Glide Slope Signal Generator

Type 232-A



Frequency Range 329-335 mc.

The 232-A Glide Slope Signal Generator provides 20 crystal controlled frequencies between 329 and 335 mc for testing aircraft landing receivers. One crystal controlled frequency is provided for the IF amplifier of the receiver.

The 232-A is a completely self-contained signal generator including its own power supply and synchronous motor driven modulator. It is a complete test equipment for Glide Slope Receivers.

SPECIFICATIONS

FREQUENCY RANGE: 329 to 335 mc (20 crystal controlled frequencies).
FREQUENCY ACCURACY: ± 0.0065%.
OUTPUT LEVEL: 1 to 200,000 microvolts.
OUTPUT IMPEDANCE: 53 ohms unbalanced.
IF FREQUENCY: 18.9 mc (By changing crystal 15 to 30 mc).
MODULATION: 90-150 cps, 1000 cps, external.
PRICE: $1500.00 FOB Factory.

BOONTON RADIO Corporation
BOONTON·N·J·U·S·A·

corded or directly viewed to give a three-dimensional pattern of electrocardiograph currents.

The displays in Fig. 1 were made using five pickups. A 300-cycle sawtooth time signal was applied to the *Z*-axis of both beams. Because the time signal turns the beam on slowly and then cuts it off rapidly, each pip of the vectorcardiogram takes on a comet-like appearance, the impulse traveling towards the head of the comet.

With a little practice, each pair of photographs in Fig. 1 can be fused to produce a third-dimensional picture. The electrodes used in this recording were placed so that the planes observed deviate from each other by 10 to 15 degrees.

This material has been abstracted from information furnished by Arthur C. Guyton, M. D., Chairman of the Department of Physiology and Biophysics, University of Mississippi School of Medicine in University, Miss.

Pentode Gain Stabilizing Circuit

By J. G. HAYDOCK, JR.
Asst. Manager, Sales Engineering
Globar Division
The Carborundum Co.
Niagara Falls, N. Y.

EFFECTS of supply-voltage fluctuations on the performance of amplifiers in gain and signal-measuring equipment and sweep-voltage amplifiers for cathode-ray oscilloscopes and tv receivers can be virtually eliminated by use of a circuit employing voltage-sensitive resistors.

Gain of pentode amplifiers is dependent to some extent on supply voltage, because of the effect that screen voltage value has on the mutual conductance of such tubes.



FIG. 1—Variation of gain with supply voltage for 12SK7 pentode in circuit using regular resistors and voltage sensitive resistors

The variation of gain with supply voltage in conventional r-f pentode circuits when a series dropping resistor is used to obtain screen voltage, is shown in Fig. 1. This curve was obtained for a 12SK7 with 250 volts on the plate, 100 volts on the screen and normal grid bias by means of a cathode resistor. A rise or fall of 10 percent in supply voltage caused a corresponding 2 to 2.5-percent increase or decrease in the gain.

The second curve in Fig. 1 was obtained with the circuit of Fig. 2



FIG. 2—Circuit using voltage-sensitive resistors has voltage divider returned to ground through cathode resistor

using the same tube and supply voltages. This circuit confines the fluctuation of gain within a range of approximately ± 0.2 percent of a mean value over the range from −10 percent to +10 percent of normal supply voltage.

Screen voltage is supplied by the voltage-divider method. The low-potential section of the divider is a voltage-sensitive resistor whose value decreases sharply as the voltage drop through it increases. The current drawn by the voltage divider is returned to ground through the cathode resistor rather than directly.

Because of the increase in current drawn by the voltage-sensitive resistor caused by a relatively small increase of supply voltage, the bias on the stage increases with supply voltage. This increase is at a rate that opposes the tendency for the stage gain to increase with supply voltage.

In the curve obtained with this circuit, values of the various resistors have been proportioned to cause the stage gain to reach a maximum at the nominal supply voltage of the tube. By using other resistor proportions this type of curve can be obtained with practically all r-f pentodes. This method of gain stabilization is effective also with some beam pentodes.

The stabilized circuit has been evaluated in a preliminary way for reducing the variations in the width of pictures on the television-receiver picture tube. Tests indicate that up to a 4-to-1 reduction in picture-width variation with line voltage is possible. This would minimize present service adjustment problems related to horizontal-sweep voltage. It also presents the possibility of making television receivers self-regulating in this respect.

Diode-Capacitor Memory

ELECTRONIC COMPUTERS are handicapped by inability of the memory to attain speeds matching practical arithmetic units. The diode-capacitor memory, developed by A. W. Holt of National Bureau of Standards, can be designed to present more than 100,000 randomly located 50-digit words per second to SEAC computer, decreasing machine computation time for mathematical problems. In contrast, SEAC's acoustic memory has a random access of 6,000 words per second while the Williams memory has an access rate of up to 60,000 words per second.

Basic circuit (Fig. 1) for the storage element consists of two di-



FIG. 1—Basic storage element in diode-capacitor memory

odes in series, with the anode of one connected to the cathode of the other, one side of a capacitor tied to their midpoint, and the other side of the capacitor returned to ground through a resistor. The point between the capacitor and resistor, denoted by *E*, is used for both reading and writing, while the two diodes are used as a squeezer to connect the capacitor to the read-write circuits.

During holding, both diodes are

Having the RIGHT CONNECTIONS *is a big help!*



Helipot* ... first in precision potentiometers ... makes sure that, in *every* Helipot, you do have the right connections. No pressure-type connections are used in *any* Helipot. Tap connections are spot-welded by a Helipot-developed process, and other electrical connections are soldered ... they all *stay put!*

The spot welding process is a particularly interesting one ... and more important, it offers a very real advantage to users of Helipot precision potentiometers. Skilled workers, using binocular microscopes, employ a new technique in spot welding the very fine electrical connections. This technique assures that tap connections are attached to a single turn *only* of the resistance wire, rather than to several adjacent turns as is usually the case with the conventional method. Thus the high resolution, so important to the proper functioning of a precision potentiometer, is not reduced, and none of the wire turns adjacent to the one tapped are shorted out.

The spot welding process offers the further advantage of providing the strongest possible type of connections ... vibration proof, shock proof, corrosion proof, unaffected by temperature and humidity changes. And to cap the climax, the new process is efficient and economical ... another example of the Helipot policy offering the lowest price consistent with the high quality you expect in Helipot products.

For information about Helipot's complete line of precision potentiometers, call your nearest Helipot representative or write direct!

*T.M. Reg. U.S. Pat. Off.

WRITE FOR YOUR COPY!

Your copy of the HELIPOT Condensed Catalog describing every model of HELIPOT Precision Potentiometers and Duodials is now ready. Please write for it on your company letterhead.

Write for Data File # 1102

Helipot *corporation*

a division of **BECKMAN INSTRUMENTS, INC.**
SOUTH PASADENA, CALIFORNIA

PLANTS AT SOUTH PASADENA, CALIFORNIA & MOUNTAINSIDE, NEW JERSEY
ENGINEERING REPRESENTATIVES IN PRINCIPAL CITIES

Helipot | *first in precision potentiometers*

THE FRONT COVER



SOLDERLESS multiple-spindle wiring is done with rotating spindles within stationary sleeves. As described in ELECTRONICS, p 272, June 1953, each spindle has two longitudinal holes, one near the edge and the other at the center. Wire is inserted in the outer hole and the terminal placed in the center. When the spindle rotates, wire is wrapped under tension.

A semiautomatic machine that makes many solderless connections simultaneously is now being used experimentally by Bell Telephone Laboratories. Basis for this method of mechanized wiring is the single-wrapped solderless connection (as shown in insert on cover) developed jointly by Bell Labs and Western Electric Co. and now being introduced into Bell telephone equipment.

Terminals of a commercial a-m receiver were modified to have the proper edged cross-section in approach to automation.

Semiautomatic wiring is done in four steps: inserting leads and wires in the spindles; placing the chassis terminals on the spindles; wrapping; removing the chassis. The last three steps are performed simultaneously for all connections.

The multiple-spindle head is aligned with the chassis, which is lowered onto it. To adapt the machine for a new placement of parts, a new spindle-holding plate is set into the assembly bench. Spindles and sleeves are merely relocated.

A 35-mm slide projector indicates successive steps to be taken by the operator. Wiring path and component number are projected for each component.

Correspondingly numbered components are removed from convenient storage bins and dropped into place.

Servicing of equipment wired in this manner is easy. Connections can be unwrapped from either end and replaced with a single-spindle tool that duplicates the original action.

biased in their back direction. For example, the anode of one diode might be held at −4 volts while the cathode of the other is held at +4 volts. Then, if the capacitor has a charge of 2 volts both diodes will be biased in their back direction, and only small currents will flow into or out of the capacitor.

When the ends of the diodes are both forced to ground potential (squeezed), one diode or the other will conduct, and a voltage will appear across the resistor. If the capacitor has been charged with 2 volts of such polarity as to make its lower terminal more negative than its upper terminal, there will appear at output E a pulse of −2 volts, which dies out with the time constant RC. This negative pulse is recognized by the reading circuits at the output as binary zero.

If the polarity on the capacitor had been in the opposite direction, the squeeze would have produced a positive pulse that would be recognized as the binary one. Thus, the content of the storage element has been read; but in the process it has been at least partially discharged, and the information has been lost from the storage element. The information must be rewritten.

Rewriting

To rewrite information it is only necessary to force point E to the desired state and hold it there until the squeeze is over. While the ends of the diodes are at zero voltage, assume that E is forced to +2 volts and held there until the diodes are returned to their normal voltages of −4 and +4 volts. Then the capacitor is left with a charge of 2 volts and upon the next squeeze will produce a positive pulse at E—a one is written.

The opposite is equally possible. Forcing E negative until the end of the squeeze will write a zero. Once the diodes have been returned to their normal voltages, the charge on the capacitor will be undisturbed by later changes at E, provided the magnitude of the voltage at E never exceeds 2 volts. Thus E can have other pulses on it, either positive or negative, and the charge stored on the capacitor will remain unaffected because both diodes will remain with backward bias. This is important for organizing many basic storage elements into an efficient memory assembly and is the reason for charging the capacitor to only ±2 volts while biasing the diodes twice as much.

The effect of finite forward conductance will reduce output pulse amplitude, and determine how long a writing pulse must last to charge the capacitor adequately. The effect of finite backward resistance is

. . . which MPB ball bearing do you need?



new MPB catalog 53-54

Most complete information ever offered on miniature ball bearings

includes:

- **Complete specifications and descriptions of more than 140 different types and sizes of miniature ball bearings**
- **Bearings from 1/10" to 3/8" o.d. shown in actual sizes**
- **Speed-load charts with factor for easy conversion to any desired speed or load**
- **Lubrication — what and how — including government specifications and commercial sources**
- **Recommended shaft and housing fits; shaft and shoulder data**
- **Radial and axial clearance graphs**
- **Typical methods of using miniature ball bearings**

For the designer of precision mechanisms this new 20 page **MPB** catalog offers practical solutions of problems involving miniaturization. As suggested by the partial list of contents above, **MPB**, originator and pioneer manufacturer of miniature ball bearings, has compiled for you the most complete and detailed information ever offered on this subject.

Request the new **MPB** catalog 53-54 on your letterhead . . . it may help develop a new product idea for you. Also request data sheet E 11.

HOW DO THEY MAKE MINIATURE PRECISION BEARINGS?
If you've ever wondered about it — you'll find the answer in "MIGHTY MINIATURES" — 15 minute, full-color, sound film. "MM" is the story of Miniature Precision Bearings — with the accent on manufacturing processes and uses of MPB bearings. It's available to qualified groups. Write Engineering Dept., MPB, Inc., Keene, N. H.

GET YOUR BEARINGS AT . . . **Miniature Precision Bearings**

Incorporated Keene, New Hampshire

Want more information? Use post card on last page.



R-B-M Relays

FOR EVERY ELECTRONIC APPLICATION

Meeting Commercial and Government Requirements

OPEN TYPE. Circuit switching—power and dynamotor loads—plate circuit—low capacitance.

HERMETICALLY SEALED. Stud or bushing mounting—solder or plug-in headers—circuit switching—power—low loss applications.

TRANSPARENT PLASTIC COVER. Most R-B-M relays now available in low cost transparent plastic cover.

OTHER PRODUCTS: Motor starting relays and overload protectors for refrigeration, appliance and general purpose motors. Industrial contactors and across-the-line starters. NEMA size 1 and smaller. Low cost general purpose relays. Low voltage D.C. manual and magnetic devices.

Let R-B-M engineering and production facilities serve you. Contact us immediately—Phone 5121

Write Dept. B-11 For ASR Bulletin

RBM **R-B-M DIVISION ESSEX WIRE CORP.**
Logansport, Indiana

MANUAL AND MAGNETIC ELECTRIC CONTROLS FOR AUTOMOTIVE, INDUSTRIAL, COMMUNICATION AND ELECTRONIC USE

critical. During the holding operation relatively long times will elapse, and even minute currents through the diodes disturb capacitor charge.

Arbitrarily long periods of information storage are achieved by regeneration; before the capacitor charge can change to a point where there is danger of losing the information, memory control circuits read the content of each cell and rewrite it.

An amplifier is required at point *E* to sense the polarity of *E* during the early part of the squeeze period, together with a gate structure that will force *E* to the desired polarity during the latter part of the squeeze period. For reading or regeneration *E* is forced to the same polarity that was read. For writing new information the polarity to which *E* is forced is independent of what was read, but is determined by the new information being written.

Gating Amplifier

For efficiency, it is essential the gating amplifier serve many basic storage elements. Buses to the diodes are made common to all digits of a particular computer word, and a particular gating amplifier serves the same digit on each of many words. Thus for 256 words of 50 binary digits each there would be 256 pairs of leads to the diodes and 50 gating amplifiers. For reference to a particular word, the proper pair of buses are squeezed to zero voltage, while all the other pairs are held at their normal value of −4 and +4 volts.

In this way each gating amplifier receives a pulse from its particular digit of the selected word so that the word is available in parallel at the gating amplifiers. They can then write into this word or rewrite it without affecting the other words in the memory since all diodes in other words remain with backward bias. Regeneration is handled by having the memory control intersperse regeneration cycles, in which the words are read one after the other and rewritten into their former state, between the computer access cycles.

A selection matrix consisting of transformers and diodes is used that has no standby power require-

Takes more than a quick eye

TODAY!



12-Information Channel-Playback System for use with The Glenn L. Martin Co.'s new T-13 Gunnery Trainer, designed and developed by Cook Research Laboratories, a division of Cook Electric Company.

AIMING HIGH today calls for more than just "drawing a bead." Split-second timing is absolutely essential to the operation of the intricate instrumentations and equipment necessary to give adequate training in gunnery to both our anti-aircraft troops and to our jet pilots.

Eleven STANDARD ELECTRIC Model S-1 Timers are shown on the large control panel in the center of the photograph above.

STANDARD

Serving industrial, governmental and educational institutions since 1884.

The STANDARD ELECTRIC TIME COMPANY

97 LOGAN STREET • SPRINGFIELD 2, MASSACHUSETTS

PRECISION TIMERS • CHRONO-TACHOMETERS • LABORATORY PANELS • PIPELINE NETWORK ANALYZERS



PROBLEM

Direct-current-operated valves were the key to improved performance of an automatic milking machine, but in field tests, the mechanically driven DC power supply for actuating the valves required excessive maintenance. In humid dairy barns, too-frequent cleanings and adjustments were necessary to obtain dependable operation.

When your plans for product development or improvement indicate a need for dependable DC power, consult Vickers' experienced rectifier engineers. There's no obligation.

SOLUTION

Rectifier power supplies, using Vickers Selenium Rectifiers, solved this DC supply problem. Vickers rectifiers require no maintenance or adjustment, are completely dependable in humid and other corrosive atmospheres. With Vickers Electric Division engineering assistance, this manufacturer not only solved his performance problems but was able to reduce product costs.



VICKERS ELECTRIC DIVISION
VICKERS Inc.
A UNIT OF THE SPERRY CORPORATION
1801 LOCUST STREET • SAINT LOUIS, MISSOURI

ment, although it does require more input drivers than would be necessary with a multidimensional diode matrix. For the transformer and-gate matrix, $2n$ inputs are required to select from n^2 words. The matrix



FIG. 2—Word selection matrix using transformer and-gates is described in text

is made up of two sets of crossing buses, X and Y; at each crossing a diode and transformer primary are connected in series, with the cathode of the diode tied to the X bus as shown in Fig. 2.

Normally all the X buses are held at +10 and all the Y buses at −10 volts. This puts backward bias on the diodes associated with each transformer, so normally no current flows through any transformer. If one X bus is dropped to −10 volts, still no current flows; but if simultaneously one Y bus is raised to +10 volts, then just one transformer at the crossing of these two buses will receive a signal, the transformer secondaries connected to the diode-capacitor will squeeze the buses together, and the desired word will be selected.

Microwave Absorption Mats

MICROWAVE ABSORBERS in the form of fibrous mats impregnated with pigmented rubber solutions have been developed at Naval Research Laboratory. These materials have given efficient broadband absorption over the range from 2,500 to 35,000 megacycles, reflecting less than 5 percent of the energy returned by a smooth metal plate.

Excelsior, curled vegetable fiber, curled and uncurled animal hair, with aluminum flakes, graphite or conducting carbon black in rubber solutions as the loss-producing pigment have been used. Rubber-bonded curled animal hair, how-



The proud papa is B. F. Michtom, Chairman of Ideal Toy Corporation, but . . .

Do you recognize his famous family?

They're all celebrities except the happy "father"! He's B. F. Michtom, who built a $25,000,000 business promoting "character" dolls inspired by famous personalities. He's holding Saucy Walker and Harriet Hubbard Ayer. The others are Mary Hartline, the Toni Doll, Shirley Temple, and Smokey Bear, protégé of the U. S. Forest Service.

"Real-life stars create plenty of excitement when they appear at famous stores," says B. F. Michtom. "But to cash in, we have to get the dolls on the counter *on time*. We call Air Express. Frantic telegrams come in: 'Sold out. 1,000 kids in store. Send more dolls!' We keep both kids and stores happy — we call Air Express again!

"Stores need mat ads. They run out of autographed photos, Jr. Forest Ranger application cards and similar promotion materials. Air Express fills the gap fast.

"Nobody needs Air Express more than we. It's indispensable. Yet we pay no premium for this superior service. In fact, Air Express rates are *lowest of all* on most of our shipments."

It pays to express yourself clearly. Say Air Express! Division of Railway Express Agency.

Air Express

GETS THERE FIRST via U.S. Scheduled Airlines

SUB-MINIATURE
PILOT LIGHTS
Approved for AIRCRAFT
AND IMPROVED IN IMPORTANT DETAILS

DIALCO

SUB-MINIATURE INDICATOR ASSEMBLIES

A great aid to your miniaturization program

MOUNT IN 15/32" HOLE
ALL LENS COLORS

Easy lamp replacement with any midget flanged base lamp types

Complete blackout or semi-blackout dimmer types

NON-DIMMING
No. 8-1930-621

MECHANICAL DIMMER
No. 11-1930-621

THESE ASSEMBLIES LOGICALLY REPLACE LAMPS NO. 319, 320, and 321

PLASTIC PLATE (EDGE) LIGHT ASSEMBLIES

AIR FORCE and BUREAU of AERONAUTICS
MIL-L-7806 DRAWING MS-25010

DIALCO *No. TT-51* (Red filter-black top)
. . . or, *No. TT-51A*, complete with No. 327 Lamp

ALSO MADE
with other filter colors and with *light-emitting top* (for indication)

ALL OF THE ASSEMBLIES ILLUSTRATED ACCOMMODATE LAMPS NOS. 327, 328, 330, and 331.

ANY ASSEMBLY AVAILABLE COMPLETE WITH LAMP

SAMPLES ON REQUEST—NO CHARGE

Foremost Manufacturer of Pilot Lights
DIALIGHT CORPORATION
60 STEWART AVENUE, BROOKLYN 37, N. Y. HYACINTH 7-7600

ever, has proved the best combination. This combination is flexibile, resilient and resists mechanical abuse and normal weathering conditions. It uses relatively inexpensive materials that are available commercially in large quantities.

Chief present disadvantages of this absorber, which the scientists have named Darkflex, are it's flammability and variations in thickness and density. Curled animal hair sheets are not subject to close control, in normal production, with considerable variation possible even in a single small sheet. Bulkiness is another disadvantage for broadband application, since the minimum thickness is about a quarter of the longest wavelength to be absorbed. Less bulky types have been developed, however, that are applicable to particular bands, such as the K-band, and the K— and X-bands.

Bulb Puncture In Gas Tubes

By V. L. Holdaway
Bell Telephone Labs.
Murray Hill, N. J.

Electrical puncture of an electron tube bulb results in abrupt failure of the device. The user may fail to identify this type of failure as it may occur at any time during normal life, depending upon the operating conditions. Often the only physical evidence is merely a small pinhole in the envelope.

Bulb puncture is caused by an electrical stress through the envolope. The stress may be produced by the potential of a contacting conductor, or in high voltage circuits by the proximity of a conductor. The condition may be intentional, resulting, for example, from the use of shields or supporting devices or may be accidental, resulting from poorly arranged wiring.

For the higher voltage tubes, the published information gives sufficient warning against operating conditions conducive to bulb puncture. Precautionary information along this line for the lower voltage tubes is generally lacking.

Damaging potential gradients are more likely to be produced through the bulb of a gas tube than the high-vacuum type. In the gas tube the inside bulb sur-

Bomac

MINIATURIZATION FOR X BAND

Miniaturization and tube development never stops at Bomac. A typical example is the new Type 6378 gas switching tube designed for X band airborne equipment. This tube is a miniaturized version of the 1B24, 1B60 and 1B24A which it supersedes. Size has been cut in half and weight reduced one fifth with no sacrifice in performance. It is used with standard ½" x 1" OD guide between standard choke flanges.



TUNING

A differential screw mechanism acting on flexible diaphragm controls the cavity capacitance by varying the gap spacing. The tube may thus be smoothly tuned to any frequency within its range. A tuning curve showing resonant frequency vs. the position of the tuning screw is shown above.

- SMALLER
- LIGHTER
- CAN BE PRESSURIZED
- SAME PERFORMANCE

Peak Power	100 KW., max.	Recovery Time (3 db.)	4μ sec.
Insertion Loss db	1.50 max.	Leakage Power	30 mw.
Ignitor Interaction (100 μa), db.	0.2 max.	Loaded Q	350 max.
Tuning Range	8490-9600 mc.	Ignitor Voltage Drop (100 μa)	200-400
Temperature Coefficient	0.2 mc./C°., max.	Ignitor Voltage Open Circuit	—500 min.

We invite your inquiries regarding
- ENGINEERING
- DEVELOPMENT
- PRODUCTION

Bomac Laboratories

INCORPORATED

BEVERLY, MASSACHUSETTS

Catalog on request. Write (on your company letterhead) Dept. E-11, BOMAC Laboratories Inc., Beverly, Mass.

GAS SWITCHING TUBES • DIODES • HYDROGEN THYRATRONS • DUPLEXERS • MAGNETRONS • MODULATORS

FAIRCHILD

Transistor Analyzer

Complete—all calibrating circuits built-in.
Needs only standard DC oscilloscope.

Developed by Fairchild in its program for transistorizing Missile Guidance Systems and other intricate electronic circuits.

Rapidly Plots Static and Dynamic Characteristics of ALL Transistors ... point contact and junction. Designed on basic principles, to meet future transistor needs.

Complete Families of Curves obtainable in 10 incremental steps for each of 5 ranges. Sweeping technique shows up anomalies.



Presents on the Scope:

Alpha vs. Emitter Current

•

Collector, Emitter and Transfer Characteristics

•

Collector Characteristics in Grounded Emitter Connection

ENGINE AND AIRPLANE CORPORATION

FAIRCHILD

Guided Missiles Division

Wyandanch, L. I., N. Y.

Other Divisions: Aircraft Division, Hagerstown, Md. • Engine Division, Farmingdale, N. Y.

FAIRCHILD ENGINE & AIRPLANE CORPORATION
GUIDED MISSILES DIVISION, WYANDANCH, L. I., N. Y.

Please send me your Detailed Transistor Analyzer Technical Bulletin.

Name and Company_____

Address_____

City_____ Zone_____ State_____

E

face, in general, assumes a potential approximately equal to that of the plasma. In most types this will be near cathode potential. The wall potential of the high-vacuum tube is more uncertain and also there is a dearth of charge carriers in the tube to complete the circuit to a tube element.

Bulb puncture is aggravated by high temperatures. The operating temperature of the glass bulb results from a heat balance between the power dissipated within the bulb plus radiant heat from surrounding components and heat energy leaving the bulb by convection, conduction and radiation. The effectiveness of these cooling processes will depend upon ambient temperature and the rate of air circulation for the convection process, conductivity of the heat-conducting path and temperature of the sink for conduction cooling and the black-body constants and temperature of the tube or radiator for radiation cooling.

The prevailing trend toward space and weight saving often results in crowding and poor ventilation with attending high temperatures. Close-fitting shields often used on miniature and subminiature tubes to reduce bulb temperature by heat conduction may produce bulb-puncture conditions.

Under a particular set of operating conditions there will be a difference between bulb temperature and the environment generally referred to as bulb temperature rise above ambient. The bulb temperature of cold-cathode tubes used at low currents or operated intermittently may not have an appreciable rise above ambient. Certain types, however, such as gas-



FIG. 1—Puncture voltage versus temperature. Test voltage raised at rate of 1,000 v per minute

Get ready for color TV with CVC high vacuum equipment

to aluminize screens

*or color plates



to evacuate tubes

The "high vacuum" equipment you will need for color TV tube production is already under design at *CVC*—we'll be ready to go when you are.

For several years our sales and engineering staffs have maintained regular contacts with the laboratories working on "color." We've helped solve knotty aluminizing and vacuum pumping problems in the lab and are translating what we've learned into designs of efficient production equipment. This is why we now stand in a unique position to recommend the *right* high vacuum equipment.

Please call on us to help you with any vacuum processing problems on color TV tubes. ***Consolidated Vacuum Corporation, Rochester 3, N. Y.*** (a subsidiary of Consolidated Engineering Corporation, Pasadena, California).

CVC

formerly DPi Vacuum Equipment Dept.

Consolidated Vacuum Corporation

Rochester 3, N. Y.

designers and manufacturers of high vacuum equipment

SALES OFFICES: PALO ALTO, CALIF. • CHICAGO, ILL. • CAMDEN, N. J. • NEW YORK, N. Y.

if you want stable and trouble-free

120 VOLT DRIVE CHOPPERS

that can be corrected to zero phase angle

Normal angle is 80°; with an external .039 mfd. capacitor a ZERO angle is obtained, drive to square wave. Permanently hermetically sealed, SPDT contacts. Residual noise less 5 mv. rms. at ½ megohm circuit impedance. Contacts rated to 100 V, 2ma., tho this current may be exceeded by 10 to 100 times this value for short intervals; the voltage may be as high as 200 V. Normally 380 to 420 cycles, and —10 to 85°C, unit may be operated over much wider frequency ranges and temperatures down to —55°C with excellent reliability. Meets 10g vibration, 50g acceleration. Specs. can be altered to special needs. Consult our engineers.

Write for Specification 107 . . . data sheet A-580

use AIRPAX

A580 400 cycle choppers

AIRPAX PRODUCTS COMPANY
DESIGNERS ENGINEERS
MIDDLE RIVER BALTIMORE 20, MD

tube voltage regulators, may exhibit a considerable temperature rise.

Operating conditions likely to produce bulb puncture are more likely to be unwittingly set up in the use of the lower voltage gas tubes that are generally in soft glass.

The dielectric strength of lime and lead bulbs is not high and decreases markedly with increased temperature. Figure 1 shows typical puncture voltages for lime and lead glass bulbs of 0.02-inch wall thickness as a function of temperature These curves are for short-time voltage application. The puncture voltage for sustained application will be somewhat lower. In continuous use a safety factor of at least two is suggested.

The dielectric strength of the bulb will be approximately proportional to the wall thickness. The wall thickness will vary from some 0.02 inch for the smaller bulbs such as the T5-½ to 0.06 inch or more for the larger transmitting types. The larger tubes, however, are generally in hard glass, which has several times the dielectric strength of the soft glasses.

The tube operating conditions should be scrutinized carefully in any application of a gas tube where contact is made with the bulb at any location by a conductor such as a shield, hold-down or clamping device, or where contact may be made accidently. The factors that should be considered are:

(1) Kind of glass in the bulb and wall thickness.

(2) Temperature of the bulb at the contact area under maximum power and ambient temperature.

(3) Maximum voltage that may appear between the external contact and any tube element, notably the filament or cathode. Abnormal conditions such as transients and oscillations, overload conditions, high line voltage or similar adverse factors should be considered. One condition often overlooked is where the bulb contact is at ground potential and the tube elements are raised considerably off ground by the voltage of a coupled circuit. This is often the case in cascaded circuits.

Aside from bulb puncture, the

a handful of components in one tiny package



Stupakoff Printed Circuits

Space is saved, assembly time reduced and errors eliminated when sturdy, compact Stupakoff Printed Circuits are used. In one tiny package—half the size of a book of matches—few or many accurately rated components—resistors and capacitors—are permanently assembled according to specifications. The only connections to be made are the external leads.

Stupakoff excels in the development and manufacture of Printed Circuits, and today is equipped with modern facilities for the mass-production of dependable units made to your specifications. Write for Bulletin 1151-A.

STUPAKOFF CERAMIC & MANUFACTURING COMPANY

LATROBE, PENNSYLVANIA



pressure sensitivity

The accurate measurement of pressures is basic in many of our aircraft instruments and controls. Our expanded activities now cover the four distinct yet allied fields of

- AIRCRAFT INSTRUMENTS AND CONTROLS
- OPTICAL PARTS AND DEVICES
- MINIATURE AC MOTORS
- RADIO COMMUNICATIONS AND NAVIGATION EQUIPMENT

Current production is largely destined for our defense forces; but our research facilities, our skills and talents, are available to scientists seeking solutions to instrumentation and control problems.

kollsman INSTRUMENT CORP.

ELMHURST, NEW YORK • GLENDALE, CALIFORNIA • SUBSIDIARY OF Standard COIL PRODUCTS CO., INC.

operation of a tube at high bulb temperatures produces a second damaging effect, that of foreign gas liberation. Gases liberated from the inside bulb walls impair tube performance and reduce tube life. The amount liberated depends on the temperature and time. For a conventionally designed and properly processed lime-bulb tube, 175 C is considered a maximum safe limit of bulb temperature.

TV Field-Strength Indicator

By JOHN B. LEDBETTER
Pomona, Calif.

A SIMPLE INSTRUMENT for checking tv signal strength is useful in setting up a monitor receiver for tv remote cues, checking reception, orienting receiver antennas and in adjusting the studio master antenna. Such a device is shown in Fig. 1.



FIG. 1—Circuit of tv field-strength indicator. Values of parts used are not especially critical

In use the test circuit is connected to the tv-receiver chassis and to the picture-tube grid. A needle-point clip will allow easy connection through the picture-tube grid lead without disturbing circuit connections. For distances up to 50 feet ordinary lamp cord or unshielded wire can be used between the 1N48 and the indicating meter. If used as a remote indicating device in conjunction with a calibrated video monitor, the meter can be used to show relative or average video level and saturation of the signal.

Low-Distortion Detector

A DETECTOR for amplitude-modulation receivers having 0.3 percent total harmonic distortion at 100-percent modulation for a modulation frequency or 420 cycles is described by F. Langford-Smith in

Plain Pointers on Projection

ONE of the basic precepts of the study of geometrical optics is that the angle of incidence equals the angle of reflection. This law, recognized by the Greek philosophers and refined by later investigators, has an important bearing on modern optical gaging by projection. In numerous instances it is desirable to project the surface of a part on the screen to check the position and size of recesses or to measure features which may not permit conventional profile shadow images. The ease and success with which this is done depend not so much on how much light is thrown on the part as on how much of this light is reflected back into the instrument's lens.

Traditionally, surface illuminators used with contour projectors have been placed at an angle on each side of the lens or optical axis. This was true of the pilot model of the Kodak Contour Projector and we frankly admit it proved somewhat less than perfect. Since the light struck the part at an acute angle, it was reflected from the surface at a similar angle—reflected away from the lens, as it were, when the part was normal to the lens for a distortion-free image.



However, between design of this pilot model and our production models, our optical engineers devised a radically different system. As shown here schematically, this consists of a 1000-watt lamp (A) so mounted that its light is reflected by a mirror (B) through the front lens (C) of the instrument. Since the light from this surface illuminator travels along the axis of the lens, it is reflected from a part (D) back through the lens with negligible loss. By staging the part to be measured perpendicular to the optical axis, the angles of incidence and reflection approach zero degrees. Light is reflected from the part back on its own path.

This permits inspection of deep recesses and results in a screen image of unusual brilliance when projecting surfaces. The latter we have frequently demonstrated by placing the works of a small watch on our contour projector. Spectators are generally impressed to see the wheels and gears in motion, and on at least one occasion we've had a watch brought to us for repair. While this was perhaps somewhat embarassing, we're reconciled by the thought that users of our projectors are saved embarrassment daily because of the accuracy with which they can gage parts to "tenths."

Inspection costs fall when surface features and profiles are checked simultaneously

YOU may be missing a chance to lower inspection costs, speed the work, if you're overlooking the surface illumination feature of the Kodak Contour Projector.

Take the Geneva wheel shown here. By optical gaging, 47 dimensions are checked to tolerances of .001" in *less than 60 seconds,* using a single chart-gage and a simple staging fixture. Conventional shadow projection is used to check 36 of these. But only through surface projection can the 11 dimensions of the hub, including five angles and three radii, be checked simultaneously. A flick of a switch and the unique, self-contained surface illuminator (described in the column at the left) makes checking surface details as easy as measuring shadow profile.

The inherent speed and accuracy of inspection and measurement on Kodak Contour Projectors are lowering inspection costs on all sorts of parts, simple and complex, large and small. The field representative in your area will be glad to show you how optical gaging can work for you. To get in touch with him, or for a copy of a booklet, "Kodak Contour Projector," write to:

Special Products Sales Division
EASTMAN KODAK COMPANY
Rochester 4, N. Y.

the KODAK CONTOUR PROJECTOR

Optical Gaging

A new sound movie, Optical Gaging, shows how to simplify complex inspection problems. We'll tell you how to get it for a showing.

Kodak

Want more information? Use post card on last page.

For Economical Control of Remote Operations . . .

THE "MULTI-GATE" SYSTEM


Provides Complete Control & Supervision Over a Single Circuit
• Used over Wire, Radio, Microwave or Carrier
• One or More Remote Points
• Complete Report-Back Facilities
• Fail-Safe Operation
• Automatic Memory and Programming
Remote Station Equipment
Control Station Equipment

Hammarlund Remote Supervisory Control equipment is particularly well-adapted to operations of petroleum refineries, pipelines, railroads, public utilities, and other organizations that have widespread physical facilities. This equipment fulfills their requirement for central coordinated control because it makes possible the operation of distant functions immediately and positively from one or more master stations.

Two basic factors, carefully pre-determined for the equipment, were flexibility and versatility. Because it is designed on building-block principles—using standard sections in individually unique combinations—great flexibility has been achieved. For all practical purposes, a customer gets a custom installation at a standard inflexible system cost. Its versatility makes it adaptable to any application in any industry or organization. Only a single circuit is required for control and supervisory report-back. The number of remote functions that may be handled by a "Multi-Gate" system is virtually unlimited.

For Detailed Information Write For Bulletin M2.

HAMMARLUND

THE HAMMARLUND MANUFACTURING CO., INC.

MAIN PLANT & OFFICES: 460 W. 34th St., N. Y. 1, N. Y.

Mid-West Sales Office: 428 N. Michigan, Chicago 11, Ill. • Export Sales Office: 13 E. 40th St., N. Y.

Radiotronics. The circuit developed at Radiation Laboratory of the University of California has only 0.8 percent distortion at 100-percent modulation for a frequency of 4 kc.



FIG. 1—Low-distortion a-m detector

As shown in Fig. 1, the detector is a conventional diode rectifier directly coupled to a cathode follower in whose output an r-f filter reduces carrier-signal output. Because load on the diode for normal a-m carrier frequencies is essentially resistive, normal effects of excessive shunting capacitance are eliminated.

There is no effect from bias currents normally developed in a diode-loading circuit using coupling capacitors because the cathode follower is directly coupled.

PERTINENT PATENTS

FROM 1950 to 1952, new applications for patents received by the U. S. Patent Office declined from 69,294 to 60,386. The National Patent Council, viewing this situation with alarm urges increased incentives to keep up the American leadership in invention so long held.

Cathode-Ray Numerals

Titles of some patents become unwieldy. This is true of a "Device of the Kind Comprising an Electronic Tube, Having a Ribbon-Shaped Beam Which is Deflected and Held in Different Positions", invented by Klaas Rodenhuis, of Eindhoven, Netherlands. The U. S. patent number is 2,642,547 and it is assigned to the Hartford National Bank of Hartford, Conn. as trustee.

From the diagrams of Fig. 1 it is seen that the device is an indicating tube operating on the prin-

...Another Crucible Service for Magnet Users



160,000

ampere turn, impulse magnetizer now available

Magnet users are reducing manufacturing costs and improving their products through the use of this new, capacitor discharge-type, impulse magnetizer — another example of Crucible's leadership in serving industry.

This Crucible development has an improved firing circuit . . . is more compact . . . requires less maintenance . . . and results in more efficient magnetization.

For further information on the availability and operation of the Crucible Impulse Magnetizer, write to Crucible Steel Company of America, General Sales Offices, Oliver Building, Pittsburgh, Pa.

CRUCIBLE first name in special purpose steels

53 years of Fine steelmaking **ALNICO PERMANENT MAGNETS**

CRUCIBLE STEEL COMPANY OF AMERICA, GENERAL SALES OFFICES, OLIVER BUILDING, PITTSBURGH, PA.

STAINLESS • REX HIGH SPEED • TOOL • ALLOY • MACHINERY • SPECIAL PURPOSE STEELS

Quick Deliveries FROM STOCK



SHALLCROSS

DECADE *Resistance* BOXES

36 STANDARD TYPES
FROM WHICH TO CHOOSE!

TYPE	DIALS	OHM STEPS	TOTAL RESISTANCE—OHMS	PRICE
542	1	0.01	0.1	$29.00
543	1	0.1	1	22.00
544	1	1	10	22.00
545	1	10	100	22.00
546	1	100	1,000	22.00
547	1	1,000	10,000	24.00
548	1	10,000	100,000	26.00
549	1	100,000	1,000,000	36.00
550	1	1,000,000	10,000,000	66.00
840	2	0.1	11	34.50
841	2	1	110	40.00
842	2	10	1,100	40.00
843	2	100	11,000	40.00
844	2	1,000	110,000	45.00
817	3	0.01	11.1	60.00
818	3	0.1	111	51.00
820	3	1	1,110	56.00
821	3	10	11,100	60.00
822	3	100	111,000	63.00
823	3	1,000	1,110,000	77.00
824	3	10,000	11,100,000	120.00
817-A	4	0.01	111.1	75.00
819	4	0.1	1,111	71.00
825	4	1	11,110	77.00
826	4	10	111,100	79.00
827	4	100	1,111,000	92.00
828	4	1,000	11,110,000	139.00
817-B	5	0.01	1,111.1	94.00
8285	5	0.1	11,111	94.00
829	5	1	111,110	101.00
830	5	10	1,111,100	113.00
831	5	100	11,111,000	155.00
817-C	6	0.01	11,111.1	105.00
8315	6	0.1	111,111	109.00
832	6	1	1,111,110	121.00
833	6	10	11,111,100	169.00

ACCURACY OF INDIVIDUAL RESISTORS:
0.01 ohm 5%, 0.1 ohm 1%, 1.0 ohm 0.25%, All Others 0.1%

SHALLCROSS MANUFACTURING COMPANY
522 Pusey Avenue, Collingdale, Pa.

ciple of electrostatic deflection cathode-ray indicators in cooperation with a system of electrodes that provide operating conditions similar to a sharp-cutoff pentode.

Indicating tubes of this general type have been seen on counting instruments. The problem of the earlier devices has been a lack of definition of the beam clearly to indicate its position. This deficiency results from peripheral electrons, due to secondary emission, that are caused to bounce from electrode structures. They create a glow on the fluorescent indicating surface where none is intended. Additionally, shadows of the grid structures fall upon the indicating screen.

It is the purpose of the Rodenhuis invention to eliminate this condition by generating a ribbon-shaped beam. This beam is made to pass wholly or in part through a deflection system and a system of electrodes so positioned that the beam is focused directly in the plane of a slotted screen. It produces thereon a sharply defined image of the beam position.

In Fig. 1 the arrangement of the suppressor and slotted screen



FIG. 1—Side view (A) and cross-section (B) of ribbon-beam c-r tube

is such that the suppressor grid is held at a potential to collect secondary electrons emitted from the slotted screen. The control grid is similar in construction to the suppressor and is arranged so that its wires are located in the shadow of those of the suppressor grid.

The anode structure is perfo-

For the new pneumatic instrumentation

Cabled Tube

The recent tremendous increase in the use of tube instead of wires for instrumentation and control purposes has led to an important new development—cabled tube. This is an armored group of long tubes twisted together to permit bending without distortion. An insulating tape is wrapped over the bundle of tubes to prevent electrolytic action. Then interlocking, flexible galvanized steel armor is applied, like BX. This protects the tubes from injury during shipment, storage, installation, and in service. Standard fittings, boxes and cabinets can be used for junction boxes and terminations. To make it possible to readily identify each tube, one tube in each layer is colored; the position of each tube in each layer in relation to the coded tube



remains the same throughout the length of the cable.

The tubes usually are copper, but aluminum tubes can be used for special purposes. For unusually corrosive situations, a plastic outer sheath can be applied. As many as 19 tubes, ¼" OD, can be cabled, and supplied in lengths up to 1,000 ft.



Showing the construction of Crescent Armored Multitube, made by Crescent Insulated Wire and Cable Co., Trenton 5, N. J., which will supply further information on request.

Since the tubes carry not electricity but air, nitrogen, helium, or a fluid, they are especially attractive in potentially explosive locations, as in refineries and chemical plants. Utilities are also turning decisively to this new cable, while automatic process control (automation) is a rising application.



Revere, as a supplier of tube for this purpose, calls this cabled tube development to your attention as a matter of general and perhaps specific interest. See Revere for copper, aluminum and brass tube and pipe, electric welded steel tube, and lockseam tube. Call the nearest Sales Office.

REVERE

COPPER AND BRASS INCORPORATED

Founded by Paul Revere in 1801

230 Park Avenue, New York 17, New York

Mills: Baltimore, Md.; Chicago and Clinton, Ill.; Detroit, Mich.; Los Angeles and Riverside, Calif.; New Bedford, Mass.; Rome, N. Y. Sales Offices in Principal Cities, Distributors Everywhere

See "Meet the Press" on NBC Television, Sundays

To solve your specific potentiometer problem, send an outline of your specs to Gamewell. You'll get prompt service on your order for a prototype to meet your requirements.

Linear and non-linear Gamewell Precision Potentiometers are described in the booklet shown below. We'll be glad to send you a copy.

THE GAMEWELL COMPANY
NEWTON UPPER FALLS 64, MASSACHUSETTS
In Canada: Northern Electric Co., Ltd., Belleville, Ont.



GAMEWELL®
PRECISION POTENTIOMETERS

Manufacturers of precision electrical equipment since 1855

rated and the perforations are covered with a gauze. Only 8 to 10 percent of the beam current passes through the gauze to the fluorescent screen past the post-acceleration electrode. The transparent tin-oxide coated layer on the screen is at the same potential as the post-acceleration electrode.

External tube masks are provided with numeral cutouts. The tube may be operated with deflection and control signals to position the beam at any instant for a numeral correspondence with the control signal. The luminescence of the screen is maintained optically uniform as a result of the positioning of the control-grid structure.

Magnetic-Field Detector

A "Device for Detecting or Measuring Magnetic Fields" is the subject of U. S. patent 2,642,479 granted Jack Weir Jones of Chester, Pa., and assigned to the Sun Oil Co., of Philadelphia, Pa. The invention is designed to detect extremely small magnetic leakage fields.

In oil pipelines magnetized scrapers and other devices are



FIG. 2—Saturable reactor pickup device used in pipe-line maintenance

FOR APPLICATIONS IN RADAR, TELEMETERING, DIGITAL COMPUTING, TELEVISION, NUCLEAR PHYSICS



Flip-Flop, Type 1101C—another of the basic elements in Burroughs' integrated line of "Unitized" Pulse Control Equipment.

"Unitized" Pulse Control Equipment

saves time and money in electronic engineering

There's no longer any need to tie up engineering personnel with the time-consuming work of developing and "breadboarding" electronic test circuits. Burroughs, a leader in the office machine industry, now offers an integrated line of "Unitized" Pulse Control equipment covering all the basic functions in pulse circuit engineering. These one-basic-function units are designed with a maximum of flexibility to be used as building blocks for test systems ranging from the very simple to the most complex. Engineers need only make a block diagram of the apparatus needed, assemble the necessary Burroughs units in the plug-in rack, and interconnect them with the various standard coaxial cables and accessories. It's really that easy! It's equally easy to reassemble your units for a different project when your present tests are completed.

YOU SIMPLY "PLUG IN" BURROUGHS FLIP-FLOPS

Burroughs Flip-Flop, Type 1101C, demonstrates the one-basic-function principle that makes Burroughs "Unitized" Equipment so suitable for your needs.

This flip-flop is a bistable circuit designed specifically to provide an output gating voltage to be used in coincidence circuits. The unit contains a pentode Eccles-Jordan circuit capable of being switched at rates up to 2.5 megacycles per second, with 0.1 microsecond pulses.

There are three inputs—Zero, One and Complement—operating from pulse amplitudes of 12 volts or more. Coaxial output jacks marked "Zero Gate" and "One Gate" supply either 0 volts or -23 volts at an impedence level of approximately 680 ohms.

Two neon lights on the front of the panel indicate the position of the flip-flop. A terminal block on the rear of the unit can be used to operate indicator lights installed at a remote point for visual monitoring.

Proved by more than two years of constant use, Burroughs "Unitized" Pulse Control equipment has been purchased by many leading electronic research organizations. Some of the users are: Massachusetts Institute of Technology, University of Michigan, Stanford Research Institute and National Union Radio Corporation.

Scale-of-Four Binary Counter Using Burroughs "Unitized" Equipment



The left flip-flop, Type 1101C, changes state with each input pulse, so that the left coincidence detector (CD) or gate, Type 1201B, is alternately opened and closed with succeeding input pulses, with the result that every other input pulse passes through the left coincidence detector, giving a count of 2. A similar flip-flop and gate combination cascaded to the first combination gives a total scale of 2 x 2=4. The number of flip-flop and coincidence detector combinations that can be cascaded is unlimited.

For full information on Burroughs "Unitized" Pulse Control Equipment, write or call Department 12E, Electronic Instruments Division, Burroughs Corporation, 511 N. Broad St., Philadelphia 23, Pa.

PULSE GENERATORS
COINCIDENCE DETECTORS
PULSE DELAYS
FLIP-FLOPS
PULSE GATERS
CHANNEL SELECTORS
MIXERS

ELECTRONIC INSTRUMENTS DIVISION

Burroughs

THE BEST KNOWN NAME IN OFFICE MACHINES

Want more information? Use post card on last page.



For Precision Electrical Parts Made of Teflon*, Kel-F‡, Nylon, or Polythene . . .

SEND YOUR INQUIRIES TO GARLOCK

The Garlock Packing Company, manufacturers of mechanical packings since 1887, places at your disposal a completely-equipped, modern plastics plant under expert technical supervision. Our complete facilities enable us to mold, extrude, machine or otherwise fabricate (from powder) electrical parts to the same high quality standards to which Garlock has rigidly adhered for over 65 years.

Garlock, therefore, invites your inquiries on:

1. **Finished Electrical Parts**—molded or machined—of Teflon, Kel-F, Nylon or Polythene.
2. **Teflon Tape**—Electrical grade—pretested for dielectric fault (maximum 85 per 100 feet of 0.005″ tape).

SHEETS, TUBES, SLEEVES AND OTHER SHAPES AVAILABLE IN TEFLON OR KEL-F

For fabricators of finished parts, Garlock can furnish Teflon and Kel-F in sheets, tubes, sleeves and a wide variety of other shapes. Teflon sheets can be supplied in sizes as large as 48″ square; Kel-F sheets and discs as large as 48″ diameter.

Mail Your Inquiries to Dept. 34, Palmyra, N. Y., or contact one of our branch offices shown below and a Garlock representative will call.

THE GARLOCK PACKING COMPANY, PALMYRA, NEW YORK

Branch Offices: Baltimore, Birmingham, Boston, Buffalo, Chicago, Cincinnati, Cleveland, Denver, Detroit, Houston, Los Angeles, New Orleans, New York City, Philadelphia, Pittsburgh, Portland (Ore.), Salt Lake City, San Francisco, St. Louis, Seattle, Spokane, Tulsa.

In Canada: The Garlock Packing Co. of Canada Ltd., Toronto, Ont.
Branch Offices: Calgary, Hamilton, Montreal, Vancouver, Winnipeg

*du Pont's trademark for its tetrafluorethylene resin
‡Registered trademark for M. W. Kellogg Company's trifluorochloroethylene polymers

GARLOCK — MANUFACTURERS OF MECHANICAL PACKINGS SINCE 1887

allowed to move through the lines with oil flow. Pipelines are steel and only a very small magnetic field can leak to the outside. The magnetometer, or gradiometer of this invention includes the induction pickup shown in Fig. 2. The arrangement of the two coils is such that a pipe inspector can carry the assembly over the pipe line. When one of the magnetized devices passes through the pipe line the faint magnetic field induces a potential in the saturable reactor coils.

The circuit of the magnetometer is shown in Fig. 3. An oscillator



FIG. 3—Combined diagram of oil-pipeline scraper magnetic detector

applies potential at some predetermined frequency to the saturable reactors mounted in the pickup assembly. Both reactors are saturated. Assuming a zero gradient of the external magnetic field, the output wave of the reactors to a detector will be as



FIG. 4—Output wave of saturable reactors to a detector

PRATT & WHITNEY AIRCRAFT ANALYZES SOUNDS AND VIBRATIONS

360 TIMES FASTER

WITH

PANORAMIC SONIC ANALYZER LP-1



Engaged in operations which demand maximum efficiency, Pratt & Whitney Aircraft has chosen the Panoramic Sonic Analyzer LP-1 to speed up and simplify sound and vibration analysis. The results of this careful selection are outlined in the Pratt & Whitney Aircraft report. The facts presented there speak for themselves.

In only one second, the LP-1 automatically visualizes on a Cathode Ray Tube the frequency and magnitude of sound and vibration components between 40 and 20,000 cps. The LP-1 is therefore an invaluable tool for analyzing random as well as steady phenomena. Special control features allow selection and magnification of narrow bands for detailed examination. Panoramic presentations are simple. They are readily interpreted by technical and non-technical personnel.

Whatever your problem ... sound, vibration, or general spectrum analysis in the laboratory or on the production line, join the many top-flight manufacturing, research, and development activities which have increased their efficiency through the use of instruments made by Panoramic, the leader.

Report from
PRATT & WHITNEY AIRCRAFT

The Panoramic Sonic Analyzer Model LP-1 is being used by Pratt & Whitney Aircraft for analyzing spectra of pressure, vibration and noise measurements. It is found that records can be obtained in one minute that would take six hours by previously used methods. It is possible, therefore, to evaluate developmental changes more rapidly and to make more thorough analyses of available data.

The instrument is usually used with a Polaroid Land Camera for analyzing data recorded on tape recorders. For more immediate results visual analysis is used while the engine is operating and the more interesting points are then photographed.

- Operate with microphones, vibration pickups and other transducers.
- Presents data graphically permitting rapid, direct readings of frequency and voltage.
- Data can be easily photographed or recorded.
- Linear and log voltage calibrations.
- Simple operation.

the pioneer is the leader

PANORAMIC
RADIO PRODUCTS, INC.

WRITE FOR COMPLETE DETAILS, PRICES AND DELIVERY TODAY.

10 SOUTH SECOND AVE., MOUNT VERNON, N. Y. Phone: MOunt Vernon 4-3970

Screen Room Filters





BETTER BY FAR BY SPRAGUE

The power lines entering your screen room must be r-f free or else the efficiency of your shielded enclosure is greatly reduced.

Sprague engineers, long experienced in the manufacture of radio noise filters for all applications, have developed numerous types specifically for shielded enclosures. A typical installation is shown at right. Note that each filter is provided with a shielded end cap adaptable to most screen room power panels.

Perhaps we can help you improve the performance of your screen room. Write Sprague Electric Co., 35 Marshall Street, North Adams, Massachusetts for further information on modern, high-attenuation filters for screen rooms.

Sprague, on request, will provide you with complete application engineering service for optimum results in the use of radio noise filters.

YOU CAN DEPEND ON

SPRAGUE

shown in curve *A* of Fig. 4. The peaks are odd harmonics due to unbalance of the coils and their saturated condition. A true balance would give zero output.

The existence of a magnetic field in the vicinity of the reactors induces even harmonics that appear at the peaks. Curve *B* shows this condition as a result of a positive gradient in the magnetic field. Positive peaks are increased and negative peaks are reduced. A negative gradient results in curve *C*, in which positive peaks are reduced and negative peaks increased. The remainder of the circuit is essentially a peak voltmeter serving as a measuring device for the gradient. The meter is calibrated by measure of known gradients.

Variations in the oscillator are prevented from affecting the system by an interconnection of the grid leaks of the oscillator tubes and the detector. A change in oscillator amplitude is accompanied by a bias change that adjusts the sensitivity of the detector in a compensatory fashion.

The detector output operates a meter device so arranged that at certain amplitudes of the meter movement, in response to the gradient detected, there is provided an audible output signal while lower levels are disregarded.

A recorder may be included in the circuit when actual levels are to be recorded.

Control Bridge

Patent 2,642,228 was recently granted to George A. F. Machlet of Elizabeth, N. J., for "Pulsing Electronic Measuring and Control Apparatus."

The patent discloses several circuits for use in control equipment where the element of control is some variation in the operating conditions. Changes in magnitude, pressure, temperature, current or voltage are among those shown as useful for the circuits of the invention.

The circuit of Fig. 5 is one of those for electronic measurement and proportioning control. The initial balance condition of the bridge circuit is set by a control factor as it varies above and below

Here's a completely new Film-Type Resistor

More rugged! More stable!

If you're looking for a resistor with unusually high electrical stability, here's your answer—Corning Resistors.

The film material is entirely new for resistors. Fired in at red heat, it makes an integral contact with the heat-resistant base to form a tough bond. The result is a rugged unit with exceptional stability, and capable of withstanding high ambient, high operating temperatures.

The resistive element of Corning Resistors is so stable it can be cycled from near absolute zero to red heat without impairing its electrical properties. Fired-in silver bands afford low resistance, low noise terminations.

The mechanical strength of Corning Resistors makes usual handling precautions unnecessary, lowers assembly costs. Mass-produced on automatic machinery, prices are practical. If you use resistors, you can't afford to overlook this important new development. The coupon will bring the information you need. Mail it today!

For maximum precision—Corning Type N Resistors—Where accuracy is important, Corning Type N Resistors have a resistance tolerance of 1%—are ideal for use in critical, low tolerance circuits and high frequency applications. Can be operated at ambient temperatures up to 140° C.

Specifications—Corning Type N Resistors

Power Rating	SIZE *Length*	SIZE *Diameter*	RESISTANCE *Min. (ohms)*	RESISTANCE *Max. (ohms)*
½ Watt	19/32"	11/64"	10	10,000
1	15/16"	19/64"	10	40,000
2	2 1/16"	19/64"	20	100,000

For high temperature operation—Corning Type S Resistors

Capable of operating at ambient temperatures up to 200° C., Corning Type S Resistors have an unusually low temperature coefficient of resistance. They operate at higher power levels—afford important space savings. Thin film construction and inherent stability provide excellent high frequency characteristics. Normal resistance tolerance is 2%.

Specifications—Corning Type S Resistors

Power Rating	SIZE *Length*	SIZE *Diameter*	RESISTANCE *Min. (ohms)*	RESISTANCE *Max. (ohms)*
1 Watt	19/32"	11/64"	10	10,000
2	15/16"	19/64"	10	40,000
4	2 1/16"	19/64"	20	100,000



Corning Load Resistors

These RF and high frequency load resistors combine high power dissipation with exceptional stability and low inductance. For dummy loads, they can be used with forced air or water cooling. Corning Load Resistors can be furnished with resistive coatings either inside or outside the heat-resistant glass tubing.

Corning Glass Works

New Products Division

Corning means research in Glass

CORNING GLASS WORKS, Dept. E-11, Corning, New York

Please send me information on:

☐ Corning Type N Resistors, ☐ Corning Type S Resistors, ☐ Corning Load Resistors

Name ..... Title .....

Company .....

City ..... Zone ..... State .....

Want more information? Use post card on last page.


Wing blade handle on threaded center shaft for easy connecting and disconnecting. Stronger—the center post is inserted after molding operation.
Watertight and pressurized, note rubber bushings and sealing rings.
Pin and socket barrel assemblies may be replaced in same fitting.
All contacts machined from copper base alloy stock silver-plated. Beryllium spring on socket contacts.
Insulator material type CMG to MIL-P-14 Spec.
Cap and collar removable for easy wiring.
Resilient bushing applies pressure to relief bushing and cable.

Here's why those in the know demand—

CANNON PLUGS

TYPE 2E Sealed Power Connector (Signal Corps numbers U-112/U to U-118/U) is typical of Cannon's foresighted engineering to do a better job. The 2E Series is designed for heavy duty service on Signal Corps power units for audio equipment.

Features:

a. Longer contact engaging length.
b. Thicker inserts of greater tensile strength to reduce breakage.
c. Closed entry socket contacts.
d. Special sealing rings which do not require sealing compound or gaskets.
e. Efficient neoprene clamp gland.

Manufactured in accordance with Specification MIL-C-1252 (Sig. C) the 2E Series Plug has cable clamping provision from 0.205 to 0.770 inclusive. Quick connect and disconnect are accomplished by a wing handle and threaded center screw that can be operated by gloved hands in extreme climatic conditions. Two shell sizes accommodate four insert arrangements of 4, 9, and 19 contacts. Watertight and pressurized, with rugged construction, Cannon's 2E Sealed Power Connectors are built for long life and trouble-free service and are adaptable to industrial application. Write for Advance Bulletin No. 2E-1.



CANNON ELECTRIC

Since 1915

CANNON ELECTRIC COMPANY, LOS ANGELES 31, CALIFORNIA

Factories in Los Angeles; New Haven; Toronto, Canada; London, England. Representatives in principal cities. Address inquiries to Cannon Electric Company Dept. L-120, Los Angeles 31, California.

a desired value. The primary control here is in the illumination of the photocells by the light from the mirror galvanometer. The galvanometer is actuated by the output current from a thermocouple that is inserted into a crucible whose operating temperature is to be controlled.



FIG. 5—Primary control depends upon illumination of photocells by galvonometer mirror

Two arms of the bridge are photocells. The other two are heater resistances. The diagonal resistance biases the triode grid negatively by the drop in the heater voltage during balance. With this bias the triode plate relay is not energized sufficiently to close the contacts, which in turn control the crucible heater relay.

Unbalance of the bridge by change in temperature in the crucible, resulting in movement of the galvanometer mirror to change the illumination of the photocells, increases triode plate current, closing the plate relay, which applies current to the crucible heater. The inventor claims his control system is fail-safe because current will not be supplied to the crucible heater by failure of the light source or other elements of the control system. Unbalance of the bridge makes the grid bias on the triode less negative.

A thermal switch is also energized when the triode plate relay is energized. The thermal switch energizes the network that heats the bridge arm resistors and the thermal-switch-controlled heaters. The crucible heats up very slowly and the rebalancing resistors arrive at maximum temperature long before the crucible reaches



twenty times *tested!*

hermetically sealed transistors

TWICE SIZE →



EVERY Texas Instruments grown junction and point contact transistor must pass more than 20 tests—in addition to continual visual checks—before it is granted the TI trademark and shipped to the user.

Texas Instruments inspects *all* transistors *all along* the manufacturing process. This 100% inspection insures that the completed product will adhere closely to published specifications (see distribution curves at lower right).

All TI transistors have moisture-proof glass-to-metal hermetic sealing. And they are *all* aged a minimum of *24 hours* at rated output as a positive operating double-check.

If *you* want transistors of this insured high quality, they are now available from Texas Instruments Incorporated. Write for new junction transistor bulletin DL-S 310.

ELECTRICAL DATA

	n-p-n Junction	
RATINGS, RECOMMENDED MAXIMUM:	**Type 200**	**Type 201**
Collector Voltage	30 volts	30 volts
Collector Current	5 ma.	5 ma.
Collector Dissipation (at 30°C)	50 mw.	50 mw.
Ambient Temperature	50°C	50°C
AVERAGE CHARACTERISTICS (at 30°C):		
Collector Voltage	5 volts	5 volts
Emitter Current	−1 ma.	−1 ma.
Collector Resistance (minimum)	0.2 megohms	0.4 megohms
Base Resistance	150 ohms	150 ohms
Emitter Resistance	30 ohms	30 ohms
Current Amplification Factor (minimum)	0.90	0.95
Collector Cut-Off Current	10 μa	10 μa
Collector Capacitance	12 $\mu\mu$fd.	12 $\mu\mu$fd.
Noise Factor (average value)	22 db.	22 db.


STATISTICAL DISTRIBUTION CURVES
Based on 250 Type 200 Transistors
Emitter Resistance (Ω)
Base Resistance (Ω)
Collector Resistance (Ω)
PERCENT OF UNITS AT OR BELOW ABSCISSA VALUE
RESISTANCE IN OHMS
RESISTANCE IN MEGOHMS

TEXAS INSTRUMENTS
INCORPORATED
6000 LEMMON AVENUE DALLAS 9 TEXAS

COLLINS uses a *Jennings*
MINIATURIZED VACUUM CAPACITOR
TO OBTAIN A 7 TO 1000 MMFD. RANGE
WITHIN A LIMITED SPACE

Jennings RADIO

COLLINS NEW 180L-2, THE FIRST CONSTANTLY MONITORED AUTOMATIC ANTENNA TUNING UNIT, IS USED OVER THE FULL MHF FREQUENCY RANGE IN ALL TYPES OF AIRCRAFT WITHOUT MANUAL ADJUSTMENT.

Capacitor Problems Solved
Ad No. 9 in a Series

A major design goal in this Automatic Antenna Tuning Unit was *interchangeability* with the 180 K-3 Antenna Matching Network. This space limitation was solved in part by using a standard **JENNINGS UCSL, 7 to 1000 MMFD., 3 KV, 30 AMP. VARIABLE VACUUM CAPACITOR,** modified to permit a rack-and-pinion drive for the actuating mechanism. The capacitor selected is only 5 ⅛ inches long and 3 ⅛ inches in diameter.

Have you a design problem involving limited space or wide capacity range—or both?

Write us for information regarding your own Capacitor problem. Literature mailed on request.

JENNINGS RADIO MANUFACTURING CORPORATION · 970 McLAUGHLIN AVE.
P.O. BOX 1278 · SAN JOSE 8, CALIFORNIA

the required temperature. The resistance of the heated resistor will not rebalance the bridge so far from balance because the photocell illumination is widely off balance.

For all practical purposes the reset resistance (R_1) on the upper left of the bridge is inoperative during the heating of the crucible because the thermal switch contacts are initially open. Transitory closing of the switch merely increases the unbalance when it occurs before the thermal switch is saturated—at a time when there is illumination unbalance of the bridge, at low crucible temperature. The contacts are opened again when the thermal switch is saturated and the reset arm cools down to room temperature before the desired crucible temperature is reached.

At the desired temperature the bridge is balanced. In this condition the lower reset resistance (R_2) is heated to maximum and the upper reset resistance (R_1) is cool. The plate current of the tube drops below relay pull-in value and the system remains in equilibrium as long as the temperature is that desired.

In other circuits shown in the invention disclosure the thermal switch and galvanometer bridge



FIG. 8—Remote oil-burner control uses r-f carrier on power line

in 1908

Nichrome*

made electric heat possible!

since then...
The Standard of Quality for Electrical Alloys

When Driver-Harris introduced Nichrome* in 1908, *dependable* electric heat became possible for the first time. And with each passing year, Nichrome looms larger as the *ideal* alloy for producing electric heat in domestic and industrial equipment.

Its consistent dependability and unique performance have earned it a world-wide reputation—and made it *the* standard of quality for electrical alloys. That's why today, the great majority of heating elements of all types—in applications ranging from electrical home appliances to large industrial furnaces—are made of this excellent alloy.

Naturally, we take particular pride in our trademark: Nichrome—granted solely and wholly to us by the United States Patent Office forty-five years ago. Representing a series of superb heating and resistance alloys, developed and produced *only* by Driver-Harris, this trademark symbolizes *long life* and *trouble-free* operation to manufacturers everywhere.

Sole producer of Nichrome®, Advance®, Karma® and over 80 other alloys for the electrical, electronic and heat-treating industries.

*T.M. Registered in United States Patent Office by Driver-Harris Company August, 1908

SPECIAL PURPOSE ALLOYS SINCE 1899 — D/H — TRADE MARK REG. U. S. PAT. OFF.

Driver-Harris Company

HARRISON, NEW JERSEY

BRANCHES: Chicago, Detroit, Cleveland, Los Angeles, San Francisco

Manufactured and sold in Canada by The B. GREENING WIRE COMPANY, LTD., Hamilton, Ontario, Canada

Factories: U.S.A., CANADA, ENGLAND, IRELAND, FRANCE, ITALY, SPAIN Representatives in 38 COUNTRIES

MAKERS OF THE MOST COMPLETE LINE OF ELECTRIC HEATING, RESISTANCE AND ELECTRONIC ALLOYS IN THE WORLD

Blank Spaces?

RELAX!

☐ Having trouble with blank spaces on your production line because deliveries of electrical insulating materials are delayed ?

☐ Or blank spaces on specification sheets because there doesn't seem to be an insulation that meets the job's requirements ?

☐ Or blank spaces on your list of insulation sources because you can't find anyone willing and able to help you solve problems on a particular application ?

Then relax and let IMC® eliminate those blank spaces

IMC specializes in electrical insulation. It manufactures and distributes nearly every conceivable type of insulation used in electrical and electronic equipment and components. Stocks are carried to tide you over in emergencies.

It is almost certain that IMC can supply the part or material you need, or will know how to develop it for you. So phone or write your nearest IMC office today. Perhaps IMC can help you prevent as well as cure those blank space problems.

Ask for Literature and Products List

INSULATION MANUFACTURERS CORPORATION

ELECTRICAL IMC INSULATION

*CHICAGO 6	*CLEVELAND 14	DAYTON 2	MILWAUKEE 2	PITTSBURGH 22
111 W. Washington Blvd. Phone CEntral 6-7330	1231 Superior Ave., N. E. Phone SUperior 1-2310	120 W. Second St. Phone Michigan 1201	312 E. Wisconsin Ave. Phone DAly 8-5200	535 Smithfield Street Phone GRant 1-7100

— AUTHORIZED REPRESENTATIVES —

*CHICAGO 6	DETROIT 2	*MINNEAPOLIS 3	PEORIA
Complete Roofing Mfg. Co. Inc. 100 S. Jefferson St. Phone CEntral 6-5300	Harry E. Brothers 15 Leverette Ave. Phone TUxedo 8-2577	H. A. Holden, Inc. 1300 Harmon Place Phone Geneva 5353	W. C. Johnson 101 Reinz Court Phone 7-7706

*LOCAL STOCKS AVAILABLE AT THESE LOCATIONS

arrangement are replaced with a cold resistance balanced bridge. The triode is replaced with a multigrid tube like the 6L7 with the bridge in one control grid and a control pulse input to another control grid to reset the crucible heater.

In one embodiment the control pulse is derived from an r-f signal impressed on the power line to control the operation of an oil burner heating system some distance away. This is shown in Fig. 6. The control pulse is transmitted when a predetermined coupling between two coils during the oscillation of the r-f circuit results in a plate current in the bridge circuit oscillator. The setting of the coupling is accomplished by a room temperature thermostat.

Testing Bits

R. S. Segsworth of Toronto, Ontario, Canada has been granted U. S. patent 2,642,482 for an "Electronic Bit Tester."

The circuit of the bit tester is



FIG. 7—Bit tester circuit depends upon magnetic loop

Full Data on the new Simplified Recording Potentiometer

Send for your copy!

This booklet unfolds the complete story of the recording potentiometer that has been acclaimed by instrument men everywhere for its unequalled versatility, accuracy, long-term dependability, and its *unit design* which makes servicing so simple and quick.

With fewer components . . . with all assemblies greatly simplified and quickly interchangeable . . . with all adjustments including range changes made quickly on the line . . . with new ruggedness to withstand vibration, shock and usual plant abuse . . . it has set new standards for sustained accuracy, and for economy in servicing and maintenance.

This new WESTON Simplified Recording Potentiometer can be used to measure and record temperature, d-c current, d-c voltage, resistance, a-c voltage, a-c current, speed, speed ratio, power, frequency, hydrogen ion (pH), light intensity or any other quantity that can be converted into electrical values. The whole story is available in this booklet. Send coupon for your copy today. WESTON Electrical Instrument Corporation, 614 Frelinghuysen Avenue, Newark 5, New Jersey.

WESTON

WESTON *Instruments*

4812

WESTON ELECTRICAL INSTRUMENT CORPORATION
614 Frelinghuysen Avenue
Newark 5, New Jersey

Send a copy of the booklet describing the WESTON Simplified Recording Potentiometer to:

NAME_____

ADDRESS_____

CITY_____ ZONE_____ STATE_____

Want more information? Use post card on last page.

shown in Fig. 7. Figure 8 illustrates the principle of the oscillating circuit that is the basis of the invention.

The oscillator operating at relatively low frequency to avoid skin effects is energized and the meter



FIG. 8—Basic oscillator circuit used in bit tester

bias adjusted for zero reading with a test bit of the desired hardness in the circuit. Any deviation from the desired hardness will be apparent by a change in the magnetic loop currents in the oscillator coil cores. A differential voltage will be delivered to the amplifier voltmeter circuit (go-no-go indicator). Lower output readings will be observed for softer-than-standard bits and a higher reading for harder-than-standard bits.

Some interesting precautionary procedures are described in the patent to make certain that the circuit operates under all desired conditions. The core in the tapped coil is movable. When the bit is placed on the core, the core is depressed against a pole piece that both closes the magnetic loop to the secondary coil and shorts a bias resistor in the oscillating circuit to operate a relay whose contacts insert the appropriate bias resistances into both oscillator and amplifier circuits. A momentary switch is provided to restart oscillation should it cease.

The circuit is selectively adjustable even to the point of accounting for imperfect contact of the bit and core. To test under imperfect contact conditions thin paper or other insulating (nonmagnetic) material is inserted between the bit and core to similate the imperfect contact and prevent re-

SOLID BRASS ELECTRONIC HARDWARE AND FITTINGS

for Industrial and Marine Applications

Precision machined from solid brass . . . plated to your requirements.

Spherical seat (ball and cone type). RF fittings including ferrules, adapters, couplings, nuts; receptacles, etc. Made in accordance with BuShips drawing RE-49A-501A for use with flexible metal hose, conduit, tubing, etc.

Rapid delivery on standard or special sizes. Let's discuss your needs! Write or phone, today.

HARDWARE DIVISION

HOPKINS Engineering Co

FACTORY: 2082 Lincoln Ave. Altadena, Calif. *Sycamore 8-1185*
Offices in WASHINGTON, D. C. and DETROIT

Want more information? Use post card on last page.

4 mmf/ft

AIR-SPACED ARTICULATED

CO-AX CABLES

offer a unique combination of

✔ FRACTIONAL CAPACITANCE
✔ HIGH IMPEDANCE
✔ MINIMUM ATTENUATION

ALONG WITH

✔ EXCEPTIONAL FLEXIBILITY
✔ LIGHT WEIGHT

38 STOCK TYPES

FOR ANY OF YOUR STANDARD OR SPECIAL APPLICATIONS

A few of the very low capacitance types are:

Type No.	*Capacitance μμ F/ft.*	*Impedance ohms*	*O.D.*
C.44	4.1	252	1.03"
C.4	4.6	229	1.03"
C.33	4.8	220	0.64"
C.3	5.4	197	0.64"
C.22	5.5	184	0.44"
C.2	6.3	171	0.44"
C.11	6.3	173	0.36"
C.1	7.3	150	0.36"

WE ARE SPECIALLY ORGANIZED TO HANDLE DIRECT ORDERS OR ENQUIRIES FROM OVERSEAS

SPOT DELIVERIES FOR U.S.

BILLED IN DOLLARS—SETTLEMENT BY YOUR CHECK

CABLE OR AIRMAIL TODAY

TRANSRADIO LTD.

CONTRACTORS TO H.M. GOVERNMENT

138A CROMWELL RD., LONDON, S.W.7 ENGLAND

CABLES: TRANSRAD LONDON

Want more information? Use post card on last page.

want it LIGHT? COMPLEX? *Fast?*

One typical DV Development

Elimination of 50 per cent of the weight of an antenna reflector has been made possible by this DV production development. Glass cloth is plastic impregnated and metal sprayed to form the front and back skins. These are then laminated with aluminum honeycomb to complete the reflector illustrated.

tell it to DV

Years of specialization as an integrated design-through-production engineering group has taught the Dalmo Victor staff a lot about complex, lightweight, electromechanical systems. Lightweight radar reflectors, shaped and welded magnesium waveguide, and fluid magnetic clutches are just a few of the individual system components to come out of Dalmo Victor engineering ideas.

Why not explore the possibilities of bringing this experience to bear on a rapid solution of your engineering and production problems?

DALMO VICTOR
SAN CARLOS · CALIFORNIA

DOWN-TO-EARTH ELECTROMECHANICAL ENGINEERING

Above—RAYDIST automatic plotting board for continuous tracking and plotting of exact location of aircraft or ships.

Below—RAYDIST mobile electronic tracking system; a precision lab. on wheels.



RAYDIST ultra-sensitive electronic tracking systems *demand* optimum precision

that's why they use

CHICAGO TRANSFORMERS

the World's Toughest

HASTINGS Instrument Company, Inc., of Hampton, Virginia, designs and builds RAYDIST—an amazingly sensitive and accurate electronic radio location system. RAYDIST systems are available for air and marine navigation tracking, for marine geophysical surveying,-chartmaking, ship speed trials, hydrography and meteorological studies—for a host of applications requiring infinitely accurate tracking and plotting. Because RAYDIST precision performance is strongly dependent upon the quality of the components used in the systems, HASTINGS specifies and uses CHICAGO MIL-T-27 Sealed-in-Steel Transformers. Wherever optimum precision and absolute dependability are requirements, you'll find CHICAGO—the world's toughest transformers.

H-TYPE
MIL-T-27
Sealed-in-Steel
Transformers



Free CHICAGO Complete Line Catalog

You'll want the full details on *all* CHICAGO Transformers—"Sealed-in-Steel" New Equipment Transformers, MIL-T-27 Transformers, Television Replacement Transformers, General Replacement Transformers and Control and Power Circuit units. Write for your free copy today, or get it from your electronic parts distributor.

CHICAGO STANDARD TRANSFORMER CORP.
3501 W. ADDISON ST., CHICAGO 18, ILL.

Export Sales Div.:
Scheel International, Inc.
4237 N. Lincoln Ave.
Chicago, Ill., U.S.A.
CABLE ADDRESS:
HARSHEEL

jection for this type of production occurrence.

TV Facsimile

A "Television Type Facsimile Transmission System" is the invention of John Hays Hammond Jr., of Gloucester, Mass. The invention is described in U. S. patent 2,642,492.



FIG. 9—TV facsimile system transmitter

In Fig. 9, the transmitter of the facsimile system is shown in interconnecting block form. The news sheet is picked up by the television camera and along with signals of a control generator the image is transmitted in the usual manner. The receiving system in a home is illustrated in Fig. 10. Control signals from the transmitter are received when a clock turns on the



FIG. 10—TV facsimile receiver is turned on by clock (not shown)

How many of these electrical insulation problems do you have?



1. Looking for an efficient coil wrapping for small spaces? EMPIRE® varnished bias-cut nylon tape is highly flexible, strong and efficient . . . makes a thin insulation of unusually high dielectric strength with good resistance to oil and water.



2. Need accurately punched mica stampings for filament, grid and plate supports? MICO produces mica stampings to extremely fine tolerances. Whenever you need precision-fabricated mica parts of the highest quality, call on MICO.



3. Looking for a better material for wiring diagrams, controls, instruments, dials and nameplates? DECORATIVE LAMICOID® resists wear, aging, weathering, oils, corrosive vapors, moisture and temperature extremes. Won't warp, check or chip. Good electrical properties. Wipes clean with a damp cloth.



4. Need a class H segment plate that's easy to work with? ISOMICA* Segment Plate — made of built-up continuous mica sheet — shows no tendency to split or flake. Small segments of heavy thickness may be punched, and larger segments can be accurately sawed, milled, punched, etc.

Whatever electrical insulation material you need — standard or special — class A to class H — MICO makes it best. We manufacture it, cut it to size, or fabricate it to your specification. Send us your blueprints or problems today.

*Trade-mark

1893-1953 60 Years of Leadership in Electrical Insulation

MICA Insulator COMPANY

Schenectady 1, New York

Offices in Principal Cities

LAMICOID ® (Laminated Plastic) • MICANITE ® (Built-up Mica) • EMPIRE ® (Varnished Fabrics and Paper) • FABRICATED MICA • ISOMICA ®

KLEIN
Quality Pliers
SPECIALLY DESIGNED

FOR THE ELECTRONICS INDUSTRY

Now, Klein quality pliers are available in new compact patterns for precision wiring and cutting in confined space. Note, too, the replaceable leaf spring that keeps the plier in open position, ready for work. All are hammer forged from high-grade tool steel, individually fitted, tempered, adjusted and tested—made by plier specialists with a reputation for quality "since 1857."

LONG NOSE PLIER
307-5-½L—Extremely slim pattern ideal for the really tight spots. Jaws are knurled to insure a positive grip.

OBLIQUE CUTTING PLIER—210-5L—For cutting small wires or trimming plastic. Entire length of cutting knives works flush against cutting surface. 5 or 6-inch sizes.

CHAIN NOSE PLIER
317-5L—A full inch smaller than standard pattern. Has a very fine knurl that will not damage soft wire. Also available without knurl.

LIGHTWEIGHT OBLIQUE CUTTING PLIER 209-5—Smaller than 210-5L with an extremely narrow head. Entire length of cutting knives works flush against cutting surface.

TRANSVERSE END CUTTING PLIER
204-6—Useful in precision work where ordinary oblique or end cutters are too bulky. Gives a clean, flush cut

DUCK BILL PLIER
306-5-½—This compact plier has jaws of sufficient width to hold small springs, yet small enough to form wire in confined places.

This Klein Pocket Tool Guide gives full information on all types and sizes of Klein Pliers. A copy will be sent without obligation.

"Since 1857"

ASK YOUR SUPPLIER

Foreign Distributor: International Standard Electric Corp., New York

Mathias KLEIN & Sons
Established 1857 — Chicago, Ill., U.S.A.
1200 BELMONT AVENUE, CHICAGO 18, ILLINOIS

receiver at the appropriate time.

These control signals set the mechanical system in operation. When the facsimile tv signals are received by the kinescope tube in the receiver, they are reflected into a camera box that photographs the pages at predetermined intervals and sends the exposed film or facsimile paper through a processing chamber where the images are developed and passed to the outside. The sheets may be torn off and read at leisure.

Hammond proposes that the system be placed in operation by a clock set for an early morning hour and when the owner of the tv-facsimile system awakes the facsimile newspaper will be awaiting him.



FIG. 11—Transmitter control (A) delivers starting and control tones, while discriminator detector (B) is located at receiver

Control circuits are shown in Fig. 11. The first is the transmitter control generator that delivers the starting and control tone to be transmitted. The second is the receiver control signal detector. This is a discriminator circuit to develop a direct voltage. Operation of a solenoid controls the receiver as shown in Fig. 10. Each operation of the receiver control solenoid permits one picture to be taken and initiates the operations of the mechanism of the processing chamber.

Mechanical Vibrator

A structure built to create a



The tape and parts pictured indicate R/M's versatility in Teflon manufacture

R/M Teflon*

gives you the plus of R/M's unmatched skill, experience, facilities

*Du Pont's trade-mark for its tetrafluoroethylene resin.

Teflon is probably the most important development of the Age of Plastics—its possibilities look endless. Parts made from it are accomplishing things long considered impossible by engineers in the electronics and electrical manufacturing fields.

If you have a problem to be solved, the chances are that R/M, with its unmatched skill, experience and facilities, can solve it. We approach every challenge with the view that nothing is impossible until proved otherwise.

You can rely on R/M for three things: dependable source for Teflon rods, tubes, sheets or tape; fabrication of Teflon parts to your specifications; collaboration in the search for new uses to which this remarkable product can be put.

Teflon Properties: High resistance to acids and gases even at high temperatures • Moisture absorption zero • Unaffected by weather • Excellent heat stability up to 500°F. in continuous operation • As tape, leaves no carbon residue along discharge path • High impact resistance • Nonadhesive • Stretches easily Tensile strength 1500-2500 psi

R/M

RAYBESTOS-MANHATTAN, INC.

ASBESTOS TEXTILE DIVISION • MANHEIM, PA.

FACTORIES: Manheim, Pa. • No. Charleston, S.C. • Passaic, N.J. • Neenah, Wis. • Crawfordsville, Ind. • Peterborough, Ontario, Canada

RAYBESTOS-MANHATTAN, INC., Manufacturers of Asbestos Textiles • Teflon Products • Packings • Brake Linings • Brake Blocks Clutch Facings • Fan Belts • Radiator Hose • Rubber Covered Equipment • Mechanical Rubber Products • Abrasive and Diamond Wheels Sintered Metal Products • Bowling Balls

If you could test a Flying Saucer..



...highly sensitive, extremely accurate

Heiland Instruments

would give you the correct answers. The Heiland Research Corporation carries on a constant program of research and development to meet the increasing demand for more sensitive, more accurate test equipment. Today, because of their dependable performance and operation, Heiland instruments are extensively used in aircraft and guided missile flight testing, medical research laboratories and for industrial research.

Heiland
DEPENDABLE
INSTRUMENTS

New Heiland "82-6"
BRIDGE BALANCE
and Strain Indicator...



The Heiland "82-6" Bridge Balance provides a simple, accurate means of calibrating static and dynamic output from resistive type transducers or strain gages, before feeding these phenomena into a recording oscillograph. Static and slowly changing phenomena may be read directly on the highly sensitive output meter.

Write or wire for features and specifications.

New Heiland Model 119
AMPLIFIER SYSTEM



A complete measuring system including Oscillograph, Amplifier and Bridge Balance units. Can be conveniently installed in a standard 19-inch relay rack, or placed side by side on table with equal ease and simplicity. Relay rack mounts are available for all units. Removable shock mount bases are available for installation in moving vehicles, aircraft, etc., where shocks and accelerations are encountered. Housed in a rugged, yet lightweight cast aluminum case finished in attractive silver-gray gloss enamel.

Write or wire for features and specifications.

The Heiland "82-6" Bridge Balance and Model 119 Amplifier System are available for immediate delivery.

Free catalog of other Heiland equipment sent on request.

HEILAND RESEARCH CORPORATION
130 East Fifth Avenue, Denver, Colorado

vibration in paper or other sheet material 160 inches across while fed from a continuous roll utilizes an unusual application of the transformer and E-lamination core.

Patent 2,642,545 was granted to E. W. Smith of Melrose Highlands, Mass. for such an apparatus.

The inventor employs his apparatus for the penetration of moisture into paper sheet during the manufacturing process. He points out that a vibration of $\frac{1}{32}$nd inch in amplitude at 360 cycles involves an acceleration of 500 g. When such forces are applied to paper for an appreciable interval, the water in intimate contact with the paper under the vibration will penetrate the paper.

The mechanism is simple though massive. The vibrator is shown in Fig. 12A, the coil in Fig. 12B and



FIG. 12—Vibrating table (A) is shaken by current in coil (B) shown in cross-section at (C)

a cross-section of the coil applied to the E-lamination core is shown in Fig. 12C. When audio frequencies are applied to the coil in the range from 60 to 500 cycles vibrations are set up in the surface of the structure.

T-W C-R Tube

In patent 2,630,544 granted J. W. Tiley and assigned to Philco Corp, Philadelphia, Pa., there is described a technique for producing a high-intensity spot on cathode-ray tubes although the tube is designed for low-voltage operation.

The traveling-wave tube technique applied to this device is shown in Fig. 13. In the neck of the cathoderay tube a helical structure is inserted with a channel-like construction open to the outer surface of the neck. A coil around the neck

NEW..

Good-ALL

Capacitors

● GOOD-ALL production techniques make it possible for MIFILM capacitors to be available in sizes smaller than other miniaturized brands.

Metal enclosed and hermetically sealed, MIFILM capacitors normally operate between −65°C and +150°C. Insulation resistance 10^{15} ohms. Power factor less than .5%. Sizes from .173" dia. x 21/32" long (.001 mfd, 600 VDC) to .750" dia. x 1⅞" long (1 mfd, 600 VDC). Slightly larger sizes to 1000 VDC.

Your inquiries regarding this revolutionary advance in miniature capacitors are invited. We invite sample orders for your evaluation.

*DUPONT'S TRADEMARK FOR ITS POLYESTER FILM.

★

MIFILM
subminiature
capacitors

★

With MYLAR* plastic dielectric.
Metal enclosed.
Hermetically sealed.

★

Write for complete catalog covering GOOD-ALL MIFILM, MARBELITE and MIRACLE X long life capacitors.

Good-ALL

ELECTRIC MFG. CO.

114 W. FIRST ST. Phone 112-113 OGALLALA, NEBR.

ROBERT A. GOODALL, *President* Cable Address, "GOODALLA"

THE Dependable
BALLANTINE MODEL 300

Famous for

SENSITIVITY
•
ACCURACY
•
STABILITY

VOLTAGE RANGE. . . . . .001v to 100v
FREQUENCY RANGE . . . . . 10 cps to 150 kc
ACCURACY . . . . . 2% ENTIRE RANGE
INPUT IMPEDANCE . . . . . ½ meg shunted by 30 uuf

- Stability insured by the exclusive use of wire-wound resistors in the attenuator and feedback network.
- Same accuracy of reading at *ALL* points on the logarithmic voltage scale and linear decibel scale.
- Only ONE voltage scale to read with decade range switching.
- No "turn-over" discrepancy on unsymmetrical waves.
- Accessories available to extend the range to 20 uv and to 10 kv.
- Provides 70 DB amplifier flat within 1 DB from 10 cps to 150 kc.

Write for further details of this and other Ballantine voltmeters and accessories

BALLANTINE LABORATORIES, INC.
100 FANNY ROAD, BOONTON, NEW JERSEY

energized from a d-c source produces a concentrated magnetic field that acts upon the beam traveling through the neck to keep it centered, adding velocity to the beam in its traverse through the helix and magnetic fields. The velocity gradually increases as it goes toward the screen of the crt.



FIG. 13—Traveling-wave c-r tube gives high-intensity spot

The helix is energized with a high-frequency field. The interaction between the high-frequency field and magnetic field produces acceleration of the beam to a much higher velocity than is experienced with high potential d-c acceleration customarily employed in crt operation. The result is a brighter spot.

Ceramic Klystron

W. W. Eitel and J. A. McCullough are the inventors of a "High-Power Klystron" tube that is distinguished from more familiar tubes by its unique structure. The invention was granted patent 2,629,066 and is assigned to Eitel-McCullough Inc., San Bruno, Calif.

The novel feature of this klystron (Fig. 14) is the construction using ceramic material. The outer walls of the cavities and drift tube, in one embodiment, are ceramic, while the drift tube and cavity



FIG. 14—Ceramic construction of klystron (A) can also take the form (B)



Du Pont "TEFLON" provides high-temperature insulation



Terminals made by
Sealectro Corp.,
New Rochelle, N. Y.

Dielectric properties remain constant over wide temperature range

Standoff and feed-thru insulator terminals often fail in service due to high-temperature breakdown. Cracking frequently occurs during degreasing operations. And breakage may occur during manufacture. Today's equipment and operating conditions require terminals that eliminate these failures and provide improved, lasting performance.

In designing such improved terminals, Sealectro Corporation sought an insulating material that had good dielectric properties, resistance to high operating temperatures and chemical attack, and the toughness and resiliency to eliminate breakage and cracking. And it had to provide for simple, positive installations.

They chose Du Pont "Teflon"* tetrafluoroethylene resin. "Teflon" is an excellent insulator. Its dielectric constant (2.0) and loss factor (0.0005) are unaffected in temperatures from —80°F. to 400°F. Du Pont "Teflon" is inert to all chemicals except molten alkali metals and fluorine. It is tough, durable . . . will not crack or arc. And the one-piece terminals assure simple, tight, lasting installations.

Du Pont "Teflon" serves many uses in electrical equipment—coaxial spacers, insulation for wire, cables and motor windings, and other parts where high temperatures, service, dielectric strength and durability are required. Perhaps it can help you improve or develop a product. For full information, write E. I. du Pont de Nemours & Co. (Inc.), Polychemicals Department, Room 2211T, Du Pont Bldg., Wilmington 98, Delaware.

*REG. U.S. PAT. OFF.

DU PONT
REG. U.S. PAT. OFF.
BETTER THINGS FOR BETTER LIVING
. . . THROUGH CHEMISTRY
Polychemicals
DEPARTMENT
PLASTICS • CHEMICALS

Which Magnecorder best fits your needs?
the PROFESSIONAL TAPE RECORDER
Voyager
The first one-case professional recorder for remotes — rugged, light, reliable. Complete with line level amplifier, $499.50. Other units available with 10 watts of audio from $590.00.
Standard Magnecorder
PT63-AH recorder includes a 3-head assembly for monitoring directly from the tape. PT7-P amplifier provides high level mixing of three channels. $850 complete.
MagneCordette
A professional Magnecorder enclosed in smart blond, mahogany, or black lacquer cabinet, $425.00. Also offered as the new Portable MagneCordette — a complete record-playback-P.A. system in a single carrying case, $499.50.
New Magnecord M-80
Watch for the brilliant new Magnecord M-80 at your dealer's — the finest tape recorder ever built for the price. Features push-button controls, slot loading, 15 kc response at 7½ ips!
PT6-VAH
PT63-AH
PT7-P
PT6-GAH
M-80
Look under "recorders" in the phone book for your dealer's name
Magnecord INC.
225 WEST OHIO ST., CHICAGO 10, ILL., DEPT. E-11

inner walls are coated with metal in a thin layer. In the manner shown in Fig. 14, the inventors have overcome a problem that has stood in the way of designing high-power klystrons. It is conceivable that the device can speed the development of uhf and microwave transmission at higher power levels.

Dual Radar

Those familiar with ppi radar techniques can appreciate the advantages of the "Dual Scanning Antenna Radar System" invented by W. A. Huber and N. T. Volsk. The invention was granted patent 2,627,069, which is assigned to the United States of America, Secretary of War.

During the long period of one rotary sweep in a radar system employing the ppi display, target objects may move a considerable distance. These inventors have devised a dual radar system operating to provide beams going out in two directions each 180 deg opposed to the other. Thus, while the upper part of the radar scope is displaying the reflection from targets in one direction the lower shows reflections from the other direction.



FIG. 15—Dual radar to give better resolution for high-speed targets

The operation of the dual scanning radar system is illustrated in the simplified block diagram of Fig. 15.

The system may be so adjusted that each transmitter-receiver system and its antenna covers a different elevation sector to expand the elevation range of a radar system of the ppi type.

MOLONEY *HiperCore* ELECTRONIC CORES



. . . for Any Electronic Application

Moloney HiperCore Electronic Cores assure better transformer performance because of their advanced wound core design. These wound cores have greater flux carrying capacity and lower losses than other types of cores of comparable sizes. In addition to better performance, a smaller, lighter core is obtained. In electronic applications, where size and weight are critical, Moloney HiperCore Electronic Cores are particularly desireable. Because they are wound cores, savings in assembly time can be favorably reflected in accelerated production. Rigid production control assures cores that test well within industry standards. More than 1000 standard sizes are available and special sizes can be made for specific applications, if desired.



Moloney HiperCore Electronic Cores are wound with grain oriented silicon steel of 1, 2, 4 or 12 mil thicknesses.

Write today for bulletin SR-205 containing specifications, performance data and prices on over 300 stock sizes.

ME 53-17

MOLONEY ELECTRIC COMPANY

Manufacturers of Power Transformers • Distribution Transformers • Load Ratio Control Transformers Step Voltage Regulators • Unit Substations

MOLONEY ELECTRIC = { BETTER PERFORMANCE / GREATER RELIABILITY / LESS MAINTENANCE

SALES OFFICES IN ALL PRINCIPAL CITIES • FACTORIES AT ST. LOUIS, MO. AND TORONTO, ONT., CANADA

Production Techniques

Edited by JOHN MARKUS

Socket Subassembly Turntable.....244
Resistor Capping Machine.....244
Inspecting Molded Tube Bases.....246
Footage-Measuring Coil Winders.....246
Encasing Resistors in Kel-F Sleeves....250
Production-Testing UHF Radiosonde Tubes.....254
Hot-Die Wire Printer.....266
Relay Lineup Fixtures.....268
Plastic Small-Parts Bags.....270
Mica-Punching Press.....272
Soldering Iron Holder Automatically Cuts Voltage.....274
Checking Tolerances Of Components...276
Resistor Lead Straightener.....278
Mica-Splitting Tool.....280
Fixtures Aid Production Of Spiral Coil Filters.....282
Storage In Mason Jars.....288
Staking Hinge Bar For Aircraft Relay..290
Lead-Forming Fixture.....292
Sealing Paper Capacitors.....294

OTHER DEPARTMENTS featured in this issue:

	Page
Electrons At Work	198
New Products	298
Plants and People	412
New Books	453
Backtalk	464

Socket Subassembly Turntable

Method of using turntable to speed training of new workers in Puerto Rico electronic plant making military radio and radar equipment

IN SUBASSEMBLY work on sockets for military radio equipment, a 30-position plywood turntable makes it unnecessary for new workers to remember more than one part or lead at a time. When used in the plant of Caribe Aircraft Radio Corp. in Coamo, Puerto Rico, this training aid rapidly developed the skill of new workers. These workers were soon able to remember as many as 24 different parts and install them in sequence on a single socket without using the turntable, even though they had never before been in a factory.

When using the turntable, the operator first places an empty socket on each of the 30 wood blocks which serve as positioning jigs. She then assembles the first wire on each of the 30 sockets in turn. Next she looks at the finished sample and proceeds to put on the second wire or part in accordance with its position on the sample. This continues until all parts have been assembled, after which the operator solders all connections on each socket in turn.

The wood turntable is cut out of ¾-inch plywood and mounted on ball rollers for easy turning on its center pivot.

Resistor-Capping Machine

TWO AIR CYLINDERS operating in synchronism serve to press metal end caps onto deposited carbon resistors. Although considerable force is employed here to obtain a friction fit that will maintain good contact throughout the life of the resistor without soldering or brazing, fixture construction is sufficiently heavy and precise so that breakage of the brittle ceramic bodies rarely occurs.

The resistors are baked at 300 F both before and after capping. Baking has been found to give a better contact and to stabilize the value of the carbon coating. Even though nowhere near the melting point of the silver plating on the caps, this temperature promotes a type of amalgamation of the silver with the carbon.

The resistor body is placed in the

Removing capped resistor from fixture at air-vise setup, using tweezers having jaws wrapped with adhesive tape to prevent scratching of deposited carbon coating on ceramic body

REMEMBER, MERLIN, WAND WAVING IS STRICTLY HOCUS-POCUS!

Pulling a rabbit out of a hat is fine for entertainment, we agree. But not even a magician can make good on the fantastic claims attributed to cheaper solders, *the mystery alloys with a secret ingredient,* that are supposed to equal the performance of higher tin content solders. Today, as always, Kester believes, the quality of the soldered connection is what counts . . . *not* an infinitesimal saving. That's why Kester Solder has been a "star performer" for more than 50 years!

For your specific solder requirements, remember Kester "44" Resin, "Resin-Five" or Plastic Rosin-Core Solder . . . with exact core size or flux-content "tailored" to every job.

KESTER

SOLDER COMPANY

4204 Wrightwood Avenue, Chicago 39, Illinois
Newark 5, New Jersey • Brantford, Canada

Want more information? Use post card on last page.

Placing resistor body on pedestal of fixture with tweezers having triangular plastic sheets riveted to insides of jaws. Curved grooves in plastic pieces conform to shape of resistor body

grooved center pedestal of the fixture with plastic-lined tweezers to prevent contamination of the coating. The operator next places end caps with attached leads in the recesses of the air cylinder plungers. Operation of the foot valve then brings the plungers together, forcing the caps onto the resistor. This technique is used in the San Juan, Puerto Rico plant of Radell Corp. for their deposited carbon resistors.

Inspecting Molded Tube Bases

Loading tube base upside down onto tapered die of automatic inspecting machine

MOLDED plastic octal bases for tubes are inspected at high speed in a bench press having a six-station dial feed, after staking of pins. The bases are loaded on tapered dies by the operator, and carried by the feed turntable to a ram where a spring-loaded hollow punch applies a 30-pound force.

The punch has an arm that contacts a snap-action switch which is actuated when a part breaks under load, thereby turning on a signal light to warn the operator. She then stops the press and removes the defective part manually.

Parts which pass the test are lifted from the dies by a pickup arm, then blown into a chute by an air blast. About 2,000 parts an hour are inspected with this setup in Sylvania's Warren, Pa. plant.

Footage-Measuring Coil Winders

TO WIND PRECISION wire-wound resistors to very nearly the exact required resistance, from wire that may be as small as No. 52, special motor-driven winders that place a very low stress on the wires and indicate footage rather than turns have been developed by Hycor Co. for use in its Vega Baja, Puerto Rico plant.

Direct operation of a Veeder

Setup for winding precision resistors for computers. Counter mounted on top of winder indicates actual footage rather than turns. Wire is being drawn from spool on shelf of bench

counter by the wire requires appreciable torque, with resulting stretching of the wire. If this occurs, the resulting strain in the wire would produce a resistance change. A resistor that was wound to correct value would then change in value during removal of the strain in subsequent oven heating.

To measure footage, the wire runs over a ball-bearing pulley to which is attached a commutator. This commutator acts in conjunction with a wire brush to give one electrical pulse for each unit length of wire passing over the pulley.

Commutator pulses operate a sensitive d-c relay, using power obtained from a selenium-rectifier power supply. The relay in turn operates the standard 115-v a-c coil of the counter. This arrangement minimizes burning of the delicate commutator contacts.

Because of the strain-minimizing requirements, a number of different



Hermaseal

LET HERMASEAL HELP YOU WITH HEADER AND SEALED RELAY ASSEMBLY PROBLEMS!

Simple or complex, standard or special, Hermaseal makes them all, 2-electrode crystal holder bases, standard octal headers up to 18-terminal headers available in complete range of sizes, styles and patterns. Hermaseal can do the wiring and supply enclosures, with either dry air fill or vacuum-pumped and pressure-filled with dry nitrogen, for relays, transformers, choke coils, etc. Hermaseal hermetically sealed assemblies meet all specifications, are available in wide range of sizes and adaptations to meet specific requirements.



Hermaseal

END CAPS FOR CONDENSERS FIVE STANDARD SIZES TO FIT MOST NEEDS!

When you need Tubular Button End Caps for condensers . . . end caps that must meet *high quality* standards . . . yet cost is a factor . . . and, you need them in a *hurry* . . . call on Hermaseal!

Hermaseal is a top specialist, a pioneer in hermetically sealed terminals, sealed headers and allied parts for the radio-electronics industry.



Hermaseal

HERMASEAL GLASS SEAL TUBES HELP SPEED-UP ASSEMBLY!

You can save time, cut down on rejects because Hermaseal Seal Tubes have metalized ends for easy soldering to end caps. Hermaseal Seal tubes are available in a wide range of stock and special styles and sizes.

Hermaseal **THE HERMASEAL COMPANY, INC.**

ELKHART 10, INDIANA

ONLY THE

Servoscope®

HAS ALL THESE FEATURES

- applicable to both AC carrier and DC servo systems.
- built-in low frequency sine wave generator for obtaining frequency response of DC servo systems.
- built-in electronic sweep with no sweep potentiometer to wear out and require replacement.
- dynamic frequency control range of 200 to 1.

SERVOSCOPE is a versatile, time-saving test instrument for use in the development of all types of Servomechanisms and Process Controls.

Write for bulletin giving complete specifications.

SERVO

CORPORATION OF AMERICA

NEW HYDE PARK, NEW YORK



Three methods of supporting spools for coil winder. Finest wire is drawn directly up from spool standing on end. Friction box arrangement at left is used for heavier wire. Simple shaft mounting at lower right serves for still heavier wire

arrangements for unreeling the spools of resistance alloy wire are employed. The finest wire, which is No. 52 Evanohm nickel-chrome, is pulled directly off one end of the spool. Tangling is prevented by drawing the wire between two loosely clamped felt pads just above the spool. These pads are cemented to the jaws of an ordinary spring-type clothespin that is taped to the strap iron frame screwed to the shelf at the rear of the workbench.

For somewhat heavier wire, around No. 40, the spool is placed on the horizontally mounted shaft of an improvised tension control unit. A metal disc is mounted on this same shaft inside of the housing of the tension box. A knob on the outside permits varying the positions of oiled felt pads that bear against the surface of the disc, to change the amount of friction and thereby change the tension at which the wire is unreeled.

The overhead pulley just above this spool of wire is on an arm that is pivoted about an inch from its opposite end. Two coil springs in series are connected from the rear end of this arm to a fixed point on the base of the tension unit. The heavier of the two springs takes care of large overall variations in wire tension such as occur when

Now available the revolutionary ELECTRO TEC process* for your LARGE SLIP RING ASSEMBLIES

featuring

• LOWER COST • CLOSER TOLERANCES • ONE-PIECE CONSTRUCTION • JEWEL-LIKE FINISH • UNIFORM RING HARDNESS • REDUCED WEIGHT



Now a Complete Service in all sizes of Slip Ring Assemblies

An assembly with 14 concentric, hard silver rings electro deposited into machined plastic blank. Dovetail locks rings in place. Machined blank insures accuracy. Diameter approx. 11", thickness approx. 5/16".

Cylindrical assembly with 25 rings. Three wide rings accommodate large contact area brushes for high current capacity. Length 14", O.D. approx. 5⅞".



An assembly with 30 rings of various widths to accommodate various current requirements. Unit is approx. 4-5/16" long, designed for flange mounting.



Cylinder type assembly approx. 3¾" long with 24 hard silver rings. 1⅛" O.D. with wall thickness less than ¼".

*PATENTS PENDING

ELECTRO TEC is now tooled up, with new expanded facilities for production of large Slip Ring Assemblies to exact customer specification. Sizes range up to 24" in diameter, either cylindrical or disc type.

The exclusive ELECTRO TEC PROCESS*—the electro-deposition of hard silver rings into an accurately machined plastic blank—consistently yields a high degree of dimensional accuracy, excellent concentricity, and a jewel-like ring finish. This process also eliminates expensive tooling and mold charges, frequently lowers costs to 30% of other methods of manufacture. The silver rings are uniformly hard for long life—75-90 Brinell.

ELECTRO TEC one-piece construction precludes dimensional variation due to accumulated errors. The plastic base is fully cured before rings are plated into it, thus preventing separation of base material from the rings.

ELECTRO TEC LARGE SLIP RING Assemblies are widely used in Radar Equipment, Fire Control Systems, Test Tables and many other critical applications. Light weight combined with rugged durability recommends their use in airborne applications.

Every user knows the ELECTRO TEC reputation for quality and superiority in miniature and sub-miniature slip ring assemblies.

Our Engineering Department is available for consultation on any of your slip ring problems without obligation.

ELECTRO TEC CORPORATION

SOUTH HACKENSACK • NEW JERSEY

ELECTRO MECHANICAL

Engineers

For research and development of electro-mechanical radar and computing equipment.

Significant advancements in the fields of airborne radar and fire control systems are requiring further applications of electro-mechanical techniques in the Hughes Radar Laboratory.

The company

Hughes Research and Development Laboratories, located in Southern California, form one of the nation's leading electronics organizations. The Laboratories are presently engaged in the development of advanced electronic systems and devices which are produced by the Hughes manufacturing divisions.

Areas of work

The work calls for devising reliable, maintainable, manufacturable designs for precision equipment developed in the Hughes Radar Laboratory. The equipment consists of mechanical, electronic and microwave devices and systems to be manufactured in quantity. The equipment designs require the use of such advanced techniques as subminiaturization, unitized "plug-in" construction, with emphasis on design for volume production. Knowledge of electronic components, materials, finishes and specifications is useful.

The future

Engineers experienced in the field of electro-mechanical design for production or those interested in entering this field will find outlets for their abilities and imagination in these activity areas. New electro-mechanical techniques are opening new applications for airborne electronic equipment. Hughes engineers will have the full benefit of working experience in these fundamental developments.

Assurance is required that the relocation of the applicant will not cause the disruption of an urgent military project.

Address resume to **Scientific and Engineering Staff**

Hughes

Research and Development Laboratories

Culver City, Los Angeles County, California

Method of using two springs in series at end of pulley arm to equalize both long-term and short-term variations in tension of wire being unreeled

the wire sticks between turns as it comes off the spool, while the lighter and more flexible spring serves to absorb rapid momentary vibrations.

For still heavier wire, around No. 26, a simpler horizontal shaft is used for the wire spool. Two metal bars, supported on a base plate, are fastened to the shelf of the bench. Between one vertical metal support and the flanged cone on the shaft is an oiled felt washer. By changing the setting of a thumbscrew pushing against the other end of the shaft, the friction between the cone and the felt can be varied to control unreeling tension.

Encasing Resistors in Kel-F Sleeves

A HEATED FORMING tool mounted on the end of a vertically clamped soldering iron is used for flaring the ends of thermoplastic sleeves required as additional insulation for deposited carbon resistors in some applications.

The tubing used for this purpose is monodichlorotrichloroethylene, marketed under the trade name of Kel-F. This material comes in long lengths of tubing, and is cut to precisely the required short lengths with an ordinary paper cutter.

Since only relatively low temperature is required for softening this

Hughes Diodes...

A New Standard of Reliability

Reliability in a germanium diode is determined principally by permanent freedom from the two major causes of diode failure—moisture penetration of the diode envelope, and electrical instability under extreme operating conditions.

HUGHES GERMANIUM DIODES are designed to prevent such failures through two exclusive features:

1. **Fusion Sealing**—The glass-to-metal seal, proved in billions of vacuum tubes, is incorporated to full advantage in diode manufacture by the Hughes-developed process of fusion sealing at high temperature. The result is a rigid *one-piece* glass envelope impervious to moisture.

2. **100% Testing**—Hughes 100% testing procedures *invite* instabilities to occur prior to shipment, assuring rejection of every defective diode. *Each* **HUGHES DIODE** is humidity-cycled, temperature-cycled, JAN shock-tested, and electrically tested under vibration. This testing procedure insures the operation of **HUGHES DIODES** under adverse conditions of moisture, temperature, vibration and severe shock.

Reliability of **HUGHES DIODES** has been proved in airborne military electronic equipment for navigation, fire control, and guided missiles.

HUGHES GERMANIUM DIODE ELECTRICAL SPECIFICATIONS AT 25° C.

Description	RETMA Type	Test Peak Inverse Voltage* (volts)	Maximum Inverse Working Voltage (volts)	Minimum Forward Current @ +1 v (ma)	Maximum Inverse Current (ma)
High Peak	1N55B	190	150	5.0	0.500 @ −150 v
	1N68A	130	100	3.0	0.625 @ −100 v
High Back Resistance	1N67A	100	80	4.0	0.005 @ −5 v; 0.050 @ −50 v
	1N99	100	80	10.0	0.005 @ −5 v; 0.050 @ −50 v
	1N100	100	80	20.0	0.005 @ −5 v; 0.050 @ −50 v
High Back Resistance	1N89	100	80	3.5	0.008 @ −5 v; 0.100 @ −50 v
	1N97	100	80	10.0	0.008 @ −5 v; 0.100 @ −50 v
	1N98	100	80	20.0	0.008 @ −5 v; 0.100 @ −50 v
High Back Resistance	1N116	75	60	5.0	0.100 @ −50 v
	1N117	75	60	10.0	0.100 @ −50 v
	1N118	75	60	20.0	0.100 @ −50 v
General Purpose	1N90	75	60	5.0	0.800 @ −50 v
	1N95	75	60	10.0	0.800 @ −50 v
	1N96	75	60	20.0	0.800 @ −50 v
JAN Types	1N126**	75	60	5.0	0.050 @ −10 v; 0.850 @ −50 v
	1N127†	125	100	3.0	0.025 @ −10 v; 0.300 @ −50 v
	1N128‡	50	40	3.0	0.010 @ −10 v

*That voltage at which dynamic resistance is zero under specified conditions. Each Hughes Diode is subjected to a voltage rising linearly at 90 volts per second.
**Formerly 1N69A. †Formerly 1N70A. ‡Formerly 1N81A.

© 1953, H. A. C.

FUSION SEALED IN GLASS *for electrical stability*

Address inquiries to Dept. E

In addition to RETMA-*registered types,* HUGHES DIODES *are also supplied 100% factory-tested to a wide range of customer specifications, including high-temperature requirements.*

"PARTS not pounds!"

...we let Fansteel FABRICATE OUR TUNGSTEN & MOLYBDENUM COMPONENTS

EWING GALLOWAY

no scrap... no rejects... no time waste

Whether you want semi-fabricated blanks or completely finished parts, you will save by letting Fansteel fabricate your tungsten and molybdenum components for you. Fansteel maintains complete facilities for fabricating, including forming, stamping, bending, deep drawing, forging, machining, brazing, welding, assembly and finishing. You'll find Fansteel engineering assistance valuable, too. Fansteel engineers are long experienced in the fabricating techniques peculiar to tungsten and molybdenum, and are well prepared to design parts with the minimum amount of metal and lowest fabricating costs.



Anodes for hydrogen thyratron electronic tubes. The disks are heavy molybdenum sheet. The shafts are made of tungsten rod.

If you are a user of tungsten and molybdenum, consult Fansteel (without obligation) for assistance in design and most economical fabrication.

Write for the informative booklet: "FANSTEEL TUNGSTEN AND MOLYBDENUM"

FANSTEEL WORLD'S LARGEST PRODUCER OF REFRACTORY METALS

TUNGSTEN & MOLYBDENUM

22501C

Fansteel Metallurgical Corporation NORTH CHICAGO, ILLINOIS U.S.A.



Use of wood holding tool for pressing Kel-F sleeve into hole in tip of warm soldering iron for initial flare of end. Soldering iron is standard 100-watt Vulcan unit made by the Lenk Mfg. Co., operated at about one-third of line voltage

plastic, the 100-watt soldering irons employed are operated at about 38 percent of line voltage. Heavy copper cylinders fitted onto the heating element and shank of the iron serve to radiate heat as well as anchor the soldering iron to a piece of angle iron which is in turn fastened to the bench. Holes of different sizes are drilled partly through the solid tip of the iron on opposite sides, so that one tip will handle both $\frac{1}{8}$-inch and $\frac{1}{4}$-inch diam-



Bench setup for final flaring of plastic sleeve over deposited carbon resistor. Right leg of operator actuates lever that opens spring-closed fixture for insertion and removal of resistors. Sleeving is left in contact with tool about three seconds to obtain desired flare

marion

advancement in instrument design

TWO VIEWS SHOWING COAXIAL MECHANISM ACTUAL SIZE



EXPLODED DIAGRAM SHOWING INTERLOCKING CONSTRUCTION

COAXIAL METER MECHANISM DESIGN* OPENS NEW FIELDS OF APPLICATION

A new Marion concept in the mechanical design of the moving coil galvanometer magnetic system has resulted in a "miniature" movement with performance characteristics and durability exceeding existing ruggedized or regular panel instruments of far greater size and weight. The Marion "Coaxial" assembly provides a magnetic field of great strength, uniformity and stability which is self-shielded. Ruggedness and stability are inherent in the basic simplicity of the design. The small size and weight make practical the application of the moving coil mechanism as a component of a great many electrical or electronic instruments or other products. This is especially pertinent in aircraft instruments where size and weight are of critical importance, yet no compromise can be made with performance and durability.

The new assembly (see exploded diagram) consists essentially of a soft iron outer pole structure, a non-magnetic yoke and a magnetized core of such diameters that the yoke fits snugly in the pole structure and the core within the yoke. The assembly is locked by attaching the bridge to the pole structure by means of two screws—the only fastenings in the entire assembly. A locking finger on the bridge holds the core and the frame in position. Rotation of the core yoke is prevented by the slot in the bridge flange which engages one of the legs of the frame. The moving coil is contained by its pivots, and bearings located in the bridge and the base of the frame.

The basic design in which all critical dimensions are machined from a common center (the bearing axis) gives far more precise and uniform alignment than is possible with stamped assemblies. The interlocked assembly assures maintenance of these close tolerances and affords far greater rigidity and strength than is available in conventional mechanisms, particularly when mass is considered.



MECHANISMS BY MARION

The Marion "Coaxial" mechanism has many applications, not only in indicating instruments, but also as a component of equipment utilizing the moving coil galvanometer principle. It is one of a number of Mechanisms by Marion that extend the field of application of moving coil galvanometers where previously size, weight or performance characteristics prevented their use.

Marion Electrical Instrument Company, 401 Canal Street, Manchester, N. H.

*Patents Pending

marion meters

Reg. U. S. Pat. Off.

MANUFACTURERS OF RUGGEDIZED AND "REGULAR" METERS AND RELATED PRODUCTS

Copyright 1953 Marion Elec. Instr. Co.

which SCREW
will be specified here?



pheoll
makes it!

HERE IS a single source able to supply all your requirements for screws, bolts and nuts. Pheoll offers the most complete line . . . the most extensive stocks available. Call Pheoll on your next order.

PHEOLL

PHEOLL MANUFACTURING CO.
5700 ROOSEVELT ROAD, CHICAGO 50, ILLINOIS

SCREWS NUTS • BOLTS • SPECIAL COLD HEADED PRODUCTS



Closeup view of final flaring operation

eter tubing for two different sizes of resistors.

As a first step, a length of tubing is placed over a wood peg set concentrically into a hole drilled in the end of a piece of broom handle that serves as a holding tool. With this tool, the sleeve is pushed into the heated hole of correct size for flaring the end inward. There is no need to spin the sleeve during this operation.

Next, resistors are inserted in these half-closed sleeves. Final closing of the other end is done at another work position. Here the resistor lead is inserted in a hole drilled entirely through the tip of the soldering iron, and the lead for the already sealed end is placed in the groove of a sliding horizontal fixture. The operator now releases a lever with her knee, thereby allowing a spring on the fixture to push the resistor body into the hole in the soldering iron for the final flaring operation. This technique is employed in the San Juan, Puerto Rico plant of Radell Corp.

Production-Testing UHF Radiosonde Tubes

By MATTHEW M. BELL
Tube Department
Radio Corporation of America
Harrison, N. J.

THIS article describes the equipment used for production-testing of the RCA type 5794 fixed-tuned oscillator triode designed for uhf radiosonde transmitting applications. The 5794 consists of a pencil-type triode and two integral resonators of the cavity type, one between grid and cathode and the other between grid and plate. The grid-

All these from one experienced source



TITEFLEX DESIGNS AND MANUFACTURES — to customer specifications — rigid waveguides and combinations of rigid and flexible waveguides. Where there is, or should be, no movement, or where complicated accessories must be connected, Titeflex *rigid* waveguides are specially recommended.



WAVEFLEX® FLEXIBLE WAVEGUIDES are fabricated to retain critical dimensions — regardless of twisting or bending. Waveflex waveguides make assembly easy, improve design, compensate for expansion or movement. Rubber jacketing protects against weather, corrosion, physical abuse.



TITEFLEX CONNECTOR—lightweight, corrosion and moisture resistant with temperature ranges of —65°F. to +400°F. This connector's insulation properties will permit 3500 volts at sea level, 1200 volts at 50,000 feet altitude. Connector is available with 2 or 3 pins. 7 amperes. Weight ⅔ of ounce. Size 2" in length.



TITEFLEX CUSTOM WIRING SYSTEMS are corrosion resistant, moisture proof, pressure-tight and efficient at temperatures of — 65°F. to +400°F. Can be furnished with Titeflex or standard AN connectors for a wide range of service requirements. Can be sheathed with metal braids, fiber glass or nylon—and jacketed with silicone or other compounds.

MORE THAN 37 YEARS of developmental experience make Titeflex a logical source of the components pictured on this page. We are currently in a position to supply connectors and wiring systems to makers of aviation and electronic equipment. If you have a problem requiring our unusual combination of products and engineering, let us quote on your requirements. The coupon will bring you information on our products.

Let Our Family of Products Help Yours

Titeflex

✓ Check products you are interested in.

☐ SEAMED AND SEAMLESS METAL HOSE

☐ PRECISION BELLOWS

☐ IGNITION HARNESS

☐ IGNITION SHIELDING

☐ ELECTRICAL CONNECTORS

☐ RIGID AND FLEXIBLE WAVE GUIDES

☐ WIRING SYSTEMS

☐ FUSES

TITEFLEX, INC.
824 Frelinghuysen Ave.
Newark 5, N.J.

Please send me without cost information about the products checked at the left.

MAIL COUPON TODAY

NAME_____

TITLE_____

FIRM_____

ADDRESS_____

CITY_____ ZONE____ STATE_____



Behind every product of

Sterling Engineering

Sterling Engineering—long a manufacturer of the very highest quality relays and associated electrical devices—now employs the complete know-how of American Machine & Foundry Company, one of the nation's leading producers of complex electronic equipment.

AMF's unparalleled skill and experience—evidenced in many automatic and electronic marvels such as radar scanning equipment, automatic gun mechanisms, air force training devices, and Pinspotter (the automatic pin boy)—joins Sterling's *own* design and production knowledge to give greater-than-ever assurance that AMF Sterling Relays can meet your *strictest* requirements.

To be sure of satisfaction, be sure you check with Sterling. Send today for our free Catalogue. Write Sterling Engineering, Laconia, N.H.

AMF products ARE BETTER...*by design*

AMERICAN MACHINE & FOUNDRY COMPANY

Sterling Relays

STERLING ENGINEERING COMPANY, INC., LACONIA, N. H.

plate cavity, tunable to 1,680 mc, has a minimum power-output rating of 300 milliwatts. A frequency adjustment screw is provided for fine tuning over a range of ± 12 mc.

Production-testing for the 5794 involves mechanical adjustment of the grid-plate cavity so that it operates at the correct frequency and meets the specifications for minimum allowable power output. Both power and frequency are measured under fixed conditions of tube electrode voltage. A further requirement is that the cavity be terminated in an r-f output-measuring system having a characteristic impedance of 50 ohms and a vswr not exceeding 1.10.

The measuring facilities to be described are unusual in that they are combined in a single piece of equipment which is specifically designed for use in the factory and can be operated by semi-skilled factory personnel.

Assembly Technique

Assembly of the fixed-tuned RCA type 5794 oscillator triode for radiosonde service at 1,680 mc involves mounting the pencil triode in a cavity to provide two integral resonators requiring precise dimensional tolerance.

Adjustable plunger-positioning jigs connected to electronic test

Inserting pencil triode in loose outer shell of cavity after placing octagonal phosphor bronze ring around grid disk. Fixture in left hand positions one plunger inside cavity

PROBLEM:

Obtain a Thermostat Element capable of quickly interrupting a circuit on heavy overloads before the Element becomes dangerously overheated

SOLUTION:

General Plate TRUFLEX® THERMOSTAT METAL with a Magnetic Iron section added solved the problem

A leading manufacturer of Aircraft Circuit Breakers had the problem of obtaining a thermostat element that would interrupt a circuit running up to several thousand amperes. Previous elements didn't move fast enough and became overheated and destroyed on heavy overloads.

General Plate provided the solution with a TRUFLEX thermostat element with a magnetic iron section, butt welded to one end, which provided magnetic assistance to accelerate operation.

General Plate fabricates complete TRUFLEX thermostat metal elements and assemblies for installation in your products. You get accurate and consistent performance because every order comes to you an exact duplicate of the original... consistently uniform in tolerances, temperature reaction and performance, thus preventing rejects and costly adjustments in assembly.

General Plate TRUFLEX thermostat metal assemblies are made to meet your specific requirements for temperature range, electrical resistance, corrosion resistance, etc. If you prefer to make your own elements, General Plate will produce TRUFLEX thermostat metal strip to your material specifications. Write for TRUFLEX thermostat metal catalog and engineering assistance.

You can profit by using General Plate Composite Metals!

METALS & CONTROLS CORPORATION
GENERAL PLATE DIVISION
311 FOREST STREET, ATTLEBORO, MASSACHUSETTS

Want more information? Use post card on last page.



Our previous series of advertisements in this publication explained, in theatrical parlance, that our design and production facilities were pretty well "sold out" by the requirements of our present customers.

Now, we are happy to say (because we enjoy making new friends) that some of the heat has been taken off, and we are able to announce "Limited seating available"—as they say at the box office.

We shall be happy to talk with you about your present and/or future needs.

L. H. Terpening Company
DESIGN · RESEARCH · PRODUCTION
Microwave Transmission Lines and Associated Components
16 W. 61st St. • New York 23, N. Y. • Circle 6-4760

TRADE MARK

equipment permit setting the plungers of the cavity to exact frequency in a few minutes in the RCA tube plant in Harrison, N. J. The operator merely turns the plunger-moving knobs of the fixture while watching meters on a test panel. Air-operated tools then crimp the outer housing of the cavity to lock the plungers in position. The complete assembly is then placed in an octal-base adapter for final performance test. One of these involves tapping with a rubber hammer to check the rigidness of the assembly, as shown in one photo.

Test Setup

A block diagram of the test equipment is shown in Fig. 1. A pencil triode, a cavity shell and the other associated parts which comprise the complete cavity are assembled prior to being brought to the test set. The pre-assembled cavity to be tested is then mounted in a specially designed fixture which holds the cavity in the correct position. Gripping jaws engage the cavity parts in such a manner that the operator can adjust both the cathode and plate plungers to obtain the desired electrical conditions while the cavity is oscillating.



FIG. 1—Block diagram of equipment for production-testing uhf radiosonde tube

The regulation of the continuously variable regulated power supplies used is better than 1 percent. This regulation is required to prevent voltage fluctuations due to current changes which occur during adjustment of the cavity.

Output Probe and Coaxial Cable

The r-f output terminal of the cavity is coupled to the test set by

Two World-Famous Organizations Become One — *and*

this is what happens...

Just a few years ago, National Pneumatic, the world's leading producer of transit and railroad safety equipment, and Holtzer-Cabot, a pioneer and leader in the electrical field, became one organization.

Manufacturing was consolidated at the big Boston plant of Holtzer-Cabot. Progress was swift and sure in both companies' ability to serve customers even better.

SIX DIVISIONS WERE SET UP

Transit and Railroad • Industrial Activators and Controls • Products for National Defense • Motors • Telephone • Automatic Doors

All the familiar products, plus many new ones are now being made under a new high efficiency. Design and Research Departments have grown on a full scale to match the increased activities of these two great companies — with some left over!

To industry this is a new, large and dependable resource. Research, development and manufacturing facilities are available for mechanical, pneumatic, hydraulic, electric and electronic products either singularly or combined. Inquiries on present products or development work are welcomed.

NP HOLTZER-CABOT HC ESTABLISHED 1875

NATIONAL PNEUMATIC CO., INC.
AND
HOLTZER-CABOT
DIVISIONS
BOSTON 19, MASSACHUSETTS

NEW YORK • PHILADELPHIA • CHICAGO
SALES REPRESENTATIVES THROUGHOUT THE FREE WORLD

HOW DID THE *screw* GET ITS NAME?

The word "screw" is supposed to come from the Latin "scrofa" which has been defined as "a digger," from the habit of swine, who are fond of rooting up the earth with their noses. However, at least one man disagrees with the explanation. He figures that the etymologists have picked the wrong end of the pig. To him, the curly tail looks more like a screw than the nose does. Heads or tails, tradition has made the word part of the language.

Today, Allmetal—maker of stainless steel screws, bolts, nuts, and many other stainless fasteners—owes its good name to a tradition of high quality and fast service. If you need anything from our line, just give us the word.

Our 96-page catalog contains engineering data and weights as well as sizes and dimensions of stock items. If you want a copy, send us a note on your letterhead. Ask for catalog 53C.

STAINLESS STEEL FASTENERS

ALLMETAL

SCREW PRODUCTS COMPANY, INC.

821 STEWART AVE., GARDEN CITY, L. I., N. Y.

means of a specially designed output probe and a length of standard 50-ohm low-loss coaxial cable. The probe, the design of which is very critical to the operation of the test set, is the outcome of extensive development work. Because it is subject to wear and considerable abuse as a result of continual handling each time a cavity is inserted or removed from the test set fixture, the probe must be mechanically rugged and easily repaired. Space factors dictate that it be small. The electrical requirements are also severe; in order to achieve an overall vswr of less than 1.10, the probe must have a vswr considerably less than this value.

A sectional diagram of the probe and its component materials is shown in Fig. 2. A low vswr is achieved by maintaining a balance



FIG. 2—Sectional diagram of output probe

between the ratio of the diameters of the inner and outer conductor and the dielectric constants of the insulating materials used.

Because the vswr of the measuring system must not exceed 1.10, the output probe and cable must be in good condition at all times. Normally, it would be necessary to check the probe periodically using a conventional laboratory-type setup to assure this low vswr. Such an elaborate check is avoided, however, by the use of a simplified checking method. Equipment for the checking method is included in the test set.

In this simple check, the output of a reference cavity is coupled to a specially constructed coaxial directional coupler. When this coupler is terminated in a 50-ohm impedance, the reflected power is a minimum. For any variation in this 50-ohm termination, an increase in reflected power occurs and is indicated on a microammeter cali-

Keep TABS on WIRING PERFORMANCE with—

Tested and
Approved
Beyond
Specification

CHESTER plasticord-plasticote WIRES & CABLES

Chester ENGINEERED plastic insulation, laboratory and field tested to more than meet specifications provides both easier working qualities and longer service life. These rugged plastic coatings offer maximum immunity to abrasion, weather, oil and most chemicals. Smooth and pliable, they pull through channels and conduit easily and offer excellent appearance in open wiring. Chester single or multi-conductor wires and cables are available for electrical, electronic, TV, radio, telephone and many other industries. Call or write for illustrated bulletins, today!

JAN-C-76 WIRES* SRIR, SRHV, SRRF, WL			LACQUERED AND NYLON WIRES
105°C, 90°C, 80°C UL APPROVED; 120°C*	*Solid colors or spiral marking		SHIELDED WIRES & CABLES
FLEXIBLE CORD			INSTRUMENT WIRES
TV LEAD-IN WIRES			COAXIAL CABLE
COMMUNICATION WIRES & CABLES TO SPECIFICATIONS			SPECIAL WIRES & CABLES TO SPECIFICATIONS

"Chesty" HAS THE ANSWERS — Plasticord and Plasticote wires are available in standard constructions or custom built to specifications. For a practical solution to unusual insulated wiring problems, call or write

CHESTER CABLE CORP.

CHESTER • NEW YORK

REGISTERED U.S. PAT. OFF.

CONSTANT

RESEARCH

and

DEVELOPMENT

HAS ENABLED US TO PRODUCE ONE OF THE FINEST COMPUTERS AVAILABLE TODAY.

AMPLIFIER GROUP, TYPE 16-31C—provides 28 contact stabilized operational amplifiers for use as summers, differentiators, integrators, and inverters. Also in the cabinet are all necessary power supplies and a complete test panel.

MULTIPLIER GROUP, TYPE 16-31L—is a servo-mechanical multiplier and incremental function generator. There are 20 channels, each of which is capable of multiplying four variables by a fifth.



RESOLVER GROUP, TYPE 16-31D—furnishes 4 resolving channels and 12 operational amplifiers. Each resolving channel may also be used for multiplying three variables by a fourth. Furnished complete with test panel, reference supplies, and power supplies.

CONTROL CONSOLE, TYPE 16-24E—Houses the grounded metal problem board and its bay, attenuators, initial condition potentiometers, networks, limiters, and all operating controls.



SERVO GROUP, TYPE 16-31P—For the operations of resolving and multiplying when used with external amplifiers. There are two resolving and four servo-multiplying channels. The equipment is furnished with test panel and power supplies.

ELECTRONIC ASSOCIATES Incorporated

INQUIRE SALES DEPARTMENT

LONG BRANCH, NEW JERSEY

brated in terms of meter readings versus vswr caused by the termination mismatch. The operator periodically plugs the output probe into the directional coupler. If the resultant microammeter reading exceeds a predetermined level (corresponding to a vswr of 1.10), the probe and cable are judged unsatisfactory for use and are removed from the test set for repair.

Power Output Measurement

The power-output measuring system is composed of a special double-stub tuner, attenuator, thermistor mount and thermistor bridge.

Plunger-setting equipment. Coaxial connection at right goes to electronic test equipment that measures frequency and power output continuously during the plunger-setting operation. Insulating blocks permit applying operating voltages to tube while in fixture

Because each of the components in the r-f system contributes some small error to the overall vswr, it was found expedient to include a stub tuner as a means of compensation. The stub tuner consists of a coaxial section with two stubs spaced approximately $\frac{1}{4}$ wavelength apart. These stubs are capacitively tuned. The use of capacitance tuning eliminates contact problems normally encountered in shorting-type stub tuners. However, because only a small capacitance change can be achieved, the device is useful only over a narrow frequency range. This frequency limitation presents no problem in the test because all of the testing is performed at the single specified frequency,

SCINFLEX ASSURES

LOW MAINTENANCE BECAUSE

IT PERMITS SIMPLICITY

When operating conditions demand an electrical connector that will stand up under the most rugged requirements, always choose Bendix Scinflex Electrical Connectors. The insert material, an exclusive Bendix development, is one of our contributions to the electrical connector industry. The dielectric strength remains well above requirements within the temperature range of −67°F to +275°F. It makes possible a design increasing resistance to flashover and creepage. It withstands maximum conditions of current and voltage without breakdown. But that is only part of the story. It's also the reason why they are vibration-proof and moisture-proof. So, naturally, it pays to specify Bendix Scinflex Connectors and get this extra protection. Our sales department will be glad to furnish complete information on request.

• Moisture-Proof • Radio Quiet • Single Piece Inserts • Vibration-Proof • Light Weight • High Insulation Resistance • High Resistance to Fuels and Oils • Fungus Resistant • Easy Assembly and Disassembly • Fewer Parts than any other Connector • No additional solder required.

The Finest
ELECTRICAL CONNECTOR MONEY CAN BUY!



BENDIX SCINFLEX

ELECTRICAL CONNECTORS

Bendix

SCINTILLA MAGNETO DIVISION of Bendix AVIATION CORPORATION

SIDNEY, NEW YORK

Export Sales: Bendix International Division, 205 East 42nd St., New York 17, N. Y.
FACTORY BRANCH OFFICES: 117 E. Providencia Ave., Burbank, Calif. • Stephenson Bldg., 6560 Cass Ave., Detroit 2, Michigan • Brouwer Bldg., 176 W. Wisconsin Avenue, Milwaukee, Wisconsin • 582 Market Street, San Francisco 4, California.

Want more information? Use post card on last page.

but the tuner must be carefully designed and constructed to be effective at this frequency.

A conventional commercial coaxial attenuator is used in the test equipment to insure operation of the thermistor within its power rating and at the proper level for use with the power bridge. In this case the level is 2 milliwatts. No detailed explanation is needed for either the thermistor mount or the power bridge except to point out that the mount must be designed to match the 200-ohm thermistor impedance to the 50-ohm line impedance. The bridge used was originally designed by the MIT

Tapping completed cavity unit with rubber hammer as part of final test

Radiation Laboratory. It is used in the type TWS-2 wattmeter and designated as a type TBN-2 thermistor bridge. This unit is described in MIT report No. 55 of March 29, 1944.

After voltages are applied to the cavity and the necessary adjustments made for frequency and plate current, the power output is read on the bridge meter. The cavity is then tuned for maximum power output.

Frequency Measurement

Included in the double-stub tuner is a small capacitance probe used to couple a small r-f signal necessary for frequency measurement. The magnitude of the energy taken is not sufficient to be measured in the system. The detuning effect of the probe is not objectionable and has a

SCHOOLROOMS OF THE SKY
...DOWN-TO-EARTH!

The world-famous "Link Trainer" of years ago simulated the very simple flight conditions of early aircraft. Yet it established the essential principle of a down-to-earth schoolroom where actual flight conditions are *exactly* duplicated . . . a principle that slashed the cost of training, in time and money.

Today's Link Electronic Equipment improves upon the early Link Trainers in this principle . . . much as a postgraduate lecture room has advanced from the Little Red Schoolhouse. This complex equipment simulates the infinitely complex conditions of near-sonic and supersonic jet aircraft . . . *all* conditions and *all* factors influencing them, from take-off to flight to refueling, navigation and landing, and it does all this electronically.

All Electronic Trainers of today utilize Link basic patents on flight simulators. These complex "schoolrooms" enable the pilot to solve on the ground the innumerable problems he will later face in the sky.

the connecting link between ground and sky

LINK AVIATION, INC. BINGHAMTON, N.Y.

LINK invites employment applications from engineers and draftsmen.



"Designed for Application"

Delay Lines and Networks

The James Millen Mfg. Co., Inc. has been producing continuous delay lines and lump constant delay networks since the origination of the demand for these components in pulse formation and other circuits requiring time delay. The most modern of these is the distributed constant delay line designed to comply with the most stringent electrical and mechanical requirements for military, commercial and laboratory equipment.

Millen distributed constant line is available as bulk line for laboratory use and in either flexible or metallic hermetically sealed units adjusted to exact time delay for use in production equipment. Lump constant delay networks may be preferred for some specialized applications and can be furnished in open or hermetically sealed construction. The above illustrates several typical lines of both types. Our engineers are available to assist you in your delay line problems.

JAMES MILLEN MFG. CO., INC.
MAIN OFFICE AND FACTORY
MALDEN, MASSACHUSETTS, U.S.A.

close temperature control is a snap with STEVENS

TYPE M BIMETAL DISC THERMOSTATS



Thermostats shown approximately full size. Other designs available.

APPLIANCES AND APPARATUS

ELECTRONIC DEVICES AND AVIONIC EQUIPMENT

INSTRUMENTS AND DEVICES

Stevens Type M* thermostats are engineered for compactness . . . lightness . . . close temperature control. Featuring quick make and break operation, fast snap of bimetal disc and series double-breaking contacts reduce arcing . . . assure positive On and Off.

Bimetal thermal element actuates a low-resistance bridging contact disc which carries current. Bimetal disc responds only to temperature of controlled device or air surrounding thermostat . . . prevents false cycling or life-shortening "jitters."

For operation in any ambient from -75°F to nearly 600°F, Stevens Type M thermostats are available with virtually any terminal or mounting arrangement in standard or hermetically sealed types.

Get faster response . . . closer temperature control. Specify Stevens Type M thermostats for your product—*for better performance, longer life.*

A-4719

*Patented

STEVENS manufacturing company, inc.
MANSFIELD, OHIO

negligible effect on the vswr of the system.

Frequency is accurately measured with a commercial coaxial-type frequency meter accurate to within ½ percent. Normally, it is necessary to take a reading at two points ½ wavelength apart with this type of instrument. However, because the components all remain fixed, positioning the meter at one of these points is satisfactory and provides good accuracy.

Although this device is excellent for setting the cavity frequency to an exact value, another problem exists. At the start of the test, the initial frequency of the cavity may be considerably different from the desired value. Adjustment of the cavity to the proper frequency is facilitated by the incorporation of an elementary frequency-spectrum viewer in the test set. This device is basically a coaxial cavity whose resonant frequency is varied by means of a synchronous motor-driven cam capacitively coupled to the end of the ¼-wavelength center stub of the coaxial cavity. An oscilloscope, which is swept at the same rate as the synchronous motor, displays the frequency spectrum. By proper cam design the frequency sweep of the coaxial cavity may be selected to give a convenient bandwidth. A sharp pip appears on the oscilloscope at the tube cavity frequency; the position of the pip on the screen serves as a means of approximating the frequency. This method is sufficiently accurate to bring the frequency of the cavity within the range of the precision frequency meter.

The author gratefully acknowledges the contributions to the development of this project made by J. G. Busby, G. G. Carne, W. A. Harris, C. M. Morris, D. W. Power and G. M. Rose.

Hot-Die Wire Printer

IDENTIFYING designations are quickly and clearly stamped on plastic-insulated wire for military radar equipment in the Coamo, Puerto Rico plant of Caribe Aircraft Radio Corp. with a wire printer made by Kingsley Stamping Machine Co., Hollywood, Calif. Two

Names that mean outstanding quality

Capehart

SYLVANIA

Motorola

Sentinel

RAYTHEON

. . . RELY ON Midland CRYSTALS

Manufacturers with front-rank reputations make sure of every component that goes into their products. Such reputations can be maintained only through constant vigilance and selection of suppliers who also have proud reputations to uphold.

Names of distinction in every field of communications depend on Midland Crystals for reliable frequency control in their products. That's tribute enough to the kind of performance Midland Quality Control has built into millions of crystals faithfully doing a first-class job on land, sea, and in the air.

Whatever your Crystal need, conventional or highly specialized
When it has to be exactly right, contact

Midland MANUFACTURING COMPANY, INC.
3155 Fiberglas Road, Kansas City, Kansas

WORLD'S LARGEST PRODUCER OF QUARTZ CRYSTALS

STILL MORE WAYS TO
SQUEEZE PENNIES
OUT OF
UPSET SPECIALS COSTS

Specially designed upset products are solving thousands of problems. Dozens of design pointers on them are yours for the asking. Send us your sketches, prints, finished products for suggestions.


An upset knurl adds only slightly to the heading cost, but a cross knurl requires an extra operation.
An inexpensive fluted shoulder usually will serve the same purpose as ears which require an extra hand fed operation.
UNDER 2"
Full length threading on studs up to 2" long is less expensive than short thread rolled on each end.
OVER 2"
To facilitate riveting, a spot produced in heading will sometimes be as satisfactory as a more costly drilled hole.
CROSS SECTION
CROSS SECTION

REPRINTS of this and of previously published charts are available on request for use in drafting and purchasing departments.

QUALITY PROMCO BRAND

MACHINE SCREWS AND SPECIAL FASTENERS ARE OUR BUSINESS

WRITE FOR OUR CATALOG

THE PROGRESSIVE MANUFACTURING COMPANY
50 NORWOOD ST., TORRINGTON, CONN.

designations are stamped at each end of each lead, about an inch apart, so that one will show even though the other is covered by a component.

Stamping is done through special sheets of thin foil. A black foil is used for light-colored wires and a white foil for dark wires.

Individual dies for each letter of



Stamping identifying numbers on insulation of leads for radar equipment. Individual dies are slipped into holder just under left hand of operator, having knurled locking screw. This holder in turn fits against the heating element of the machine

the designation are locked in position on the heating element in the movable upper part of the machine. A built-in dial thermometer indicates to the operator when the dies have reached correct operating temperature.

The wire to be printed is placed in a positioning groove on the anvil of the machine, and the operating lever is lowered to bring the dies and foil down on the wire, much as in stamping initials on leather goods. The foil is automatically advanced a small amount after each operation of the machine to expose fresh foil for the next printing.

Relay Lineup Fixtures

TO LINE UP THE moving armature of an aircraft relay accurately with respect to the two pole faces of the relay, Phillips Control Corp. in San Juan, Puerto Rico, uses a simple clamping device mounted at an angle on a block of wood. After all screws are loosened, the relay is placed in the device and the

Illustrations show relative sizes

AIRBORNE radar and other electronic equipment can be made much smaller and lighter by use of these modern, smaller tubes. UNITED has designed types 577, 578 and X-22 as exact electrical replacements for types 371-B, 8020 and 1616, in applications where it is vitally important to save space and weight.

Write for full specifications.

UNITED ELECTRONICS, 42 Spring Street, Newark 2, N. J.

(TRANSMITTING TUBES EXCLUSIVELY Since 1934)

Ceramic Insulated for
LOW LOSS...
MINIMUM CREEPAGE
NEW TYPE 2C TAP SWITCHES



Designed and constructed for precision service, long operating life and rugged duty, Type 2C instrument switches are an advanced design of the proven Tech Laboratories Type 2A. Ceramic insulation and improved contacts greatly increase their efficiency. Low r.f. loss and sharp reduction of creepage, plus a constant contact resistance of only 1 or 2 milliohms, give these precision switches matchless performance records. Write for full details.

SPECIFICATIONS

Contact resistance: 1-2 milliohms

Contact material: Silver alloy

Contact design: Laminated wiper arm, self-cleaning, shorting or non-shorting

No. of contacts: 2 to 24 single pole, shorting or non-shorting
2 to 11 double pole, shorting or non-shorting
2 to 5 triple pole, shorting or non-shorting

Spacing: 15° or 20°, shorting or non-shorting

No. of poles per deck: 1 to 4

No. of decks: According to requirements

Life: 200,000 cycles, min.

Current carrying cap.: 3 amp.

Max. operating voltage: 120 V., a.c.

Mounting: Single hole, ⅜"-32 bushing, standard length for up to ¼" panel, special lengths to order

Size: 1¾" dia.

Detent: Ball and spring

Weight: Approx. 1 oz. per deck

TECH LABORATORIES, INC.

Manufacturers of Precision Electrical Resistance Instruments

PALISADES PARK NEW JERSEY

clamping lever at the top is brought down. This brings the armature into accurate alignment.

The operator now tightens the assembly screws on one side of the relay, then presses a release button and indexes the entire top of the fixture 180 degrees for tightening the screws on the other side. The indexing feature eliminates the need for rotating the entire fixture and insures that the relay will stay rigidly in position during tightening of the screws. This is essential to prevent damage to the screw slots.

Relay holding fixture, designed to provide optimum working angle for tightening alignment screws

Plastic Small-Parts Bags

AFTER PUNCHING and inspection, mica spacers for vacuum tubes are placed in transparent plastic bags in the Rio Piedras, Puerto Rico plant of Sylvania Electric of P. R. Inc. Each filled bag is sealed with a standard heat-sealing tool, to keep out dust and moisture. The bags are made for this purpose by Howard Plastics, Council Bluffs, Iowa.

After sealing, an identifying label is stapled to each bag giving quantity, part number, type of mica and other pertinent information. The staples go through the sealing flap and hence do not break the air seal of the container. These bags serve equally as well for ship-



IVAN is watching you

IVAN is a dyed-in-the-wool Communist. There are only 6 million party members like him in all Russia, yet these Communist brass-hats enforce the iron dictatorship of the Kremlin over *200 million* Russians.

He's sold to the hilt on Red ideas. Which means he's out to get *you*. He believes it's either you or him . . . that the world is too small for both.

Ivan is working hard to beat you down. He has a big head start.

Right now he's got you in a bad spot.

Ivan is afraid of only one thing.

He fears your ability to out-produce him in guns, tanks, planes.

Frankly, he doesn't think you value your free system enough to do it . . . to make willingly the sacrifices he has squeezed out of the Russians.

But he's wrong!

Because you and all of us have set out to build more and better weapons—to do it faster all the time.

We must use every bit of know-how and inventive skill we have to improve our machines and methods—to turn out more and more for every hour we work. Only in this way can we become militarily strong.

But we've got to supply essential civilian needs as well. We can't allow needless shortages to take prices skyrocketing and lower the value of our dollar.

Sure, that means sacrifices for everybody. But doing this double job well is the only sure way to stop Ivan in his tracks—and to save the freedoms which are ours and which he has never known.

FREE . . . this important booklet tells you how our American System Grew Great

How Americans developed better machines, power and skills to build a great nation . . . Why we have been able to produce constantly more per hour . . . How this has given us the world's highest living standard.

How we can meet today's challenge—Why we must expand our productive capacity . . . supply arms and essential civilian needs, too. Read how this dynamic process works in free booklet, "The Miracle of America," endorsed by representatives of management and labor. Send for your free copy today!

MAIL THE COUPON—
The Advertising Council, Inc., 25 West 45th St., Dept. B. P. New York 19, N.Y.

Name_____

Address_____

Occupation_____

This advertisement, approved by representatives of management, labor and the public, is published in the national interest

McGRAW-HILL PUBLISHING COMPANY

THE BETTER WE PRODUCE
THE STRONGER WE GROW

DEPEND ON

Bendix Red Bank



RELIABLE ELECTRON TUBES

With electronic controls taking over more and more operational functions in aircraft, it's becoming increasingly important that the electron tubes used be dependable under conditions of high altitude, continuous vibration, varying voltages and frequent shock. Because of their advanced design and construction . . . born of never-ceasing research and special production skills . . . Bendix Red Bank Reliable Electron Tubes have the dependability necessary to meet these severe operating conditions. You can depend on our long, specialized experience to give you the right answer . . . for all types of regular as well as special-purpose tube applications. Call on us for full details.

Manufacturers of Special-Purpose Electron Tubes, Inverters, Dynamotors and Fractional D. C. Motors

TYPE AND MODEL INDEX				TYPICAL OPERATING CONDITIONS		
Bendix No.	RTMA No.	JAN No.	General Type	Heater Voltage	Plate Voltage Per Plate	M.A. Load
TE-2		5839	OCTAL FULL WAVE RECTIFIER	26.5	350	70
TE-3	5838		OCTAL FULL WAVE RECTIFIER	12.6	350	70
TE-5		5852	OCTAL FULL WAVE RECTIFIER	6.3	350	70
TE-10	5993		MINIATURE FULL WAVE RECTIFIER	6.3	350	70
TE-22	6106		OCTAL FULL WAVE RECTIFIER	5.0	350	100

BEAM POWER AMPLIFIER TUBE	
SPECIFICATIONS	
BENDIX NO.	TE-8
RTMA NO.	5932
HEATER VOLTAGE	6.3 V
PLATE VOLTAGE	250 V
SCREEN VOLTAGE	250 V
GRID VOLTAGE	12.5 V
G. M.	4000
PLATE CURRENT	45 MA
POWER OUTPUT	3.5W

Manufacturers of Special-Purpose Electron Tubes, Inverters, Dynamotors and Fractional HP D. C. Motors

Bendix DIVISION OF Red Bank

EATONTOWN, N. J.

THE NAME Bendix AVIATION CORPORATION MEANS MORE

West Coast Sales and Service: 117 Providencia Ave., Burbank, Calif.

Export Sales: Bendix International Division, 205 East 42nd St., New York 17, N. Y.

Use of transparent plastic bags for storing and shipping punched mica parts for tubes

ment or storage, and permit visual inspection of their contents.

Mica-Punching Press

MICA INSULATORS for subminiature tubes are punched from irregularly shaped sheets at high speed by combining manual skill and dexterity of workers with use of a fast-acting foot-operated punchpress in the Rio Piedras, Puerto Rico plant of Sylvania Electric of P. R. Inc.

The goal in punching mica is to get as many pieces as possible out of sheets that vary widely in shape and size, without producing defects through overlapping onto an already punched hole. Operators are trained to judge visually and shift

Punching mica spacers complete with holes for tube leads and supports, with fast-acting punchpress

MECHANICAL FILTERS FOR INDUSTRY



Collins Mechanical Filter with hermetically sealed shield removed. Compare size with matchbook.


ONE SUPPORTING DISK AT EACH END
RESONANT MECHANICAL SECTION (6 RESONANT DISKS)
INTERCONNECTING RODS
BIAS MAGNET
MAGNETOSTRICTION TRANSDUCER COIL
455 KC ELECTRICAL SIGNAL (INPUT OR OUTPUT)
MAGNETOSTRICTION CORE
455 KC ELECTRICAL SIGNAL (INPUT OR OUTPUT)
2 - 13/16"

Engineers's drawing of 455 kc Mechanical Filter interior.

SELECTIVITY CURVES FOR THREE TYPICAL MECHANICAL FILTERS

Type F455B-31



Type F455B-08



Type F250Z-2



THE COLLINS Mechanical Filter was first revealed to the Radio Industry during the 1952 IRE Convention. Since that time the original Mechanical Filter Type F455B-31 has become available in production quantities. Other Collins Mechanical Filters, designed to operate at various bandwidths in the intermediate frequencies, are also available in engineering sample quantities. All of the Mechanical Filters listed here offer a close approach to the ideal rectangular selectivity curve. Consult the chart of available Mechanical Filters (right) for the solution to your selectivity problem.

A request on your letterhead will bring full technical specifications, price and delivery information.

Type No.	Center Frequency	Bandwidth	Terminal Arrangement
F250A-60	250 kc	6.0 kc	Solder
F250Z-1	248.7 kc	3.0 kc	Solder
F250Z-2	251.3 kc	3.0 kc	Solder
F455A-08	455 kc	800 cycle	Solder
F455A-31	455 kc	3.1 kc	Solder
F455A-60	455 kc	6.0 kc	Solder
F455B-08	455 kc	800 cycle	Plug-In
F455B-31	455 kc	3.1 kc	Plug-In
F455B-60	455 kc	6.0 kc	Plug-In
F500A-14	500 kc	1.4 kc	Solder
F500A-31	500 kc	3.1 kc	Solder
F500B-31	500 kc	3.1 kc	Plug-In
F500B-14	500 kc	1.4 kc	Plug-In

FOR ELECTRONIC DEVELOPMENTS, LOOK TO . .

COLLINS RADIO COMPANY, Cedar Rapids, Iowa

11 W. 42nd St., NEW YORK 36 | 1930 Hi-Line Drive, DALLAS 2 | 2700 W. Olive Ave., BURBANK

Want more information? Use post card on last page.

REPUBLIC

on its RECORD

Republic has been serving the electronics industry with high quality capacitor foil for a number of years. During those years it has been Republic's policy to give each job exacting, personal attention; to impose Republic quality on quantity orders.

Republic specializes in just one thing — rolling plain aluminum foil. Each roll of Republic Aluminum Foil is custom made for your machines, for your specific applications. Each roll has clean, straight cut edges, accurate gage. Each roll is manufactured to hold the user's work stoppages and rejects to the minimum. Use of Republic Aluminum Foil helps you to have greater production, lower cost.

Republic capacitor foil is available in widths of ¼" and wider, and in gages from .00017" to .005". When you specify aluminum foil, it helps to remember that Republic constantly watches the *little* things that mean *bigger* production for you.

REPUBLIC FOIL & METAL MILLS
INCORPORATED
DANBURY CONNECTICUT

SALES OFFICES: 209 W. Jackson Blvd., Chicago 6, Ill.
666 Mission St., San Francisco 5, Cal.

the mica between punchings, without the aid of mechanical positioning guides. An expert operator can make the holes appear in a sheet almost as fast as if it were being peppered by a machine gun.

The press used for for this operation is made by Perkins Machine Co., Warren, Mass. A metal fence is bolted to the front of the press for safety, with just enough clearance underneath for easy position-



Method of feeding mica under safety fence of press

ing of the mica sheets. The operator looks over the top of the fence. Copper tubing entering through the fence blows a blast of air across the die to keep it clean, since particles of mica might cling to the tiny hole-punching dies that are combined with the blanking die here.

Soldering Iron Holder Automatically Cuts Voltage

VOLTAGE to a pencil-type soldering iron is automatically reduced from 6.3 v to 5 v when the iron is placed in a special holder mounted on the transformer chassis. This voltage-reducing action is obtained automatically by hinging the holder and



Bottom view of chassis for soldering iron holder



TURN YOUR CAMERA into TWINS...

with the GPL VARI-FOCAL LENS

(3" to 15" or 6" to 30" range)

One camera and a GPL vari-focal lens equals the work of two or more chains . . . at only the cost of a lens. One camera can handle an entire show, for the lens has a 10:1 change in focal length in two 5:1 steps—from 3 to 15 inches and 6 to 30. One camera can be used in studio or field with either range. Interchangeable back elements provide quick shift of two ranges.

Fully color-corrected, this lens has perfect overall focus at f/5.6 or higher numbers, in 3-15 range. Flat field over entire range. Motor driven lens is operated from camera or control room.

The GPL Vari-Focal Lens is adaptable to image orthicon cameras of all types.

Now in network use, this lens offers station operators new scope in camera work—new economy in making twins of any camera.

Write, wire or phone for full optical and mechanical specifications.

General Precision Laboratory
INCORPORATED
PLEASANTVILLE NEW YORK

GPL

Export Department:
13 East 40th St., New York City
Cable address: Arlab

Cable address: Prelab

Camera Chains • Film Chains • Field and Studio Equipment • Theatre TV Equipment • GPL-Continental Transmitters

Want more information? Use post card on last page.

the Waterman TWIN POCKETSCOPE®

MODEL S-15-A

Size:
12" x 6" x 7"
16¼ Pounds

ANOTHER EXAMPLE OF Waterman PIONEERING . . .

The WATERMAN TWIN POCKETSCOPE, model S-15-A, presents a new concept in multiple trace oscilloscopy with independent vertical channels each having a sensitivity of 10 millivolts rms/inch, and a response within —2 db from DC to 200 KC—a pulse rise time of 3 microseconds. These features combined with the provisions for intensity modulating either, or both, traces, results in greater flexibility. The sweep generator is operated either in the repetitive or triggered mode from 0.5 cycles to 50 KC with synchronization polarity optional. All attenuators and gain controls are of the non-frequency discriminating type. Remember that portability has not been overlooked! The amazing small size of the S-15-A tips the scales of opinion heavily in its favor. Imagine, all of these essential characteristics in an instrument weighing only 16¼ lbs. You can carry it to any job, anywhere!

WATERMAN PRODUCTS CO., INC.
PHILADELPHIA 25, PA.
CABLE ADDRESS: POKETSCOPE

MEMO... Write for details today!

WATERMAN PRODUCTS INCLUDE

S-4-A SAR PULSESCOPE®
S-5-A LAB PULSESCOPE
S-11-A INDUSTRIAL POCKETSCOPE
S-12-B JANized RAKSCOPE®
S-14-A HIGH GAIN POCKETSCOPE
S-14-B WIDE BAND POCKETSCOPE

Also RAYONIC® Cathode Ray Tubes and Other Associated Equipment

WATERMAN PRODUCTS

Voltage of pencil-type soldering iron is automatically reduced 1.3 v when iron is placed in holder on bench, thereby minimizing pitting of soldering iron tip when not in use. Operator uses iron here for soldering Nichrome resistance wire to terminals on ceramic bobbins for precision resistors

placing under it a snap-action switch. The weight of the pencil-type soldering iron is sufficient to actuate the switch, thereby changing from one tap to another on the primary winding of the Stancor type P-4022 power transformer used with the soldering iron. This unit is used throughout the entire plant of Caribe Aircraft Radio Corp. in Coamo, Puerto Rico.

Checking Tolerances of Components

ALL resistors and capacitors used in the production of Raytheon's PRC-6 hand-carried f-m trans-

Thumb of operator is here pressing button that closes clamping jaws and initiates measurement of carbon resistor to be sorted for tolerance

PROJECT TINKERTOY



ALSIMAG®
OPEN DIES
on Steatite and Titanate Ceramics



In AlSiMag you have the experience, the correct ceramics and the tooling available for ceramics for PROJECT TINKERTOY type insulators.

ALSIMAG STEATITE COMPOSITION 507 combines high strength and low dielectric losses. Produced with great uniformity and dimensional accuracy to further speed automatic assemblies. Fully proved by perfomance.

American Lava Tiolektrik® dielectrics with dielectric constants ranging from 6 to more than 6000 are available from open dies for PROJECT TINKERTOY. These superior ceramic condenser dielectrics can be had in other sizes for this or other applications.

52ND YEAR OF CERAMIC LEADERSHIP

AMERICAN LAVA CORPORATION

A Subsidiary of Minnesota Mining and Manufacturing Company

CHATTANOOGA 5, TENNESSEE

OFFICES: METROPOLITAN AREA: 671 Broad St., Newark, N. J., Mitchell 2-8159 • SYRACUSE, N. Y.: 330 Arlington Ave., Phone 76-5068 • CLEVELAND: 5012 Euclid Ave., Room 2007, Express 1-6685 NEW ENGLAND: 1374 Mass. Ave., Cambridge, Mass., Kirkland 7-4498 • PHILADELPHIA: 1649 N. Broad St., Stevenson 4-2823 • ST. LOUIS: 1123 Washington Ave., Garfield 4959 CHICAGO: 228 N. LaSalle St., Central 6-1721 • SOUTHWEST: John A. Green Co., 6815 Oriole Dr., Dallas 9, Dixon 9918 • LOS ANGELES: 5603 N. Huntington Dr., Capitol 1-9114

ASSISTANCE ON NEW MODULAR PROJECTS:

In AlSiMag you have the WIDEST CHOICE OF CERAMIC MATERIALS, both in steatites and titanates, backed by the largest engineering staff in the industry. Send us your requirements for engineering study and recommendations.

North American F-86F Sabre Jet

VIBRATION DATA

recorded by

14-channel Brush Magnetic Head

A precision Brush multichannel head assures faithful reproduction in the Davies magnetic tape data recorder, used to record vibration in jet aircraft and shock waves in seismic and oil field exploration.

This head has one synchronizing channel and 13 data channels, all of which record on a single tape 1¾" wide. *Precision gap alignment* permits recording on one machine and playback on another machine with all signals in perfect time-phase relationship—an exclusive advantage of Brush multichannel heads.

For complete information, write Brush Electronics Company, Dept. K11, 3405 Perkins Ave., Cleveland 14, Ohio.

Magnetic Tape Data Recorder, made by Davies Laboratories, Inc., Riverdale, Md., uses Brush Magnetic Heads for Accurate Recording.

BRUSH ELECTRONICS COMPANY

INDUSTRIAL AND RESEARCH INSTRUMENTS
PIEZO-ELECTRIC MATERIALS • ACOUSTIC DEVICES
MAGNETIC RECORDING EQUIPMENT
ULTRASONIC EQUIPMENT

BRUSH ELECTRONICS

formerly The Brush Development Co. Brush Electronics Company is an operating unit of Clevite Corporation.

mitter-receiver are sorted according to percent variation from specified values with a unique semiautomatic machine employing electronic measuring circuits and solenoid-operated



Rear view of tolerance sorting machine, with spare standards stored in bottom. Machine was made by Industrial Instruments, Inc., Jersey City, N. J.

sorting gates. The operator places each component in turn on an anvil equipped with clamps which close down on the pigtail leads to get good connections. A button located between the clamps is pushed to actuate the clamps and initiate the measuring operation.

By the time the operator has removed the part and dropped it into the chute below, the machine has set the gates or doors so that the part drops into the correct bin corresponding to a predetermined percentage of tolerance. Up to 12,000 parts a day can be checked in this manner.

Initial setup of the machine merely involves plugging in the proper standards of capacitance or resistance. The most used standards are made up as plug-in units stored at the bottom of the equipment housing.

Resistor Lead Straightener

A SIMPLE FIXTURE made from wood and metal is used for straightening the axial leads of deposited carbon resistors in the San Juan, Puerto Rico plant of Radell Corp. The operator places a resistor crosswise in the device, rolls the slide back

VARIAN associates

LOCKNUT TUNERS
for extreme ruggedness



VA-6313/V-280

VA-6314/V-290

CONVENTIONAL CONNECTIONS

HIGH-ALTITUDE INSULATED LEADS



VA-6310/V-260



VA-6312/V-270

SHAFT TUNERS
smooth, chatter-free

X-BAND KLYSTRONS in QUANTITY

rugged local oscillators for radar and beacon services

full production quantity prices

firm basis for new equipment design

READY NOW for your specification into production equipment. This comprehensive series of Varian X-Band Klystrons includes the type variations illustrated—all having these outstanding features:

Non-microphonic characteristic
Negligible barometric-frequency coefficient
Rapid warmup—on frequency in 30 seconds
Low-voltage operation—see data below
Production tested—under high-amplitude vibration

		V-260, V-270		V-280, V-290		X-13	
GENERAL DATA	Frequency Range, kmc	8.5-10.0		8.5-10.5		8.2-12.4	
	Heater Voltage, v	6.3		6.3		6.3	
	Heater Current, amp.	1.2		1.2		1.2	
	Tuner	slotted shaft		locknut		micrometer	
MAXIMUM RATINGS	Resonator Voltage, v	350		385		500	
	Resonator Current, ma	42		74		65	
	Reflector Voltage, v	0 to -1000		0 to -1000		0 to -1000	
TYPICAL OPERATION	Resonator Voltage, v	200	300	200	300	300	500
	Frequency, kmc	9.3	9.3	9.3	9.3	10	10
	Resonator Current, ma	17	28	23	42	28	58
	Power Output, mw	20	70	15	48	90	560
	Electronic Tuning Range, mc	30	48	50	82	46	43
	Temperature Coefficient, kc/°C	60	60	60	60	100	100
	Reflector Voltage, v	-120	-160	-80	-100	-230	-400
	Load VSWR, less than	1.1	1.1	1.1	1.1		
	Warm-up Time, sec to oscillation	15	15	15	15	15	15

FOR LABORATORY x-band measurement—the basic Varian X-13 Klystron general-purpose signal source is now available for early shipment in production quantities.

• Trademark

Field representatives in 21 Cities.

VARIAN associates
PALO ALTO 1, CALIFORNIA

Want more information? Use post card on last page.

National
NC
PROVEN DEPENDABLE QUALITY
Components



POPULAR NATIONAL DIALS

For years, National dials have been the popular choice of amateurs, experimenters and commercial users because of their smooth, velvety action, easily-read scales, and quality construction. Many dials, like the N and ACN dials shown, can be specially calibrated or supplied with blank scales for commercial application. Write for drawings and prices.

NEW TYPE FWT BANANA PLUGS

Moulded of mica-filled bakelite in accordance with JAN specifications, this new type is styled for easy gripping. Leads can be brought direct from the prongs or through the holes at the base of the plug. Top of plugs are designed to receive additional plugs. Prongs and screws are nickel-plated brass. Write for drawings and specifications.



Write for drawings

National
NC
EST. 1914
NATIONAL COMPANY, Inc.
MALDEN, MASSACHUSETTS

Resistor in straightening device just before operator rolls slide over its leads to straighten them

and forth over the leads about three times, then pushes the slide forward to roll the resistor into the transverse slot through which it drops into a box underneath.

Straightening is done between sheets of metal fastened to the fixture base and to the bottom of the slide. The resistor body itself rolls in precisely cut wood grooves in the bottom piece and in the slide, to insure that the leads will be centered with respect to the resistor at the same time as they are straightened.

Mica-Splitting Tool

TRIMMED BLOCKS of mica are split into sheets of uniform thickness manually at high speed with a simple bench-mounted splitting tool in the Rio Piedras, Puerto Rico plant of Sylvania Electric of P. R. Inc.

The operator passes each piece under the right-hand cutting tool as often as possible with a quick motion much like that used in cutting cole slaw. If the last piece is obviously too thin for use, it is thrown into a discard hole cut into the bench under the operator's hand. When there is a possibility that the last piece is usable, it is tested by passing under the other cutting tool, which is set to the



PYROFERRIC IRON CORES

- Scientifically manufactured under strictest quality controls to closest electrical and mechanical tolerances.
- Let us engineer your Core production requirements. Our engineering consultant service is available without charge.
- M.P.A. data sheets and tables give complete information including recommended sizes and tolerances, as well as a cross-reference index of manufacturers' material designation.



PYROFERRIC

PYROFERRIC BLDG. | BRONX BOULEVARD at 216th St., N.Y.C. 67

Please send me M.P.A. data sheets and tables No. 305.

NAME _____ TITLE _____

FIRM _____

ADDRESS _____ CITY _____ STATE _____

Write on your letterhead for latest catalog No. 23S.

Want more information? Use post card on last page.



What is your Delay or Regulating Problem?

For the most effective solution use the
**SIMPLEST, MOST COMPACT
MOST ECONOMICAL
HERMETICALLY SEALED**

AMPERITE
THERMOSTATIC DELAY RELAYS

STANDARD

Provide delays ranging from 2 to 120 seconds.

- Actuated by a heater, they operate on A.C., D.C., or Pulsating Current.
- *Hermetically sealed.* Not affected by altitude, moisture, or other climate changes.
- Circuits: *SPST only*—normally open or normally closed.

Amperite Thermostatic Delay Relays are compensated for ambient temperature changes from −55° to +70°C. Heaters consume approximately 2 W. and may be operated continuously. The units are *most compact, rugged, explosion-proof, long-lived,* and—*very inexpensive!*

MINIATURE

TYPES: Standard Radio Octal, and 9-Pin Miniature.

PROBLEM? Send for Bulletin No. TR-81

BALLAST-REGULATORS

T9 BULB

- Amperite Regulators are designed to keep the current in a circuit *automatically regulated* at a definite value (for example, 0.5 amp).
- For currents of 60 ma. to 5 amps. *Operates on A.C., D.C., or Pulsating Current.*
- Hermetically sealed, light, compact, and most inexpensive.





Maximum Wattage Dissipation: T6½L—5W. T9—10W.

Amperite Regulators are the simplest, most effective method for obtaining *automatic regulation* of current or voltage. *Hermetically sealed,* they are not affected by changes in altitude, ambient temperature (−55° to +90°C), or humidity. Rugged; no moving parts; changed as easily as a radio tube.

Write for 4-page Technical Bulletin No. AB-51

AMPERITE CO., Inc. 561 Broadway, New York 12, N. Y.
In Canada: Atlas Radio Corp., Ltd., 560 King St., W., Toronto 2B

Method of holding block of mica as it is rapidly passed under the splitting tool to obtain pieces that are precisely the desired thickness

minimum tolerance limit for thickness.

The splitting blades are carefully ground and sharpened to enter the mica block cleanly for perfect splitting. The angle at which the cutting tool is ground makes it practically impossible for operators to slice their thumbs, and serves also to separate the split sheets without passing them entirely through the splitting tool. Thickness of split is easily controlled by adding or removing shims from under the blades. Both red India mica and green Canadian mica are split in this way.

Fixtures Aid Production of Spiral Coil Filters

WINDING AND ASSEMBLY of spiral coils in various sizes for r-f filters is expedited through use of simple fixtures and production techniques involving only ordinary tools, in the Coamo, Puerto Rico plant of Caribe Aircraft Radio Corp.

The hand-cranked winding fixture employs easily interchanged mandrels for winding spiral coils with various numbers of turns and different spacings, to get desired inductance values. Since heavy enameled wire is employed and none of the coils have more than ten turns, manual rotation of the

ONLY THE LFE 401 OSCILLOSCOPE

Offers all these Important Features



HIGH SENSITIVITY AND WIDE FREQUENCY RESPONSE OF Y-AXIS AMPLIFIER

The vertical amplifier of the 401 provides uniform frequency response and high sensitivity from D-C. Coupled with a sensitivity of 15 Mv./cm peak to peak at *both D-C* and A-C is a response characteristic which is 3 db. down at 10 Mc. and 12 db. at 20 Mc. Alignment of the amplifier is for best transient response, resulting in no overshoot for pulses of short duration and fast rise time. An example of the wide band response of the amplifier is shown in the accompanying photographs.



37.5 Mv., 0.2 μ sec width, 1 μsec sweep full scale



75 Mv., 0.2 μsec width, 1 μsec sweep full scale



LINEARITY OF VERTICAL DEFLECTION

The vertical amplifier provides up to 2.5 inches positive or negative uni-polar deflection without serious compression; at 3 inches, the compression is approximately 15%. The accompanying photographs illustrate transient response and linearity of deflection.

SWEEP DELAY

The accurately calibrated delay of the 401 provides means for measuring pulse widths, time intervals between pulses, accurately calibrating sweeps and other useful applications wherein accurate time measurements are required.

The absolute value of delay is accurate to within 1% of the full scale calibration. The incremental accuracy is good to within 0.1% of full scale calibration.

SPECIFICATIONS

Y-Axis

Deflection Sens. – 15 Mv./cm, p-p
Frequency Response – DC to 10 Mc
Transient Response – Rise Time (10%-90%) 0.035 μ sec
Signal Delay – 0.25 μ sec
Input line terminations – 52, 72 or 93 ohms, or no termination
Input Imp. – Direct – 1 megohm, 30 $\mu\mu$f
Probe – 10 megohms, 10 $\mu\mu$f

X-Axis

Sweep Range – 0.01 sec/cm to 0.1 μ sec/cm
Delay Sweep Range – 5-5000 μ sec in three adjustable ranges.
Triggers – Internal or External, + and –, trigger generator, or 60 cycles, undelayed or delayed triggers may be used.
Built-in trigger generator with repetition rate from 500-5000 cps.

General

Low Capacity probe
Functionally colored control knobs
Folding stand for better viewing
Adjustable scale lighting
Facilities for mounting cameras

PRICE: $895.00

Additional Features:

TRIGGER GENERATOR with variable repetition rate from 500 to 5000 cps.

POSITIVE & NEGATIVE UNDELAYED TRIGGERS and a **POSITIVE DELAYED TRIGGER** are externally available.

An **INPUT TERMINATION SWITCH** for terminating transmission lines at the oscilloscope.

A **FOLDING STAND** for convenient viewing.

FUNCTIONALLY COLORED KNOBS for easier location of controls.

Designed and built *for* electronic engineers, the 401, with its high gain and wide band characteristics, and its versatility, satisfies the ever-increasing requirements of the rapidly growing electronics industry for the ideal medium priced oscilloscope.

Write for Complete Information

LABORATORY for ELECTRONICS, INC.
75-3 PITTS STREET • BOSTON 14, MASS.

PRECISION ELECTRONIC EQUIPMENT • OSCILLOSCOPES • MAGNETOMETERS • COMPUTERS • MICROWAVE OSCILLATORS

Locate line faults instantly at ranges 1/2 to 200 miles

Model 124 Line Fault Analyzer

Now you can locate power, telephone or telegraph line faults instantly and accurately under all weather conditions. Sierra Model 124 Analyzer eliminates virtually all lost time, hard work and hazard of finding breaks, shorts, opens or other discontinuities. Operating from a powerhouse, transformer bank, substation or terminal point, it pinpoints faults from ½ to 200 miles away with accuracy of ±1 mile on the 200 mile range.

The Analyzer operates on radar techniques, sending a high amplitude pulse along a conductor and presenting echoes from discontinuities as pips on a radar-type "A" scope. Operation is extremely simple, and distances are read direct in miles. Calibrated sweep ranges of 5, 25, 50 and 100 miles are provided. A sweep delay extends range to 200 miles, or permits line segments as small as five miles to be presented full-screen. A movable distance marker can be ranged from 5 to 100 miles.

Model 124 weighs just 59 pounds; and is completely contained in a weatherproofed carrying case.



Figure 1

Test on 60 kv line, instrument on 100-mile sweep. Negative pip to right of center indicates line grounded at 60 miles. Other pips are switchyards, transformer bank, substation tap, carrier coupling capacitor, change in line configuration.

For complete details, see your Sierra sales representative or write direct for Bulletin 102A

sierra

Sierra Electronic Corporation
San Carlos, California, U.S.A.
Sales representatives in major cities

Manufacturers of Carrier Frequency Voltmeters, Wave Analyzers, Directional Couplers, Wide-Band RF Transformers, Custom Radio Transmitters.

Copyright 1953 Sierra Electronic Corporation

2768



Winding a spiral coil by guiding wire onto spiraled mandrel with left hand while turning crank of mandrel with right hand. Mandrels for other coils are stored in holder at left

arbor is entirely satisfactory.

To wind a spiral coil, the operator first inserts the wire into the proper hole in the base of the fixture and bends it at right angles to form the starting lead for the coil. This lead is now inserted in the slot in the mandrel, and the coil is wound by guiding the wire in the spiral grooves with the left hand while turning the crank with the right hand. When winding is completed, the arbor is locked in position, slot upward, by tightening a knurled nut over its shaft. With long-nose pliers, the end of the winding is squeezed down flat against the diameter of the half-round end of the arbor. A quarter-round pin is now pushed in from the left and the wire is squeezed

Forming lead for spiral coil to correct shape with long-nose pliers

New ELECTRICAL TUBING gives Better Performance 5-WAYS



Here's why...

VARGLAS Tubing is now impregnated with G. E. PERMAFIL

Here's how...

1 BETTER DIELECTRIC RETENTION

. . . 7,000 volts — and keeps its high dielectric value under toughest service conditions.

2 BETTER FLEXIBILITY

. . . twist it — tie it — bend it — wrap it! No crack — no peel — no dielectric loss.

3 BETTER HEAT RESISTANCE

. . . withstands more than 2,000 hours at 105° to 110° C — 1,000 hours at 125° C — extensive periods even at 150° C.

4 AVAILABLE IN COILS

. . . so that you can cut the length you need — no more, no less, no waste. Standard colors — wide range of sizes — meets or exceeds all A.S.T.M. specifications.

5 CAN BE AFTER-TREATED

. . . in baking and varnishing operations. Reacts better than most oleoresinous materials and other synthetic coated tubings.

Send for FREE Sample — Full Information

Varflex CORPORATION

Makers of Electrical Insulating Tubing and Sleeving

VARFLEX Corporation, 308 Jay St., Rome, N. Y.

Please send me full information as well as a free sample of your new Varglas Tubing impregnated with General Electric Permafil. I am particularly interested in samples suitable for .....

Name .....

Company .....

Street .....

City ..... Zone ..... State .....

MOUNT 6 OPEN RELAYS
IN THIS SPACE

DECOHM TYPE D-3

miniaturized telephone type

"Molded Coil" Relay

Nickel silver springs used
Twin or single contacts rated from 1 to 5 amps
Coil resistance 1 to 10,000 ohms
Dimensions: 11 16 x 1-3 8 x 1-7 16 inches
Phosphor bronze hinge pin for longer life

"Molded Coil" construction provides "protection plus" in a competitively priced relay!

The Decohm D-3 relay is a small, compact, highly sensitive relay built to meet exacting military standards. Its size, range and sensitivity make it an ideal relay for all types of communications, aeronautical and industrial applications. The coil of the D-3 is sealed in a homogeneous mass which makes it impervious to most adverse ambient operating conditions. The molded coil dissipates heat readily and promotes longer relay life.

SPECIFICATIONS

CONTACT COMBINATIONS: Forms A-B-C-D-E-F-G-H 12 springs maximum
CONTACT MATERIAL: 2 amp. twin palladium contacts are standard
OPERATING VOLTAGE: 1 to 150 volts DC
OPERATING TIME: .009 sec. min. to .035 sec. max. .004 seconds standard
COIL PROTECTION: Coil completely imbedded in molded plastic. Withstands toughest moisture and humidity requirements and temperatures from -70 C to +140 C. Will operate one normally open contact on ⅛ watt, or 4 double throw contacts on less than 1 watt and still meet a 10G vibration test.



OPERATING CHARACTERISTICS — The graph curve shows coil temperature rise above ambient with zero to 4 watts applied to the D-3 relay coil.

Write for

DAVIS ELECTRIC COMPANY
Cape Girardeau, Missouri
Manufacturers of
"Molded Coil" and Hermatically Sealed Relays, TV Yokes, Electrical Assemblies

Fixture used for holding disc capacitors in position while soldering to spiral coils. Empty grooves at top are for another type of filter

axially against this so the terminating lead of the coil is exactly in line with the axis of the coil. The quarter-round pin is then retracted and the lead is cut to complete the winding.

A typical filter uses three button-type ceramic capacitors and two coils. A coil lead is inserted in the center hole of the capacitor and a hook-joint is formed on the other side, to which is hooked a similar joint in the lead of the other coil. These joints are crimped with



Pulling r-f filter assembly into housing. Soldering iron holder on bench is made from pipe and pipe fittings. Holder for solder spool is U-shaped piece of scrap iron screwed to bench, with spun-on terminals projecting inward from ends to serve as shaft. Solder spool is removed by spreading end supports apart

FREQUENCY STANDARDS *Modular system*

DESIGNED AS A

The Type 2001-2 series provides frequencies from 30 to 30,000 cycles with an accuracy of .001% (at room temperatures) in units suitable for integration with instruments of your own design — or for panel rack mounting with your own power sources — or for line operation.



WHICH WILL MEET YOUR
CUSTOM NEEDS
FROM A COMBINATION OF
STOCK UNITS

TYPICAL COMBINATIONS

2001-2	2001-2 + M
2001-2 + L	2001-2 + M + P
2001-2 + L + P	2001-2 + L + P + R
2001-2 + H	2001-2 + H + P + R
2001-2 + H + P	2001-2 + M + P + R

TYPE "2001-2" FREQUENCY STANDARD
Frequencies, 200 to 3,000 cycles. Output, approximate sine wave at 5 volts.

ACCESSORY UNITS

"L" UNIT.
DIVIDER, (MULTI-VIBRATOR TYPE)
Provides frequencies from 30 to 200, controlled by the 2001-2 unit.
Output, approx. 5V. Approx. sine wave.

"M" UNIT
AMPLIFIER
Provides 2 watts at 6 and 110 volts.

"D" UNIT.
DIVIDER, (COUNTER TYPE)
Provides 40 to 200 cycles controlled by the 2001-2 unit. (fail safe)

"P" UNIT
POWER SUPPLY
Provides power for combinations of units illustrated, if other sources are inconvenient or not available.

"H" UNIT
MULTIPLIER
Provides frequencies from 3,000 to 30,000 cycles, controlled by the 2001-2 unit. Output, approximately 5 volts.

"R" UNIT
PANEL MOUNTING
Accommodates up to three units. Standard size is 8¾ inches high, 19 inches long.

For details, please request our "Type 2001-2" Booklet.

American Time Products, Inc.

580 Fifth Avenue ***New York 36, N.Y.***

OPERATING UNDER PATENTS OF WESTERN ELECTRIC COMPANY

IT'S TIME FOR TALK OF DOLLARS AND SENSE in

Buying Shielded Enclosures

for suppressing r-f interference

If you're thinking of buying a shielded enclosure, chances are you'll be faced with technical claims that are apt to be confusing. Worse yet, you might end up with an enclosure that does not come up to *your interpretation* of the claims, or does not maintain its initial rating. It pays to investigate.

To help you in choosing the best enclosure for your needs, Ace has just prepared a booklet which interprets the confusing nomenclature of this fast-growing industry. Written by Richard B. Schulz, Electro-Search, consulting engineer for Ace, it enables you to evaluate answers to such questions at the right . . . questions you must ask to get your money's worth. You'll quickly learn whether a manufacturer's claims are based upon guaranteed measurements or *just plain guesswork!*

HOW TO GET WHAT YOU PAY FOR

Ask the manufacturer these questions—

1. What is the guaranteed attenuation (not insertion loss) of your shielded enclosure from _____mc to _____mc?
2. Is this guarantee based upon actual test data?
3. If so, what is your method of measurement and by whom performed?
4. Does this method measure the attenuation to (a) a plane wave, (b) an electric induction field, or (c) some combination of these?
5. Were power line filters installed at time of measurement? If so, which filters?
6. Is the guaranteed attenuation of power line filters (terminated in 50 ohms) at least as high as overall room attenuation over same frequency range?
7. What test data support this guarantee?
8. Is the enclosure bolted from the inside or the outside?
9. Are panels interchangeable? Can the door be placed in any wall position, including corners, without special adaptation?
10. Can the room be increased in width as well as in length?

Write for *Your Money's Worth in Shielded Enclosures.* IT'S FREE.

Send for FREE booklet that tells you how to evaluate the answers to these important questions.

Ace Shielded Enclosures

First and Still Finest By Every Measuring Standard

The highest attenuation known to the electronic industry . . . attenuation over the widest frequency range—these are characteristic of Ace Shielded Enclosures. Years of shielding production, coupled with the knowledge of the nation's top shielding engineers give you the ultimate in shielding effectiveness.

There's no guesswork with Ace, just plain fact. And reams of guaranteed test data to back it up. Every enclosure design is thoroughly tested and approved by independent engineering laboratories to clearly prove their full value. That's why, year after year, Ace remains the country's largest shielded enclosure manufacturer . . . with more satisfactory installations than any other.

A COMPLETE LINE OF SCREEN ROOMS
FOR INDUSTRY, SCIENCE, AND MILITARY
JAN-1-225; 16E4 (ships); MIL 16910; MIL-S-4957
(Write for Engineering Bulletin No. 3)

ACE ENGINEERING & MACHINE CO., INC.

3644 N. Lawrence Street • Philadelphia 23, Pennsylvania

Soldering disc capacitors into position through drilled holes in housing. Wood block is used as grip so operator does not burn fingers

pliers, then the two end capacitors and an external lead are similarly attached. The assembly is now placed in a half-round positioning fixture having correctly spaced grooves for the capacitors, and all joints are soldered.

The filter assembly is next inserted in its metal housing by threading the insulated lead through the hole in the end of the housing and using this lead to pull the coils and capacitors in. The flexible lead is now pushed into a drilled hole in a wood block to provide a heat-insulating handle for the next operation, that of soldering the edges of the capacitor discs to the housing. For this operation, a soldering iron having a pointed tip is supported vertically, point down, by a holding fixture made from pipes and fittings. Each soldering hole in turn is carefully brought up to the tip of the iron and solder is applied inside the hole. Extreme care is required here to prevent the solder from getting outside the hole, as the hot solder might burn off the silver plating from the filter shield.

Storage In Mason Jars

BECAUSE DEPOSITED carbon resistors can rarely be produced to a specific resistance value and tolerance by the electric oven batch process, the carbon-depositing department must keep well ahead of the assembly line in the San Juan,

EVENLY Wind

SMALL TOROIDAL COILS AT HIGH SPEEDS WITH MINIMUM WIRE BREAKAGE

The MICAFIL Model RW-0 Toroidal Coil Winder automatically winds toroidal coils continuously around 360° and sector coils from 30° to 180°. To produce smooth, even layers of wire, the winder is adjusted easily to wind any wire size between 26 and 45 AWG and to obtain the proper pitch. Winding direction can be changed and feeds can be adjusted while machine is in operation.





CAPACITY

Coil Sizes
- Minimum finished I.D. . . . . ¼"
- Maximum finished O.D. . . . . 2"
- Minimum finished O.D. . . . . ½"

Wire Sizes . . . . . 26 to 45 AWG

Winding Speed—
according to wire size . . up to 800 rpm

Shuttle Capacity—
according to wire size . . . . 48 to 500 ft.

MICAFIL Toroidal Coil Winders are made in three larger sizes for winding coils up to 8" O.D. and with 11 AWG Wire.

SPIRALING DEVICE—Device winds spirals for shuttle loads—in advance . . . Newly developed to permit continuous operation of Coil Winder . . . Winds to predetermined lengths.

SHUTTLES—Made in four different ring diameters to accommodate range of spiraled wire sizes . . . Larger wire capacities . . . *More than one coil can be wound with single loading* . . . Changed within 2 minutes . . . Loaded in less than a minute.

ACCURATE MECHANICAL TURNS COUNTER—Preset for required number of turns . . . Automatically stops winder when turn count is reached.

Let Cosa Engineers study and recommend the winder for your needs. Or, write for Literature.

COSA CORPORATION
405 Lexington Ave., New York 17

Your source for all Precision Machine Tools — from Small Bench Lathes to Large Boring Mills

IN DETROIT AREA contact COSA CORPORATION of Detroit, 16923 James Couzens Highway, Detroit 35, Mich.

Want more information? Use post card on last page.



ANTENNA

research, development and production

As one of the pioneers in antenna research and development, the Gabriel Laboratories has built a solid background of experience in handling all types of Antenna problems — both military and civilian.

On our staff are several of the top ranking antenna specialists in the country. The research and test facilities include a number of microwave pattern ranges, altitude and temperature chambers, and the usual measurement and test equipment necessary to determine antenna performance and characteristics in the entire radio and microwave spectrum.

The government and many of the country's largest electronic companies have come to the Gabriel Laboratories for aerial development and subsequent large scale production by our affiliates: — the Workshop Associates Division and Ward Products Corporation, divisions of the Gabriel Company.

A GABRIEL PRODUCT

THE GABRIEL LABORATORIES

Division of the Gabriel Co.

135 Crescent Road, Needham Heights, Mass.

Mason jars on racks provide dust-proof storage for deposited carbon resistor bodies. Masking-tape labels are placed high enough on jar so that low stocks can be easily noted

Puerto Rico plant of Radell Corp. Batches of resistor bodies are fired, then automatically measured and sorted into different resistance ranges well in advance of needs. From this stock, units are drawn for processing to fill current orders.

Ordinary mason jars prove ideal for storing the reserve stock of resistor bodies. Their clear glass permits quick visual inspection of the supply on hand, so that subsequent oven batches can be aimed for the low points in the stock. The resistance value and range in each jar are identified by lettering on labels cut from masking tape. White enameled screw-type covers proved most satisfactory for the jars.

Staking Hinge Bar for Aircraft Relay

A STAINLESS STEEL pin is staked onto each end of the hinge bar assembly for an aircraft relay in one punchpress operation at the San Juan, Puerto Rico plant of Phillips Control Corp.

Each pin has a knurled end which is forced into the hole in the bar in a preliminary operation. The bar is then set into the positioning fixture on the bed of the press with long tweezers; these minimize finger accidents.

As the press descends, a spring-loaded pin comes down first and

On land . . . on sea . . . in the air . . .

"THERE'S NO JOB TOO TOUGH FOR A HUSKY!"

For quality, efficiency and reliability - select the relay you need from Price Electric's complete line. A few of the many types available appear on this page. A more complete listing and description is available in our *Relay Reference Folder*, which will be sent free upon request.

HUSKY relays consistently meet the most exacting specifications and perform their required functions under the most adverse conditions.

SERIES 5002-A RELAY
(AN 3320-1)
(MIL-R-6106)

CONTACTS: S.P.N.O. rated 25 Amps resistive.
COIL VOLTAGE: 26.5 Volts DC.



BALANCED ARMATURE RELAY
SERIES 1200

CONTACTS: D.P.D.T. rated 3 Amps at 115 Volts AC, non-inductive.
COIL VOLTAGE: 3 to 48 Volts DC.
MAXIMUM COIL RESISTANCE: 8500 Ohms.
AVAILABLE HERMETICALLY SEALED

SERIES 5724-IHS RELAY
(AN 3304-1)
(MIL-R-6106)

CONTACTS: 4 from C, rated 3 Amps at 115 Volts AC, non-inductive.
COIL VOLTAGE: 26.5 Volts DC.

MINIATURE HERMETICALLY SEALED RELAY
SERIES 700 HS

CONTACTS: D.P.D.T. rated 2 amps at 115 Volts AC, non-inductive.
COIL VOLTAGE: 6 to 48 Volts DC.
MAXIMUM COIL RESISTANCE: 4000 Ohms.
HERMETICALLY SEALED ONLY

ROTARY STEPPER
SERIES 8400

Drives up to 3 wafer switches (or other load not exceeding 8½ inch-ounces total torque).
CONTACTS: Make-Break or Break-Make.
COIL VOLTAGE: 6 to 115 Volts DC.

CO-AXIAL RELAY
STYLE 6394

CONTACTS: S.P.D.T. rated at 100 Watts (RF Load).
COIL VOLTAGE: *AC*—115 or 230 Volts.
DC—6 to 110 Volts.

HIGH VOLTAGE RELAY
STYLE 6225

CONTACTS: S.P.D.T. (Double-Break) rated 10 Amps at 115 Volts AC, Cold Break, non-inductive.
COIL VOLTAGE: 115 Volts, 60 cycles AC or 130 Volts, 60 cycles AC.

LONG FRAME TELEPHONE-TYPE RELAY
SERIES 5900

CONTACTS: 12 form *A* or 8 form *C*, rated 3 Amps at 115 Volts AC, non-inductive.
MAXIMUM COIL RESISTANCE: 20,000 Ohms.
COIL VOLTAGE: 6 to 230 volts DC or AC.
AVAILABLE HERMETICALLY SEALED

SYNCHRONOUS TIME DELAY RELAY
SERIES 4050

CONTACTS: S.P.N.O. to D.P.D.T. rated 10 Amps at 115 Volts AC, non-inductive.
COIL VOLTAGE: 115 Volts, 60 cycle AC or 230 Volts, 60 cycle AC.
TIME INTERVALS (FIXED): 15 sec. to 15 min.
AVAILABLE HERMETICALLY SEALED

MIDGET RELAY
SERIES 1030

CONTACTS: D.P.D.T., rated 2 Amps at 115 Volts AC, non-inductive.
COIL VOLTAGE: 3 to 24 Volts DC.
MAXIMUM COIL RESISTANCE: 8500 Ohms.
AVAILABLE HERMETICALLY SEALED

RELAY REFERENCE FOLDER A handy guide to Husky relays, containing photographs and specifications of 42 types. Helps you find the type relay you need in just a few seconds. Address request to Dept. NS.

Price Electric CORPORATION

1500 CHURCH, FREDERICK, MARYLAND

PRICE ELECTRIC CORP., FREDERICK, MD. HUSKY RELAYS, CONTROLS

Pick 'DIAMOND H' RELAYS

Shown Actual Size

...FOR HIGHER VIBRATION RESISTANCE

Vibration resistance range of "Diamond H" Series R Relays has been more than doubled, extending now from 0 to well over 1,000 cycles per second at 15 "G's."

Continuing engineering developments such as this are constantly broadening the adaptability of Series R Relays for a wide variety of applications . . . guided missiles, jet aircraft, fire control and detection, radar, communications, high speed camera, geophysical and computer apparatus . . . and similar applications requiring positive operation under critical conditions.

Hermetically sealed, miniature aircraft relays, Series R devices are basically 4PDT, but are also available in DPDT and 4PDT with two independent coils, either or both of which will operate the unit. Available with all standard mounting arrangements, including ceramic socket for interchangeability. Their design permits unusually compact grouping and provides a firm bond between relay and chassis. See us for special arrangements.

In their field still the smallest and lightest, (1.6 cu. in., 3.76 oz.) combining highest operating shock resistance (to 50 "G" and higher), widest temperature range (−65° to +200° C.) and greatest ability to break high currents and high voltages, Series R Relays consistently operate over 400,000 cycles without failure at 5 A. and go 3,500 or more under 30 A. at 30 V., D.C., resistive. They carry voltages up to 300 D.C. at 4/10 A. for more than 400,000 cycles. With low contact loading, life expectancy is 10 million cycles or better.

Operating time is 10 ms. or less; drop out time 3 ms. or less. Coil resistances up to 35,000 ohms are standard; to 50,000 ohms available for special units. Sensitivity approaches 100 mw. at 30 "G" operational shock resistance. Inter-electrode capacitance is less than 5 mmf. contacts to case—less than 2½mmf. between contacts, even with plug-in type relay and socket.

Designed to meet all requirements of USAF Spec. MIL-R-5757B, they far surpass many. Bulletin R-150, giving basic performance data under varying conditions, is yours on request. Our engineers are prepared to work with you to develop variations to meet your specific requirements. Tell us your needs.

THE HART MANUFACTURING COMPANY

202 Bartholomew Avenue • Hartford, Connecticut



Method of using tweezers to insert aircraft relay hinge bar in press for staking bearing pins. Finished bar can be seen on bed of press

holds the hinge bar tightly in position. At the same time, two cam-driven pins force the two stainless steel hinge pins in to the correct depth and hold them there while staking rods on each side of the spring-loaded center pin come down and stake the hinge bar over the shanks of the pins.

Lead-Forming Fixture

METAL PEGS IN wood blocks serve both as centering guides and as forms for bending loops in leads for small components prior to assembly on terminal boards. When loops are formed in this manner at the correct points in the leads, the parts can be rapidly dropped over the wrap-around pins on terminal boards at subassembly positions. A quick squeeze of each loop with pliers provides the mechanical strength for mounting the parts on their terminals. This technique is used at Caribe Aircraft Radio



Method of preforming leads of mica capacitor with the aid of pegs on a wood block. Unused pins here serve for positioning another type of component and forming its leads. Library of blocks is maintained to take care of all parts used on the terminal boards

FREED *Instruments & Transformers*

Famous For **QUALITY · DEPENDABILITY · ACCURACY**



No. 1030
Low Frequency "Q" Indicator



No. 1020B
Megohmmeter



Decade Inductors

No. 1040
Vacuum Tube Voltmeter

FREED

HIGH FIDELITY-HIGH LEVEL OUTPUT TRANSFORMERS

The Freed "Quality Grade" audio transformers are wide band, high fidelity components featuring astatic construction, longitudinal balance, low harmonic distortion, uniform response, high efficiency, and constant impedance match throughout the audio frequency spectrum. Maximum neutralization of stray fields is accomplished by use of humbalanced coil structures and multiple alloy shielding. High fidelity is achieved on every tap of the universal impedance winding without line reflection or transverse coupling.

All Quality Grade Components are thoroughly impregnated in a special non-hygroscopic varnish, and fully encapsulated in a moisture proof, high melting point compound.

TUBES TO LINE, TUBES TO VOICE COIL, LINE TO LINE, LINE TO VOICE COIL									
CATALOG	APPLICATION	IMPEDANCE LEVEL OHMS PRIMARY	SECONDARY	MAXIMUM POWER LEVEL V.U.*	RATIO	MAX PRI DC PER SIDE Ma.	D.C. UNBAL. Ma.	FREQ. RESPONSE C. P. S.	CASE NUMBER
QGA 25	PP 2A3, 6B4, 6L6 300A, 275A to Univ. 500 ohm line	5,000 SPLIT	U-500	+42 (15 WATTS)	3.16:1	50	5	±0.5 DB 20-30000	DC-5BT
QGA 26	As above to Universal Voice Coil	5,000 SPLIT	U-16	+42	17.7:1	50	5	±0.5 DB 20-30000	DC-5BT
QGA 27	Push-pull 6V6, 6AQ5, 7C5, 6M7 to Univ. 500 ohm line	8,000 SPLIT	U-500	+42	4:1	50	5	±0.5 DB 20-30000	DC-5BT
QGA 28	As above to Univ. Voice Coil	8,000 SPLIT	U-16	+42	22.4:1	50	5	±0.5 DB 20-30000	DC-5BT
QGA 29	P.P. 6F6, 6V6, 6AQ5, 7C5, 7B5, 6AR5, 6K6, 6L6 to Universal 500 ohm line	10,000 SPLIT	U-500	+42	4.47:1	40	4	±0.5 DB 20-30000	DC-5BT
QGA 30	As above to Universal Voice Coil	10,000 SPLIT	U-16	+42	25:1	40	4	±0.5 DB 20-30000	DC-5BT
QGA 31	P.P. 807, 1614, KT-66, (Williamson Amplifier) to Univ. 500 ohm line	10,000 SPLIT	U-500	+45.5 (36 WATTS)	4.47:1	50	5	±0.5 DB 20-30000	DC-6AT
QGA 32	As above to Universal Voice Coil	10,000 SPLIT	U-16	+45.5	25:1	50	5	±0.5 DB 20-30000	DC-6AT
QGA 33	P.P. Parallel 2A3, 6A5G, 300A to Univ. 500 ohm line	2,500 SPLIT	U-500	+45.5	2.24:1	100	10	±0.5 DB 20-30000	DC-6AT
QGA 34	As above to Universal Voice Coil	2,500 SPLIT	U-16	+45.5	12.5:1	100	10	±0.5 DB 20-30000	DC-6AT
QGA 35	P.P. 6L6 or P.P. Parallel 6L6 to Univ. 500 ohm line	3,800 SPLIT	U-500	+47 (50 WATTS)	2.75:1	130	13	±0.5 DB 20-30000	DC-7BT
QGA 36	As above to Universal Voice Coil	3,800 SPLIT	U-16	+47	15.4:1	130	13	±0.5 DB 20-30000	DC-7BT
QGA 37	High level multiple line to Universal Voice Coil	U-500	U-16	+42	5.6:1	0	0	±0.5 DB 20-30000	DC-5BT
QGA 38	High level multiple line to Universal Voice Coil	U-500	U-16	+47	5.6:1	0	0	±0.5 DB 20-30000	DC-7BT

U-16 IMPEDANCES IN OHMS
2, 4, 8, 12, 16

U-500 IMPEDANCES IN OHMS
50, 123, 200CT, 250, 330, 500CT
125 and 500 ohms can be used for 150 and 600 ohms

SEND FOR COMPLETE CATALOG OF FREED INSTRUMENTS AND TRANSFORMERS

No. 1210
Null Detector & Vacuum Tube Voltmeter

No. 1010
Comparison Bridge



No. 1110A
Incremental Inductance Bridge

FREED TRANSFORMER CO., INC.

1728 WEIRFIELD ST. (RIDGEWOOD) BROOKLYN 27, N.Y.



A bank of MICRO switches in the floor selector of a Montgomery automatic elevator.

MICRO switches help make Montgomery Elevators *Automatic*

Every time you push a button in a Montgomery automatic elevator a MICRO switch is actuated.

Engineers of the Montgomery Elevator Company, one of the largest manufacturers of automatic elevators, selected MICRO switches because of these important characteristics:

- **Millions of accurate repeat operations**
- **Positive snap-action opening and closing**
- **Totally enclosed dust-resistant contacts**
- **Absolute repetition of motion**
- **Long-life dependability**

From 6 to 24 switches are used per floor control, depending on the number of automatic functions performed. The usual installation consists of six MICRO switches per floor. These stop the elevator as directed by the up and down buttons, control the car direction and the floor signal lights.

This choice of MICRO switches by Montgomery engineers is typical of the confidence placed in these small, precise, dependable switches by designers in every phase of industry. MICRO switch engineering service, based on skill and experience in every type of electrical switching problem, is available for cooperation with you and your design staff. Let MICRO engineers help you select the right switch for your application. Call or write the nearest MICRO branch office.

MICRO
MAKERS OF PRECISION SWITCHES
FREEPORT, ILLINOIS

A DIVISION OF
MINNEAPOLIS-HONEYWELL REGULATOR COMPANY



Operator can drop components quickly over terminals on board when leads have preformed loops

Corp., Coamo, Puerto Rico in connection with the manufacture of military radar equipment.

Sealing Paper Capacitors

RAPID assembly and sealing of tubular paper capacitors is achieved at Pyramid Electric Co. through use of mounting racks that hold about 60 capacitor tubes. The tubes are placed between two strips of wood in a jig that sets over a height-controlling wood strip mounted on the bench. After loading a jig, the

Placing capacitor tubes in jig. A wooden strip on the table beneath the rack keeps all the tubes at the proper height until thumbscrews are tightened



- RESEARCH
- ENGINEERING
- CRAFTSMANSHIP
- PRECISION
- PRODUCTION
- DELIVERY
- QUALITY

THE INSIDE STORY

Top quality means top performance after long service. Bliley quality control far exceeds the perfunctory steps necessary to produce and ship crystals which meet a nominal specification.

Bliley precision process techniques, rigidly followed in orientation, slicing, lapping, and plating guarantee peak crystal performance. That extra touch of engineering and craftsmanship makes the big difference in your equipment.

That's the Bliley inside story!

Bliley CRYSTALS

BLILEY ELECTRIC COMPANY

UNION STATION BUILDING • ERIE, PA.

Want more information? Use post card on last page.

RYAN
Ryan Aeronautical Company is another of the world-famous manufacturers who rely on nationally known
KAY-LAB PRECISE ELECTRONIC EQUIPMENT



Only KAY-LAB ABSOLUTE D. C. POWER SUPPLIES provide
.01%
STABILITY
REGULATION
CALIBRATION

precisely!
KAY LAB
SEND NOW FOR COMPLETE DETAILS FREE!
for electronic instruments

KALBFELL LABORATORIES, INC.
1090 MORENA BLVD.
SAN DIEGO 10, CALIFORNIA

Only SMITH
Phone Tip and Banana Plugs have MOLDED Plastic Handles

SMITH is FIRST to provide phone tips and banana plugs with precision-molded plastic handles for better fit, durability, and appearance. Depend on SMITH for the best and newest in electronic connecting devices. Whether your needs can be filled from the standard lines in our catalog, or whether you require special components or assemblies, we welcome your inquiries. Write Dept. E for FREE catalog No. 53-A, the industry's most comprehensive presentation of connectors, with complete pictorial and schematic data.

ELECTRONIC COMPONENTS
TV ACCESSORIES
PLUGS, JACKS
SWITCHES, TEST LEADS
HARDWARE

HSH INC.
HERMAN H. SMITH, INC.
2326 NOSTRAND AVENUE, BROOKLYN 10, N. Y.

Capacitor bodies are inserted in tubes and ends of leads bent over rods to insure proper centering

tubes are locked in position by tightening thumbscrews at each end. On each jig are two metal rods, one running over each end of the paper tubes.

At another work position, a capacitor body is inserted in each tube and the ends of their pigtails are bent over the rods to hold the capacitor centered in the tube.

In the final step of the process, cement is applied to each end of the capacitor through the nozzle of a trigger-operated gun. The gun, operating at 60 to 80 lb air pressure, makes it possible for the operator to control the flow of cement precisely, filling each unit completely and smoothly without overflow.

Squirting cement into ends of tubular paper capacitors with high-pressure cement gun. Racks are inverted for filling other ends of units


CATHODE LIFE
THE INCREASE IN LIFE FOR SUBNORMAL VOLTAGES MAY NOT BE REALIZED IN ALL TUBES DUE TO SECONDARY EFFECTS.
CATHODE EMISSION
① OXIDED COATED
② THORIATED TUNGSTEN
③ PURE TUNGSTEN
PER CENT TUBE EMISSION (MAX AVAILABLE CURRENT)
PER CENT CATHODE HEATER VOLTS

ELECTRONIC TUBE-LIFE VS. VOLTAGE

Current-carrying ability of all electronic tubes is affected seriously by voltage deviation. The loss of emission at undervoltage results in shorter tube life. Curve 1 "Oxide Coated" applies to most of the thyratrons, pliotrons and receiving tubes. Curve 2 "Thoriated Tungsten" applies to small transmitter tubes and some battery-heated tubes. Curve 3 "Pure Tungsten" applies to oscillator tubes.

For maximum tube life and performance, include G-E Inductrols as "original equipment"

Automatic voltage regulation provides an effective and economical means of avoiding losses in power capacity

The life and efficiency of the electronic equipment you manufacture depends, to a large extent, on the performance of the electronic tubes. Tube life is adversely affected by over- or under-voltage conditions *that can easily be prevented.*

G-E dry-type induction voltage regulators, called Inductrols, offer you an effective and economical means of maintaining correct operating voltage. Two types are available for indoor service on circuits 600 volts and below, single-phase 3 to 240 kva; three-phase 9 to 520 kva.

1. **Automatic** Inductrols maintain a closely regulated output voltage from a varying supply voltage with a bandwidth of ±1%. The standard range of regulation is plus and minus 10%.
2. **Hand-operated or manually controlled motor-operated** Inductrols provide a variable output voltage from a relatively constant supply voltage. They supply 100% raise and 100% lower regulation.

You can put your confidence in—

GENERAL ELECTRIC

Typical applications for G-E Inductrols that have proved highly effective include: radar equipment, induction heating equipment, medical and industrial x-ray equipment, TV and radio transmitters.

For further information, contact your nearest G-E sales office, agent or distributor...or return the attached coupon.

HERE'S HELPFUL G-E DATA ON INDUCTROLS

For full details on dry-type induction voltage regulators, return this coupon . . . today!

Single-phase INDUCTROLS, indoor service 600 volts and below on circuits 3 to 240 kva—GEC-795A ☐

Three-phase INDUCTROLS, indoor service 600 volts and below on circuits 9 to 520 kva—GEA-5824 ☐

Application bulletin, Inductrols and electronic equipment—GEA-5936 ☐

General Electric Company
Section C423-201, Schenectady 5, N. Y.

Name _____

Company _____

Address _____

City _____ **Zone** _____ **State** _____

NEW PRODUCTS

Edited by WILLIAM P. O'BRIEN

Control, Testing and Measuring Equipment Described and Illustrated . . . Recent Tubes and Components Are Covered . . . Fifty-Four Trade Bulletins Reviewed

OTHER DEPARTMENTS:
featured in this issue:

	Page
Electrons at Work	198
Production Techniques	244
Plants and People	412
New Books	453
Backtalk	464



TRANSISTORS
of all-welded metal

GENERAL ELECTRIC CO., Syracuse, N. Y., is producing a new line of junction transistors that are evacuated, hermetically sealed and of all-welded metal construction. The welded metal construction allows power ratings of almost 1 watt, with two units in a class-B push-pull circuit. They have been demonstrated to operate under water at temperatures up to 100 C.



TINY PENTODE
is heater-cathode type

RADIO CORP. OF AMERICA, Harrison, N. J. The 5840 is a premium sharp-cutoff pentode of the subminiature type for use primarily as a broad-band r-f or i-f amplifier in mobile and aircraft receivers where dependable performance under shock and vibration is a prime consideration. It features a pure-tungsten heater to give long life under conditions of frequent on-off switching and three leads to the cathode to permit isolation of the input and output circuit returns and to reduce the cathode lead inductance.



MODULAR SYSTEM
of digital pulse units

AUDIO PRODUCTS CORP., 2265 Westwood Blvd., Los Angeles 64, Calif. The modular system of digital pulse units consists of 16 electrically and mechanically compatible modulars that perform all the basic functions of digital pulse operations, such as gating, pulse forming, counting and coincidence marking, as well as simpler electronic tasks like amplification, signal inversion and impedance matching. In operation the modulars are easily assembled, firmly linked together by mechanical means and quickly interconnected by patch cords. Thus design and development engineers can readily operate in the most complex systems at block diagram level without concern for circuit details. Since each unit (size—2¾ in. high × 4½ in. wide × 9 in. long) performs a multiplicity of independent functions selectively, a complete system consisting of 16 modular units and a regulated power supply has a capability of 72 separate functions with as many as 31 functions simultaneously available. Simple digital instruments can be quickly patched up by using the modular system.



TV TUBE
aids noise suppression

SYLVANIA ELECTRIC PRODUCTS INC., 1740 Broadway, New York 19, N. Y., has announced a new tube, type 6CS6, designed for combined sync-separator, noise-suppressor use. It is designed to be used in circuits that accomplish sync separation by feeding the video signal extending in a positive direction to grid three where the negative grid-leak bias development automatically adjusts the clipping level. Noise suppression is obtained in the 6CS6

FOR YOUR EQUIPMENT-



Specify Types from the Finest—most Complete Line of Premium Subminiature Tubes

Sylvania Research and Engineering pioneered the development of the cathode-type subminiature tube.

For more than a decade, engineering and production efforts have been directed towards the evolution of this premium line of high reliability types.

Many of the types listed were originally sponsored by the Armed Services. Others have been designed by Sylvania to furnish additional reliable types required for newer applications. Beyond this, there are other types not listed above which are presently undergoing active development.

Outstanding Design Features

- **Low inoperative failure rate**
- **Stable characteristics**
- **Long life**
- **Fatigue and impact resistant**
- **Vibration resistant**
- **High temperature operation**

all originated by Sylvania

5636 Pentode Mixer	†**5907** Semi-remote Cut-off Pentode
5639 Video Output Pentode	†**5908** Pentode Mixer
5641 Rectifier	*__5916__ Pentode Mixer
5643 Thyratron	**5977** Low Mu Triode
5644 Voltage Regulator	**5987** Power Control Triode
5647 T-1 Detector	**6021** Medium Mu Double Triode
5718 Medium Mu Triode	**6110** Double Diode Detector
5719 High Mu Triode	**6111** Low Mu Double Triode
5840 Sharp Cut-off Pentode	**6112** High Mu Double Triode
5896 Double Diode Detector	**6153** Sharp Cut-off Pentode Low Cgp (Separate suppressor)
5899 Semi-remote Cut-off Pentode	**6154** Remote Cut-off Pentode Low Cgp (Separate suppressor)
5902 Audio Power Pentode	**6205** Sharp Cut-off Pentode (Separate suppressor)
*__5903__ Double Diode Detector	**6206** Semi-remote Cut-off Pentode (Separate suppressor)
†**5904** Medium Mu Triode	
†**5905** Sharp Cut-off Pentode	
†**5906** Sharp Cut-off Pentode	

* 26-volt heater. † 26 volts all elements.
All other types are 6.3 volt heaters.

For complete data sheets and specifications concerning any of the above tube types and for application information, see your Sylvania Sales Engineer or write to: Sylvania Electric Products Inc., Dept. 3R-1011. 1740 Broadway, New York 19, N. Y.

SYLVANIA

LIGHTING • RADIO ELECTRONICS TELEVISION

In Canada: Sylvania Electric (Canada) Ltd., University Tower Bldg., St. Catherine St. Montreal, P. Q.

by applying a video signal extending in a negative direction to grid one. Strong noise impulses will cause tube cutoff momentarily and thus reduce the harmful effects of noise on picture-tube sweep circuits. The 6CS6 grid number three has a sharp-cutoff characteristics to facilitate the clipping action which removes picture information from the sync pulses. This tube is in the T-5½ bulb style and has a 6.3-v heater.



PULSE TRANSFORMERS
are tiny plug-in type

TECHNITROL ENGINEERING CO., Philadelphia 33, Pa., is now manufacturing two new miniature, plug-in pulse transformers featuring selective turns ratios. Each of the new units has a tapped secondary permitting selection of a turns ratio of 3 to 1, 4 to 1, 5 to 1, 6 to 1 or 8 to 1. TP-AVA is recommended for narrow pulses, 0.2 μsec to 0.5 μsec wide. TP-BVA is for wider pulses, 0.5 μsec to 2.5 μsec. Bulletin 166-1 gives complete information on the company's transformers.



OSCILLOGRAPH
can record 50 data traces

CONSOLIDATED ENGINEERING CORP., 300 N. Sierra Madre Villa, Pasadena 8, Calif. Fifty active data traces can be accurately recorded on 12-in. paper or film by the type 5-119 recording oscillograph. A 36-trace type with identical features is also available. Records 250 ft in length may be made at speeds from 0.10 in. to 100 in. per second. Automatic safety circuits are incorporated to give immediate warning should some failure occur to cause record loss. Circuits are provided to check condition of the main and reserve lamps, timing lamp, heater operation and paper supply. Additional test circuits check the warning systems. Frequencies from 0 to 3,000 cps may be recorded by installing precision galvanometers. Oscillograph models are available for operation from either 26-v d-c or 115-v a-c power. Further information is given in bulletin 1536.



DECADE INDUCTORS
are plug-in type

BURNELL & CO., 45 Warburton Ave., Yonkers 2, N. Y. Some of the many advantages of the new plug-in decade series of decade coils are: (1) greater flexibility in lab setups; (2) lab precision with greater economy; (3) elimination of interwiring and selector-switch capacities; (4) simplicity of service and replaceability of individual units; and (5) allowance of more than one simultaneous setup with a given set of coils. Each plug-in decade is equipped with a male plug at one end and female plug at the opposite end permitting the user to plug as many together as desired which simultaneously connects them in series. One basic set of 4 decade units will provide inductance values in decade steps of 1 to 10. At present one series of plug-in decade units is available over the entire inductance range of 1 millihenry to 180 henries.



PHOTO TRANSISTOR
is *npn* junction type

TRANSISTOR PRODUCTS, INC., Snow and Union Sts., Boston 35, Mass., has developed a type X-25 germanium *npn* junction photo transistor. Its immediate applications will include use in automatic punch-card accounting machines, automatic dimmers for automobiles and automatic brilliance controls on tv receivers. It has sufficient power output to operate a relay. Maximum operating power is 60 mw and maximum nondestructive power 400 mw. It may be considered as a light-sensitive device with an incorporated amplifier.



D-C AMPLIFIER
for wide-band operation

FURST ELECTRONICS, 3322 W. Lawrence Ave., Chicago 25, Ill. Model

only audio record offers you all this valuable new information

. . . and it doesn't cost you a cent!

20 PRIZE-WINNING ARTICLES

from Audio's International Sound Recording Contest

Here's a wealth of new ideas on how to use tape and disc recordings to achieve greater economy and efficiency in radio, TV and sound studio operation.

With reference to these articles, one of the contest judges commented as follows: "I have never received so much information which was new and exciting in such a short time in all of my years in the business." And another judge stated that "the information and descriptions of recording operations conducted in small radio stations and recording studios throughout the country has been quite an education."

Contest winners include entries from 11 different States, as well as from Canada and Switzerland. The 20 best articles, which were awarded cash prizes totaling $1400, will be published in the pages of Audio Record. The information thus made available to the industry will be of real value to sound recordists everywhere.



QUICK FACTS ON MAGNETIC TAPE RECORDERS

Each year, Audio Record brings you a complete, up-to-date listing of all makes and models of tape recording machines—with conveniently arranged price and performance data. This directory issue, published in September, is the most complete and authoritative compilation of tape recorder information available to the industry. Over 75,000 copies of the last issue were distributed.

. . . plus many other articles of timely interest to the sound recordist

Audio Record keeps you well informed on all the latest trends and technical developments in all phases of tape and disc recording. It is not an advertising publication and its sole purpose is to render a needed and useful service to the industry.

Audio Record, published 8 times a year, is currently distributed free of charge to a request mailing list of about 35,000 sound recordists in broadcasting stations, recording studios, schools and colleges throughout the country.

IT'S YOURS FOR THE ASKING

A letter or post card will add your name to the Audio Record mailing list. And if you would like to have others in your organization read it also, send their names along, too. Just write to Audio Devices, Inc., using the Dept. No. listed below. All requests addressed to this Dept. will be started with the July-Aug., 1953 issue, so you will be sure to get *all* the prize-winning articles, as well as the 1953 Tape Recorder Directory Issue.

AUDIO DEVICES, Inc.

Dept. AR-1, 444 Madison Ave., New York, N. Y.

Export Dept.: 13 East 40th St., New York 16, N. Y., Cables "ARLAB"

audiodiscs
audiotape
audiofilm
audiopoints

WEIRD DEVELOPMENTS

The other day we got a request for quotation from the Foul Fiends of the Air Procurement Agency, material required in conformance with a horrible list of spook specs. Sales didn't think we had a ghost of a chance, but the boys in the back room brushed the dead crows aside and went to work.

It seems that this year the Ghouls are trying out a new apparition apparatus which computes the spirit resistance of the victim during the ephemeral expedition so as to energize the ectoplasm at the optimum rate and range. Rate-correction is derived from the victim's tooth-chatter rep-rate up to within a few microseconds of the awful climax.

The required relay pulses electroplasm to the Cold cathode of the Spiritron whose emanations produce greenish light and jangle the chains through a phantom link. (The throat-clutch is engaged manually.) The normally closed contact puts a damping diode on the atmosphere control and prevents accidental dematerialization.

Fortunately, operating temperatures are never higher than cold blood, and even though humidity and corrosion requirements are — well — unspeakable, the boys have developed a very neat relay with controlled contact shudder, unaffected by screams of 60 db max. up to 2 kc and as sensitive as a will-of-the-wisp.

The job was done so promptly and brilliantly that we hope to cash in on this year's Hallowe'en business. The boys who did it are still out on a bat so we haven't anybody for the coffin-nail jobs right now, but brass-tack requests for relay developments will get a spirited† response.

For example, this little prototype for switching 1000 watts was developed in about a month.

SIGMA

SIGMA INSTRUMENTS, INC.

62 PEARL ST., SO. BRAINTREE, BOSTON 85, MASS.

220 wide-band d-c amplifier is designed specifically to increase the sensitivity of c-r oscilloscopes with extended l-f response. It can be used to extend the range of vtvm's, frequency analyzers and other instruments when unusually low frequencies are encountered. In l-f applications its use eliminates long waiting times due to necessary coupling time-constants. Its use will also increase the sensitivity of d-c voltmeters. The new amplifier uses push-pull amplification and a special cross-coupled circuit achieves good stability and low drift. This circuit also provides excellent phase inversion for equal results with balanced or unbalanced input signals. Maximum gain is adjusted to approximately 100 and the input attenuators reduce this gain to approximately 10 and 1 (40, 20 and 0 db).



TRANSFORMER
gives power to tube plate

MAGNATRAN, INC., 246 Schuyler Ave., Kearney, N. J., has added a new air-cooled plate transformer to its line of heavy-duty electronic components. Its purpose is to furnish power to plates of rectifier tubes which in turn supply high d-c voltage to all types of electronic equipment. These transformers are conservatively designed for trouble-free life and to withstand abnormal impulse voltage encountered in rectifier service. In addition to the open-frame core and coil construction, all coils are layer wound with wire locked in place by means of special construction of the layers of insulation. This maintains con-

Engineers–look before you leap!

You want a good job, naturally. But if you also care about your future, you will seek it with a good *company*. As a first step in the right direction, we recommend that you send for a copy of the booklet, "This Is Lear." After you read it, we believe you will want to consider employment with Lear, Incorporated—designers and manufacturers of quality aeronautical products for nearly a quarter of a century. Write today to William P. Lear, Director of Research and Development, for a free copy of this interesting booklet. It may be just the "break" you are looking for.



LEAR, INC.
EXECUTIVE OFFICES:
3171 South Bundy Dr., Los Angeles 34, California

how to select...

PRECISION POTENTIOMETERS

New specification file is valuable guide for design engineers

Here's help for you in the selection of precision potentiometers. Fairchild Camera and Instrument Corporation has prepared detailed specification sheets on each potentiometer model in its extensive line. In each of these you'll find outline drawings and electrical and mechanical specifications to help you select the proper type potentiometer. While your requirements may not precisely pattern these specifications, adequate data is furnished for your initial decision.

For your copy of this useful specification file, write to Potentiometer Division, Fairchild Camera and Instrument Corporation, 225 Park Ave., Hicksville, Long Island, N. Y., Department 140-42A.

FAIRCHILD
PRECISION POTENTIOMETERS

stant, proper coil distance throughout the life of the transformer.

MILLISEC RELAYS
are plug-in, factory-sealed

STEVENS-ARNOLD, INC., 22 Elkins St., South Boston, Mass., has available a line of plug-in, factory-sealed, ultrahigh-speed (Millisec) relays. They are being offered (1) to cover a wide range of temperatures, (2) in a larger variety of types and (3) with a choice between gold contacts and platinum-rhodium contacts. Gold covers the range of 0 to ½ ampere at 0 to 110 v d-c. Platinum-rhodium covers the range of 0 to ½ ampere at 10 to 110 v d-c. A listing of the additional types, together with complete engineering information, is given in the new catalog 337.



RECTIFIER
for magnetic devices

INTERNATIONAL RECTIFIER CORP., 1521 E. Grand Ave., El Segundo, Calif., has developed a small, compact single-phase bridge rectifier, type D-3575, for the operation of magnetic devices such as relays, solenoids and electric counters. The unit is designed for use directly from 117-v a-c systems and is rated to deliver an output of 9 w at 90 v

Fabricated CLEVELITE*

YES, THERE IS A GRADE FOR EVERY NEED!

Its high dielectric strength, low moisture absorption, mechanical strength, low loss and good machinability, are essential characteristics of the component parts of your products.

The world-wide use of CLEVELITE is the result of High Quality and Fine Service.

Tell us your needs. Our Laboratory staff and our large production facilities are at your disposal.

Send for our new folder with complete details on the SEVEN GRADES of CLEVELITE and their applications.

CLEVELITE MEANS HIGH QUALITY!

*Reg. U. S. Pat. Off.

Each day sees some new problem solved by the outstanding electrical and physical properties of CLEVELITE.

The CLEVELAND CONTAINER Co.
6201 BARBERTON AVE. CLEVELAND 2, OHIO

PLANTS AND SALES OFFICES at Chicago, Detroit, Memphis, Plymouth, Wisc., Ogdensburg, N. Y., Jamesburg, N. J.
ABRASIVE DIVISION at Cleveland, Ohio
CANADIAN PLANT: The Cleveland Container, Canada, Ltd., Prescott, Ontario

REPRESENTATIVES

NEW YORK AREA R. T. MURRAY, 604 CENTRAL AVE., EAST ORANGE, N. J.
NEW ENGLAND R. S. PITTIGREW & CO., 62 LA SALLE RD., WEST HARTFORD, CONN.
CHICAGO AREA PLASTIC TUBING SALES, 5315 N. RAVENSWOOD AVE., CHICAGO
WEST COAST IRV. M. COCHRANE CO., 408 S. ALVARADO ST., LOS ANGELES

VICTOREEN'S
VOLTAGE REGULATOR TUBES

Replace expensive electronic regulating circuits.

- RELIABLE
- LONG LIFE
- SPACE SAVING

For applications requiring reliable voltage regulation in low current circuits . . . Consider the advantages of a single tube to perform one of these vital functions:

Voltage regulation of power supplies.
Voltage reference for control of higher currents.
Voltage limiting to prevent circuit overloading.
Voltage adjustment for fine control of precision power supplies.
Write for additional specifications.

GLOW TUBES
57 Volts

Maximum Current 800 μa
Regulation
200-800 μa is 3.0%

HIGH VOLTAGE REGULATORS
400 to 2500 Volts

Maximum Current 100 μa
Regulation
5-55 μa is 1.5%

HIGH VOLTAGE REGULATORS
3000 to 5000 Volts



Maximum Current 250 μa
Regulation
5-55 μa is 1.5%

HIGH VOLTAGE REGULATORS
5000 to 20,000 Volts



Maximum Current 100 μa
Regulation
10-60 μa is 1.5%

ADJUSTABLE REGULATORS
645 to 705 Volts

Maximum Current 55 μa
Regulation
5-55 μa is 3%

DISTRIBUTORS
Allied Radio Corp., Chicago
Gifford-Brown, Des Moines
Harrison Equipment Co., Houston
Radio Shack Corp., Boston
Terminal Radio Corp., New York City
W and W Distributing Co., Memphis

WEST COAST REPRESENTATIVE
Carlton Engineering Co., Los Angeles

BETTER COMPONENTS MAKE BETTER INSTRUMENTS

The Victoreen Instrument Co.
3800 PERKINS AVE. • CLEVELAND 14, OHIO

d-c, continuous duty. With the addition of a 3-μf or larger filter capacitor, the rectifier will deliver 117 v d-c for operation of devices normally designed for this voltage. The magnetic device, therefore, can be used in conjunction with this rectifier to operate directly from the conventional 117-v a-c line.



TV REMOTE CONTROL
for any current set

SEMCO ENGINEERING & MFG. CO., 8407 S. Hoover St., Los Angeles 44, Calif., has introduced a remote control that goes on any current set in a matter of a few minutes. It has provisions to receive the uhf stations by merely installing the snap-in uhf coil strips in unused channels. It saves the cost of a uhf converter. The unit has the latest cascode channel tuner, with double sensitivity; a signal booster amplifier for weak stations or fringe areas, which gives brighter and sharper pictures. Among its other features it has sound output connections for headphones at the control box. This is desirable for late night viewing in apartment houses.

PLUG-IN CIRCUITS
available in 20 versions

ELECTRONIC ENGINEERING CO. OF CALIF., 180 So. Alvarado St., Los

fine wire made finer!

custom drawn
custom insulated
custom spooled

to your most exacting requirements

Backed by fifty years (1903-1953) of fine-wire specialization! During all this time we have supplied bare and insulated wires to many of the most critical wire users.

Your specifications and requirements for *insulated wires* in the East are processed by our Winsted Division; in the West, the Cassopolis Division has been established to facilitate rapid shipments. Insulators and others requiring *bare wires* should contact the Ossining Division for prompt and efficient service.

Our research and development staff is always available to aid our customers in their requirements.

BARE WIRES

TEXTILE-COVERED WIRES

INSULATED WIRES

SPECIAL WIRES

HUDSON WIRE COMPANY

Hudco — Bare Wires

Winco — Insulated Wires

Winsted Division
Hudson Wire Company
Winsted, Conn.
Phone: Frontier 9-3341

Cassopolis Division
Hudson Wire Company
Cassopolis, Mich.
Phone: Cassopolis 56

Ossining Division
Hudson Wire Company
Ossining, N. Y.
Phone: Ossining 2-4710

ANTENNA STRAIN INSULATORS

● The largest of the porcelain rod insulators shown in the illustration develops 12,000 lb. strength. It is available, if specified, with rain shield and/or corona rings. All hardware is silicon aluminum alloy. Smaller units, in porcelain or steatite, are suited to lighter duty for strain or spreader use. Engineering and production facilities are also available for design and manufacture of units to almost any performance specification. Write for Bulletin 301, with complete description and specification data. Lapp Insulator Co., Inc., Radio Specialties. Division, 107 Sumner St., Le Roy, N. Y.

Angeles 57, Calif., is manufacturing plug-in electronic circuits with a case which may be completely taken apart without tools. They are available in 20 catalog versions as well as special types. The cast-aluminum case can be easily disassembled by removing the tube shield, tube, and then unscrewing the base ring. This allows the entire assembly to be lifted apart for inspection. These plug-in circuits retain all of their shock and vibration advantages without dipping or potting in wax or resinous compounds. All the plug-ins are moisture and fungus-proofed by spraying with a special dielectric compound before being cased in a corrosion-resistant container. The plug-in case measures 4 $\frac{3}{16}$ in. overall in height and 1 $\frac{1}{2}$ in. in diameter. Seated height in a standard octal socket is 3 $\frac{5}{8}$ in. and average weight for a circuit is 3 $\frac{1}{2}$ oz.



HYDROGEN THYRATRON can handle up to 10 kw

CHATHAM ELECTRONICS CORP., 630 Mt. Pleasant Ave., Livingston, N. J., is producing a new miniature hydrogen thyratron for pulse-generating applications. The tube can handle peak power up to 10 kw. Designated as the VC-1258 type it will fit a standard ceramic miniature socket. It is rated at 1,000 peak anode volts, 20 amperes peak anode current and 40 ma average anode current. Repetition rates in excess of 10,000 pps are possible at reduced ratings. The VC-1258 will withstand all shock

FERRANTI

TRANSFORMERS

HERMETICALLY SEALED



A NEW LINE OF STANDARD TYPES

- Designed to MIL-T-27 specifications
- MIL-T-27 standard steel cases
- Rugged sealed terminals
- Core and coil securely anchored to mounting studs
- High Vacuum impregnated

These types have been selected to provide standard, readily available components of the highest quality, including the specific types chosen by ASESA for universal military use.

Complete specifications on this wide range of units are contained in a new catalog. Your copy will be sent promptly on request.

In addition to the group listed in this catalog, we manufacture reactors and transformers of all varieties, including the more economical types for use where conditions do not require the superior qualities of those listed in our catalog. We can offer competitive quotations on types to suit your exact needs.

FERRANTI

FERRANTI ELECTRIC
INCORPORATED

30 Rockefeller Plaza New York 20, N.Y.

JK PRODUCTS

Speeding Electronic Progress through crystal research



The JK G-12 is a precision 100 kc G-T cut crystal intended for operation in Meacham Bridge and similar oscillators. Available for operation at series resonance or into large load capacities. Resistance approximately that of usual lamp used for amplitude stabilization, simplifying bridge circuit design. The JK G-12 is vacuum sealed. Equipped with octal base it is more convenient than usual "soldered-in" type of precision standard crystal. Suitable for transistor oscillators. Will fit JK 07EH temperature control unit. Consult us on specific applications.

JK STABILIZED G-12 CRYSTAL

Did you know? Surgical cleanliness during manufacture is an important reason for the unequalled stability of JK Crystals. In an airconditioned, dust-free plant crystal blanks are repeatedly cleaned with chemicals, washed in distilled water and spun dry — plain tap water or even a fingerprint would impair stability. The final crystal, vacuum sealed in a glass holder, provides stability equal to a watch that would remain accurate to within three seconds over a year's time. Creative research combined with today's most modern production facilities brings you today's finest — JK "Crystals for the Critical".



THE JAMES KNIGHTS COMPANY, SANDWICH 3, ILLINOIS

and vibration tests required of a ruggedized electronic tube.



POWER SUPPLY
has less than 2 mv ripple

HANOVER DEVELOPMENTS, 401 E. 74th St., New York 21, N. Y. Weighing 15 lb and measuring 10 in. × 12 in. × 9 in. high, the type 205 d-c power supply delivers 6 v 5 amperes, or 12 v 3 amperes, with variation less than 0.05 percent for a line-voltage change from 105 to 125 v. Ripple is less than 2 mv. Regulation is better than 0.5 percent for a load change from 0 to full load. Recovery time is instantaneous for line-voltage changes, and in the order of 0.2 sec for load changes. Applications include the supply of heaters in d-c and low-frequency amplifiers, and the replacement of storage batteries where a constant source of low voltage d-c at high current is required, such as colorimeter and spectrometer light sources.

FOCUSING DEVICES
use ceramic magnets

FERROXCUBE CORP. OF AMERICA, 35 Marshall St., North Adams, Mass. The tv focusing device illustrated uses two Magnadur ceramic mag-

"Color Television"

A special issue containing

• 15 N.T.S.C. Monographs–

The National Television Systems Committee has authorized IRE to publish its long awaited Monographs in the January 1954 special Color Television issue of "Proceedings of the I·R·E" — thus giving them industry-wide distribution for the first time in print.

• 25 additional Color TV articles–

will also appear in this issue, which brings the reader up-to-the-minute on the developments of Color Television. Copies of the first Color Television issue are still available and combined with this second Color Television issue will form a complete bibliography of major historical importance. Also included in the January issue will be a complete listing of the N.T.S.C. system specifications as submitted to the F.C.C.; and field test reports on the system's performance.

in "Proceedings of the I·R·E" January '54

Available to non-members for $3.00. Extra copies to I R E members are $1.25. All members get one copy free!

Another History Making Issue!



I R E is an organization of 33,312 member-engineers. There are no company memberships. Operating continuously since 1913, its sections meet in 78 cities. 21 specialized Professional Groups widen the scope of its member-services and 40 technical committees help the industry.

"Proceedings of the I·R·E"

Published by

THE INSTITUTE OF RADIO ENGINEERS

1 East 79th Street, New York 21, N. Y.

Please place orders before December 10th.

Want more information? Use post card on last page.

Projecting Themselves Through

QUALITY



argus, world-famous producers of cameras and projectors depends on PHALOCORD cord sets to carry the current load for their amazing new line of projectors.

Colorfully contrasting PHALOCORD cord sets add a bright, smart touch to the handsome ARGUS projector — but the big reason for their nation-wide demand is, of course, complete dependability *on the job!*

SPT-2
Green Thermoplastic
Insulation
Matching Plug

Use PHALOCORD and you'll use the finest!

PHALO PLASTICS CORPORATION

CORNER OF COMMERCIAL ST., WORCESTER, MASSACHUSETTS

Insulated Wires, Cables and Cord Set Assemblies

net rings in a double lens system that is focused by adjustment of the relative position of the two toroids. This reduces stray fields to a minimum and provides a highly symmetrical field of maximum sharpness and spot symmetry. Magnadur is a new and unique p-m material with very high coercive force and resistance to demagnetization as well as excellent magnetic stability. Its high resistance permits the use of Magnadur magnets in the presence of h-f fields without undesirable losses, as is the case with metallic magnets. Bulletin FC-6000 gives complete technical data as well as demagnetization and energy product curves for Magnadur permanent magnets.



TINY TRANSFORMERS
cover the a-f range

TRIAD TRANSFORMER CORP., 4055 Redwood Ave., Venice, Calif., has available an expanded line of miniature magnetically shielded, hermetically sealed transformers. Used with transistor or tube amplifying equipment, these transformers cover the audio-frequency range. Advanced techniques in the handling of very fine wire permit this extreme miniaturization without compromise on insulation or moisture protection. The transformers are available in standard MIL cases with mounting studs so arranged that the units may be mounted in closest proximity to each other. All essential information for each transformer is carried on a permanently attached decal. Known as the JAF series,


what
luminizing
means
Aluminizing means the efficient use of light
light is energy—energy is the pay off
Aluminizing means a brighter TV picture,
greater contrast, lower beam current, smaller
spot size, sharper focus, reduced screen
scorch—all from the efficient use of light
On the inside of any TV tube face is a coating
of phosphor crystals—the picture screen. As
the electron beam—tracing the picture—strikes
these crystals, they glow, giving off light in
all directions. And there's the problem!
Half the light thus generated is inside the tube,
either lost to usefulness or lighting areas that
should be dark. Both brightness and
contrast suffer.
But—put a mirror behind the phosphor and
"wandering" light is reflected back through the
tube face. Aluminizing creates this
desired mirror!
To aluminize a picture tube, deposit a
nitrocellulose film evenly over the phosphor.
Over that, deposit a film of aluminum only
millionths of an inch thick.
Under heat,
evaporate the nitrocellulose film to leave a thin,
smooth coating of aluminum. Result—an
efficient light reflecting mirror to
specifications.
Simple as it sounds, Rauland research
engineers worked for three years to solve the
problem and were among the first to do so.
Rauland
Subsidiary

just right

for built-in applications



Adjust-A-Volt 300BU
variable auto-transformers

This versatile unit smoothly controls plenty of power for its size. Highly efficient, small and compact, the 300BU is designed for panel-mounted applications like line voltage control for power supplies and instruments, control of heat in small ovens, motor speed control and light intensity variation. New design brush assembly, pre-adjusted at the factory, maintains constant pressure from full-brush to no-brush . . . assures longer life, more reliable operation. Ganged assemblies are available.

3 wire fused unit for 2 KVA duty

Sturdy, attractive Type 3PF1500B Adjust-A-Volt for over-voltage connection—suitable for bench or panel mounting. Equipped with 3 prong plug-cord, output receptacle and fuse.

get your copy NOW

Write for new 18-page catalog No. 553-5 on full Adjust-A-Volt line ranging from 0.34 to 16.8 KVA. Full specifications, circuit diagrams, prices.

STANDARD ELECTRICAL PRODUCTS COMPANY

2239 E. THIRD ST. • DAYTON, OHIO

these and other transformers are described in catalog TR-53.



WIDEBAND TUNER
has ± 0.5 db a-f response

PILOT RADIO CORP., Long Island City, N. Y. Model AF-723 f-m/a-m tuner has a hum level 70 db below 1.0 v. Maximum audio output is 5 v. Audio distortion is 0.2 percent at 1-v output. Audio frequency response is ±0.5 db, 20 cps to 20,000 cps. Frequency range for f-m is 88 to 108 mc; a-m—540 to 1,700 kc. Antenna input for f-m is 300 ohms to match external dipole, or built-in line-cord antenna; a-m—internal ceramic powdered iron loop stick with provision for matching to standard RETMA external antenna.



FILTER
for l-f and h-f control

CINEMA ENGINEERING CO., Division of Aerovox Corp., 1510 W. Verdugo Ave., Burbank, Calif., is now producing type 6517-E variable high and low-pass filter. There are two positions for low-frequency control and the same number for high-frequency control. Standard RETMA rack mounting is used. Net weight is 15 lb. Features include wide frequency spectrum with the overlapping cutoff frequencies; zero phase distortion over transmission range; all inductance toroidally wound; hum pickup eliminated; complete flexibility afforded by two key switches, allowing insertion of either filter section or both upon cue. It was designed for sound

small size?
long life?
and
high temperature operation?

ASTRON HY-METS*

High Temperature Metallized Paper Capacitors

Type MQL

Answer several of your capacitor and assembly problems with one quick stroke. Specify ASTRON Hy-Mets—for long life in high temperature operation. Now you can have the subminiature size of metallized paper capacitors for high temperature operation without derating.

Hermetically sealed Hy-Mets utilize ASTRON's new solid impregnant—to eliminate possibility of any oil or impregnant leakage from −55C to +125°C. Hy-Mets offer high insulation resistance, longer life, lower power factor and exceptional stability over extremes in operating conditions. ASTRON Hy-Mets are the subminiature for the biggest job.

Available in a variety of metal tubular, cardboard, and JAN case styles for voltage applications up to 600 Volts DC in a wide range of capacitance values.

Write for Bulletin AR-19 on Hy-Mets, giving complete data on sizes, ratings, mounting styles, engineering performance characteristics and test specifications.



Type MDL

Astron manufactures a complete line of dry electrolytic, metallized paper, plastic molded and subminiature paper capacitors, and standard and subminiature RF interference filters for every radio, television and electronic use.

DEPEND ON—INSIST ON

ASTRON

ASTRON CORPORATION, 255 Grant Avenue, East Newark, New Jersey

*Trade Mark

Winchester Electronics

ELECTRICAL

CONNECTORS FOR AN SHELLS

...for POWER, CONTROL and COMMUNICATIONS circuits

Precision-manufactured to meet the exacting requirements of Specification MIL-C-5015A for the military services, these Winchester Connectors are ideally suited for commercial and industrial applications requiring the same rugged dependability.

FOR SIZE 24AN SHELLS



456PR RECEPTACLE — 455PR PLUG

Double contact AWG #12. *(450-451 Single Contact Connector similar to above except for Size 18 AN Shells).*

FOR SIZE 28AN SHELLS



901 PLUG — 902 RECEPTACLE

Twenty-eight (28) contacts AWG #16

FOR SIZE 36AN SHELLS



202BPR RECEPTACLE — 201 BPR PLUG

SERIES "200" CONNECTORS:

201-202: Twelve (12) contacts AWG #20, three (3) contacts AWG #12.
201B-202B: Twelve (12) contacts AWG #16, three (3) contacts AWG #12
201BPR-202BPR: Same as 201B-202B except pressure-tight sealed.

FOR SIZE 44AN SHELLS



422 RECEPTACLE — 421 PLUG

Twenty (20) contacts AWG #16, three (3) contacts AWG #12. *(301-302 similar to above except for AN Shell Size 40 and only one (1) AWG #12 contact).*

Connector "inserts" are standard or pressure-tight, as required, and fit AN Shell types 3100, 3101, 3102, 3106 and 3108 shown above.

SPECIAL FEATURES:

MONOBLOC* CONSTRUCTION eliminates unnecessary creepage paths, moisture and dust pockets, and provides stronger molded parts.

MOLDED MELAMINE BODIES, in accordance with MIL-P-14, mineral filled and fungus-proof, provide high arc and dielectric resistance.

HIGH VOLTAGE CONTACTS are removable from the molded body, permitting ease of soldering for the high voltage cable wires. All contacts are precision machined, gold plated over silver for consistent low contact resistance and prevention of corrosion.

Patent Numbers: 2,513,080; 2,411,861

Wire or write our Sales Department about your special requirements.

Winchester Products and Winchester Designs are Available Only From Winchester Electronics, Incorporated.

WINCHESTER ELECTRONICS
INCORPORATED

West Coast Branch: 1729 WILSHIRE BOULEVARD SANTA MONICA, CALIFORNIA

GLENBROOK, CONN., U.S.A.

*Trade Mark

and electronic laboratory research and control; sound recording, transmission and reproduction control.

RIBWOUND RESISTORS
in high wattage ratings

MILWAUKEE RESISTOR CO., 708 W. Virginia St., Milwaukee 4, Wisc., is manufacturing ribwound resistors up to and including 2,000 w. Wound with a specially designed resistance wire on high-temperature refractory cores, these units afford greater wattage dissipation in low resistance values. All connections are silver soldered to provide absolute protection against resistance failure. Coating is high-grade enamel fired at extreme temperatures to assure freedom from moisture and complete heat dissipation. The resistors can be furnished as fixed, adjustable or with multi-taps where desired resistances are known.

CAPACIPROBE
requires no pre-zeroing

ELECTRONICS PRODUCTION SERVICE CO., 871 Washington St., Canton, Mass. Model C102 Capaciprobe was designed as an aid to engineers engaged in the development of r-f pulse and switching circuitry. It enables its user to measure accurately and rapidly total capacitance at any point within a circuit with that circuit operating under its normal d-c conditions. Basically, the unit consists of a stable r-f oscillator, a current-conversion buffer, a parallel tuned circuit, and

HOW MANY *db*— AT 5,000 MEGACYCLES? AT 25,000 MEGACYCLES?



PRD

precision variable attenuators

- METALLIZED GLASS ATTENUATING ELEMENTS
- PRECISE, PERMANENT CALIBRATION
- BROADBAND CHARACTERISTICS
- NEGLIGIBLE INSERTION LOSS
- BACKLASH-FREE
- LOW REFLECTION
- WELL SHIELDED CASING

The use of metallic-film-on-glass techniques to provide attenuation at microwave frequencies is no longer new. This type of PRD attenuator is now well recognized for its constancy of attenuation with time as well as for its insensitivity to variations of humidity and temperature.

PRD has now augmented this line of attenuators with units employing metallized mica elements to provide broader-band characteristics for the millimeter region of the microwave spectrum. As a consequence, it is now possible to offer complete coverage of the range from 2,600 to 40,000 megacycles per second in designs varying from a simple level set attenuator to a precisely calibrated secondary standard. Write today for our complete catalog of microwave test equipment — address Dept. E-11.

Polytechnic RESEARCH & DEVELOPMENT COMPANY, Inc.

55 JOHNSON STREET, BROOKLYN 1, NEW YORK

WESTERN SALES OFFICE

741 NO. SEWARD STREET, HOLLYWOOD 38, CALIF.



ITEMP WIRES
26 WINDSOR AVENUE
MINEOLA, LONG ISLAND
Representatives in principal cities

teflon
INSULATED WIRES

MAGNET WIRE
14 to 50 AWG high dielectric
Excellent power factor
Resistant to moisture and chemicals
Essential to miniaturization

HOOK-UP WIRES
28 to 14 AWG
Various wall thicknesses
11 solid colors
55 spiral striped color combinations

Operating temperature range -90° to +260°C

DuPont's trade name for Polytetrafluoroethylene

Quantity production through quality control

a novel variable sensitivity resonance detector. No pre-zeroing is required. The range of model C102 covers the fundamental circuit range of 0 to 110 μμf (accuracy ±1 percent). The unit operates from 95 to 125 v a-c.



CERAMIC
for high-temperature use

AMERICAN LAVA CORP., Chattanooga 5, Tenn. A new ceramic, AlSiMag 539, is finding many industrial uses. It is an excellent material for fixtures, jigs and work holding devices for fast production line handling of brazing, welding, electronic heating and flame polishing. It is also valuable as a material for making pins, pads, plates, spacers and kiln furniture for high-temperature sintering operations. Nozzles for welding tips and other extreme high-temperature devices have given outstanding performance. The ceramic is a relatively fine-grained silicon carbide material. It has been repeatedly heated white hot and quenched in dry ice without fracturing.



HERMETIC SEAL
fits push-button switches

AUTOMATIC & PRECISION MFG. CO., 252 Hawthorne Ave., Yonkers 5,

7 Reasons why Regohm is a natural for your control system

This compact, electro-mechanical controller provides sensitivity, speed of response and system stabilization under severe operating conditions. Its design and operating features have made Regohm useful for automatic control systems in which heavier, more expensive and complex, but less accurate equipment had previously been the only available solution.

(1) **SMALL SIZE** · Regohm is a compact, plug-in device; lightweight, extremely rugged and position-free. The unit's small size does not limit its power-handling capacity. This makes Regohm a "natural" where economy of space and weight are your major considerations.

(2) **POWER AMPLIFYING** · Regohm is a high-gain electro-mechanical power amplifier. Milliwatt variations in signal energy can control energy changes millions of times greater.

(3) **IMPEDANCE MATCHING** · Signal and controlled circuits are isolated, both electrically and structurally. Signal coils may have ratings from 0.01 to 350 amperes. Controlled resistors on a panel in which Regohm is plugged, can have values from zero to infinity, depending on the controlled system.

(4) **SYSTEM STABILIZING** · A thoroughly reliable, sturdy dashpot aids in system damping. It can easily and readily be adjusted over a wide range to match the dynamic characteristics of the Regohm to those of your present system.

(5) **ANALYTICALLY DEFINABLE** · The response of Regohm is independent of the rest of the servo system. Its response characteristic can be expressed in terms of conventional "transfer functions." Regohm acts as an integrating error-rate proportional controller. No appreciable steady-state error can occur. Regohm's effect can be calculated in advance, simplifying design and facilitating prediction of performance.

(6) **CONTINUOUS CONTROL** · In "closed loop" systems a high-speed averaging effect occurs as Regohm's armature oscillates over a small amplitude. This provides intermediate values between step resistances and results in continuous, stepless control in systems operating at power frequencies and below.

(7) **LONG LIFE** · In properly engineered installations, Regohm's life is measured in years. Plug-in feature simplifies replacement and maintenance—there are no parts to renew or lubricate. Shelf life is substantially unlimited.

Our engineering and research facilities can help you apply Regohm to your servo system or regulator problem. Write for Bulletin 505.00, containing a complete discussion of Regohm's characteristics and applications. Address Dept. E, ELECTRIC REGULATOR CORP., Norwalk, Conn.

REGOHM

CONTROL COMPONENT IN: Servo systems • battery chargers • airborne controls • portable and stationary generators • marine radar • inverters • locomotive braking systems • mobile telephones • guided missiles • signal and alarm systems • telephone central station equipment • magnetic clutches • railroad communication systems.

Want more information? Use post card on last page.

Specify

ADVANCE RELAYS

FOR PRECISE CIRCUITRY



There are many reasons why Industry *specifies* ADVANCE RELAYS: They meet or surpass Military and Civilian requirements—many types have AN approval—many are hermetically sealed—*all* are lightweight—small—rugged—compact—and *all* are precision-built for efficient, trouble-free, long life performance.

If you have relay problems involving contact loads, coil resistances, close differential, timing features, input sources, critical environment or any particular requirements involving unusual or accurate circuit behavior, ADVANCE can supply the relay.

A complete line of relays for radar, radio, electronic and electrical equipment applications.

Write for new, descriptive Catalog containing detailed information about ADVANCE Relays and facilities.

ADVANCE ELECTR[illegible]Y
2435 NORTH NAOMI[illegible]A

Sales Representatives in Principal Cities of U. S. and Canada

N. Y., has added to its line of switche boots the Hexseal series 3030. The new units are high-pressure hermetic seals for all standard pushbutton switches. When installed, the boots replace the switch lock-nuts on the exterior of the panel, and serve as both seal and lock-nut. Hermetic sealing is maintained by a gasket rib—an integral part of the boot—which seats firmly against the panel to keep out moisture, dust or combustible vapors. Made of silicone rubber, which is chemically bonded to the nut, Hexseals are flexible from —80 to 500 F, and are unaffected by exposure to sun and weather. The material used surpasses the requirements of MIL specification B-5423.



SIGNAL GENERATOR
for aircraft radio use

THE HICKOK ELECTRICAL INSTRUMENT CO., 10514 Dupont Ave., Cleveland 8, Ohio. Model 292XAL airline microvolt signal generator provides continuous coverage from 125 kc to 165 mc on fundamentals. It provides complete coverage of the aircraft band including all the necessary i-f frequencies and covers all r-f frequencies with calibrated output. It can be externally modulated from 15 to 10,000 cps, and measures both input and output of units under test. The unit maintains dependable and accurate frequency calibration, is free of wave distortion, and has no spurious signals in the output system. It features temperature compensation, self-contained crystal oscillator reference level and crystal control. The attenuator is especially designed to attenuate



is CORROSION RESISTANCE

. . . your problem?

Long experience in the development of precision instruments enables Ketay to manufacture Synchros, Servos and Resolvers to meet the cycling humidity requirements of MIL-E-5272

As a leader in the use of *corrosion resistant* materials in Synchros, Servos, Resolvers, Control Equipment and related instruments, Ketay has enormously broadened their usefulness for both the government and industry.

Ketay has built an outstanding record as originators of units to meet individual specifications. Ketay engineers will be glad to discuss your requirements.

CORROSION RESISTANT UNITS

Ketay offers a complete line of Corrosion Resistant Instruments, four of which are pictured above. From left to right they are:

- Synchro, Size 23, Frame O.D. 2.250", 26 V and 115 V 400 & 60 Cycles. (Transmitter, Receiver, Resolver, Differential, Control Transformer) Also available in same frame size: Servo Motor—115 V 60 Cycles.
- Synchro, Size 15, Frame O.D. 1.437", 26 V and 115 V 400 Cycles. (Transmitter, Receiver, Resolver, Differential, Control Transformer) Also available in same frame size: Servo Motor Mk 7—115 V 400 Cycles.
- Synchro, Size 11, Frame O.D. 1.062", 26 V and 115 V 400 Cycles. (Transmitter, Receiver, Resolver, Differential, Control Transformer) Also available in same frame size: Servo Motor Mk 14—115 V 400 Cycles.
- Synchro, Size 10, Frame O.D. .937", 26 V 400 Cycles. (Transmitter, Receiver, Resolver, Differential, Control Transformer) Also available in same frame size: Servo Motor—26 V 400 Cycles.

Send for illustrated Catalog today!

Ketay

MANUFACTURING CORPORATION

Executive Offices
555 Broadway
New York 12, N. Y.

•

West Coast Sales
12833 Simms Avenue
Hawthorne, California

DESIGN
DEVELOPMENT
MANUFACTURE
. . . of precision instruments components, systems.

Kinetix Instrument Division • Marine Division • Pacific Division • New York Division • Research & Development Division

Want more information? Use post card on last page.



Leading. Manufacturers Rely on RPC for Quality and Quantity in Precision Resistors!

Within a few years RPC has attained a position of leadership in the manufacture of precision wire wound resistors. This is no accident. It is the result of STRINGENT *control of quality*—use of the *finest available materials*—test equipment and standards that are matched only by a few outstanding laboratories.

RPC Precision Resistors meet Government specifications. They are acceptable for all types of equipment—test instruments, electronic computers and scientific equipment. Requirements of JAN-R-93, MIL-R-93A are fully met. Advanced methods of production have made possible large or small orders at reasonable cost with prompt delivery. Write for catalog and helpful information about RPC's resistors.

ENGINEERING DATA

RPC Type	Government Specification JAN-R-93	Government Specification MIL-R-93A	Dimensions (Inch) Length	Dimensions (Inch) Diameter	Resistance (Ohms) Min.	Resistance (Ohms) Max. With Low T. C. Alloy .0015 Dia.	Resistance (Ohms) Max. With Low T. C. Alloy .001 Dia.	Watts JAN or MIL	Watts Comm'l
AFB*	RB10	RB15	15/32	17/32	0.1	.160 Meg	.680 Meg	.25	.5
AQB*	RB10	RB15	15/32	17/32	0.1	.235	1.0	.25	.5
AFC*	RB11	RB16	5/8	17/32	0.1	.225	1.0	.33	.5
AQC*	RB11	RB16	5/8	5/8	0.1	.350	1.5	.33	.5
AFF*	RB12	RB17	1	17/32	0.1	.475	2.0	.5	1
AQF*	RB12	RB17	1	5/8	0.1	.700	3.0	.5	1
AJ6	RB13	RB18	1-9/32	11/16	0.1	1.25	5.0	.5	1
ALP	RB14	RB19	2-1/16	13/16	0.1	2.5	10.0	1	2

* NOTE—Can be furnished with 1-1/2" long 28 gauge tinned wire leads instead of lug terminals. Suffix "W" after type denotes wire leads.

Resistors described above only part of many types available.

RESISTANCE PRODUCTS CO.

714 RACE ST. HARRISBURG, PENNA.

• Precision Wire Wound • High Voltage • High Megohm
• High Frequency • Hermetically Sealed

faithfully without frequency discrimination.



R-F WATTMETER
a variable impedance unit

SIERRA ELECTRONIC CORP., 1049 Brittan Ave., San Carlos 2, Calif. Model 141 variable impedance wattmeter is designed for fast, accurate power measurements between 2 and 30 mc. Designating its input impedance as $Z = R + jX$, R can be adjusted over a broad range of 5 to 500 ohms and jX can be adjusted between -250 and $+250$ ohms. Up to 250 w of power may be dissipated, and overall accuracy of the directly indicated power measurement is within 10 percent. Accuracy of impedance magnitude is within 5 percent. The equipment weighs 79 lb and measures approximately 26 in. wide × 17 in. high × 18 in. deep.



PULSE TRANSFORMERS
are tiny and encapsulated

ELECTRONICS PRODUCTION SERVICE Co., 871 Washington St., Canton, Mass. The miniature pulse transformers illustrated are capable of transferring pulses in the millimicrosecond to μsec range. They have wide application in digital computer, radar, and telemetering systems. The transformers are completely encapsulated in a color coded thermosetting resin, which enables the units to withstand severe mechanical shock and environmental conditions. Some en-

"SCOTCHCAST" EMBEDMENT RESIN

now available in new low-viscosity form

And now comes "Scotchcast" No. 3—a cold-pouring electrical embedment resin that costs less because it can be mixed with larger amounts of filler. That means better electrical properties, lower co-efficient of expansion, higher heat dissipation.

"Scotchcast" provides dependable insulation and protects against thermal and mechanical shock, oil, moisture, chemicals and weather. Well-known manufacturers find it gives longer life to most types of coils.

"Scotchcast" No. 3 has longer pot life, generates less heat during curing, resists heat after curing, has lower viscosity for ease of impregnation.

For complete data, write Minnesota Mining & Mfg. Co., Dept. ES-113, St. Paul 6, Minnesota.

1 AFTER WINDING, coils are fitted into plastic cases.

2 SEALING COILS in "Scotchcast" Resin No. 3.

"SCOTCHCAST" Electrical Embedment Resins

The term "Scotch" and the plaid design are registered trademarks for the more than 300 pressure-sensitive adhesive tapes made in U. S. A. by Minnesota Mining & Mfg. Co., St. Paul 6, Minn.—also makers of "Scotch" Sound Recording Tape, "Underseal" Rubberized Coating, "Scotchlite" Reflective Sheeting, "Safety-Walk" Non-slip Surfacing, "3M" Abrasives, "3M" Adhesives. General Export: 122 E. 42nd St., New York 17, N. Y. In Canada: London, Ont., Can.

Call on Lewis

when you need

DEPENDABLE

SPRINGS

WIREFORMS

STAMPINGS

QUALITY, ECONOMY and PROMPT SERVICE on Every Order—Large or Small!

There is never any letdown in Lewis quality or service. Your order will be given prompt, efficient attention regardless of size. You can be sure that the springs, wireforms or stampings you order will be fairly, economically priced. What's more, Lewis has the extensive, modern facilities, the long-experienced engineers and skilled production craftsmen to supply you with springs, wireforms and stampings tailored to your exact needs.

If you have any tricky or tough problems involving springs, Lewis's engineers will be glad to help you solve them. Or, if you need large or small quantities of standard springs in a hurry —just call on Lewis! Send us your drawings, specifications or samples today!

LEWIS SPRING & MANUFACTURING CO.
2556 W. NORTH AVENUE, CHICAGO 47, ILLINOIS

Lewis PRECISION SPRINGS

The Finest Light Springs and Wireforms of Every Type and Material

gineered characteristics include: a coefficient of coupling between any two windings, 0.97; pulse repetition rate, up to 5 mc; static capacitance between any two windings, less than 2.0 μμf; temperature range, —65 C to 125 C. The units measure ⅜ in. × ¾ in. × ¾ in.

ATTENUATOR PADS
for microwave measurement

TELEWAVE LABORATORIES, INC., 100 Metropolitan Ave., Brooklyn 11, N. Y., have just put a miniaturized type of microwave attenuator pad on the market. Known as Micropads, the new products are extremely compact and rugged with no fine wires or delicate elements. Ability to withstand overloads of more than 100 percent is also a feature. Platinum-film microwave resistors are employed. Micropads are finding increasingly widespread application wherever ultrahigh precision microwave measurement is essential but space is limited.



SWEEP GENERATOR
for uhf applications

NEW LONDON INSTRUMENT CO., P.O. Box 189, New London, Conn. Featuring single range tuning and a 0 to 30-mc sweep width, the model-130 uhf sweep generator is designed for either laboratory, production test or service department use. Other features are: at least 1-v output into 75 ohms; a continuously variable attenuator; a blanked signal on the return sweep, thus providing a reference base line; no beating; no multiplication;

onsistently

ependable



C-D probably has the answer to your electrolytic problem! Is it for a motor? TV circuit? Photoflash? Micro-wave communications? If anybody has the answer to your electrolytic problem, it's likely to be Cornell-Dubilier, the greatest name in capacitors. Write for the complete catalog to: Dpt. K-113, Cornell-Dubilier Electric Corp., General Offices, South Plainfield, New Jersey.

CORNELL-DUBILIER

world's largest manufacturers of capacitors

ANTENNAS

ROTATORS

CAPACITORS

VIBRATORS

CONVERTERS

SOUTH PLAINFIELD, N. J. • NEW BEDFORD, WORCESTER AND CAMBRIDGE, MASS. • PROVIDENCE, R. I. • INDIANAPOLIS, IND. • FUQUAY SPRINGS, N. C. • SUBSIDIARY, THE RADIART CORP., CLEVELAND, O.

Want more information? Use post card on last page.

Stycast 0005 is a newly developed plastic material featured by low dissipation factor, excellent high and low temperature stability and machining ease.

Stycast 0005 will not flow even when subjected to temperatures as high as 200°C. Prolonged heating under stress should be limited to 125°C.

Stycast 0005 will withstand temperatures as low as -70°C without adverse effects, either electrical or physical.

Stycast 0005	
Dissipation Factor *60 to 10^{10} cps*	below .0005
Dielectric Constant *60 to 10^{10} cps*	2.53-2.56
Tensile Strength	11,000 psi
Hardness, *Rockwell M Scale*	105

Stycast 0005 machines easily when normal procedures in the machining of plastics are followed.

Stycast Hi-K—*a NEW opaque plastic rod and sheet stock of ADJUSTED DIELECTRIC CONSTANT*

Available in Dielectric Constant 8 through 20.

From 10^3 to 10^{10} cps the variation in dielectric constant is ±0.15. Dissipation factor is below 0.001.

Machinability excellent.

Emerson & Cuming, Inc.
PLASTICS for ELECTRONICS
869 Washington Street, Canton, Mass.

New England	Washington, D. C.	Mid West
R. W. Gray, Inc. 572 Washington Street Wellesley, Massachusetts Wellesley 5-5296	D. J. Shamp 1500 Massachusetts Avenue Washington 5, D. C. HUdson 3-4167	Caine Sales Company 3020 N. Cicero Avenue Chicago 41, Illinois SPring 7-4022

and simplicity of operation. A low-cost balun is available for conversion to 300-ohm load.



VOLTAGE REGULATOR
for 400-cycle supplies

AVION INSTRUMENT CORP., Division of American Car and Foundry Co., 299 State Highway No. 17, Paramus, N. J., has developed the model 116-A precision a-c regulator for 400-cycle supplies. The rms output voltage is adjustable, with regulation to 0.01 percent up to half the rated load (50 va) and to 0.02 percent up to the full rated load (100 va). This regulation is maintained with allowable input-voltage fluctuations of ±10 percent about the adjusted output level, and frequency fluctuation of ±5 percent. Recovery time from transients is less than 0.01 sec. Developed harmonics are less than 1 percent. The unit is effective when used in the development of aircraft or other electronic equipment requiring precision regulation of voltage supplies.



CRYSTAL CONVERTER
employs only three tubes

MOHAWK ELECTRONIC RESEARCH LABORATORIES, INC., R.D. 4 Amster-



Checking perforated metal card in Bell's new "card file" which uses Phototransistors to help route Long Distance telephone calls along the best routes. If the first voice-way is in use, a "detour" is swiftly found. The equipment is known in telephony as a "card translator."

CARDS FOR CONVERSATION

To find out how to route Long Distance calls a dial system needs lots of information—fast. To provide it Bell Laboratories engineers developed a new kind of card file—one that dial systems can read.

Punched holes on metal cards tell how calls should be handled. When a call arrives the dial system "asks" the "card file" how to proceed to a particular area. Instantly the appropriate instruction card is displaced so that its pattern of holes is projected by light beams on a bank of Phototransistors. In a flash the Phototransistors signal switches to set up the best connection. Cards are quickly changed when new instructions are needed.

The "card file" will have its widest use in speeding Long Distance calls that are now dialed by a telephone operator and may one day be dialed by you personally. It is another example of how Bell Telephone Laboratories helps telephony to grow, as costs are kept down.



New Phototransistor unit. Light entering the cylinder is focused by the lens on a piece of germanium that responds by generating current. Like the Transistor, the Phototransistor was invented in Bell Telephone Laboratories.

BELL TELEPHONE LABORATORIES

There are many opportunities for creative scientists and engineers at Bell Telephone Laboratories. For details see our advertisement on page 471

You Can Speed Production-Line Soldering with New, Active, Non-Corrosive RTS 200

Federated Metals' new RTS 200 rosin core solder has proved in production operations to be 5 ways better than ordinary rosin solders:

30% GREATER SPREAD—by test the spread of RTS 200 is 30% greater than that of conventional rosin core solders.

4 TIMES FASTER OXIDE PENETRATION—oxide films and corrosion products on the parts you are soldering need not slow down operations. RTS 200 pierces these retarding agents 4 times faster than ordinary solders.

NON-CORROSIVE—despite the exceptional activity of the RTS 200 flux at soldering temperatures, there is *no harmful corrosive residue* when tested under the high humidity conditions of military specification MIL-S-6872.

NON-TOXIC—the chemicals used in RTS 200 flux are commonly used in industry and have no toxicity factor whatsoever.

STABLE FLUX—experience of over one year with the type flux used in RTS 200 shows that it is just as active after standing as when used immediately. If you store RTS 200 for extended periods, you need not worry about its stability, as you do with ordinary solders.

Try this new, industry-tested active solder *today*. Available in a variety of wire sizes, compositions and quantities. For information see your distributor or write any one of Federated's 14 plants or 22 sales offices across the nation. There is one near you.

dam, N. Y., announces a new vhf cascode crystal converter. Employing only 3 tubes and measuring out 3 × 3 × 5 in., the unit is small enough to be mounted inside a communications receiver cabinet. If desired, as many as 5 units may be mounted on a standard 7 × 19-in. relay rack panel. A 6BQ7A is employed as a cascode r-f amplifier. One 6J6 combines the function of crystal oscillator and frequency multiplier while another 6J6 is used as a combined mixer and multiplier. Usable average sensitivity is better than 0.5 μv and noise figure averages 5 db. The bandwidth of these units is essentially flat over a 6-mc range but may be peaked to favor any portion desired. Standard i-f output frequency is 14 to 20 mc.



TWIN POWER TRIODE
for voltage regulation

CHATHAM ELECTRONICS CORP., Livingston, N. J., is in production on the new type 6AS7G high-perveance twin power triode for voltage regulation. Used as a series or passing tube in regulated power supplies, it incorporates certain design changes to offer the following features: absence of grid current; plate current and characteristics held within ± 10 percent; very low microphonics; and improved triode balance and reduction of plate-current drift. Upon request tubes can be supplied to meet the following additional specification beyond JAN quality level: plate voltage, 150 v; grid voltage, —55 v;

For TELEVISION·RADIO·RADAR INSTRUMENTS

FOR EVERY CIRCUIT PROTECTION PROBLEM

CONTROLS·AVIONICS

REMEMBER ONE NAME . . .

BUSS FOR FUSES

THE INDUSTRY'S *Most Complete* LINE

Here's why it pays to get **all** your fuses from this one reliable source:

More than a third of a century of service stands behind every fuse that bears the BUSS trademark. Your customers have faith in BUSS fuses. They know that the BUSS name represents fuses of unquestioned high quality.

To maintain these high standards, each BUSS fuse is **electronically tested** for correct calibration, construction and physical dimensions.

● **On Special Electrical Protection Problems Consult BUSS Fuse Engineers . . .**

They will gladly help you select the fuse that suits your needs best . . . if possible, a fuse available from local wholesalers' stocks.

Plus A COMPLETE LINE OF FUSE CLIPS, BLOCKS AND HOLDERS



FOR MORE INFORMATION *mail this coupon today*

Bussmann Mfg. Co., University at Jefferson
St. Louis 7, Mo. (Division of McGraw Electric Co.)

Please send me bulletin SFB containing facts on BUSS small dimension fuses and fuse holders.

Name.....

Title.....

Company.....

Address.....

City & Zone.....State.....

1151


PRECISION-ENGINEERED
HOUSINGS
DESIGNED FOR
ELECTRONICS
MORE THAN 3000 SIZES, IN A COMPLETE RANGE OF METALS—STEEL, BRASS, ALUMINUM, Mu-METAL.
OLYMPIC HOUSINGS are designed for easy assembly. Minimum variations in dimensions at any stage. Built-in flexibility assures modification and fabrication to meet blueprint specifications.
• Delivery from stock—no shipping delays
• Tooling costs eliminated
OLYMPIC HOUSINGS are engineered to incorporate three major elements of construction—Uniformity, Strength, Compactness.
On your next project—let OLYMPIC craftsmen give you facts, figures and specifications. Send for new illustrated folder E4 today.
STANDARDIZE WITH OLYMPIC
OLYMPIC
METAL PRODUCTS COMPANY, INC.
ALPHA, NEW JERSEY

cathode resistor, 100 ohms; grid resistor, 47,000 ohms; and plate current limits, 43 to 73 ma.

ELECTRONIC COUNTER
uses no vacuum tubes

COMPUTER RESEARCH CORP., 3348 W. El Segundo Blvd., Hawthorne, Calif., has developed a rugged, electronic predetermining counter, capable of counting up to 1,800,000 cpm without the use of vacuum tubes. The unit incorporates true ring elements in an improved ferroresonant circuit that is not sensitive to heat. It can start or stop counting on any count, control operations by the use of frequency division, or emit an output pulse at any predetermined count, for use in driving external devices. The output pulse is also adaptable for direct use with magnetic amplifiers for controlling large amounts of power without vacuum tubes or switches.



TEST ADAPTERS
for 9 tube socket types

VECTOR ELECTRONIC CO., 3352 San Fernando Road, Los Angeles 65, Calif. The adapters illustrated are used for making voltage resistance and waveform measurements from the tube side of an electronic equipment. In testing, the adapter is inserted between the electronic tube and its socket, completing the circuit and providing convenient test tabs. Adapters are made for nine socket types. For most work the short, unshielded adapters are adequate, but for hard-to-reach locations a longer adapter with shielded leads is available. Where there is a need to break tube circuits or alter the pin connections the Experimenter type is available. This third type also provides means for

the solution to your noise suppression problem...

AEROVOX

R-F noise suppression FILTERS*

High reliability R-F noise suppression with high attenuation... high current ratings... still smaller hermetically-sealed metal-case housings... advanced pi-type construction for greatest efficiency...

Aerovox Filters are ideal for R-F noise suppression in military and commercial aircraft, vehicular low-voltage DC applications, and for special applications such as shield rooms and critical equipment.

FEATURES...

- **Aerolite† metallized-paper sections provide maximum reliability and life factors.**
- **Unique "fault-isolation" characteristic offers added protection against surge voltages.**
- **High attenuation of R-F currents. Maximum attenuation available, from .15 mc to 400 mc.**
- **Low DC resistance assures minimum heating and low voltage drop.**
- **Operating temperature range from −55° C to +85° C. At full rating (150 v.d.c.) operating temperature range is from −55° C to +70° C. All units rated for continuous duty.**
- **Test voltage for all units, 200 v.d.c. at room temperature for period not exceeding 1 minute.**
- **Case construction of non-magnetic metal suitably protected for severest service requirements.**
- **Available with special terminals, special mountings and other special considerations for specific needs.**

* **SCREEN ROOM FILTERS also available with extra-high attenuation (120db) for AC and DC applications. For literature and further information on screen room and R-F noise suppression filters, write Aerovox Corporation, New Bedford, Mass.**

†trade-mark

AEROVOX Capacitors

AEROVOX CORPORATION

NEW BEDFORD, MASS.

Hi-Q DIVISION
OLEAN, N. Y.

ACME ELECTRONICS, INC.
PASADENA 4, CALIF.







THREE

IN ONE

UNIVERSAL BRIDGE

TF 868

RESISTANCE, CAPACITANCE, INDUCTANCE and power factor are measured quickly and accurately on this Marconi engineered instrument. Three basic bridges are used with a 1,000 cps oscillator and 3 tube logarithmic amplifier with wide range automatic gain control. Simple to use, the main dial is direct reading, without arithmetic, on all ranges (0.1 Ω - 10 MΩ, 1 μμf - 100 μf, 1 μH - 100H) to an accuracy of one per cent. Its industrial-designed appearance fits well in modern surroundings and partners its outstanding electrical performance. Let us mail you full particulars.

MARCONI INSTRUMENTS

Specialists in Communication Test Equipment

23-25 BEAVER STREET · NEW YORK 4

CANADA: CANADIAN MARCONI CO., MARCONI BUILDING, 2442 TRENTON AVENUE, MONTREAL
ENGLAND: Head Office: MARCONI INSTRUMENTS LIMITED · ST. ALBANS · HERTS.
Managing Agents in Export: MARCONI'S WIRELESS TELEGRAPH COMPANY LIMITED MARCONI HOUSE, STRAND · LONDON · W.C.2

adapting tubes to nonmating sockets.



DELAY LINES
are highly miniaturized

PCA ELECTRONICS INC., 6368 DeLongpre Ave., Hollywood 28, Calif., has available the first of a series of continuously variable distributed-constant delay lines. They are designed to provide a continuously variable time delay of 0 to 0.5 μsec, with a rise time as low as 0.05 μsec at full delay. Available for immediate shipment are delay lines, terminated internally, of 500 ohms nominal characteristic impedance and on special order, lines with an impedance up to 1,500 ohms. These lines are highly miniaturized, measuring 7½ in. × 1¼ in. × 1½ in. and are ruggedly constructed to withstand vibration and shock.



CONTROLS
for printed circuit use

CHICAGO TELEPHONE SUPPLY CORP., Elhart, Ind. Two new variable composition resistors have been announced to fill the need for controls for use in printed-in circuit applications. There are three outstanding design features: (1) Protection against bending during handling is achieved by recessing each blade-type terminal in a notch in the bakelite base of the control. (2) Valuable mounting space is conserved on the printed-circuit

One Source of Supply by E-I — for every hermetically sealed termination

Specify — E-I sealed leads and multiple headers

HUNDREDS OF STANDARD TYPES AT MASS PRODUCTION PRICES TO MEET EVERY REQUIREMENT

— at your fingertips!

Development, production and design engineers will find the complete E-I Data File a helpful addition to company files. The new brochure includes standardized terminations that economically solve all but the most unusual terminal problems. If custom types are required, E-I can supply these quickly, to exact specifications at quantity production prices.

CALL OR WRITE FOR THE NEW E-I DATA FILE NOW!

ELECTRICAL INDUSTRIES
44 SUMMER AVENUE, NEWARK 4, NEW JERSEY

DIVISION OF
AMPEREX
ELECTRONIC CORP.

1. BULLETIN 949-A

On hermetically sealed terminals. Discusses cushioned glass construction, thermal shock resistance, preferred types and special terminals. Explains code systems and methods of installation.

2. BULLETIN 950-A

On hermetically sealed multiple headers. Explains vacuum tight feature, cushioned glass construction, strain-free qualities. Tin dipped for easy soldering and silicone treated for highest electrical resistance.

3. BULLETIN 951

With complete information on octal type plug-in and multiple headers. Feature a new principle of hermetic sealing. Solid metal blanks insure maximum mechanical strength and rigidity.



4. BULLETIN 952

Complete information on E-I end seals for hermetic sealing condensers, resistors and other tubular electronic and electrical components. Provide a permanent hermetic seal. Completely strain-free.

5. BULLETIN 953

Individual, color-coded hermetically sealed terminals. Available with glass inserts colored in standard, easily identified RMA color codes. Coloring is in the glass —no lacquers or enamels are used.

6. BULLETIN 960

Compression type multiple headers. Super rugged, absolutely rigid and practically indestructible. An exclusive E-I achievement offers vastly greater resistance to shock and vibration. Guaranteed vacuum-tight.

EXPORT AGENTS:
PHILIPS EXPORT CORP., 100 EAST 42nd STREET, NEW YORK 17, N. Y.

*PATENT PENDING

ALL RIGHTS RESERVED

Announcing

FOR 2000 mc.

GABRIEL OFFSET FEED ANTENNAS

- **HIGH GAIN**
- **LOW VSWR**
- **LOW SIDE LOBES**

MODEL 2K6T: *A 6 foot microwave antenna. — Gives outstanding performance from 1700 to 2110 mc. — New offset feed design increases efficiency of assembly thereby achieving high gain of better than 30 db. Write for further information.*

THE GABRIEL COMPANY

Endicott Street, Norwood, Massachusetts

WORKSHOP ASSOCIATES DIVISION

panel by placing terminals close in to the mounted bushing. (3) Adequate clearance for circuit paths is provided by ample spacing between terminals. The controls are available in both $\frac{3}{4}$ in. diameter (type U70) and in $1\frac{1}{8}$ in. diameter (type U45). The $1\frac{1}{8}$ in. diameter control is also available with spst and dpst 3 ampere, 125 v switch.



SERVO CONTROLS
feature high precision

KEARFOTT CO., INC., 1150 McBride Ave., Little Falls, N. J. Synchro transmitters and control transformers with maximum error limits of 7 minutes are now available. Only 1.062 in. in diameter and 1 23/32 in. long, models for either 26-v or 115-v 400-cycle excitation can be obtained. By virtue of their unique integral construction, these units assure performance under extreme conditions of humidity, temperature, altitude and vibration.



FLYBACK
is multipurpose device

HALLDORSON TRANSFORMER CO., 4500 Ravenswood, Chicago 40, Ill. The FB410 multipurpose flyback

NEW HOME OF AIR MARINE MOTORS INC.

manufacturers of Sub-fractional Electric Horsepower Motors.

Some of the country's leading manufacturers we are proud to serve...

RCA
RAYTHEON
DU MONT
FAIRCHILD
WESTINGHOUSE
GE
CEC
Thompson Products, Inc.
DOUGLAS
National
NATIONAL COMPANY, Inc.
wilcox
ELECTRIC COMPANY, INC.
Motorola

AIR MARINE MOTORS INC.
369 BAYVIEW AVE.
AMITYVILLE, L.I.

Want more information? Use post card on last page.

YOU CAN ALWAYS RELY ON EDISON COMPONENTS

for Electronic and Communications Equipment Because of:

HERMETICAL SEALING in rigid glass.

TAMPER-PROOF stability that defies time and abuse.

ACCURACY. Patented feature permits calibration *after* sealing.



THERMAL TIME DELAY RELAYS

Cathode and filament protection • Gyro Erection • Prevent surges and false starts in sensitive auxiliary equipment • Miscellaneous circuit switching

SPECIFICATIONS

Standard Octal Base

Delays . . . 2 seconds to 5 minutes
Heater . . . 5 watts nominal, continuous operation
Voltages: 6.3, 26.5 and 117
Contacts . . . 6 amps maximum, 3 amps to 450 volts a.c. or d.c.
Vibration . . . 1/16" amplitude at 55 cps. 50g shock.
Ambient . . . −60 to +85°C **Seated Height** . . . 3¼ max.

Miniature 7-Pin Base

Delays . . . 5 seconds to 75 seconds
Heater . . . 2.5 watts nominal, continuous operation
Voltages: 6.3 and 27.5
Contacts . . . 2.5 amps max. 1 amp at 125 volts d.c.
Vibration . . . 1/16" amplitude at 55 cps. 50g shock.
Ambient . . . −60 to +85°C **Seated Height** . . . 2¼ max.



SEALED THERMOSTATS

Ambient protection for frequency standards • Precision heat control for electronic laboratory instruments • Overheat detection and fire alarm

SPECIFICATIONS

Heavy duty—type D8	*Precision control—type S1*
Max. temp. . . . . 320°C	**Max. temp.** . . . . 190°C
Max. watts 1000	**Max. watts** 150
Max. amps. . . . . 8.0 d.c.	**Max. amps** 1.0
Calibration tolerance . . . ±2.5°C	**Control** differential at ¼ amp = 0.1°F
Length, 2¾"; **dia.,** 9/16" (approx.)	**Length,** 2½"; **dia.,** ⅜" (approx.)

Write for free bulletins and application data to:

Thomas A Edison
INCORPORATED
Instrument Division
DEPT. 54, WEST ORANGE, NEW JERSEY

YOU CAN ALWAYS RELY ON EDISON

transformer answers a growing need for a single unit possessing electrical and mechanical characteristics applicable for replacement in a wide variety of tv chassis, both new and old. It is equipped with a universal mounting bracket that permits replacement of many different mounting types without drilling a single hole. The unit accommodates horizontal yoke windings of from 8 mh to 25 mh and width coils whose control ranges fall anywhere between 0.1 mh and 30 mh. Flexible construction permits conformation with popular inductively coupled and autotransformer-type horizontal output circuits. A separate winding for agc and/or horizontal phase detection is provided. No additional dual-winding width controls are needed.



POTENTIOMETER has 0.02-percent linearity

BIRKLAN CORP., 200 E. Third St., Mt. Vernon, N. Y. Standard linearity of 0.02 percent is a feature of the series 1800 potentiometer. Resistance range is 1,000 to 150,000 ohms with a resistance tolerance of 1 percent. In the middle resistance range and above linearities better than 0.02 percent can be furnished. The unit has 10 full turns of travel at each end. The resistance element continues through the overtravel and can be tapped in that interval. Each unit is supplied with a continuous linearity curve calibrated against a standard accurate to 0.001 percent. The unit is rustproof, contains no fungus nutrient and may be operated over a wide temperature range. It is impervious to torque damage in normal



Regohm Circuit Controller, shown at actual size, with cover removed. Designed, developed and manufactured by the Electric Regulator Corp., Norwalk, Conn.

1/10¢ *lengths* of BH "649" ride the thermometer

Small enough to fit in the hand . . . it can control energy millions of times greater than that needed to activate it. That's the Regohm, manufactured by the Electric Regulator Corporation. It is a compact, versatile control component of the direct-acting finger type with wide acceptance as a voltage, current and speed regulator.

Electric Regulator engineers said, "We needed an insulation that would be permanently flexible through high and low temperatures. We found what we needed in BH "649" Fiberglas Tubing, and got these added advantages: BH "649" is easy to handle, it slips over wires quickly and speeds assembly time. It withstands the roughest handling without damage. It can be cut in short lengths without fraying or cracking. Its smooth, glossy surface adds to the appearance of our products."

BH "649", pioneer in the field of vinyl plastisol tubings, now offers true Class B protection at 130°C. with its improved coating formulation. Rated dielectric strength and flexibility continue after exposure to 150°C. for 300 hours, 200°C. for 20 hours, 232°C. for 3 hours—and for even longer periods if not abused after conditioning. Its resistance to chemicals and oils, as well as its high physical strength, has helped solve many tough insulation problems in a wide range of applications.

Why not investigate the advantages of BH insulations today. BH "649" is just one of a large family of Fiberglas tubings and sleevings developed specifically for the electrical industry. If you'll send facts on your requirements—voltages, temperatures, unusual conditions—we'll be happy to make recommendations and send samples for testing.

Bentley, Harris Manufacturing Co.
1311 Barclay Street
Conshohocken, Pa.

BH FIRST IN
use of Fiberglas
heat-treated Fiberglas
true high temperature flexibility
vinyl-coated Fiberglas
silicone rubber coating
colors in silicone rubber
true Class B (130°C.) protection

BH *Fiberglas** SLEEVINGS

*BH Non-Fraying Fiberglas Sleevings are made by an exclusive Bentley, Harris process (U. S. Pat. No. 2393530). "Fiberglas" is Reg. TM of Owens-Corning Fiberglas Corp.

Want more information? Use post card on last page.



ELECTRO insulating materials combine these important qualities: high dielectric and tensile strength, minimum bulk, excellent thermal conductivity and flexibility, marked resistance to heat, oil, acid and moisture. That's why these insulating materials are used effectively in the design and production of high temperature electrical equipment that is *smaller, safer* and *lighter.*

ELECTRO HI-TEMPERATURE FIBERGLAS* INSULATION has helped numerous manufacturers of motors, transformers and electronic equipment to do a better and safer insulating job. We would like the opportunity to help you. Send us your insulation problem or write to our Department E-1 for technical data and samples.

*T. M. REG. U. S. PAT. OFF. by Owens Corning Fiberglas Corp.

applications by virtue of a built-in traveling-nut-type limit stop.

CONNECTORS
have double-wiping contacts

U. S. COMPONENTS INC., 454 E. 148th St., New York, N. Y., has developed new features in their 980 series connectors, consisting of double-wiping contacts and guide-pin ejection springs. The double-wiping contacts offer external as well as internal wiping when connectors are mated. This assures a dependable contact under all conditions of usage eliminating possibility of circuit failure due to poor connector contact. Guide-pin ejection springs are normally compressed with balanced force when connectors are mated and serve the purpose of reducing separation force upon disconnection. They further serve as an auxiliary current path for heavy guide-pin currents. Brochures are available upon request.



POWER-LINE CARRIER
has closer channel spacing

WESTINGHOUSE ELECTRIC CORP., 2519 Wilkens Ave., Baltimore 3, Md. A complete new line of power-line carrier equipment (type FD) for power-system relaying, telemetering, supervisory control and voice communication is now available. One of the features offered in the new equipment is closer channel spacing, made possible by highly selective receiver filters and crystal control of frequency. Frequency ranges are 40 to 90 and 90 to 200 kc. Assemblies operate from

want a HIGH VACUUM rotary pump that pumps WATER VAPOR?

Here's the NEW GAS BALLAST PUMP backed by MILLIONS OF HOURS of trouble-free operation

Ends Water Vapor Trouble
Maintains Fast Pump Down Time

Eliminates Oil Reclaiming
Greater Capacity Under 1 mm Hg
Up To 80% Less Oil Charge
Capacities from 1¼ cfm to 400 cfm
Pressures Down To 10^{-5} mm Hg

Here's important news for everyone who works with high vacuum. The new NRC Rotary Gas Ballast Pump gets it for you faster — saves you time and money and is backed by millions of hours of trouble-free operation.

By keeping water vapor from condensing, this pump prevents contamination of the pump oil. The result—it never loses capacity like conventional rotary pumps when pumping condensable vapors. It continually maintains a fast pump down rate.

NRC Rotary Gas Ballast Pumps are available in a complete line of vane, piston-type and 2-stage pumps.

Send today for new bulletin explaining principle, construction and operation data on the NRC Rotary Gas Ballast Pump.

NRC National Research Corporation
Equipment Division
Seventy Memorial Drive, Cambridge, Massachusetts



CAROL
multi-conductor cable

Here's the cable that gives the best in electrostatic and interference shielding—for stationary and portable microphones, speakers, P. A. systems, automobile radios and other electronic devices.

Tinned soft copper conductors are stranded for exceptional flexibility, paper served for easy stripping, individually insulated with low capacitance rubber or polyethylene, in some sizes. Wires are cabled to perfect roundness, cotton served and shielded with tinned copper braid. Outer jacket is either rubber, neoprene or plastic, depending on service requirements.

For expert engineering assistance and prompt service on all your cable applications, write or call Carol today.

CAROL
CABLE DIVISION
of The
CRESCENT COMPANY INC.
Pawtucket, Rhode Island

Want more information? Use post card on last page.

either station battery or alternating current.

INVERTERS
operate from car batteries

AMERICAN TELEVISION & RADIO CO., 300 E. Fourth St., St. Paul, Minn., has available a line of inverters that operate from 6 or 12 v car storage batteries and provide 110-v a-c 60-cycle output in various power capacities for the operation of dictating machines, tape recorders, wire recorders, radio sets, test equipment and other related small electrical or electronic apparatus. Inverter models are also available for operation from other d-c input voltages ranging from 6 v d-c to 220 v d-c in automobiles, busses, trucks, planes, trains, ships and residential d-c districts.



CONNECTORS
automatically interlock

HARVEY HUBBELL, INC., State & Bostwick Ave., Bridgeport, Conn., has available a line of electrical connectors that feature an automatic locking connection that can never disconnect accidentally. The Interlock plug locks automatically

OFFERING

- **sub-miniature, rotary, electrical equipment for specialized applications...**
- Mission-Western Engineers, Inc., offer a wide range of basic motor designs adaptable to highly specialized applications.

400 cps 115 VAC 1 Ø Gearmotor. 80 inch ounces at 22 RPM. Dimensions: 1.50" dia. x 2.81" long.
400 cps 115 VAC 1 Ø Gearmotor. 10 inch ounces at 10 RPM. Dimensions: 1.06" dia. x 2" long.

320/1000 cps 115 VAC 1 Ø motor and 3" fan assembly. 8500 RPM at 400 cps. With 2" fan, 10,000 RPM at 400 cps. Motor Dimensions: 1.45" dia. x 1.75" long.

400 cps, 115 VAC 1 Ø motor and L-R #2 Centrifugal Blower, 22 CFM free air. With 60 cps motor, 10 CFM With 28 VDC motor. 35 CFM.

Permanent Magnet DC motor & L-R #1½ Centrifugal Blower. 20 CFM free air. Motor dimensions: 1¼" dia. x 2" long.

Permanent Magnet DC Motors & Gearmotors. Output Speeds to 1 RPM. Frame diameter 1 3/16" or 1¼". Also available (1¼" dia. frame only) in Split Series DC when design forbids use of Permanent Magnet type.

If you have a problem involving design or application of AC or DC type motors, why not write us for engineering assistance and recommendations on a Mission-Western designed motor?

Many other types and frame sizes, in both AC and DC, available.

Mission-Western is associated with Western Gear Works—since 1888 a leader in the mechanical power transmission field. 6326

MISSION-WESTERN
ENGINEERS, INC.
132-134 West Colorado St., Pasadena 1, Calif.
Want more information? Use post card on last page.

Simplify Your Access Panel and Door Assemblies...

Fastening removable access doors and panels need not be a laborious and costly production or assembly operation—not if they're fastened with QUICK-LOCK.

Designed for simple installation, QUICK-LOCK requires no special tools. It speeds up mounting and demounting detachable panels with only a 90° turn required to lock and unlock it *in a jiffy*.

The flexible mounting and tapered stud makes QUICK-LOCK ideal for assembling curved sheets and insures a tight fit when locked. Stud is self-ejecting when unlocked. Minimum deflection is assured—only initial loads are carried by the helical spring. Solid supports take up increased loads.

Industrial and agricultural equipment manufacturers would do well to analyze the cost-saving features of QUICK-LOCK's simple design. A good way would be to call in a Simmons Engineer and discuss the economy of a QUICK-LOCK installation as compared to your present fastening method. Why not send for him today?

SIMMONS FASTENERS

SIMMONS FASTENER CORPORATION • 1750 NORTH BROADWAY, ALBANY 1, N. Y.

Want more information? Use post card on last page.

CUSTOM STYLING...
without costly tooling!

Lower production costs with Johnson stock-mold knobs and dials...



Suitable for the finest electronic equipment, JOHNSON knobs and dials offer modern design and custom styling without costly tooling. Featuring tough, black phenolic construction and heavy brass inserts, they are perfect for heavy duty application in the laboratory on test and measuring instruments, on radio receivers or transmitters, or on studio equipment and industrial controls. Gripping surface is excellent. 12 flutes instead of the usual 8, add comfortable "feel" and beauty.

Available in three basic knob diameters, 1⅛", 1⅜", and 2⅜". Knobs can be assembled with matching black molded phenolic skirts of 1½", 2⅛", or 3" diameters; or nickel silver, chromium plated dial plates, 1½", 2⅜", or 4". Finish diffuses light reflection, markings are clearly visible.

Other types and modifications available on special order. For complete information on JOHNSON knobs and dials, write for your copy of General Products Catalog 973

Cat. No.	Illus.	Description	Knob Dia.	Height	Skirt or Dial Dia.
116-214-1	1	Instrument knob, black phenolic, ¼" shaft	½		⅝
116-214-2	1	Instrument knob, black phenolic, ⅜" shaft	½		⅝
116-221	2	Knob with black phenolic skirt	1⅛	13/64	1½
116-261	2	Knob with black phenolic skirt	1⅜	29/64	2⅛
*116-281	2	Knob with black phenolic skirt	2⅜	1 13/64	3
116-220	3	Knob only, black phenolic	1⅛	11/64	
116-260	3	Knob only, black phenolic	1⅜	29/64	
*116-280	3	Knob only, black phenolic	2⅜	51/64	
116-222	4	Knob with beveled satin chrome dial 116-222-1 100-0 over 180° 116-222-4 ON-OFF over 60° 116-222-2 10-0 over 270° 116-222-5 Single line 116-222-3 7-1 over 180°			
116-226	5	Spinner Knob	1⅛	11/64	
116-266	5	Spinner Knob	1⅜	29/64	
*116-286	5	Spinner Knob	2⅜	51/64	
116-262	6	Knob and chrome dial, 0-100, 180° Single line indicator	1⅜	15/64	2¼
*116-282	6	Knob and chrome dial, 0-100, 180° Single line indicator	2⅜	1 1/64	4
116-265	7	Vernier dial, 0-100, 180° 3 to 1 friction drive	1⅜	15/64	2¼
116-285	7	Vernier dial, 0-100, 180° 5 to 1 friction drive	1⅞	15/64	4

All knobs and dials fit standard ¼" shafts. *Also available for ⅜" shafts.

E. F. JOHNSON COMPANY

CAPACITORS, INDUCTORS, SOCKETS, INSULATORS, PLUGS, JACKS, DIALS, AND PILOT LIGHTS

228 SECOND AVENUE SOUTHWEST • WASECA, MINNESOTA

when plugged in and can be quickly and easily disconnected when desired. This locked, vibration-proof connection has constant low contact resistance and actually makes contact on two separate surfaces which are under constant coil-spring pressure. Any decrease in contact pressure on one contact surface will be automatically increased on the other surface. Various types are available: automatic locking plugs and jacks, both metal and insulated; right angle plugs, connectors and splicing links; flexible aluminum terminal strips that can be cut to any length and bent or curved to any shape for form-fitting wiring design; and a versatile 4-in-1 test prod with interchangeable attachments that lock automatically to the prod coupler.



INDUCTORS
solenoid and pi wound

INDUSTRIAL TELEVISION, INC., 359 Lexington Ave., Clifton, N. J., has announced a new line of components for manufacturers of military electronic equipment and high-quality commercial instruments. First introduced were variable slug-tuned inductors, both solenoid and pi wound, in a wide range of standard values or custom wound to specification. They are particularly suited for use as video peaking inductors in amplifiers where electrical performance, miniaturization and reliability are paramount. Designated the IT-123CS (solenoid) and the IT-123CP (pi) series these variable inductors are wound on forms of series FM-3001 black nylon (other colors available) with slugs of Pyroferric P-4399. Design-center induction range for solenoid types is 1 to 100 micro-



MOLYBDENUM PERMALLOY POWDER CORES*

(New technical data now available)

HIGH Q TOROIDS for use in Loading Coils, Filters, Broadband Carrier Systems and Networks—for frequencies up to 200 KC

COMPLETE LINE OF CORES TO MEET YOUR NEEDS

★ **Furnished in four standard permeabilities—125, 60, 26 and 14.**

★ **Available in a wide range of sizes to obtain nominal inductances as high as 281 mh/1000 turns.**

★ **These toroidal cores are given various types of enamel and varnish finishes, some of which permit winding with heavy Formex insulated wire without supplementary insulation over the core.**

For high Q in a small volume, characterized by low eddy current and hysteresis losses, ARNOLD Moly Permalloy Powder Toroidal Cores are commercially available to meet high standards of physical and electrical requirements. They provide constant permeability over a wide range of flux density. The 125 Mu cores are recommended for use up to 15 kc, 60 Mu at 10 to 50 kc, 26 Mu at 30 to 75 kc, and 14 Mu at 50 to 200 kc. Many of these cores may be furnished stabilized to provide constant permeability ($\pm 0.1\%$) over a specific temperature range.

*Manufactured under license arrangements with Western Electric Company

WAD 4744

THE ARNOLD ENGINEERING COMPANY

SUBSIDIARY OF ALLEGHENY LUDLUM STEEL CORPORATION

General Office & Plant: Marengo, Illinois

DISTRICT SALES OFFICES . . . New York: 350 Fifth Ave.

Los Angeles: 3450 Wilshire Blvd. Boston: 200 Berkeley St.

INTERNATIONAL RECTIFIER
CORPORATION
1521 E. Grand Ave., El Segundo, Calif. · Phone: ORegon 8-3778
CHICAGO: 205 W. Wacker Drive · Phone: Franklin 2-3889
NEW YORK: 501 Madison Avenue · Phone: Plaza 5-8665



henries and for pi windings, 100 to 20,000 microhenries.



ALLIGATOR CLIP
aids live-circuit testing

INSULINE CORP. OF AMERICA, 3602-35th Ave., Long Island City 1, N. Y., has brought out the No. 524 fully insulated alligator clip that facilitates the testing of live circuits in television and radio receivers and in electrical equipment in general. The spring-loaded jaws, which are actuated by a thumb button in the body of the clip, hold firmly on conductors up to ¼ in. in diameter. Connection to the clip is made with standard banana plugs.



SPEAKER
designed for high fidelity

OXFORD ELECTRIC CORP., 3911 S. Michigan Ave., Chicago 15, Ill., has added to its line of loudspeakers the high-fidelity 15-in. model HF-15LN. Frequency range is 50 to 10,000 cps. Alnico magnet weight is

It Costs You Less to Use STONE'S Small Diameter Bushings— Than Bushings of ANY OTHER MATERIAL



Actual size photograph unretouched

Stone's spiral wound bushings are bonded with special adhesives which retain their precision-made cylindrical forms, thus guaranteeing rapid and easy assembly over rivets, plain and threaded posts, and other small metal components.

Uniformity of size with diameters ranging downward to .046" and lengths to .040" is a Stone quality unequalled in the industry.

Most important from a cost standpoint is the flexibility of construction possible because of Stone's wide variety of immediately available materials—including hi-dielectric kraft, fish paper, and plastic films—a selection assuring lowest cost for whatever job you have in mind.

Call or write us today for prompt attention.

STONE PAPER TUBE COMPANY, INCORPORATED
STONIZED PRODUCTS COMPANY, INC.

900-922 Franklin Street, N. E., Washington 17, D. C.

14 oz. It has a 25-w power rating and an input impedance of 8 ohms. Voice coil is 1½ in. in diameter. The speaker is finished with a silver Hammerloid enamel and has a blue pot cover.

SOLDERING FLUXES
are noncorrosive

FIM, INC., 170 Fifth Ave., New York 10, N. Y., is now marketing two new aluminum soldering fluxes. One flux (No. 18) in paste form is especially designed to solder aluminum with tin, lead, zinc, cadmium and their alloys. When heated the solder melts and spreads over the aluminum surface wherever the flux has touched. Any plain solder, torch or soldering iron can be used. Another flux (No. 24) in powder form solders all commercial metals such as steel, stainless steel, copper, brass, nickel, silver and aluminum. It is also suitable for dip soldering. Both fluxes are noncorrosive.



RASTER TIMER
provides ten sweeps

AMERICAN ELECTRONIC LABORATORIES, INC., Philadelphia, Pa. The purpose of the model-101 raster timer is to enable accurate time measurement of recurrent or transient phenomena, without losing sight of the entire cycle of events. It presents a series of 10 calibrated sweeps, one above the other on the screen, so that assuming a useful area of 4 in. × 4 in., the equivalent of a 40-in. viewing screen is created on the horizontal axis. The sweeps provided are 1, 3, 5 or 10 milliseconds each, crystal controlled to 0.01 millisecond, and each of the 10 sweeps carries time markers allowing measurements to an accu-





NE-11-20-S SPECTRUM ANALYZER

Description

The Spectrum Analyzer is test equipment designed primarily for use with aircraft radar and beacon equipment operating over a frequency range of 8470 to 9630 mc/s. Housed in a compact portable carrying case, the whole assembly weighs approximately 90 pounds.

In operation, the Spectrum Analyzer displays on an oscilloscope a pattern representative of the distribution of energy among the various frequencies in the output of a pulsed oscillator. This equipment is equal to our government models TS-148/UP.

Applications

This very sensitive micro-wave receiver will provide accurate measurement of the spectra of radio frequency oscillations in radar and beacon equipment. It will also measure, within its own range, frequencies of echo boxes, magnetrons, test sets, local oscillators and a variety of resonant cavities. It can also be used to check magnetron pulling and AFC circuits, and as a frequency-modulated oscillator to tune T/R Boxes and R/T Boxes in transmitter-converters.

The Analyzer is so sensitive that the magnetron signal can usually be picked up at some distance from the source, thus making the equipment easy to use in any convenient location.

Specifications

Power Supply	50-1200 Cps; 105-125 Volts; 125 Watts
Frequency-meter Range	Calibrated directly from 8470 mc/s to 9630 mc/s
Sweep Frequencies	Continuously Variable from 10 to 30 Cps
Attentuation (Spectrum Amplitude)	Uncalibrated. Variable from 3 to 70 db.
Operating Temperature Range	—40° C. to +55° C.
Frequency swing of analyzer r-f oscillator (sawtooth FM)	40 to 50 mc/s
Overall i-f bandwidth at half power points	50 kc/s
Sensitivity to CW — Spectrum Amplified Pos. — 80 db. below 1 watt for 1 inch of deflection on Oscilloscope Screen.	
— Spectrum Position — 55 db. below 1 watt for 1 inch of deflection of Oscilloscope Screen.	
Maximum dispersion of spectra	1.5 mc/s per inch
Maximum error	± 5 megacycles

We will gladly furnish all details regarding specifications, prices, and delivery.

Write, wire or telephone for information.

NORTHEASTERN ENGINEERING INC.

Manchester, New Hampshire

Telephone 2-6485

small OPEN GEAR TRAINS
made to your specifications



Many units, such as timers, transmitters, vending mechanisms, and similar devices require the adoption of small open gear trains for intermittent duty.
Beaver Gear Works is equipped to make these trains to any degree of accuracy required. Beaver Gear engineers, knowing what is expected, and qualified to assist in details of fine-pitch gear applications, can advise you as to what will work best under various conditions and can specify the correct design.

THE *Finest* IN GEARS

Beaver Gear Works Inc.

1021 PARMELE STREET, ROCKFORD, ILLINOIS

Saratoga Industries

STAR PERFORMANCE AS MANUFACTURERS OF TRANSFORMERS, REACTORS, FILTERS, TOROIDAL COILS FOR THE ELECTRONICS INDUSTRY

Now in its ninth year of operation, Saratoga Industries, Inc. has built a solid reputation for the manufacture of precision windings. Approved for in-plant testing under MIL-T-27, Saratoga Industries, Inc. is also prepared to handle all types of commercial production. Saratoga engineers invite your inquiry to help solve your problems relating to reactors, transformers, filters and windings of all types.

SARATOGA INDUSTRIES, INC. SARATOGA SPRINGS, N. Y.

racy of 0.05 millisecond or better, or 0.1 to 0.05 percent of the total presented sweep time. All circuits within the unit are stabilized so that there is no jitter or wandering of the standing pattern of recurrent phenomena, which may be required for photographic recording.

TWIN TETRODE
for mobile transmitters

AMPEREX ELECTRONIC CORP., 230 Duffy Ave., Hicksville, Long Island, N. Y. Type 6252 twin tetrode is a lower power version of the 5894/AX9903. Its maximum plate dissipation rating is 20 w under ICAS conditions and it works efficiently with a power output of 112 w at 600 mc. It has been successfully operated as a frequency multiplier over the entire uhf tv band. The tube is particularly suitable for low-drain mobile transmitters and multiplier chains. It is only 3 in. in overall height and slightly less than 1¾ in. maximum diameter.



TUNED CIRCUITS
are stable and precise

VANGUARD ELECTRONICS CO., 3384 Motor Ave., Los Angeles 34, Calif., announces a series of rigidly constructed single and double-tuned circuits noteworthy for stability and precise performance. The circuits are housed in a ¾-in. × ¾-in. × 2-in. aluminum container. Features include: a rigid coil form held under force fit in metal bushings, a heavy metal bracket to secure the entire structure, grounding bushings and adjustment studs to the

PROJECT TINKERTOY

Released By The Government And Now Available To Industry

what it is

Project TINKERTOY is the code name for a development by the National Bureau of Standards. It consists of a design system and automatic machinery for the MECHANIZED PRODUCTION OF ELECTRONIC EQUIPMENT. This program was sponsored by the Navy Bureau of Aeronautics as an industrial preparedness measure in production research.

how it affects your production of electronic equipment

A high speed mechanized production process, the Project TINKERTOY method is also economical for small quantities.* Production of one *or* one million units is practical without design change. The ultimate in standardization of tooling and assembly is possible, and a minimum of skilled labor is required. Under this new design system you easily shift production over a wide range of products — rapidly and economically. This new mechanized production method guarantees uniformity of product *plus* automatic quality control, giving increased reliability. Production engineering costs are minimized because the development model actually *is* the final production design.

* Small pilot runs, using an equivalent hand module assembly method, are actually competitive with quantity production runs by present day methods.



The heart of the N.B.S. system is the "module", consisting of half a dozen ceramic wafers interconnected by a dozen "riser" wires. Each wafer can contain as many as four tape resistors, ceramic disk condensers, or a tube socket, plus silvered connections to the proper riser wire. A single module can contain an entire circuit including a tube socket and twenty components as illustrated below left. Coils and other miscellaneous components can also be included. Several modules can be sandwiched between two photo-etched circuits providing a complete package. Audio, video, IF and RF amplifiers; oscillators, sweep circuits and counters have been made by this method. Tests by Sanders Associates have shown this equipment capable of withstanding environmental conditions beyond Military requirements.



This entire circuit can be contained in one module



Section of radio altimeter before and after adaptation to Project TINKERTOY by Sanders Associates



Hand module assembly jig

Sanders Associates is proud to have been a member of the team contributing to this revolutionary development of the National Bureau of Standards and sponsored by the Navy Bureau of Aeronautics. Our responsibility was the developing and establishing of hand assembly facilities for pilot-line production. Sanders Associates successfully applied the Project TINKERTOY principles to a submarine detecting device, a radio altimeter and other military equipments.

Now Sanders Associates is able to offer to the industry its "know-how" obtained during two years of redesign engineering in association with Project TINKERTOY. We are ready to assist in engineering the conversion of conventional electronic equipment to the modular design technique, leading to automatic production. Why not send for our recent bulletin on Project TINKERTOY? Address inquiries to Department 62.

SANDERS ASSOCIATES INCORPORATED

NASHUA, NEW HAMPSHIRE

reliability in electronics

TEFLON* CAN improve your products!

JOHN CRANE

Exceptional qualities of "JOHN CRANE" TEFLON make it highly desirable for a wide range of equipment and parts lines. Manufacturers of precision equipment and component parts cannot overlook its remarkable electrical, thermal, mechanical and anti-corrosive advantages. Note Teflon's outstanding properties and characteristics.

*DuPont Trade-mark

Low power factor high dielectric strength

ELECTRICAL PROPERTIES: Power factor less than 0.0005 over the entire spectrum from 60 cycles to 30,000 megacycles, with a dielectric constant of between 2.00 and 2.05 • Short-time dielectric strengths from 1,000 to 2,000 v., per mil in thickness of 5-12 mils • High resistance to surface arc • Volume resistivity greater than 10^{15} ohm-cm • Surface resistivity drops to only 10^{13} ohms at 100 percent relative humidity.

Corrosion resistant

ANTI-CORROSIVE PROPERTIES: Resists all chemical liquids and gases except molten alkali metals and fluorine and chlorine trifluoride • No detectable changes in properties over 1-year outdoor weather test • Zero water absorption.

Outstanding thermal characteristics

THERMAL AND MECHANICAL PROPERTIES: Tensile strength 1,500 to 2,500 psi. at 77 deg. F. • Durometer hardness 55 to 70 • Stiffness 60,000 psi. at 77 deg. F • Friction coefficient against polished steel (static) .09—.12 • Remains flexible down to −94° F. Serviceable up to +482° F.



Typical Application

TYPICAL APPLICATIONS: For such applications, as vhf, uhf, or high voltage—high temperature insulator forms, heat-resistant linings, oil and fire-wall seals, gaskets, valve discs or seats, packings, flexible bellows, diaphragms, slot liners, heat sealer jaws and dough rollers. Let our engineers fit "JOHN CRANE" TEFLON to your specific needs.

"JOHN CRANE" TEFLON parts can be manufactured to your specifications. Investigate now. Let us know your requirements. Send for our 12-page illustrated catalog.

Crane Packing Company, 1802 Cuyler Ave., Chicago 13, Ill.

JOHN CRANE

CRANE PACKING COMPANY

container. Coil frequencies range from 50 kc to 100 mc. Standard units are offered with adjustable iron cores from top and bottom. Cup cores are available for high Q in special applications.



B+ BOOSTER
has built-in time delay

WORKMAN TV, INC., Teaneck, N. J., has introduced its new model 5TV4, B+ booster. The unit replaces the 5T4G in tv receivers for more height, width and gain. A built-in time delay acts as a choke input. Other advantages are additional filtering and infrequent replacement. Literature is available.

PRINTED VINYL TAPE
for wire identification

PRINTED CELLOPHANE TAPE CO., 521 No. La Brea, Los Angeles, Calif., has announced a printed pressure-sensitive Vinyl (self-adhesive) tape for wire, cable and conduit identification. In a field where marker conformability and flexibility are a must, this tape fulfills all of the qualifications. Extremely thin with 100 percent dead stretch on itself, it is also resistant to fungi and is inert to

FOR COLOR TELEVISION AS WELL AS BLACK and WHITE



A CRYSTAL CONTROLLED TV PICTURE AND SOUND RF SIGNAL SOURCE

USED WITH THE

NEW MEGA-PIX SR. INTERNAL or EXTERNAL SOUND MODULATION

PICTURE CARRIER CAN BE MODULATED WITH ANY STANDARD VIDEO SIGNAL

Individual output controls for sound and picture carriers.

Built-in 400 cps sound modulating frequency with carrier deviation variable to 25 kc.

Video bandwith of 5 mc.

Provision for DC insertion.

Jack for audio input from external source. Standard pre-emphasis provided.

SPECIFICATIONS

OUTPUT SIGNAL FREQUENCIES: Television RF Picture and Sound Frequencies, Channels 2 to 13.

ACCURACY OF PICTURE AND SOUND CARRIERS: ±0.01%.

MAXIMUM PICTURE AND SOUND CARRIER OUTPUT: At least 30,000 microvolts into open circuit.

AMPLITUDE CONTROL RANGE: Individual output level controls for Sound and Picture Carriers plus simultaneous control range of 20 db, 20 db, 10 db, 6 db and 3 db switched, 10 db variable.

RF OUTPUT IMPEDANCE: 72 ohms.

VIDEO INPUT IMPEDANCE: 72 ohms.

VIDEO INPUT SIGNAL REQUIRED: Approx. 2 volts, peak to peak, black negative.

VIDEO BANDWIDTH: 5 mc.

SOUND CARRIER DEVIATION: Continuously variable from 0 to 25 KC.

SOUND MODULATING FREQUENCY: 400 cps., or by external audio. Standard pre-emphasis provided.

PICTURE CARRIER MODULATION PERCENTAGE: Adjustable, 0 to over 95%.

PRICE: $990.00, f.o.b. Pine Brook, N. J.

KAY

KAY ELECTRIC COMPANY

14 Maple Avenue — Phone CAldwell 6-4000 — Pine Brook, New Jersey

Design in Confidence

with

DIEHL

LOW INERTIA A.C. SERVO MOTORS...

. . . for Feedback Control Systems

25 watt, 115 volt, 60 cycle, 2-pole, 2-phase motor with auxiliary fan cooling. *One of the many Diehl Low Inertia A.C. Servo Motors available.*

CONSIDER THESE FEATURES

• High starting torque • Low rotor moment of inertia • Widest selection of ratings • Samples of many sizes available from stock • Engineering assistance offered when desired • Production quantities available in a reasonable time — at a reasonable price.

Diehl *originated* the Low Inertia A.C. Squirrel Cage Induction Motor — and Diehl's leadership in the field is still being maintained!

Originally designed for high-performance military servo systems, these motors are now being extensively used in the armed services with various types of electronic equipment. In industry, too, Diehl Servo Motors and components are being successfully applied in the design of automatic controls and a wide variety of other applications where optimum performance at reasonable cost is essential.

Meeting all appropriate JAN specifications, the two-phase servo motors can be supplied in sizes ranging from 2 watts to 750 watts mechanical output, 60 or 400 cycle supply. The smaller sizes include units with integrally-mounted tachometer generators for feedback. Many of the ratings are available with the control winding impedance specially designed for operation directly from the plates of electron tubes. Samples of most 60 cycle, and some 400 cycle, units are available for immediate shipment.

Our engineering staff will gladly help you select the motors best suited to your specific requirements. A request on your letterhead will bring you a copy of Technical Manual No. E-1153 describing Diehl Servo Motors and related equipment.

Other Available Components:

D.C. SERVO SETS • RESOLVERS

MINIATURE PERMANENT MAGNET D.C. MOTORS

Diehl

DIEHL MANUFACTURING COMPANY

Electrical Division of THE SINGER MANUFACTURING CO.

Finderne Plant, SOMERVILLE, N. J.

Atlanta Baltimore Boston Chicago Detroit New York Philadelphia Worcester

most solvents. Known as PEE-CEE Vinyl tape No. 471, this material is fungistatic and the ink is sealed into the vinyl backing, thus providing an abrasion-resistant marker.



WAVEGUIDE WINDOW
covers 8,200 to 12,400 mc

AIRBORNE INSTRUMENTS LABORATORY, INC., 160 Old Country Road, Mineola, N. Y., has developed a nonresonant waveguide window that covers the full bandwidth of the RG-52/U waveguide (8,200 to 12,400 mc) with a swr of less than 1.08. For special applications, windows with a maximum swr of 1.05 can be obtained. The window has a metal frame than can readily be soldered into the waveguide flange. It can be used for pressurized equipment and will withstand a pressure differential of 17 psi. It is unaffected by temperature changes from −75 C to 100 C.

SPDT SWITCHES
for one-way actuation

MINNEAPOLIS-HONEYWELL REGULATOR CO., Micro Division, Freeport,



TECHNOLOGICAL DEVELOPMENTS IN ELECTRONICS



Bring Industrial Applications to the Foreground

Technological developments in electronic circuitry, components and equipment, the result of the national defense effort, are now being applied to industrial electronic controls.

The use of electronic controls possesses the greatest growth possibilities in this fast growing electronic business. There are countless applications in every type of manufacturing . . . metal working, food processing, candy making, cosmetics, glass, chemical, automotive, aircraft, to mention a few that utilize electronic controls and new equipment.

But the saturation point is as yet completely out of sight.

Alert manufacturers, to insure their share of this vast market, are telling their product story in ELECTRONICS. Whether they make components or complete equipment, they are reaching the men who are responsible throughout industry for recommending and selecting electronic controls for industry. These men are the subscriber-readers of ELECTRONICS. In the sales pages of ELECTRONICS, manufacturers reach the men who control an unlimited market with ALL industry as its future!

ABP **electronics** ABC

330 West 42nd Street — A McGRAW-HILL PUBLICATION — New York 36, N. Y.

Want more information? Use post card on last page.

Here's a laminate with high insulation resistance

It's the New G-E 11541 TEXTOLITE* Industrial Laminate

It offers outstanding characteristics! G-E 11541 has high insulation resistance and retains maximum stability under humid conditions. *It can be readily hot-punched and fabricated* without losing its basic properties, and will provide long service under difficult conditions.

It's brand new! This versatile G-E Textolite industrial laminate has just been placed on the market—after intensive development and testing by G-E engineers. Now you can develop even better performance characteristics in the equipment you manufacture—by using G-E 11541 Industrial Laminate.

It's amazingly versatile! G-E 11541 is a paper-base phenolic laminate available in a variety of sizes and thicknesses. It has excellent electrical properties, which make it suitable for a wide variety of applications.

For full details and samples, get in touch with your nearest fabricator or assembly manufacturer, today. Or write: General Electric, Section 1327-1B, Chemical Division, Pittsfield, Massachusetts.

*Reg. U.S. Pat. Off.

You can put your confidence in—

GENERAL ELECTRIC

Ill., has announced two new precision snap-action switches designed for one-way actuation by cams, dogs or slides. They have spring-loaded, hinged roller-arm actuators. One design has a $\frac{3}{16}$ in. diameter roller and the other, a $\frac{3}{8}$ in. diameter roller. They are particularly useful in providing an electrical impulse to relays or solenoids from only one direction of a reciprocating movement. Each of the switches is available with either solder-lug terminals or screw terminals. They are listed by Underwriters' Laboratories for 15 amperes, 125, 250 or 460 v a-c; $\frac{1}{2}$ ampere, 125 v d-c; $\frac{1}{4}$ ampere, 250 v d-c. Contact arrangement of both switches is spdt.



TINY SEALED RELAYS measure 1.6 cu in.

THE HART MFG. CO., 110 Bartholomew Ave., Hartford, Conn. New performance characteristics for the series R hermetically sealed, miniature aircraft-type 4PDT relays have been developed, providing an even wider range of variations to meet such requirements as guided missiles, jet engine controls, communications, radar, fire control, geophysical and computer apparatus. Only 1.6 cu in. in size and 3.76 oz in weight, with operational shock resistance to 50 g and higher and temperature ranges from —65 to +200 C, the relays have interelectrode capacitance less than $\mu\mu f$ contacts to case, less than $2\frac{1}{2}$ $\mu\mu f$ between contacts, even with plug-in type relay and socket. Vibration range is from 0 to 500 cps and upward at 15 g without any chatter.



Four-channel recording correlates simulated jet bomber airspeed and altitude conditions

At Eclipse-Pioneer, engineers make good use of Sanborn 4-channel recording systems in conjunction with high precision analogue computers to establish performance criteria for automatic flight systems and components.

At other laboratories Sanborn Systems are being used to record such phenomena as: stress, strain, pressure, displacement, thickness, velocity, acceleration, current, voltage, temperature, torque, light, flow, force, load, position, rpm, radiation and tension.

SANBORN OSCILLOGRAPH RECORDING SYSTEMS HAVE MANY APPLICATIONS. They are used in a great many different fields where accurate and permanent graphic registration of almost any electrical phenomena (whose frequency range is zero to 100 cycles per second) is required.

Sanborn Systems are widely used because of the availability and ready interchangeability of amplifiers and preamplifiers, as well as such Sanborn advantages as: inkless recording in true rectangular coordinates, high torque movement, time and code markers and wide choice of paper speeds. In addition, a basic choice of systems, 1-, 2-, and 4-channels, provides a system to fulfill almost any laboratory requirements.



WRITE FOR CATALOG

Sanborn Company
INDUSTRIAL DIVISION
CAMBRIDGE 39, MASSACHUSETTS, U.S.A.

Want more information? Use post card on last page.

Double Trace

STOPS DOUBT!

...WHEN A SINGLE SCOPE WON'T DO THE JOB

If you're trying to compare two phenomena occurring simultaneously with two conventional oscilloscopes, chances are you're having "double-trouble". You just can't fix your eyes on two screens at the same time and, what's worse, hope to measure two high speed transients at the same instant. Even with an electronic switch you're apt to miss those important signals.

ETC Multi-Channel Oscilloscopes reduce such problems to their simplest form—by combining a number of different traces at the same instant on the face of a single tube.

Whether you need to measure 2, 4, 5, 6, or even 8 phenomena . . . in electronic or medical research, material or geological tests . . . there's an ETC Oscilloscope that can do the job. Write for full details on the particular type for your problem.

MULTI-GUN C.R. TUBES
. . with 2 to 10 guns . . . round or square face . . . 3 to 12 inches. Special purpose tubes made to your specification.

ETC

electronic tube corporation

1200 E. MERMAID LANE, PHILADELPHIA 18, PA.

At 30 g operational shock resistance, sensitivity approaches 100 mw.

VARIABLE INDUCTOR is stable and versatile

VARI-L CO., INC., Box 1433, Stamford, Conn. By the addition of a permanent magnet to provide a stable bias flux in the core, the model PA-63 variable inductor is given new versatility and stability. It has Q's, over most of its range, of from 115 to 130, and there are no sharp peaks or valleys. Electrostatic coupling between control and signal windings is greatly reduced. Less d-c means less heating internally, and reduces creepage due to temperature rise. Manual adjustment of the magnetic bias gives better control over L-C ratio and permits operation at the point of best linearity. Illustrated is the inductor with cover removed for access to the bias magnet. Note the potted construction, size being indicated by inch scale.



VERSATILE MOTOR is 1-in. in diameter

EASTERN AIR DEVICES, 585 Dean St. Brooklyn 17, N. Y., has produced a line of extremely small pre-

mitchell-rand
features electrical insulating tapes

BI-SEAL

self-bonding Polyethylene, for resistance to corrosion and chemicals.

BI-PRENE

self-affixing Neoprene, for resistance to oils and chemicals.

UNAFFECTED BY LOW TEMPERATURES • SUPERIOR AGING • CORROSION-CHEMICAL OIL RESISTANT • EXCELLENT CONFORMABILITY • SELF BONDING • MOISTURE-RESISTANT • HI-DIELECTRIC STRENGTH

BI-SEAL INSULATION CHARACTERISTICS

Electrical Properties		
Dielectric strength	1000 volts/mil avg.	
Power factor	60 cycles	0.0006
	1000 cycles	0.0006
	106 cycles	0.0004
Dielectric constant	60 cycles	2.32
	1000 cycles	2.34
	106 cycles	2.13

Physical and Chemical Properties Resistance to:	
Ozone	Excellent
Oxygen	Excellent
Acids	Excellent
Alkalies	Excellent
Moisture vapor transmission	Negligible
Castor Oil	Good
Commercial Hydraulic Fluids	Excellent
Aging qualities	Excellent
Operating temperatures	197°F to —67°F
Application temperatures	150°F to —40°F



BI-PRENE INSULATION CHARACTERISTICS

Physical Tests on Press Cured Slabs 10"/310°F	
Tensile	1980 p.s.i.
Elongation	400%
200% Modulus	1030 p.s.i.
Ozone	6 hours to cut

Physical Properties on Aging
80°C Oxygen Bomb for 14 days
67.4% of original elongation
62.8% of original Tensile

Air Bomb at 26°F for 30 Days at 80 p.s.i.
160% of original elongation
66% of original Tensile

Oil Resistance
A. S. T. M. Reference fluid number one — 11.7% maximum swell in 24 hrs. A. S. T. M. Reference fluid number two—69.7% maximum swell in 24 hrs. 18 hr. exposure in oil at 121°C — Tensile decreased 4.5%. Elongation increased 70%.

Here are two multi-purpose electrical insulating tapes for wire or cable splicing . . . the self-bonding BI-SEAL and the self-affixing (air-curing) BI-PRENE . . . to meet the strictest requirements for unusual as well as ordinary cable splice applications for the smallest wire or the largest cable . . . wherever tape can be used for splicing.

The outstanding characteristics and excellent insulation properties, plus the feature that once applied BI-SEAL and BI-PRENE tapes fuse into a solid mass, impossible to unwrap or delaminate, enables these products to offer complete and lasting protection against moisture, acids, alkalies, oils, chemicals, sunlight, corrosion, fungus, ozone, etc.

Write for samples and detailed data

MITCHELL-RAND SINCE 1889 — Electrical Insulation Headquarters

mitchell-rand INSULATION COMPANY, INC.

51 MURRAY ST. • COrtlandt 7-9264 • NEW YORK 7, N.Y.

MIRAGLAS VARNISHED TAPES, CLOTHS AND SLEEVINGS • MIRAGLAS TAPES, BRAIDED SLEEVINGS AND TYING CORDS • MIRAGLAS SILICONE TREATED CLOTHS, TAPES AND TUBINGS • MICA TAPES, CLOTHS AND MICA-FIBERGLAS COMBINATIONS • FIBRE, PHENOL FIBRE AND MIRALITE POLYESTER RESIN SHEET INSULATING PAPERS—DURO, FISH, PRESSBOARD, ETC. • VARNISHED CAMBRIC TAPES, CLOTH AND SLOT INSULATIONS • COTTON TAPES AND SLEEVINGS • TWINES AND TIE TAPES • ASBESTOS TAPES, SLEEVINGS AND CLOTH, TRANSITE AND ASBESTOS EBONY • ARMATURE WEDGES AND BANDING WIRE • VARNISHED TUBINGS, HYGRADE, MIRAGLAS, HYGRADE VF, MIRAGLAS SILICONE • THERMOFLEX AND FLEXITE EXTRUDED PLASTIC TUBING • PERMACEL MASKING TAPES AND ELECTRICAL TAPES • BI-SEAL, BI-PRENE; FRICTION TAPES AND RUBBER SPLICE • COMPOUNDS—TRANSFORMER, CABLE FILLING, POTHEAD, ETC. • INSULATING VARNISHES OF ALL TYPES.

WORKING with *Pulses?*



YOU NEED THE NEW

MODULAR SYSTEM

A basic electronic tool for design and use of pulse methods for information transmission, storage, and computation.

THE MODULAR SYSTEM consists of 16 highly flexible electrically and mechanically compatible units, together with a regulated power supply which are easily assembled and interconnected by patchcords to perform all the basic functions of digital pulse operations. Each unit (size: 2¾" high x 4½" wide x 9" long) performs a multiplicity of independent functions selectively, a complete system having a capability of 72 separate functions with as many as 31 functions simultaneously available. Design and development engineers can readily operate in the most complex systems at "block diagram" level without concern for circuit details.

- Saves engineering time by providing pre-constructed standard units: amplifiers, pulse-formers, frequency dividers, electronic counters.
- Complex instruments can be patched-up and operating within minutes after the need is conceived.
- Provides non-electronic laboratories with the advantages of pulse instrumentation.
- Using the Modulars as "logical boxes" design engineers can test concepts of non-vacuum tube computers.
- Together with an Oscilloscope serves as graphic training aid in digital pulse instruction.

Write today for descriptive brochure.

AUDIO PRODUCTS CORPORATION

Dept.-B1 2265 Westwood Boulevard

Los Angeles 64, California

cision motors (only 1 in. in diameter), that are designed to operate fans, blowers, instruments, controls and low-power drives. With a maximum 115 v input, these motors can be used for single, two or three-phase 400-cycle operation, at running speeds of approximately 10,500 and 21,000 rpm, and for single or two-phase 400-cycle operation at a speed of approximately 7,000 rpm. They can also be used for variable frequency service. Power ratings of approximately 1/100 hp can be obtained with the 400-cycle unit. Modifications include high-ambient and high-altitude versions as well as servo, hysteresis, synchronous and gear motors.



FREQUENCY METER is accurate to 0.2 percent

NASSAU RESEARCH & DEVELOPMENT ASSOCIATES, INC., 66 Main St., Mineola, N. Y. Frequencies from 2,400 to 10,200 mc can be measured on the model-802 frequency meter to an accuracy of 0.2 percent. A transmission indication is obtained on a built-in sensitive 50-μa meter. A reactive indication is obtained by using an external tee section. The resonant elements consist of two high-Q coaxial cavities tuned by a precision micrometer head. A vernier-type crank knob allows rapid tuning and precise setting of frequency. Broadband noncontacting shorts are used to eliminate all sliding contacts. The cavities are plated with silver and rhodium, insuring a high-conductivity surface that will not tarnish or corrode. An

Want more information? Use post card on last page.

where is the real future in electronics?



Everyone has done a lot of military work . . . but it becomes more and more apparent every day that the electronics industry must find new markets in the industrial field. That is where the real future in electronics lies!

Westinghouse, as a leader in the production of industrial equipment, has the necessary sales, distribution and field engineers organized to enter this new market. Now is the time to get into our organization, so that when the industrial field expands, you will be in on the ground floor!

This is not a case of an organization offering just a future! Salaries are open, commensurate with experience and ability. Our patent award plan is known and respected throughout the industry. There are excellent opportunities for advanced study and degrees. The Westinghouse Electronics Division offers all of the usual employe benefits, plus!

Investigate the real future!

SYSTEMS ENGINEER

DUTIES: Systems analysis and evaluation; systems coordination; and systems test planning. Involves feedback systems, computers, video systems, indicators, switching, etc., as applied to radar and missile guidance systems.

REQUIREMENTS: 3 or more years' experience and a B.S. degree in Electrical Engineering or Physics.

TECHNICAL WRITERS

DUTIES: For writing Engineering progress reports on advanced radar and missile systems.

REQUIREMENTS: 3 years' experience and a B.S. degree in Electrical Engineering or Physics.

INDICATOR DESIGN SPECIALIST

DUTIES: Advanced development and design of new types of indicators for radar and missile guidance applications.

REQUIREMENTS: 3 years' experience and a B.S. degree in Electrical Engineering or Physics.

MAGNETIC AMPLIFIER ENGINEER

DUTIES: Design and application of magnetic amplifiers in such new fields as multi-vibrator and sweep circuits, in addition to the more common applications.

REQUIREMENTS: 3 or more years' experience and a B.S. degree in Electrical Engineering or Physics.

TRANSFORMER DESIGN ENGINEER

DUTIES: The development and design of pulse transformers, filters, iron-core radio frequency transformers and advanced electronic transformers of all types.

REQUIREMENTS: 3 years' experience and a B.S. degree in Electrical Engineering or Physics.

To apply send resume of education and experience to

R. M. Swisher, Jr.
Employment Supervisor, Dept. M-5
Westinghouse Electric Corporation
109 West Lombard Street
Baltimore 1, Maryland

Westinghouse
ELECTRONICS DIVISION
BALTIMORE, MARYLAND

POLYPENCO® 2-PART SERVICE...

to help designers gain the full benefits of TEFLON*

1.

TECHNICAL HELP ON APPLICATIONS AND FABRICATION



Polypenco controlled-quality Teflon resulted from Polymer's pioneering in the field of extruded industrial plastics. And ever since, Polymer engineers have more than kept pace with the newest ideas and methods to make the application and fabrication of POLYPENCO Teflon easier, more economical. The benefits of technical data, application and field experience and field engineering service are yours for the asking.

2.

DELIVERY OF EXTRUDED SHAPES, MACHINED AND MOLDED PARTS

In addition to complete stocks of POLYPENCO Teflon rod, strip and tubing, Polymer offers you quick delivery of controlled-quality Teflon parts machined or molded to your specifications. Take advantage of our years of experience spent working with designers in all the important electronic, electrical and mechanical fields.

*registered trademark of the Du Pont Company

mail now!

SEND ME THE FACTS...

...on Polypenco Teflon—how it is applied ☐
—prices on shapes available ☐

NAME_____ TITLE_____

COMPANY_____

ADDRESS_____

CITY_____ ZONE____ STATE_____

The POLYMER CORPORATION of Penna., Reading, Penna.

output jack provides means for connecting an external amplifier or galvanometer for increased sensitivity.



TRANSISTOR MOUNT
vacuum seals the unit

CONSTANTIN AND CO., Lodi, N. J. The new transistor mount is a glass-to-metal sealed base combined with a metal cover, which permits mounting of the germanium in a complete vacuum or inert-gas atmosphere. This makes the germanium impervious to all outside conditions and considerably increases the life of the transistor. The mounts are available as small as 0.250 in. long, 0.165 in. wide and 0.437 in. high. The base is constructed of glass to kovar metal with three 0.018-in. leads sealed through. The cover, a metal can, is constructed of 10-percent nickel-silver metal. All parts with the exception of the cover are hot-tin dipped at 530 F to facilitate easier soldering and eliminate rejection in production.



RX METER
covers 500 kc to 250 mc

BOONTON RADIO CORP., Boonton, N. J., announces a new type 250-A RX meter, a completely self-con-

THE MOST CRITICAL CONTROL PROBLEMS *are solved at*

CLAROSTAT®

ULTRA-PRECISION CONTROLS HEADQUARTERS

FEATURES...

Individual sections or tandem assemblies up to 18 sections.

Resistance tolerance: Standard overall, plus/minus 5%. Plus/minus 0.5% available where resolution permits.

Linear and non-linear within plus/minus 0.5%, or a voltage ratio accuracy of 0.005 where resolution permits.

Resistance range of 10 to 100,000 ohms. Non-linear, maximum of 350 ohms per degree of rotation.

One or more taps available. Taps can be located to within one winding convolution.

Power rating: 3 watts at 40° C. Non-linear, approximately 0.01 watt per degree of rotation.

Rotation: Effective up to maximum of 358°. Mechanical, any value up to 360°.

Torque: 1 oz.-in. maximum per section.

Insulation: 1000 V.A.C. at atmospheric pressure.

End brackets and other types of mountings meet any mechanical considerations.

These units exceed applicable JAN-R-19 specifications.

Section-by-section assembly of tandem controls, with critical checkups of mechanical and electrical factors at each step insure *ultra precision.*

For applications requiring *ultra-precision* controls, again you can "stand pat with Clarostat."

Originated by Clarostat, such ultra-precision potentiometers are now used in intricate and critical assemblies such as servo-mechanisms, range finders, fire-control systems, computing devices, and so on.

And now the latest, further-refined, plug-in version, Series 52, is available. Arch-shaped low-loss phenolic casing. Prong terminals engaging with corresponding sockets for plug-in circuitry. Side terminal lugs on each unit facilitate checking section voltages. Heavy metal end brackets insure rigid mounting.

Built by craftsmen working under instrument-shop conditions, these Clarostat Series 52 units are *the finest controls ever offered.*

STAND PAT WITH CLAROSTAT

Data on request. Let us collaborate on your ultra-precision control requirements.

Controls & Resistors

CLAROSTAT MFG. CO., INC., DOVER, NEW HAMPSHIRE

In Canada: Canadian Marconi Co., Ltd., Toronto, Ontario

FAST, POSITIVE
Double-break
ACTION
A tapered rod operates through two compression springs in the shorting bar and against a return spring. The exceptionally fast double-break action thus obtained reduces arcing to a negligible minimum.

SWITCH SUCCESS "SECRET" No. 1

Hetherington Aviation and Industrial Products

- High quality push-button and snap-action switches in the 15-50 ampere range
- Special switch box assemblies
- Aircraft control stick grip assemblies
- Indicator lights
- Switch-indicator light combinations
- Trim tab control switches
- Auto pilot, tank jettison, canopy release, seat ejector or seat positioning switches
- Bomb or rocket firing mechanisms
- Microphone circuit switches
- Audible signal silencers
- Limit switches . . . and many others

This little beryllium device is the heart of Hetherington push-button and snap-action aircraft-type switches. Its unique, patented design and sturdy construction assure faster, more positive switching action in less space with less weight—*and with a life cycle exceeding military requirements.* It is a No. 1 "secret" of Hetherington's success in matching or surpassing exacting specifications—military or civilian—for switch dependability in the 15 to 50 ampere field.

HETHERINGTON, INC., Sharon Hill, Pa.
(West Coast Division: 8568 W. Washington Blvd., Culver City, Calif.)

HETHERINGTON Switches

tained r-f bridge that permits the direct measurement of equivalent parallel resistance and capacitance of two terminal networks over an unusually wide frequency range. The instrument has a frequency coverage of 500 kc to 250 mc in eight ranges, a resistance range of 15 to 100,000 ohms, and a capacitance range of +20 μμf to −100 μμf. Resistances from 0 to 15 ohms may be determined by indirect means; the capacitance range can be increased to 0 to 120 μμf by the use of auxiliary resonating coils. The meter is particularly useful for measuring the performance of resistors and transistors at elevated frequencies and also provides a convenient tool for the determination of characteristic impedance, attenuation and velocity of propagation of transmission lines.

TAPE RECORDER is completely portable

ECTRO, INC., Delaware, Ohio. The Cub Corder is a new, completely portable tape recorder equipped for recording, playback, erase and monitoring. The recorder, which is housed in a single compact unit, weighing less than 13 lb, is designed to record for two full hours, or sufficient time to record up to 20,000 words before battery recharging is necessary. It lends itself to a wide variety of on-the-spot uses where plug-in current is not readily available. The Cub Corder motor is powered by a 4-v, nonspill storage battery which has a normal life span of 450 hours. When in need of recharging, the battery can be brought back to full strength

KEPCO
VOLTAGE REGULATED POWER SUPPLIES

VOLTS	CURRENT	REGU-LATION	RIPPLE	6.3 V.† AC. CT.	MODEL
0-1500	0-200 Ma.	0.5%	20 Mv.		1520
0-1200	0-20 Ma.	0.1%	10 Mv.	10 Amp.	1220
0-1000	0-500 Ma.	0.5%	20 Mv.		1350
200-1000	0-500 Ma.	0.5%	20 Mv.		1250
0-1000	0-50 Ma.	0.1%	10 Mv.	10 Amp.	1020
0-600	0-3 Amp.	0.5%	10 Mv.		780
0-600	0-2.25 Amp.	0.5%	10 Mv.		770
0-600	0-1.5 Amp.	0.5%	10 Mv.		760
0-600	0-750 Ma.	0.5%	10 Mv.		750
0-600 0-150 Bias	0-300 Ma. 0-5 Ma.	0.5% *	10 Mv. 5 Mv.	10 Amp.	615
0-600	0-300 Ma.	0.5%	10 Mv.	10 Amp.	500R
#1 0-600 #2 0-600	0-200 Ma. 0-200 Ma.	0.5% 0.5%	5 Mv. 5 Mv.	10 Amp. 10 Amp.	800
0-600 0-150 Bias	0-200 Ma. 0-5 Ma.	0.5% *	5 Mv. 5 Mv.	10 Amp.	815
#1 200-500 #2 200-500	0-200 Ma. 0-200 Ma.	0.5% 0.5%	5 Mv. 5 Mv.	6 Amp. 6 Amp.	510
200-500	0-200 Ma.	0.5%	5 Mv.	6 Amp.	245
0-400 0-400 0-150 Bias	0-150 Ma. 0-150 Ma. 0-5 Ma.	0.5% 0.5% *	5 Mv. 5 Mv. 5 Mv.	10 Amp. 10 Amp.	2400
0-400 0-150	0-150 Ma. 0-5 Ma.	0.5% *	5 Mv. 5 Mv.	10 Amp.	400
100-400	0-150 Ma.	0.5%	5 Mv.	10 Amp.	141
100-400	0-150 Ma.	0.01%	1 Mv.	10 Amp.	2000
0-350	0-3 Amp.	0.5%	10 Mv.		730
0-350	0-2.25 Amp.	0.5%	10 Mv.		720
0-350	0-1.5 Amp.	0.5%	10 Mv.		710
0-350	0-750 Ma.	0.5%	10 Mv.		700
100-325 0-150 Bias	0-150 Ma. 0-5 Ma.	0.5% *	5 Mv. 5 Mv.	10 Amp.	131
0-300 0-150 Bias	0-150 Ma. 0-5 Ma.	0.5% *	5 Mv. 5 Mv.	5 Amp.	315
0-150	0-50 Ma.	0.5%	5 Mv.		150
3-30	0-30 Amp.	0.5%	0.1%		3030
1-13	0-10 Amp.	0.5%	10 Mv.		3200
0.3-3	0-100 Ma.	5 Mv.	1 Mv.		3100



MODEL 700

OUTPUT DC: 0-350 volts, 750 ma.

REGULATION: ½% for both line, 105-125 volts, and load variations, 0-750 ma.

RIPPLE: 10 millivolts.

This unit is available delivering:
- 1.50 amp.—Model 710
- 2.25 amp.—Model 720
- 3.00 amp.—Model 730

KEPCO

Voltage-Regulated Power Supplies are conservatively rated. The regulation specified for each unit is available under all line and load conditions within the range of the instrument.

DC POWER SUPPLY SPECIFICATIONS

REGULATION: As shown in table for both line fluctuations from 105-125 volts and load variations from minimum to maximum current.

***REGULATION FOR BIAS SUPPLIES:** 10 millivolts for line 105-125 volts. ½% for load at 150 volts.

†All AC Voltages are unregulated.

All units are metered except Models 131, 315 and 3100.

All units are designed for relay rack mounting or bench use.

WORKMANSHIP

Workmanship is of a quality with the highest existing production standards and best instrument electronic practices consistent with the intended use of the item as a continuous duty voltage regulated power supply. Oil filled paper condensers and resistor-board construction are included in the design.

FOR NEW POWER SUPPLY CATALOG—WRITE DEPT. No. 789

MANUFACTURERS OF ELECTRONIC EQUIPMENT • RESEARCH • DEVELOPMENT

KEPCO LABORATORIES

131-38 SANFORD AVENUE • FLUSHING 55, N.Y.

STRUTHERS-DUNN

Standard relays and timers match 4 out of 5 requirements

5,348 RELAY TYPES

S-D

STRUTHERS-DUNN, INC., 150 N. 13th St., PHILADELPHIA 7, PA.

BALTIMORE • BOSTON • BUFFALO • CHARLOTTE • CHICAGO • CINCINNATI
CLEVELAND • DALLAS • DETROIT • KANSAS CITY • LOS ANGELES
MINNEAPOLIS • MONTREAL • NEW ORLEANS • NEW YORK • PITTSBURGH
ST. LOUIS • SAN FRANCISCO • SEATTLE • SYRACUSE • TORONTO

either by connecting it directly from the recorder into an automobile cigarette-lighter outlet (the ideal means while in transit) or from an accessory charger which recharges the battery from regular 115–230 v current.



TINY TUBE CLAMPS
reduce bulb temperatures

THE BIRTCHER CORP., Los Angeles, Calif., has developed a new subminiature tube clamp for use under conditions of extreme heat, vibration and shock. The clamp is made of a specially developed heat treatable alloy; having a thermal conductivity approximately 70 percent of pure copper. Kool Klamps have been designed to provide maximum heat flow and have been subjected to exhaustive tests and found to reduce bulb temperatures by as much as 40 C. They are made in two types: the clip holder was designed to permit insertion of the tube from top or end; the sleeve holder was designed for end insertion only and is preferred where overall height is critical.



TEST CHAMBER
with built-in thermometer

STATHAM DEVELOPMENT CORP., 12411 W. Olympic Blvd., Los Angeles 64, Calif. Model TC-1 temper-



AIRCRAFT TRANSFORMERS



Keystone is a *respected* source for special purpose and custom-made aircraft transformers and magnetic amplifiers. As suppliers to several of the nation's leading prime contractors, we're accustomed to working to unusually difficult standards of accuracy . . . so far as weight, quality and electronic accuracy are concerned.

If you require miniature transformers you'll also find KEYSTONE an unexcelled resource. Engineering service available. Get acquainted with the KEYSTONE brand of service and dependability at once.

"MotoMag"
Registered trademark of Keystone Products Co.

This is the FIRST of *five* pre-designed magnetic amplifiers that will save precious engineering time. If you're designing an aircraft unit — design it around this KP-10-400 Magnetic Amplifier. Then watch your costs tumble down!



MOTO-MAG KP-10-400 is useful in positioning servos, computers, servo motor controls, remote control devices and other units requiring variable phase power. Send for Mechanical and Electrical specifications. Since units are already built, single pieces are available for experiments and tests at modest cost.

Prompt attention given all inquiries

KEYSTONE PRODUCTS COMPANY

UNION CITY 2, NEW JERSEY • Call UNion 6-5400

Packed with POWER!

Silicohm miniature POWER RESISTORS

Wire Wound—Silicone Coated Resistors

Complete welded construction from terminal to terminal. Temperature coefficient 0.00002/deg. C. Ranges from 0.1 Ohm to 55,000 Ohms, depending on Type, Tolerance 0.05%, 0.1%, 0.25%, 0.5%, 1%, 3%, 5%.



RH TYPE

Available in 25, 50 and 250 watt sizes. Silicone sealed in die-cast, black anodized radiator finned housing for maximum heat dissipation.

RS TYPE

Available in 2 watt, 5 watt, and 10 watt sizes. Silicone sealed offering maximum resistance to abrasion, high thermal conductivity and high di-electric strength.

DALOHM deposited CARBON RESISTORS

Dalohm precision deposited carbon resistors offer the best in accuracy, stability, dependable performance and economy. Available in ½ watt, 1 watt and 2 watt sizes.

DALE PRODUCTS, INC.

Want more information? Use post card on last page.

ature test chamber, a compact economical unit for testing ambient temperature variations between —65 and +275 F, can now be equipped with a thermometer as an integral component. This design eliminates the constant expense of replacing thermometers bent or broken by falling test objects. Forced circulation prevents any significant temperature variations between the thermometer and the object on the test tray. Cooling in the test chamber is accomplished with carbon-dioxide ice, and heating by a high-capacity strip heater. Thermostatic control maintains temperature by balancing heat against dry-ice evaporation. The completely portable and self-contained test chamber is ideally suited for the performance of ambient temperature tests on basic instruments, electronic subassemblies, small equipment and organic materials.



SWITCH reverses polarity instantly

POMONA ELECTRONICS CO., 524 West 5th Ave., Pomona, Calif. Model MS-1 meter reversing polarity switch, designed to assist the radio and electronics technician, reverses polarity when making circuit tests without removing test lead to meter. It can be attached instantly by plugging into test lead holes on Simpson tester model 260 for which it is exclusively designed. The MS-1 is operated by inserting the unit on the left side of the meter in the corresponding

the most widely used Electronic Supply Guide

FREE SEND FOR IT

ALLIED'S COMPLETE 268-PAGE 1954 CATALOG

World's largest stocks of ELECTRONIC SUPPLIES FOR INDUSTRY

Simplify and speed your purchasing of electronic supplies and equipment. Send your orders to us for quick shipment from the world's largest stocks of special-purpose electron tubes, test instruments, audio equipment, electronic parts (transformers, capacitors, controls, etc.). Our expert Industrial supply service saves you time, effort and money. Send today for your Free ALLIED Catalog—the complete, up-to-date guide to the world's largest stocks of Electronic Supplies for Industrial use.

one complete dependable source for everything in electronics

ALLIED RADIO
100 N. Western Ave., Dept. 11-L-3
Chicago 80, Illinois

Want more information? Use post card on last page.

How to fly a guided missile in your laboratory



Practically any electrical, mechanical or physical phenomenon — even the full flight of a guided missile — can be precisely re-created in the laboratory from Ampex magnetic tape recordings.

Ampex retains and plays back data in the same electrical form in which it is received, making its playback in effect equivalent to a rerun of the original test. But it has these added advantages: Data can be repeated at any time or place, can either be scanned or studied in whole or part, can be speeded up or slowed down, can be fed to automatic reduction systems. Furthermore, desired portions of the data can be reduced to oscillograph traces, pen recordings or any other form that could have been made at the time of the original test.

Besides the convenience and versatility of the data itself, Ampex Magnetic Recorders and the tape they use have these desirable physical qualities:

- *Ampex Tape Recorders, being rugged, compact and portable, are usable where other equipment would not be feasible;*
- *Tape requires no processing, hence is immediately available for playback;*
- *Tape stores an enormous quantity of information at low cost and in minimum bulk.*
- *Ampex Tape Recorders cover extremely wide frequency range:*
  Model 306 — 0 to 5000 cycles/sec.
  Model 307 — 100 to 100,000 cycles/sec.
  Model 303 — Pulse width modulation
  Many other models are also available.

AMPEX

MAGNETIC RECORDERS

For further information write to Dept. E-1037A

AMPEX ELECTRIC CORPORATION
934 CHARTER STREET • REDWOOD CITY, CALIF.



for

FASTER ASSEMBLY . . .

LOWER EQUIPMENT *and* LABOR COSTS . . .

AND *corrosion resistance, too, when required*

specify

PEM WELD FASTENERS

of steel or STAINLESS steel

PEM Weld Fasteners are designed for Production.

SHANK locates and protects threads against weld splatter . . . eliminates retapping.

ENGINEERED PROJECTIONS prevent burnouts in thin sheets.

SIMPLE ELECTRODES . . . no pilots required.

ROUND COMPACT SHAPE . . . no indexing in assembly . . . fit on narrow flanges.

WRITE for literature and samples for trial.

Penn Engineering & Manufacturing Corp.
Doylestown, Pennsylvania

PEM

tip jacks. The toggle switch position on the MS-1 will indicate polarity of the circuit being tested. This eliminates the necessity of reversing the meter test leads manually to obtain correct polarity. It saves time in circuit testing and reduces shock hazard. The unit is of compact durable phenolic construction.

TINY DIFFERENTIAL
is extremely accurate

BELOCK INSTRUMENT CORP., 13-11 111th St., College Point, N. Y. The $\frac{1}{16}$-in. subminiature differential is designed for application where accuracy must be maintained in a minimum of space. The end gears are available in 64 or 96 pitch and any pitch diameter that can be cut from a $\frac{1}{2}$-in. maximum outside diameter to $\frac{1}{4}$-in. minimum root diameter. All gears are phosphor bronze to insure maximum life of the differential. Minimum backlash combined with low breakaway and running torques give the differential extremely high accuracy for a unit of this type and size. Breakaway torque is 0.15 oz in.; maximum torque, 12 oz in.; maximum rpm, 600; and backlash, 18 minutes.



CONTROL SYSTEM
for broadcast transmitters

THE HAMMARLUND MFG. CO., INC., 460 W. 34th St., New York 1, N. Y., has introduced a control system for unattended broadcast transmitters designed and built in accordance with the recently announced FCC regulation. Only a single a-f tele-

phone circuit is required. VHF or microwave may be used but no d-c circuit is needed. The system also features full control of up to 9 separate circuits, and includes up to 4 emergency alarm indications. It consists of 3 separate sections: (1) The control panel (illustrated) for installation at the operator's console; (2) a second section of equipment installed at the control point, consisting of a number of a-f tone transmitters and receivers; and (3) a section installed at the remote broadcast transmitter, consisting of a-f tone generators and selective amplifiers, the telemetering transmitter, the control selector and an alarm keying mechanism.

LOADING COIL
for mobile antennas

K-W ENGINEERING WORKS, 3145-A N. 48th St., Milwaukee 16, Wisc. The Dyna-Q mobile antenna loading coil provides the radio amateur, small-boat owner and other users of the medium-frequency services with a dynamically efficient inductance for resonating the antenna. The Q approaches 300 at 4.0 mc. Used with a 10-meter whip above the coil the loading coils are suitable for either base or center loading. With shorting jumpers the coil will serve from 3 to 30 mc. Insulation is polystyrene, and fittings, chrome-plated brass. Turns need not be pruned from the coil,

FOR RAPID, PRECISE DIRECT-READING FREQUENCY MEASUREMENTS to 150 Megacycles

THE BERKELEY F-2 Frequency Meter

DESCRIPTION: The BERKELEY Series F-2 Frequency Meter is a precise direct-reading instrument for the measurement of frequencies from 0 cps to 150 mc. Basic sections are (1) the Model 5575 VHF Converter,* (2) the Model 5570, which contains a HF Heterodyne unit and (3) a high speed 8-digit Events-Per-Unit-Time meter. Frequencies up to 42 mc. are read directly on the 8-digit EPUT panel. Frequencies between 42 and 150 mc. are applied through the VHF Converter; reading is the sum of a rotary selector switch marking and the EPUT indication. External adjustment of crystal control to WWV is provided to obtain an accuracy of 1 part in 10^7, ± 1 cycle.

*NOTE: Model 5575 Converter is available separately for owners of BERKELEY Model 5570 42 mc. Frequency Meters, to extend range to 150 mc.

APPLICATIONS: Rapid, accurate transmitter monitoring, crystal checking, general laboratory and production line frequency determination. Addition of a BERKELEY Digital Recorder will provide an automatic printed record of the last 6 digits; ideal for plotting frequency drift or indicating stability.

MODEL 5575

MODEL 5570

SPECIFICATIONS

RANGE:	0 cycle to 150 megacycles.
ACCURACY:	± 1 count, ± crystal accuracy (short term: 1 part in 10^9).
POWER REQUIREMENTS:	117 volts, ± 10%, 60 cps, 360 watts.
INPUT REQUIREMENTS:	Approximately .1 volt rms. (100 ohm impedance standard, 100K on request).
DISPLAY TIME:	1 to 5 seconds continuously variable.
TIME BASE:	0.002, 0.02, 0.2 and 2 seconds.
DIMENSIONS:	Two cabinets; Model 5570, 32" high x 21" wide x 16" deep, Model 5575, 10½"x 21"x 16".
PRICE: (f.o.b. Richmond)	Series F-2 Frequency Meter complete $2,590.00
	Model 5575 VHF Converter only .....$ 600.00
	Model 5570 Frequency Meter (0-42 mc.) $1,990.00

Prices and Specifications subject to change without notice.

Please request Bulletin G-11

Berkeley division BECKMAN INSTRUMENTS INC. 6200 WEST 83rd, RICHMOND, CALIF.

M-19

TRY IT ON YOUR MOST CRITICAL APPLICATIONS



ON PRINTED CIRCUIT WORK, the "Airbrasive" Unit will "trim" resistance elements or remove oxidation from conductive surfaces. Because it can be controlled so precisely, extremely accurate work is possible.

S.S.WHITE INDUSTRIAL "AIRBRASIVE" UNIT

The unique "Airbrasive" cutting process has brought amazing speed, precision and economy to many electronics manufacturing operations, a few of which are described at the right. Perhaps you'll be able to realize similar advantages in applications of your own.

With the "Airbrasive" Unit you'll be able to drill, etch and cut hard and brittle materials—do light deburring—remove deposited surface coatings—and etch and mark glassware and ceramics. Since the cutting is done by means of a high-speed, gas-propelled stream of abrasive, there is no contact with the work. Therefore—there's no shock... no frictional heat... no vibration... and the accuracy of the cut is unaffected by irregularities in surface contours.



ON DEPOSITED CARBON RESISTORS, the "Airbrasive" process provides a fast, accurate method of cutting spiral bands. Cuts as fine as .008" can be made.

BULLETIN 5307
has full details on the amazing new S.S.White Industrial Airbrasive Unit. Write for a free copy.



ON SHAPING FRAGILE CRYSTALS, the "Airbrasive" Unit's precision and cool, shockless action eliminates the possibility of shattering or distorting the crystal.

It has been demonstrated that the "Airbrasive" Unit will do jobs that are impossible to accomplish by previously known methods. What is your problem? Our engineers will be glad to make trials on your samples and advise you as to the suitability of the Unit for your needs.

THE S.S.White INDUSTRIAL DIVISION
DENTAL MFG. CO.
Dpt. EB 10 East 40th St.
NEW YORK 16, N. Y.

Western District Office • Times Building, Long Beach, California

thus the frequency of the antenna can be lowered as well as raised.



RELAYS
in four new types

JOSEPH POLLAK CORP., 81 Freeport St., Boston 22, Mass., is producing a newly developed line of relays among which are the series 100 d-c computer relay (illustrated), the series 300 d-c miniature relay, the series 400 a-c or d-c coaxial relay, and the series 500 d-c communications relay. Bearings of the series 100 have essentially zero friction and the relay has a life span of ten million cycles. The series 300 weigh under 2 oz and incorporate a special antivibration feature. The series 400 withstand 10-g vibration at 10 to 55 cps under operation tests. Since the series 500 relays can perform mechanical work in addition to operating contacts, they are ideal for those applications where automatic punching is required for control-system applications. A 12-page catalog is available.



POWER SUPPLY
is also demodulator

DOELCAM CORP., Soldiers Field Rd., Boston 35, Mass. The VFDD is a

precision flight-test instrument consisting of power supply and 3-channel demodulator unit designed specifically to serve as the link between sensing instruments and oscillograph recording equipment. The power-supply section is ideally suited for exciting many types of transducers, such as gyros, accelerometers, position indicators or synchros. The demodulator section comprises 3 demodulator channels to transform 400-cps signals to d-c for use with recording galvanometers. The unit features regulated voltage—constant within 1 percent under all operating conditions; frequency stabilization—drift will not exceed 0.2 percent; and linear demodulation—linearity within 1 percent of full scale.



MARKING MACHINE
operates automatically

MARKEM MACHINE CO., Keene 40, N. H., has announced a new marking machine for printing on flat folding boxes, corrugated cartons, plastic panels, abrasive stones and other flat objects up to ¾ in. in thickness. Objects to be marked are automatically fed into the machine, printed and ejected at a rate of 80 imprints per minute. The automatic feed table has adjustable side gages that are easily moved to accommodate objects up to 5 in. × 14 in. Maximum imprint area is 2⅞ in. × 6⅛ in.; and the imprint may be located anywhere in an area 5 in. × 11 in. The unit, model 45AE, is mounted on a floor stand

THE PROBLEM

MAKING A CONTROL MORE ADAPTABLE

A designer wanted to provide the aircraft thermostat shown below with a sensitive, accurate means of control. The problem was complicated by the fact that the thermostat had to be located in a remote and inaccessible spot — while the control dial had to be adaptable enough to allow its being mounted at the pilot's station, the flight attendant's panel or any other desirable location. To solve the problem, the designer chose —

THE LOW-COST SOLUTION

AN S.S.WHITE REMOTE CONTROL FLEXIBLE SHAFT

The shaft provides the required degree of sensitivity and allows the control dial to be mounted wherever desired. According to the manufacturer, "Test results indicate that the operation of the shaft is satisfactory at temperatures ranging from —65°F to +160°F. There is no measurable variation in torque required to turn the shaft or in torsional deflection incurred in initiating cam movement."



Send for the Design Engineer's Bible

The 256-page Flexible Shaft Handbook has many helpful suggestions on how to use, select and apply flexible shafts. Copy sent free if you request it on your business letterhead.

THE S.S.White INDUSTRIAL DIVISION
DENTAL MFG. CO.
Dept. E, 10 East 40th St.
NEW YORK 16, N.Y.

Western District Office • Times Building, Long Beach, California

Want more information? Use post card on last page.



and occupies floor space of 36 in. × 28 in.; total height, 50 in. It is powered by a ½ hp motor.



INSULATING TUBING
is especially rugged

ANCHOR PLASTICS CO., INC., 36-36 36th St., Long Island City 6, N. Y. An Ethocel tube in red and black was recently specified by the Signal Corps for a banana-type plug used on Radio City Products' model TX297/U multimeter. The test set, which is used to measure circuit values, must withstand extremes in operating conditions and all components have to be especially rugged. Ethocel tubing extruded to specifications was chosen for this purpose because of its toughness and insulating values. Coloring of the plastic is throughout the material assuring positive identification of polarity even after years of use. The Ethocel insulated banana plug is connected to a heavy neoprene-covered wire which terminates in a molded neoprene junction.



CONNECTORS
are quick-disconnecting

WINCHESTER ELECTRONICS, INC., Glenbrook, Conn. A new addition

to the line of quick-disconnecting connectors is the QRE 208. Particularly suitable for rack and panel mounting, floating contacts have 0.073-in. diameter solder cups for No. 16 AWG and assure proper play for self-alignment. Four heavy guide pilots and sockets serve to polarize mating connector parts. Contacts and metal parts are precision machined and gold plated over silver for low contact resistance, prevention of corrosion and ease of soldering. Molded melamine bodies provide high dielectric, arc resistance and mechanical strength. Monobloc one-piece construction eliminates unnecessary creepage paths and dust pockets. Four $\frac{7}{32}$-in. diameter holes are provided on both the plug and receptacle for mounting purposes. Voltage breakdown between contacts at sea level is 5,700 v d-c; at 60,000 feet altitude, 1,200 v d-c. Weight of plug is 13.9 oz; receptacle 24 oz.



PROCESS CONTROL is a multisequency device

POTTER INSTRUMENT CO., INC., 115 Cutter Mill Road, Great Neck, N. Y. A versatile new electronic predetermined counter has been designed for use wherever precise, multiple sequence control of manufacturing processes is desired. Increased production and reduced spoilage are achieved with the use of the new counter because it is possible to govern the operation of production machinery in terms of lineal measurement, shaft revolutions, quantity, volume or weight at operation speeds as high as 60,000 per minute. The new true-count method is not affected by speed changes or shutdowns, thus offering precise control not otherwise possible. The 4-se-

ONE SOURCE
for every Wire and Cable requirement

U.S. WIRE AND CABLE CORP.

Electronic and Communication... Electrical and Industrial . . . in every field *U.S. Wire and Cable* plays an active part as a dependable manufacturer. Products of our new enlarged factory surpass all standard field and laboratory tests. Of our extensive line, the items shown here are only representative. We invite your inquiries for our Catalogue and further information.

HIGH FREQUENCY COAXIAL CABLES: These cables not only conform to, but in most cases *surpass* JAN-C-17-A specifications for RG type cables. Our continual laboratory tests assure you that these cables will exceed your requirements in the Electrical, Electronic, and Industrial uses to which they will be applied.

INSTRUMENT and RADIO HOOK-UP WIRES: Furnished with Nylon, Polyethylene, Vinyl or other types of plastic insulation, or without jacket. UNDERWRITERS' LABORATORIES approved, these wires are used for Control Wiring, Automatic Dispensing Machines, and in Radio & TV Equipment.

MICROPHONE and INTERCOM CABLES: A complete selection of Shielded and Unshielded types which can be used for Lead-in, Phono Pick Ups, Speaker Installations, and Public Address purposes in the Radio industry.

TV ANTENNA WIRES: Designed in all shapes (*Flat, Round, Twin Leads, Tubular*) to fulfill the requirements of Television, Mobile Communications, UHF, VHF, Community Antenna Systems, Antenna Rotor Leads, and other Electronic purposes.

UNITED STATES WIRE & CABLE CORP.

PROGRESS AND MONROE STREETS
UNION, NEW JERSEY

Consult us about your wire and cable problems.
Catalog on request.

Representatives in Principal Cities

TIMING DEVICES for MILITARY APPLICATIONS


7008

5103


5700


5900


5148

HAYDON*, through research, development and engineering, is able to introduce timing motors and devices that offer major advances over previously available equipment. The 7008 Series Elapsed Time Indicator is an outstanding example. Designed specifically for 400 cycle operation in airborne equipment. Barrel diameter is only 1.525", is 2-45/64" long and it weighs only 6 oz. Power consumption is less than 3 watts and it indicates in units of tens of hours up to 10,000 and repeats. Write for Engineering Bulletin No. 4.

HAYDON 5700 Series Elapsed Time Indicators provide simple, compact and accurate metering of elapsed time for 60 cycle operation.

HAYDON 5103 Time Delay Relay is designed so that the synchronous motor performs its true function as a time standard. Switching work is accomplished by a relay coil, which, when energized, triggers the load switch for release at the end of the delay time. Write for Engineering Bulletin No. 3.

Series 5900 HAYDON Time Delay Relays provide time delay or interval timing in ranges from 0 to 10 minutes.

HAYDON 5148 Series automatic reset, D. C. timers are very versatile and can be used for either time delay or interval timing.

For experienced help in working out your requirements and specifications, write us today.

*TRADEMARK Reg. U. S. Pat. Off.

HAYDON
AT TORRINGTON
HEADQUARTERS FOR
TIMING

HAYDON Mfg. Co., Inc.
Subsidiary of GENERAL TIME CORP.
2435 ELM STREET
TORRINGTON, CONNECTICUT

quence unit illustrated is one of a line now available. Each channel may be preset for any number from 0 to 9,999. Switching through the 4 channels is automatic at the end of the preset count. Separate relay outputs for each channel provide a voltage pulse for each at the end of its count.



POTENTIOMETERS are miniature wire-bound

AEROHM CORP., 282 Moody St., Waltham 54, Mass. The AP-½ linear wire-wound potentiometer has been designed to solve requirements for small space and light weight. Its all-metal case is only ½ in. in diameter × ⅝ in. deep. The standard model pictured weighs less than ½ oz. This potentiometer will operate between −55 C and +85 C. At 25 C its dissipation is approximately 5 w. It also features soldered electrical connections, precious metal contacts to windings and slip rings, coin-silver tabs to protect end turns and gold-plated fork terminals to facilitate wiring. Resistances range from 10 to 10,000 ohms. Shaft locks, rotational stops, special shafts and bushings are available on order.



VELOCITY PICKOFF has cylindrical p-m core

CONTROL COMPONENTS CO., 46 Walnut St., Brookline 47, Mass., has

added a series of high-sensitivity linear-motion velocity pickoffs known as LVsyns to their line of linear displacement differential-transformer pickoffs. The LVsyn is a shielded cylindrical coil assembly having a coaxial hole and a cylindrical high-coercive force permanent-magnet core. The magnet core is free to move in the coaxial hole which runs the full length of the coil assembly. The relative velocity of the core with respect to the coil assembly results in the output signal. The pickoff is being used in control systems requiring velocity feedback and in machine design and ballistic instrumentation problems. Maximum displacement ranges are from a few thousandths of an inch to several inches. The sensitivity is a function of the size of the pickoff. For example, the 6V8, which has a stroke of 1 in., has a sensitivity of 450 mc per ips.



PLASTIC COIL CORES are highly durable

ANCHOR PLASTICS CO., INC., 36-36 36th St., Long Island City 6, N. Y., has announced extruded plastic coil cores for relay transformer, choke and other coils. The solid-wall plastic cores are more economical as well as more durable than the spiral-wrapped variety. Since they are of one piece construction without any seams they have greater strength and can therefore be made with thinner walls. The latter feature makes for increased magnetic flux strength due to the decreased distance between the coil and the iron core. An additional advantage of these cores is the possibility of color coding. Ex-

TIMING MOTORS for MILITARY APPLICATIONS

CONSTANT RESEARCH on improved timing motors enabled HAYDON* to introduce among other advanced timing components, its 6700 series 400 cycle timing motor. This is an hysteresis type synchronous timing motor, essentially two phase. It is furnished with capacitor for self starting operation on single phase. Variations in temperature, voltage and heat do not affect timing, which is as accurate as the frequency control.

The HAYDON 9200 Series D. C. motor for timing applications is designed for operation from 6 to 30 volts. It can be supplied uncalibrated for use with external resistance or calibrated with resistance type leads.

The 9250F Series HAYDON D. C. motor provides the more uniform torque and speed characteristics of a unit wound for 28 volts, and has an R. F. interference filter. It offers superior performance over a wide temperature range as well as under load. The current and power drain is lower and no calibration is required.

The 1600 Series is the basic motor of the HAYDON line. This motor offers dependable performance, small size, total enclosure, operation in any position, controlled lubrication, simple assembly and a wide range of standard speeds from 60 to 1/60 rpm. Can be supplied to service specifications.

HAYDON Sales Engineers will gladly demonstrate that HAYDON motors will meet your requirements. Write details of your needs and we will be glad to help.

*TRADEMARK Reg. U. S. Pat. Off.

HAYDON Mfg. Co., Inc.
Subsidiary of GENERAL TIME CORP.

2435 ELM STREET
TORRINGTON, CONNECTICUT

HAYDON AT TORRINGTON HEADQUARTERS FOR TIMING


PUTTING MANY VOICES
ON ONE TRANSMITTER
A basic part of microwave radio links is carrier equipment to put the desired number of voice channels into one wide frequency band for transmission between distant points. But many of the early installations of microwave systems depended on "custom-built" carrier equipment—often an expensive modification of telephone carrier equipment designed for wire-line transmission.
For nearly a decade Lenkurt has been filling a practical need in multi-channel radio systems by providing carrier equipment specifically for radio and designed for quantity manufacture. Using frequency division methods to assure maximum system versatility, Lenkurt radio carrier systems multiplex from 4 to 72 voice channels for transmission over any suitable radio equipment. Each carrier-derived channel is "toll quality"—it can be used by telephone companies connected to the nationwide toll network as well as in the private systems of railroads, pipe lines, electric utilities and government agencies.
Radio channelizing equipment by Lenkurt, leading independent manufacturer of telephone carrier systems, is used with VHF and microwave equipment of most major radio manufacturers in both common carrier and private communications installations throughout the world.
Lenkurt
LENKURT ELECTRIC CO.

truded coil cores are made to specification in square, rectangular, round or oval shapes and in any color.

FOCUS COIL
for lab and military use

SYNTRONIC INSTRUMENTS, INC., 100 Industrial Road, Addison, Ill. Designed for use as a precision standard for checking the distortions in production focus coils and as a component in units or applications requiring sharpest focus, a new electromagnetic focus coil has been announced. Type F10 fits c-r tubes having a 1½-in. maximum neck diameter. The coil will withstand up to 18 kv accelerating potential. Spot distortion is entirely eliminated by a $\frac{1}{10}$-in. wall machined case. This results in an extremely uniform focusing field. External magnetic fields are completely eliminated by the nature of the design. As a result, there is no distortion or beam bending in the magnetic gun, no beam shadowing and no interference with other components. The unit may also be used for centering the beam if desired. Complete mechanical and electrical data are available.

RESISTORS
meet military requirements

REON RESISTOR CORP., 117 Stanley Ave., Yonkers, N. Y., has available its RB series high-quality precision wire-wound resistors in tolerances up to 0.02 percent. Ratings of ¼, ⅓, ½ and 1 watt are provided in resistances ranging from 0.1 ohm

to 3 megohms, stable mechanically from −55 C to 105 C. Tinned brass lug terminals designed for resiliency as well as strength are fitted on these resistors, which show less than 0.05-percent change in resistance after completion of MIL-R-93A tests.

H-V SELENIUM RECTIFIER enclosed in phenolic tubes

BRADLEY LABORATORIES, INC., New Haven, Conn. The SE7 line of h-v selenium rectifiers incorporates a new design in which the plates are produced on multiple tools. The unit is completely enclosed in a phenolic tube with an internal spring closure. Units in the line are rated up to 6,000 v peak inverse. The individual rectifiers range from 200 μa d-c to 12.5 ma d-c. The units measure from ¼ to ⅜ in. in diameter and from ⅜ to 5¼ in. long.



POSITION INDICATOR for measurement and control

DOELCAM CORP., Soldiers Field Rd., Boston 35, Mass. The Microsyn position indicator is a small electromechanical signal generator that accurately transforms angular displacement into an electrical signal for measurement of any mechanical variable. This electrical signal output, in conjunction with an appropriate feedback system, may be used to control industrial processes. It features linear output, resolution to 1/100 degree, negligible reaction torque and sensitivity up to 7 v per degree. Tested and perfected as a standard military component for use in gyro instruments and computers, it is now finding wide application in the industrial fields of

FILTERS

when you choose them, don't overlook the thinking behind them.

To the coils and capacitors that normally comprise a filter, Lenkurt adds something extra — **specialized engineering experience.** This means consistent laboratory quality even in mass production quantities. And in filter design problems, Lenkurt offers sound background experience combined with a fresh creative approach.

An excellent example is furnished by a recent filter miniaturization problem. A 140 kc low-pass filter was required to isolate signals up to 140 kc from others over 164 kc. Lenkurt engineers succeeded in reducing it to 1/10th the normal size for such a filter. Subminiature toroids were used and a series-derived network eliminated many capacitors. For its performance see the accompanying graph.

Lenkurt can serve both your routine filter requirements and your special needs. Write today for further information.



Photo shows a miniaturized filter — an example of Lenkurt engineering development.



Performance chart of the Lenkurt miniaturized filter (described in the text).

Lenkurt

LENKURT ELECTRIC SALES CO.

Want more information? Use post card on last page.

B&W

Precise

AUDIO TESTING

for designing, production checking, research or *"proof of performance"* FCC tests for broadcasters.

A low-distortion source of audio frequencies between 30 and 30,000 cycles. Self-contained power supply. Calibration accuracy ±3% of scale reading. Stability 1% or better. Frequency output flat within 1 db, 30 to 15,000 cycles.

MODEL 200 . . . . . $138

AUDIO OSCILLATOR

For fundamentals from 30 to 15,000 cycles measuring harmonics to 45,000 cycles; as a volt and db meter from 30 to 45,000 cycles. Min. input for noise and distortion measurements .3 volts. Calibration: distortion measurements ±5 db; voltage measurements ±5% of full scale at 1000 cycles.

MODEL 400 . . . . . $168

DISTORTION METER

Combines RF detector and bridging transformer unit for use with any distortion meter. RF operating range: 400 kc to 30 mc. Single ended input impedance: 10,000 ohms. Bridging impedance: 5000 ohms with 1 db insertion loss. Frequency is flat from 20 to 50,000 cycles.

MODEL 401 . . . . . $85

LINEAR DETECTOR

Speeds accurate analysis of audio circuits by providing a test signal for examining transient and frequency response . . . at a fraction of the cost of a square wave generator. Designed to be driven by an audio oscillator.

MODEL 250 . . . . . $10

SINE WAVE CLIPPER

Instruments of laboratory accuracy

Bulletin EL-113 gives complete details

Barker & Williamson, Inc.

237 Fairfield Avenue • Upper Darby, Pa.

process control, data transmission, measurement of mechanical variables and analog computation. Write direct for bulletin M.

MOISTURE METERS
available in two types

MARCONI INSTRUMENT LTD., 23 Beaver St., New York 4, N. Y. The Kappa electronic moisture meters operate at radio frequency on the capacity change principle and are capable of measuring the moisture content of a substance with water content as low as 0.5 percent, and at the other end of the scale, as high as 70 percent water. The instrument is manufactured in two degrees of sensitivity—the all-purpose and the S type. The S type has an expanded scale between 0 and 15 percent moisture. The all-purpose type permits a discrimination better than 0.07 percent moisture.

DEFLECTION YOKE
fits 1½-in. neck crt's

SYNTRONIC INSTRUMENTS, INC., 100 Industrial Rd., Addison, Ill., has designed a magnetic deflection yoke for military and oscilloscope applications. Type Y15-5 is especially suited to push-pull applications requiring maximum resolution and high efficiency. It is available in normal, high or extremely high sensitivity. The yoke is of the square core, parallel-opposed magnetic-field type and fits 1½-in. neck diameter c-r tubes. Deflection angle is up to 50 deg. Type Y15-5 is

available over a wide range of impedances in single-ended or push-pull combinations.



CONDUCTOR
is flexible, water-cooled

TITEFLEX, INC., 500 Frelinghuysen Ave., Newark 5, N. J., has developed a water-cooled l-f conductor that (1) has the necessary flexibility to be coiled repeatedly, even in small diameters; (2) has a large enough i.d. to carry 3 gallons of water per minute to cool the coils; and (3) will carry low-voltage, high-amperage current with minimum power loss. An induction heating setup employing these new conductors, used for relieving stresses in large diameter pipe, is illustrated. With these conductors the asbestos stocking over the coil never deteriorates from excessive heat and therefore never needs replacement on that score.

SUPER-REGULATOR
has high-gain d-c amplifier

KALBFELL LABORATORIES, INC., 1090 Morena Blvd., San Diego 10, Calif. Model 121 super-regulator was designed for use with ordinary regulated or unregulated power supplies. It produces the ultimate in power-supply performance. It affords an extremely low impedance d-c voltage source with very low ripple and noise content. Output impedance is 0.005 ohm at d-c and 0.001 ohm for a-c. The unit employs a high-gain d-c amplifier (gain in excess of 105 db). It has an etched-board type of construc-

Official U. S. Navy photograph of submarine attack teacher.

Every dial must work *and read* 100% accurately, when you're...

¾" from Davey Jones

When a ¾" hull is all that's between you and enough water to crush you like a paper cup, there's no tolerating errors. Your instruments must be unerringly accurate – and have scientifically precise dials that are *easy to see, easy to read.* For it makes no difference how accurate an instrument is, if its readings are not equally accurate.

That's the advantage of U. S. Radium dials and edge-lighted panels. Their clean, modern lines are a reflection of the "human engineering" in their design. For accurate, at-a-glance, readings, they have few, if any equals.

Whatever your requirements – for dials, edge-lighted panels, or nameplates – whether luminous or nonluminous – and in whatever materials or finishes you desire – you name it, we make it. Get the finest – U. S. Radium. Write or phone for complete information. Dept. E-11, U. S. Radium Corp., 535 Pearl Street, New York 7, N. Y.

MAKERS OF: Luminescent Materials: Radioactive, fluorescent, phosphorescent • Powders: Cathode-ray tube, television tube • Radium Locators: Pendants, lenses, buttons, screws, markers • Static Eliminators • Radioactive Foils – Alpha-Ray Ionization Sources • X-Ray Screens • Processed Isotopes • Neutron Sources.

SEE OUR CATALOG IN SWEET'S

STANDARD

Radio Interference and Field Intensity

MEASURING EQUIPMENT

Complete Frequency Coverage—14kc to 1000 mc!

NM-10A

VLF

14kc to 250kc

Commercial Equivalent of AN/URM-6B.

Very low frequencies.

NM-20B

HF

150kc to 25mc

Commercial Equivalent of AN/PRM-1A. Self-contained batteries. A.C. supply optional. Includes standard broadcast band, radio range, WWV, and communications frequencies.

NMA-5A

VHF

15mc to 400mc

Commercial Equivalent of TS-587/U.

Frequency range includes FM and TV Bands.

NM-50A

UHF

375mc to 1000mc

Commercial Equivalent of AN/URM-17.

Frequency range includes Citizens Band and UHF color TV Band.

These instruments comply with test equipment requirements of such radio interference specifications as MIL-I-6181, MIL-I-16910, PRO-MIL-STD-225, ASA C63.2, 16E4, AN-I-24a, AN-I-42, AN-I-27a, MIL-I-6722 and others.

STODDART AIRCRAFT RADIO Co., Inc.

6644-A Santa Monica Blvd., Hollywood 38, California • Hollywood 4-9294

tion that keeps all units within very close tolerance, and also provides increased life and reliability. No electrolytic capacitors are employed in the operating circuitry. The unit is extremely useful whereever analysis of more than one circuit operating from the same supply is being performed.

LIQUID PLASTIC
for component sealing

JAVEX, P. O. Box 646, Redlands, Calif., has announced a line of Epoxy resins that are being widely used and accepted in the electronic field for bonding, coating and encapsulation of all types of components. Javabond, the new liquid plastic, possesses excellent electrical properties and practically zero shrinkage. Excellent adhesion to metals, ceramics and other materials, make it possible to fulfill the demands of unusual applications. It sets to a hard consistency, and may be extended or colored with fillers.



TV BAR GENERATOR
covers 18 cps to 108 mc

ELECTRONIC MEASUREMENTS CORP., 280 Lafayette St., New York, N. Y., has announced a new r-f a-f crystal marker and tv bar generator. Model 700 gives complete coverage from 18 cps to 108 mc on fundamentals. It provides a bar generator for tv adjustment with a variable number of bars available for horizontal or vertical alignment and a square-wave generator to 20 kc. It features a Wien bridge a-f oscillator with sine-wave output from 18 cps to 300 kc and crystal

marker and amplitude control. Other features include individually tuned coils, constant r-f output impedance, stepped r-f attenuator, electrostatically shielded transformer, thorough shielding, Colpitts r-f oscillator from 300 kc to 108 mc on fundamentals—up to 216 mc on second harmonic—and variable percentage of modulation.



F-M/A-M TUNER
incorporates 10 tubes

PILOT RADIO CORP., Long Island City, N. Y. The AF-824 tuner has a frequency range of 88 to 108 mc on f-m and 540 to 1,700 kc for a-m. Sensitivity for f-m is 10 μv for 20-db quieting; a-m—10 μv for 0.2-v output. Selectivity on f-m is 6 db down at 200 kc; a-m— 6 db down at 9 kc. Peak to peak separation is 320 kc, linear for 190 kc. Audio distortion is less than 0.2 percent at 1-v output. Maximum audio output is 3 v. Power consumption is 117 v, 60 cycles, 50 watts.

I-F TRANSFORMER
with single-end tuning

ELECTROMETRIC CO., Woodstock, Ill. Tuning both coils from the same

Precision
ATTENUATION
to 3000 mc!

- VSWR less than 1.2 at all frequencies to 3000 mc.
- TURRET ATTENUATOR featuring "Pull - Turn - Push" action with 0, 10, 20, 30, 40, 50 DB steps.
- Accuracy ±.5 DB, no correction charts necessary.
- 50 ohm coaxial circuit. Type N Connectors.



Inquiries are invited concerning single pads and turrets having other characteristics

STODDART AIRCRAFT RADIO CO., INC.
6644-A SANTA MONICA BLVD., HOLLYWOOD 38, CALIFORNIA
HOllywood 4-9294

Want more information? Use post card on last page.

For Parts that must be
TAKEN OFF — PUT BACK — BUTTONED TIGHT

LION FASTENERS



LOCKS TIGHT WITH A QUARTER TURN
Always at correct tension

Lion Fasteners are *right* for buttoning parts that must be removed repeatedly for inspection, maintenance, or other reasons.

Vibration and shock can't loosen a Lion Fastener. Even an inexperienced service man can't replace it wrong. A quarter turn opens it. Another quarter turn locks it. The tension is *designed into it.*

Lion Fastener Spring Assembly is quickly spot welded or riveted in place. The stud cannot be lost. It is grommeted tight to the sheet. They will button sheets .040 plus or .020 minus over or under standard rating. The misalignment is as much as .156. The one-piece forged stud is tested to 1425 lbs. Write today for demonstration kit and application data.

TYPICAL APPLICATIONS: INSPECTION PLATES • COWLING
ELECTRICAL PANELS • CABINETS • DUCTWORK

Free DEMONSTRATION KIT contains sample Lion Fasteners to help you visualize their adaptability to your product. Write on your company letterhead. No obligation.

LION
FASTENERS, INC.
500 MAIN ST., HONEOYE FALLS, N. Y.
In Canada:
A. T. R. Armstrong Co., 50 St. Clair Ave. West, Toronto

end is one important feature of a new miniature i-f transformer type TX100, now available. Both coils can be tuned either from the top or from the bottom. This permits faster set alignment, reducing radio set production costs. Another result is a greater freedom of radio chassis design. Field trouble is minimized because all connections are soldered. Coil leads are not subject to breakage because they are soldered directly to the tops of the terminals. High Q is the result of a unique delay-line-type winding. Because the type TX100 is temperature compensated for low drift, it delivers constant high performance over a wide temperature range. It can be used for any application requiring a ¾-in. i-f transformer; and is available in a wide range of inductances and Q's for a-m, f-m, tv and military applications.

Literature

Induction Generators. Ai Research Mfg. Co., Los Angeles 45, Calif. Operating principles of a line of induction generators for aircraft and guided missiles are outlined in booklet No. EB-3-1. The booklet, illustrated with charts and photographs, contains descriptions of design features, operating function, performance characteristics and applications. In addition, equations are supplied to allow modification of performance characteristics.

C-R Oscillograph. Allen B. DuMont Laboratories, Inc., 760 Bloomfield Ave., Clifton, N. J., has issued a descriptive bulletin on the type 301-A, a miniaturized wide-band quantitative c-r oscillograph. The bulletin's front cover is an actual-size illustration of the instrument's front panel, while fold-outs of the bulletin illustrate depth of instrument, providing an actual-size, 3-dimensional mock-up of the unit. Complete electrical and mechanical specifications are included.

Electromagnetic Focus Coils. Syntronic Instruments, Inc., 100 Industrial Road, Addison, Ill., has available a new catalog page illustrating and describing two new

HOW Barnstead PURE WATER HELPS RCA

RCA requires Pure Water . . . copper-free to an extreme degree and free from organic impurities for trouble-free TV picture tubes. That is why RCA makes use of Barnstead 200 gph double-effect Stills in combination with Barnstead 1000 gph Demineralizers.

LIKE RCA... THOUSANDS OF PLANTS THE WORLD OVER MAKE USE OF BARNSTEAD EQUIPMENT FOR OBTAINING PURE WATER

If you use water, in any of countless manufacturing and processing operations, you will find that Barnstead equipment producing either demineralized or distilled water, or both, will insure better products, consistent results, fewer rejects; and will cut your costs in many ways. Join the thousands of companies the world over who look to Barnstead for the solution to their Pure Water problems. Write today stating your problem. Our engineers will make recommendations without obligation . . . recommendations that will cut costs and increase production.

The Right Equipment For Your Pure Water Needs

75 Years of Progress in Pure Water 1878 1953

We Make Both . . . Stills and Demineralizers

Barnstead STILL & STERILIZER CO.

84 Lanesville Terrace, Boston 31, Mass.

Want more information? Use post card on last page.

electromagnetic focus coils. Type F10, for 1½-in. neck diameters, is for laboratory, military and special-purpose applications. Type F30, for 2½-in. neck diameters, is for projection, laboratory and special-purpose applications. Complete technical information includes dimensional drawings and electrical and mechanical data.

Guided-Missile Instrumentation. Electronic Engineering Co. of California, 180 So. Alvarado St., Los Angeles 4, Calif. A 24-page booklet discusses company facilities and experience and also illustrates and describes such equipment as timing and firing systems, radar components, a chain radar system, telemetering equipment, digital data-transmission equipment, missile-tracking optical equipment, plotting boards and data-reduction equipment. Also included are a listing of government contracts and plug-in unit information.

Vibrator Power Supplies. Collins Mfg. Co., 726 N. Kresson St., Baltimore 5, Md. A single-sheet bulletin illustrates and describes the Vibration miniature high-frequency vibrator power supplies. The units discussed operate at 400 cycles and higher; and are designed for input voltages from 1.5 to 32 v d-c; for outputs, 400-cycle a-c or filtered h-v d-c. Included are specifications for the representative, custom-designed model VC2-4.

Electronic Parts Catalog. Radio Shack Corp., 167 Washington St., Boston 8, Mass. The 224-page edition of the 1954 electronic parts mail-order catalog includes a 32-page rotogravure section covering high-fidelity custom music systems. Highlighting the newer products are extensive listings of transistors and germanium diodes; antennas, converters and test equipment for uhf-tv; printed circuit components; and radiation detection apparatus. The catalog lists and illustrates over 30,000 products.

Electronic Equipment Decals. Tekni-Labels Co., 232 N. Glenoaks Blvd., Burbank, Calif., has available a booklet describing its electronic equipment decals for design



New Freedom FROM JAMMING!

THIS NEW CONTINUOUSLY VARIABLE BANDWIDTH CONVERTER stops jamming carriers and heterodyne-beat-note interference which normally mar reception of long-distance CW and AM signals. Carriers as close-in as 500 c/s activities are world-known for reliable anti-jamming performance by both military and commercial companies. They are employed with AM radio-receivers located in some of the toughest signal jamming spots in the world by governments, airlines and telephone/telegraph companies. Special SIGNAL SPLITTERS are available for use with modern high-quality single-sideband receiving equipment to eliminate signal jamming in the selected sideband. A general purpose radio-communications receiver with built-in SIGNAL SPLITTER features will also be available shortly.

J. L. A. McLAUGHLIN CORPORATION
LA JOLLA, CALIFORNIA, U. S. A.

Want more information? Use post card on last page.

MILWAUKEE TRANSFORMERS

A TYPE FOR EVERY NEED
A PERFORMANCE TO EXCEED EVERY DEMAND!

Hermetically Sealed Components That Perform Superbly and Lastingly in Airborne and Ground Applications



WRITE FOR FREE BROCHURE

AUDIO, POWER, PULSE TRANSFORMERS
REACTORS — FILTER NETWORKS
Custom Engineered to rigid MIL T-27 government and commercial requirements.

MILWAUKEE TRANSFORMER CO.
5231 NORTH HOPKINS STREET
MILWAUKEE 9, WISCONSIN

laboratories, engineers, experimenters, hobbyists, amateurs and military services. It lists alphabet and trademark decals. Designs included effect a great saving if only one item of equipment is to be marked. Use of these decals speeds work also, because the equipment can be titled right at the technician's bench. Included among the decals described are those for dials, panel titles, tv, audio, receiving tubes, transmitters, instruments and receivers.

Microwave Test Equipment. Douglas Microwave Co., Inc., 338 E. 95th St., New York 28, N. Y., has available a catalog presenting its complete line of precision microwave test equipment and component parts. The instruments described therein embody the latest design improvements and, where possible, are designed for broadband applications. Corrosion resistance is maximized by utilizing appropriate electroplating finishes. In general, all conducting surfaces are silver plated and rhodium flashed to insure permanent high conductivity. Detailed specifications concerning the catalog items are available.

Antennas and Boosters. Channel Master Corp., Ellenville, N. Y., has published an informative 16-page booklet discussing the factors that determine the performance of tv antennas and boosters. Written specifically for the benefit of tv installation and servicemen, the profusely illustrated booklet defines and analyzes gain, directivity and impedance. It also covers the four standards of booster performance—gain, noise figure, vswr and balance-to-unbalance ratio. An explanation of how these qualities are isolated and measured in the laboratory is also included.

Environmental Test Cabinets. Hudson Bay Division, Refrigeration Systems, Inc., 646 W. Washington Blvd., Chicago 6, Ill. Descriptive bulletin 108-102 covers a recently improved line of environmental test cabinets. The line includes stratosphere test chambers for altitude simulation between atmospheric pressure and 100,000 ft,



LFE

SOLID DELAY LINES STOP TIME . .

Suitable for video integration, computers, time markers, moving target indication, etc.

LFE Solid Delay Lines offer important advantages in obtaining precise delay intervals for pulse or modulated signals:

Wide ranges of delay	Smooth pass band
Low attenuation	Wide temperature range
Low spurious response	Minimum size and weight
Wide bandwidth	Rugged construction

For complete information, write: Specialties Division

LABORATORY for ELECTRONICS, INC.
75-3 PITTS STREET • BOSTON 14, MASS.

PRECISION ELECTRONIC EQUIPMENT • OSCILLOSCOPES • MAGNETOMETERS • COMPUTERS • MICROWAVE OSCILLATORS • SOLID DELAY LINES

HEAT RESISTANT WIRES FOR EVERY APPLICATION . . .

DON'T DELAY

Winter will soon be here and you will be glad if you have protected vulnerable pipe lines with Lewis heating cable. Specially insulated Nickel Chrome conductor will operate satisfactorily at 500°F.

Write for quote

- HEATING UNITS
- HEATING ELEMENT
- RESISTANCE LINE CORD
- THERMOCOUPLE WIRE
- ASBESTOS LEAD & FIXTURE WIRE
- INSULATED RESISTANCE WIRE
- FIBERGLAS INSULATED WIRE
- WIRE TO ANY SPECIFICATIONS

Send your electronic control, communications or appliance wiring specifications for a recommended solution by our engineers.

FOR A TRIAL ORDER OR A CARLOAD *consult*

THE LEWIS ENGINEERING CO.
Wire Division
NAUGATUCK CONNECTICUT

HOLD THEM TIGHT with a BIRTCHER CLAMP

There is a Birtcher Clamp . . . *or one can be designed* . . . for every tube you use or intend to use.

Regardless of the type tube or plug-in component your operation requires . . . and regardless of the vibration and impact to which it will be subjected . . . a Birtcher Tube Clamp will hold it securely and *rigidly* in place.

Catalog and samples sent by return mail.

The BIRTCHER CORPORATION
4371 Valley Blvd.
Los Angeles 32, Calif

Please send catalog and samples by *return mail.*

Company _____ E-11-3
Attention of: _____
Address _____
City _____ State _____

Want more information? Use post card on last page.

Low Signal Level Performance of X'tal Diodes

Sensitive DC-VTVM and New Diode Tester Solve an Old Problem

One of the most puzzling problems connected with germanium and silicon high frequency diodes is their seemingly unpredictable behavior at *low* signal levels. Generally accepted diode *specifications*, such as their voltage drop in the passing direction, or leakage current in the blocking direction, are practically *meaningless*, as far as rectification, limiter-action, mixing-properties and other performance-



characteristics of these diodes at *low* signal levels are concerned. For instance, a certain diode, when being fed an RF signal of 25mV, may show a DC output of 9mV while another seemingly identical diode may generate only 3mV. Yet, both will fully meet the same specifications published for their particular type. The simple reason for this amazing discrepancy is that our present, generally accepted, diode specifications are based on *high* signal level measurements.



Many users of X'tal diodes have therefore developed a habit of selecting their diodes for *low* level-operation by picking the apparently most efficient ones from whatever diode-supply may be available. Often a damaged "star performer" seems irreplaceable.

This unsatisfactory, haphazard situation has led our company to the development of a new *low-level diode tester*, type MV-177, shown above. It feeds an accurately measured AC signal into the crystal, while its DC output is measured with an MV-17B millivoltmeter. The meter is sensitive enough (1mV full scale) to show DC outputs of "good" diodes, down to AC input levels of 1mV, where rectification efficiency may be 2% or less (see DC output vs. AC input curve for typical "good" and "bad" diodes, on the left).

This is but one example showing how the high sensitivity of the MV-17B DC millivoltmeter can be put to practical use. For further information concerning this unusual VTVM and its numerous research applications, also, if desired, a complete description of the Low Level Diode Tester, write to:

MILLIVAC INSTRUMENT CORPORATION

P.O. BOX 997, 444 SECOND STREET, SCHENECTADY, NEW YORK

"Time Progresses, So Do We"

temperature control between −100 and +200 F and humidity control between 20 and 95 percent. Each of the 3 types of available units is illustrated. Views are also included showing typical control, and air-circulating and conditioning arrangements.

Paper Tubulars. Cornell-Dubilier Electric Corp., 333 Hamilton Blvd., South Plainfield, N. J. Bulletin NB154 covers the new Budroc steatite-cased paper tubular capacitors. The capacitors described are of noninductive construction and housed in a ceramic (steatite) tube with Polykane end seals. Outstanding features, test data and average temperature characteristics charts are given.

Six-Channel Recorder. Goodyear Aircraft Corp., Akron 15, Ohio, has released a 4-page folder illustrating and describing model GN215-R5 GEDA 6-channel recorder that was specifically developed as an accessory to analog computers. The unit discussed is particularly adapted to the recording of solutions to complex dynamic problems and the testing of such devices as servomechanisms. Complete technical specifications are given.

Piston Capacitors. JFD Mfg. Co., Inc., 6101 16th Ave., Brooklyn 4, N. Y., has available a new 4-page brochure, No. 220, on piston-type variable trimmer capacitors for industrial, military, experimental and radio trade requirements. Also available is a one-page flyer (form No. 226) detailing the company's new miniature uhf piston capacitor —the Mighty Midget model VC3-G —complete with capacitance range, dielectric details, figures on moisture resistance, temperature coefficient of capacitance and universal mounting.

Transistor Manual. CBS-Hytron, A Division of the Columbia Broadcasting System, Inc., Danvers, Mass. Profusely illustrated, the new 8-page transistor manual is in three parts—theory, data and application. It contains nine different basic transistor applications. Both point-contact and junction transistor operation are explained by



NET-11 AGASTAT

NEW!

TWO STEP AGASTAT

Trademark

TIME DELAY RELAYS

Single units for applications requiring a sequence of time delay relay periods—such as sequential starting of motors—or an adjustable momentary impulse, as in operating air valves of air cylinders on indexing machines. Time delay range of from 0.1 seconds to 10 or more minutes, with a secondary delay period up to 15 seconds. Compact, lightweight pneumatically timed units, low in cost and remarkably versatile.

Write for specifications—and ask our application engineers for help with your timing problem. Address Dept. A7-114.

AGA DIVISION
ELASTIC STOP NUT CORPORATION OF AMERICA
1027 Newark Avenue, Elizabeth, New Jersey
Pioneers in pneumatic timing

STERLING

A DEPENDABLE SOURCE FOR TRANSFORMERS MIL-T-27 & COMMERCIAL

- *Pulse*
- *Audio*
- *Power*
- *Filter Choke*
- *Filament*
- *RF Coils*

Custom Built to your Specifications

WE SOLICIT SAMPLES AND SHORT RUN PRODUCTION

STERLING TRANSFORMER CORP. BROOKLYN, N. Y.

297 North 7th St., Brooklyn 11, N. Y.

---

7 REASONS WHY Precision COIL BOBBINS

improve your coils . . .

- Quality Controlled
- Greater Insulation
- Better Heat Dissipation
- Higher Moisture Resistance
- 15 to 20% Stronger
- Lighter Weight
- More Winding Space

PRECISION Coil Bobbins are finished to your exact specifications. Only the finest dielectric materials are used.

Cores furnished in an infinite variety of sizes and shapes—kraft, fish paper, acetate, combinations, or phenol impregnated materials. Flanges cut to specifications—plain or fitted with leads, slots or holes; embossed or recessed.



Send specifications for free sample and request new Arbor List of over 2000 sizes.

PRECISION PAPER TUBE CO.

2041 W. Charleston St. Chicago 47, Ill.
Plant No. 2, 79 Chapel St., Hartford, Conn.
Also Mfrs. of Precision Paper Tubes

QUARTZ CRYSTALS

For Precision Frequency Control

fast service

order's mailed within 24 hours from time received

On all crystal orders of less than five units of any one frequency in the range 1500 KC to 15000 KC.

CRYSTAL TYPES

FC-18: 800 to 20,000 kcs/sec. Available in Holders: No. F-605, F-609, F-612, F-700, or F16.

FC-23: 10 to 100 mgs/sec. in Holders: F-10, F-16, F-605, F-609, F-612, or F-700.

FC-25: 200 to 500 kcs/sec. Holders: F-16, F-605, F-609, F-612, or F-700.

FC-37: 90 to 250 kcs/sec. Available in Holders: No. F-13 or F-16.

FC-100: 90 to 200 kcs/sec. Holder: F-16.

Holders illustrated actual size.

F-16

All Crystals calibrated to .0025% or better of specified frequency into a 32 mmf load unless otherwise ordered.

QUALITY • SPEED

for complete details and prices write . . . wire . . . or phone . . .

International CRYSTAL Mfg. Co.

18 North Lee, Oklahoma City, Okla. Phone F05-1165

vacuum-tube analogy. Also clearly described are conduction by holes, and *pnp* and *npn* transistors. Reduction of equipment size, elimination of filament-power requirements, instantaneous operation and exceptionally long life are among the advantages cited. Included in the manual's application section, which constitutes an introduction to transistor circuitry, are hearing-aid and radio-receiving circuits that employ transistors and a circuit for use in switching applications.

Electrical Insulation Price Catalog. Insulation Manufacturers Corp., 565 W. Washington Blvd., Chicago 6, Ill., has available a new 140-page catalog including information on standard put-ups, terms and aggregation policies. A table of contents and an alphabetical product index serve as guides to product prices in 12 different sections. The catalog includes prices on such material as: cords and twines, untreated woven tapes, sleevings and tubings, paper and paper products, slot wedges, reinforced or laminated plastics, vulcanized fibre, plastic or resinous films, pressure-sensitive tapes, varnishes and compounds, mica products, varnished fabrics and paper combinations and miscellaneous materials.

Packaged Plug-In Circuits. Electronic Engineering Co. of Calif., 180 South Alvarado St., Los Angeles 57, Calif. A new line of packaged plug-in circuits which may be taken apart is described in a new 12-page brochure that tells how the units were designed, advantages in their use, applications and specifications for the 20 off-the-shelf versions. The brochure also lists 26 other types of plug-in circuits that are available on special order plus information on how the new take-apart units may be used to advantage in all types of electronic equipment.

Transformers. Chicago Standard Transformer Corp., Addison and Elston, Chicago 18, Ill., has released a new catalog sheet, bulletin 467. The publication describes 6 transformers recently added to the com-

(Advertisement)

Indicating Meter Gives Automatic Direct Control

This Contact Meter Relay provides sensitive, direct control for alarm and automatic shut-off, or continuous on-and-off circuit interruption on ½ uA. or 0.1 MV.

It operates direct on the low power (0.2 microampere, 0.1 millivolt) output of photo cells, resistance bulbs, and thermocouples without intermediate circuitry, and will provide hi-limit, lo-limit, or hi-and-lo-limit control.

3 meter sizes:
451-C—4½"
351-C—3¼"
261-C—2½"



Model 451-C

Platinum alloy micro-contacts are mounted on the jeweled moving coil armature-type indicating movement and stationary indicator. The contacts lock in by a holding coil in the relay at the pre-set value to close the control circuit. The meter resets electrically . . . requires no solenoid or pusher.

The contacts are released by interrupting the locking circuit, either manually or by automatic interruptor. The contact locking arrangement assures positive contact without floating or contact chatter. Spring action provides clean break.

Model 451-C (shown) has a full scale 4" 90° arc with ranges of 0-20 microamperes or 0-5 millivolts. It is also available in compensated temperature millivoltmeters. Models 351-C and 261-C also have a full 90° arc. The meters are sensitive to changes of less than 1% of scale range. Differential between make and break is less than 1%.

Contact Meter Relays are used in electronic equipment, industrial speed-feed controls, chemical process titration and temperature controls, radiation warning and control devices, digital computers, auto-switching of standby microwave equipment.

Unbreakable clear plastic case and large-scale easy-reading dial with rugged shock-resistant construction. For further specifications write or call Bradley Thompson, Assembly Products, Inc., Chagrin Falls 43, Ohio. Phone Chagrin Falls 77374.

TAKE NO CHANCES WITH VITAL EQUIPMENT... *Specify*

SERIES 6918 or 6924

RACKS by PAR-METAL



18½" or 24" DEEP, for 19" WIDE PANELS

- *Panel Spaces:* 61¼", 70", or 77" high.
- Finished in Prime Coat, Black Wrinkle, Grey Lacquer, Grey Wrinkle.
- Series 6918 or 6924 Racks may be used in *"rows"* or *"gangs,"* as corner trims are removable from *front* of cabinet.
- Standard shelves and roller trucks are manufactured by us for use with these Racks.

THESE RACKS ARE MODERATELY PRICED and AVAILABLE FOR SHIPMENT FROM STOCK

Planning an electronic product? Consult Par-Metal for

RACKS • CABINETS CHASSIS • PANELS

Our P-6924 Rack as used by Gai-Tronics, Inc., Reading, Pa.

Remember, Par-Metal equipment is made by electronic specialists, not just a sheet metal shop.

Made by Electronic Specialists!

PAR-METAL

PAR-METAL PRODUCTS CORPORATION
32-62 — 49th ST., LONG ISLAND CITY 3, N. Y.
Tel.: Astoria 8-8905
Export Dept.: Rocke International Corp.
13 East 40 Street, New York 16, N. Y.

WRITE FOR CATALOG!



quality "precision" LEADS of TUNGSTEN MOLYBDENUM NICKEL NICKEL-CLAD COPPER and ALLOYS

quality hand-wound COILS of Tungsten and Molybdenum

quality MACHINED TUBE COMPONENTS to customers' specifications

Your products can only be as good as the parts you put into them!

SEND US YOUR BLUEPRINTS or SPECIFICATIONS FOR QUOTATIONS!

Electronic Parts Manufacturing Co., Inc.
508 25th St., Union City, N. J.
Send me copy of your brochure.
Name_____
Address_____

ELECTRONIC PARTS MANUFACTURING CO., Inc.
508 25th St., Union City, N. J.

USE "Double Feature"

INSULATING TUBING AND SLEEVING

TURBOTUF®

Easily the most economical insulating tubing and sleeving for commercial use . . . equally and ideally suitable for the insulation demands of Classes A & B. Separate A & B inventories unnecessary — space and dollars saved when you use TURBOTUF.

Easily the finest insulating tubing and sleeving — Meets exacting specifications for durable resistance to icy or sweltering temperatures . . . made of superior materials to give long wear — won't crack, bend, chip, or peel under rigorous abrasion . . . excellent pliability — can be knotted, bent, tugged at, stamped on — springs back in perfect condition . . . easier to handle because of its uniformity . . . won't fray . . . not affected by oils, alcohols, alkalies and weak acids — high dielectric strength and long life.

PROTECT YOUR EQUIPMENT — SAVE MONEY — GET "DOUBLE FEATURE" TURBOTUF

Insulating Material TURBO® BRAND Specialists Since 1920

The William and Co., Inc.

Dept. E-11 Willimantic, Conn., U.S.A., Tel. HArrison 3-1661

TURBOTUF Insulating Tubing and Sleeving • TURBO Insulated Wires • Wire Markers • Extruded Tubing • Varnished Saturated Sleeving and Tubing • Cambric Cloths, Tapes, Papers • Mica

SALES REPRESENTATIVES IN PRINCIPAL CITIES

pany's line of stock components. Complete electrical and physical specifications are listed for three power transformers: P-6348, PC8422 and PM8422; two audio output transformers: A-3337 and A-3839; and a heavy-duty plate transformer, P-8044, for amateur use.

Photo-Recording Manual. Allen B. DuMont Laboratories, Inc., 760 Bloomfield Ave., Clifton, N. J. A 36-page manual offers a complete review of the problems and associated solutions encountered in photographing c-r patterns. The publication is profusely illustrated with actual photo-recordings, scales, graphs and diagrammatic sketches. In addition to technique information, it contains complete descriptions and specifications of the company's line of photo-recording equipment. The manual is offered to qualified personnel requesting copies on business letterheads.

Instrumentation For Research. Minneapolis-Honeywell Regulator Co., Wayne and Windrim Aves., Philadelphia 44, Pa. The 6-page bulletin, 14-1, describes various electronic instruments that will help speed research and test problems. The bulletin briefly covers the way such instruments can help the research man, and includes descriptions of various servo-components and accessories which are also useful to the research and laboratory men.

Feed-Through Terminals. The Fusite Corp., 6000 Fernview Ave., Cincinnati 13, Ohio. A new 20-page catalog describes a complete line of hermetically sealed glass-to-steel electrical feed-through terminals. Ten different groups of terminals are described and drawn in detail. These include such variations as miniature singles, standard size singles, stand-offs, threaded bushing, multiples, miniature multiples, plug-ins and crystal can headers. Flange and panel treatments are also discussed. Besides the listing of the terminals, pertinent information is also included on specifications and electrode designs. Soldering suggestions are described

WE HAVE THE CONNECTIONS



TO MAKE BETTER TRANSFORMERS

The transformer illustrated above has 16 terminal connections. For the electronic application under which this transformer is used, each series of connections must provide exact electrical characteristics.



Our experience in making precision transformers is of long standing. We welcome your inquiry. When transformer applications call for rugged, out-of-the-ordinary service, a design such as this may be the answer to your problem.

ACME ELECTRIC CORPORATION

Main Plant: 3111 Water St., Cuba, N. Y.
West Coast Engineering Labs.: 1375 W. Jefferson Blvd., Los Angeles, Calif.
In Canada: Acme Electric Corp., Ltd., 50 North Line Rd., Toronto, Ont.

Acme Electric
TRANSFORMERS

Make a GM PORTABLE D'ARSONVAL

GALVANOMETER

the Heart of Your Instrument



FOR MEASURING HEMOGLOBIN content of blood samples, the Fisher Scientific Co. of Pittsburgh uses a Model 100 G-M Galvanometer in its popular Electro-Hemometer (at left). Whatever your own particular instrument field, you can achieve this same self-contained portability, ruggedness and high sensitivity with G-M Galvanometers. Complete catalog on request.

GM LABORATORIES · Inc

4336 NORTH KNOX AVE., CHICAGO 41

In Canada: Cossor (Canada) Ltd., 301 Windsor St., Halifax, N. S.

HOW TO INAUGURATE COLOR TV WITH MINIMUM INVESTMENT



In Use by Leading Receiver, Tube and Component Mfrs.; TV Broadcasters; Research Laboratories

By Acquiring Units as Your Requirements Develop.

1. **BASIC EQUIPMENT**
   Produces NTSC encoded signals from color bars.
2. **SUPPLEMENTAL EQUIPMENT**
   Creates accurately certified NTSC encoded pictures from color transparencies. Feeds phase equalized picture and sound transmitter.
3. **RECOMMENDED EQUIPMENT PLUS FULL FACILITIES**
   Transmits, receives,, monitors and analyzes, composite NTSC color pictures.

Illustrated Literature on Request

TELECHROME INCORPORATED

The Nation's Leading Suppliers of Color TV Equipment
88 Merrick Road Amityville, N. Y.
AMityville 4-4446

G-V
MINIATURE
THERMAL
RELAY

Advanced Engineering Features!

- Miniature and Octal Sizes
- Hermetically Sealed in Metal Shell
- Adjustable and Non-Adjustable
- Heater Voltages up to 230 Volts
- Fully Temperature Compensated
- Suitable for Military and Industrial Use
- Unequalled for Ruggedness and Precision

Not Only a

TIME DELAY RELAY...

...with performance features that surpass larger octal relays.

More and more engineers are finding other uses for these precise and rugged units—jobs which thermal relays of the usual bi-metal design often cannot do... such as:

- TUBE HEATER VOLTAGE REGULATION
- POWER SUPPLY OVERLOAD PROTECTION
- OVER- OR UNDER-VOLTAGE ALARM OR CUT-OFF
- LOW OR HIGH FREQUENCY CUT-OFF

To receive technical information on these new applications, as it comes off the press, *and* our bulletin on Time Delay Relays, just mail the coupon below.



G-V
CONTROLS INC.
16 Hollywood Plaza
East Orange, New Jersey

G-V CONTROLS INC. • 24 Hollywood Plaza, East Orange, N. J.

Please send me your bulletin on Thermal Time Delay Relays and information on new thermal relay applications. I am particularly interested in

_____

Name_____ Position_____

Company_____

Address_____

_____

while short case histories on the use of the terminals are included.

Rivet Catalog. Townsend Co., New Brighton, Pa., has issued a 12-page catalog describing in detail its complete line of Cherry Blind rivets—the rivet that is installed by one man from one side of the work and is comparable to conventional rivets in strength and installation speed. The new catalog includes information on applications, mechanical specifications, types, descriptions and data on the rivet guns for application, and a list of stock blind rivets available.

Transducer. Statham Laboratories, Inc., 12401 West Olympic Blvd., Los Angeles 64, Calif. A single-sheet bulletin covers the model GI transducer, a research tool designed for the measurement of forces from ±1.5 oz to ±80 oz and for the measurement of displacements of ±0.0015 in. Included are an illustration and dimensional diagram, and a selection table showing force ranges, displacement ranges, nominal bridge resistances, rated input, full-scale open-circuit outputs and natural frequencies. Complete technical specifications are given.

Submicrosecond Flash Unit. Edgerton, Germeshausen & Grier, Inc., 160 Brookline Ave., Boston, Mass., has published a 4-page folder illustrating and describing the type 2307 double-flash submicrosecond flash unit for silhouette photography. The unit described was developed for the measurement of the velocities and patterns of air shock waves produced by explosives or the speeds of objects moving up to 8,000 feet per second. The entire electronic control equipment and the optical system are contained in a metal case 12 in. high × 10 in. × 20 in. long, weighing 45 lb.

Electrical Control. Micro Switch, Division of Minneapolis-Honeywell Regulator Co., Freeport, Ill. Catalog No. 59 is a 12-page booklet dealing with Microtrip, an electric clutch control for power machines. The well illustrated booklet contains charts giving information for



One of the world's most modern swiss-type automatics

STROHM SWISS-TYPE AUTOMATIC—
advanced engineering design for today's
toughest jobs *and* tomorrow's
increasing demands. Volume production.
Extreme tolerances. Easy adaptability.
Moderately priced!
Prompt delivery!



Exclusive distributors
HOFMANN
NEEDLE WORKS, INC.
MACHINERY DIVISION
635 59th STREET, WEST NEW YORK, N. J.
N.J. Plant: UNion 3-1300 • NYC: LOngacre 5-5770

---

sub-miniature
AND
moisture-proof

IN-RES-CO
S-15 & S-30
WIRE WOUND
RESISTORS

THE ECONOMICAL SOLUTION where moisture proof resistive elements of comparatively small size are required for commercial applications. Type S-15 is ⅜" long by ¼" diameter; type S-30 measures ¾" by ¼" diameter. Both types are moisture proof and capable of high performance over long periods of continuous service. IN-RES-CO Resistors for every ordnance or civilian requirement are available at a cost that solves circuit design problems both performance-wise and cost-wise. Check up now, on the complete line of IN-RES-CO quality wire wound resistors.



TYPE S-15
¼" DIA. x ⅜" LG.

TYPE S-30
¼" DIA. x ¾" LG.

INSTRUMENT RESISTORS CO.
COMMERCE AVENUE — IN-RES-CO — UNION, NEW JERSEY

FOR JAN SPECIFICATION RESISTORS — consult the new illustrated literature describing the complete in-res-co line. Write for your copy today!

APPLICATION-DESIGNED RESISTORS FOR ELECTRONICS AND INSTRUMENTATION

Two Pictures . . . ONE IS ART



Oster

Thousands of paintings have been put on canvas, but only the select few have the lasting quality of great art.

We're not artists, but we do know something about quality. Osters have produced top-notch products for over a quarter of a century. We have a group of well-trained, conscientious engineers who will design and produce what you want in

BLOWERS • MOTORS • ACTUATORS
SERVOS • SYNCHROS

You'll find we're as precise as the old masters about the quality of our product.

You Can Depend on SAFER Flight . . . EXTRA Fight with OSTER Products

JOHN OSTER
MANUFACTURING COMPANY
AVIATION DIVISION
RACINE, WISCONSIN

NEW Type 2113, 12-Channel

PICTURE SIGNAL GENERATOR

for Production Testing and Closed-Loop T.V.

The Type 2113, 12 Channel Picture Signal Generator has been specifically designed for production line testing of TV receivers. Used in conjunction with the equipment listed below, the manufacturer can produce his own "Indian Head" test pattern and is no longer dependent on local transmissions. This signal generator has also received wide acceptance for dealer demonstrations of TV receivers in areas where transmitting facilities are not yet available.

SPECIFICATIONS

OUTPUT SIGNALS AND ACCURACY: Picture and sound R. F. signals on all 12 standard TV channels. Picture carrier accuracy 0.01%; sound carrier better than ±4.5 KC of "standard" on all channels.

PICTURE CARRIER OUTPUT: At least 50,000 microvolts into a 75 ohm terminated coaxial cable.

R. F. OUTPUT IMPEDANCE: Output is into a 75 ohm coaxial cable. Two probes are supplied for use with 75 ohm cable to match 75 or 300 ohm receiver antenna input circuits.

VIDEO INPUT IMPEDANCE: 75 ohms single ended.

VIDEO INPUT: Minimum 1 Volt Peak to Peak, black negative polarity.

PICTURE CARRIER MODULATION: Continuously variable 0 to 87%.

D. C. RESTORER: A D.C. restorer is provided to maintain constant average picture brightness when using program material for video modulation.

SOUND CARRIER DEVIATION: Continuously variable 0 to 40 KC.

SOUND MODULATION: Modulation from 400 cps internal oscillator or external signal such as music. Input either high impedance, unbalanced, or 600 ohms balanced. Either input can be selected by front panel switch.

These other TIC Instruments complete the "package"

TYPE 2120 PICTURE SIGNAL GENERATOR: A single channel TV transmitter for use where a high percentage of picture modulation is required for checking inter-carrier buzz.

TYPE 1311 VIDEO DISTRIBUTION AMPLIFIER: A 5 channel amplifier recommended where multiple 75 ohm, unity gain outlets are desired.

TYPE 2200 SYNC. SIGNAL GENERATOR: Provides all necessary RTMA sync. blanking and drive signals plus linearity blanking, in either polarity, for monoscope or studio camera operation.

TYPE 2300 MONOSCOPE: A "must" for checking linearity, resolution and smear in TV receivers and video distribution facilities. Recommended for use with Type 2200 Sync-Generator.

Manufacturers of a Complete Line of TV Test Equipment

TIC Tel-Instrument Co. Inc.

728 GARDEN STREET • CARLSTADT, N. J.

choice of the proper controls, auxiliaries and accessories.

Anniversary Booklet. Insulation Manufacturers Corp., 565 W. Washington Blvd., Chicago 6, Ill., has published a 25th-anniversary booklet that presents easy-to-read information on company policies and operations. One section describes the nature of IMC and how it differs from other companies. This is followed by material on products, who supplies them, and their use. Graphic charts illustrate the company's organizational plan, sales growth and sales territories. Complete lists of directors, officers and employees are given. Copies are available on request.

Pyrometer Supplies. Minneapolis-Honeywell Regulator Co., Wayne and Windrim Aves., Philadelphia 44, Pa., illustrates and describes its pyrometer supplies in the newly revised buyers guide, 100-5. All general thermocouple assemblies and components are listed, as well as many special-purpose items. Prices and several pages on selection, care and application of thermocouples round out this 48-page catalog.

Production Engineering. Designers for Industry, Inc., 2915 Detroit Ave., Cleveland 13, Ohio. A 4-page bulletin gives a practical definition of how products are adapted to production-engineering techniques which include design analysis, production processing, process specification and work simplification. It includes a description of how these services are applied in the development and testing of prototype production models and special-purpose machinery.

Dual-Beam C-R Voltmeter. Allen B. DuMont Laboratories, Inc., 760 Bloomfield Ave., Clifton, N. J., has published a bulletin on the new type 322-A c-r oscillograph. The bulletin contains complete technical specifications, description, and photo-recordings made with the new instrument. The unit described is an improved, redesigned counterpart of the type 322 dual-beam c-r oscillograph with the added feature



Miniature and Sub-Miniature

SLIP RING ASSEMBLIES
BRUSH BLOCK ASSEMBLIES
COMMUTATORS

and other
Electro-Mechanical Components

PRECISION MADE
TO YOUR OWN SPECIFICATIONS

Precision molded products with exacting tolerances in precious and non-precious solid metals of all alloys. All types of Thermo-Plastic and Thermo-Setting materials.

Slip Ring Assemblies fabricated or one-piece precision molded to your specifications in Nylon, Kel-F, Mineral filled Mellamine, Phenolic, and other materials. Rings and leads spot welded or brazed together for positive electrical circuit.

Our Swiss methods and techniques are geared to meet exacting requirements. We invite your inquiries.

COLLECTRON CORPORATION

MUrray Hill 2-8473 • 216 East 45th Street • New York 17, N. Y.



SHOCK PROOF
VACUUM TUBE RETAINERS

These retainers are used to secure Vacuum Tubes and to resist side motion of Vacuum Tubes used in radio equipment which is subject to shock and vibrations. These retainers meet the requirement of all JAN specifications. The insulated portion is made of a melamine base Fibre Glass Phenol which provides 300 volts insulation to ground and withstands a temperature of 350 F. The insulated plate can readily be fastened or released by hand.

Available for envelope types T7, T6, MT8, T9, T12, ST12, T12ZDL, ST14, S14, ST16, T5½, T6½, MT-IC, ST19, T14, ST128CT-9.

Manufacturers of Electronic Components

JAMES IPPOLITO & CO., INC.
401 CONCORD AVENUE, BRONX 54, N. Y.

THIS
in your power screwdrivers
— SPEEDS WORK
— CUTS COSTS

THE MAGNA FINDER
(patent pending)

. . . picks up the screw . . . instantly positions it . . . so that with one-hand operation the bit automatically enters the slot and drives it home. Alnico magnet has ten times the "pull" and holds screw firmly without tilting or shifting.

Interchangeable with regular power Screwdriver finders. Available for all makes of power drivers and all sizes of screws. Thousands in use.

Magna Bit Holders*, Magna-Tip Hand Screw Drivers* and Magna-Tip Hex Drivers also employ the revolutionary, cost-saving Magna principle.

*U. S. Patent No. 2,550,775.



Write for folder 95E, information and prices:

MAGNA DRIVER CORP.
779 Washington St. Buffalo 3, N. Y.

SMALL PARTS can play a BIG PART in...

Lower Production Costs!

Multi-Swage METHOD

Leading manufacturers in the electronics, machinery, appliance and toy fields have been saving substantially by using precision Multi-Swage parts instead of those previously made by turning, drilling, stamping or forming.

HERE ARE ONLY A FEW TYPICAL TINY PARTS MADE BY BEAD CHAIN'S Economical, Dependable MULTI-SWAGE METHOD



LET BEAD CHAIN MAKE YOUR

Tiny Parts to your Specifications at far less cost!

The advanced manufacturing method developed and used exclusively by Bead Chain swages practically any type of small tubular part from flat stock into precision forms with positive, tight seams . . . and does it *Automatically*. If you can use high-volume production . . . we can deliver it at a much faster rate . . . and at far less cost! Scrap is eliminated! Deliveries to you are dependably prompt!

We can supply you with parts that are beaded, grooved, shouldered and made with almost any metal. Diameters up to 1/4", lengths to 1 1/2"

This catalog can save you a lot of production time and money! Write for it today!

GET PROOF-POSITIVE COST COMPARISONS!

Send us a blueprint or sample and quantity requirements. We will quickly show you the big economies we can deliver.

BEAD CHAIN

Original and World's Largest Producer of Bead Chain

THE BEAD CHAIN MFG. CO.
BRIDGEPORT 5, CONNECTICUT

Please send me your Catalog of Multi-Swage Parts

NAME_____

TITLE_____

COMPANY_____

ADDRESS_____

KEY NO

THE BEAD CHAIN MANUFACTURING CO., BRIDGEPORT 5, CONN.

of built-in independent voltage calibration for both beams, and which also incorporates the new tight-tolerance type 5AFP c-r tube.

Toroids & Coils. Burnell & Company, 45 Warburton Ave., Yonkers 2, N. Y., has available a 12-page catalog which gives valuable and complete information on toroids, high-quality coils and various audio filter networks. It includes complete descriptions, attenuation and Q curves that will prove valuable for equipment design engineers. Write for catalog 101-A.

Continuous Level Indicator. Fielden Instrument Division, Robertshaw-Fulton Controls Co., 2920 N. Fourth St., Philadelphia 33, Pa. The new Telstor electronic level indicator is illustrated and described in a graphic 8-page bulletin just released. The instrument discussed features simplified circuitry, accuracy to ±2 percent and continuous indication at remote or local stations.

Attenuator Bulletin. Waveline Inc., Caldwell, N. J., has available a new 4-page brochure illustrating the company's complete line of fixed and variable attenuators, covering the frequency range from 2,600 to 26,500 mc. These attenuators are calibrated to ±0.3 db. Complete specifications and prices are included for 21 types.

Recording Potentiometer. Weston Electrical Instrument Corp., 614 Frelinghuysen Ave., Newark 5, N. J., offers a new booklet that fully illustrates and describes all features of its simplified recording potentiometer. The instrument discussed is of completely new design with all parts interchangeable, with a universal slide wire that never needs changing, and which permits chart speeds to be changed on-the-line by a simple screwdriver adjustment.

Strain Gages. Baldwin-Lima-Hamilton Corp., Philadelphia 42, Pa., has announced a new price list of SR-4 strain gages, instruments and accessories. Specifications for 105 sizes and types of gages are tabulated. Considerations in selecting

. . TO A

SENIOR ENGINEER

Interested In a Challenge As Great As All Tomorrow

If . . .

you're the man we hope you are, you now have a good position. Perhaps you have not thought of a change but will consider the *right* opportunity.

You have from 5 to 25 years of experience in electronics or an allied field. You desire to do more than just carry assignments to satisfactory conclusions.

You would appreciate an opportunity and the "go ahead" to pioneer . . . with the assistance of your own staff of specialists . . . you now want to know what you personally can achieve through your creative engineering talent.

If you fill these qualifications, we have an opportunity that will fascinate you. You will work on the development of the most interesting electronics equipment with one of the foremost engineering teams in the world. You will work in the Boston Engineering Laboratory located only minutes away from Harvard, MIT and Northeastern Universities, entirely separated from the problems of production. The last word in equipment would be at your fingertips. No richer benefits are offered anywhere . . . regardless of the standards by which you measure.

. . . Are YOU the man we are seeking? If so, phone us or send in a resume to . . .

Don Bradley, Personnel Supervisor

SYLVANIA
ELECTRIC PRODUCTS INC.
Boston Engineering Laboratory
70 Forsyth Street, Boston, Mass.
Phone: Kenmore 6-8900

ELECTRONIC GLASS WORKING EQUIPMENT

. . . For Radio, Television Tubes, Incandescent Lamps, Glass Lathes for Television Tubes



TURNTABLES ▶
We make over 100 types of turntables; tilting models and positioners.

More Eisler Stem and Sealing Machines are in use in the Electronics Industry than all other makes combined. There is a reason: they are simple, well-built, compact, last long, have good production, and are constantly being improved to give more production.



We make Transformers, Spot and Wire Butt Welders, Wire Cutting Machines and 500 other items, indispensable in your production. Eisler Engineers are constantly developing New Equipment. If you prefer your own designs, let us build them for you. Write to Charles Eisler who has served The Industry over 33 years.

Dr. Charles Eisler, *President*

EISLER ENGINEERING CO., INC.
751 South 13th St., Newark 3, N. J.
Near Avon Avenue

NEW MULTIMETER KIT $26.50
SIGNAL TRACER KIT $23.50
NEW SCOPE KIT $59.50
CONDENSER CHECKER KIT $19.50
VACUUM TUBE VOLTMETER KIT $24.50
TUBE CHECKER KIT $29.50
SIGNAL GEN. KIT $19.50
GRID DIP METER KIT $19.50
HEATH COMPANY
BENTON HARBOR 14, MICHIGAN

Heathkit
TEST EQUIPMENT

BUILD YOUR OWN — INCREASE KNOWLEDGE — SAVE MONEY — BUY DIRECT FROM MANUFACTURER . . . Top quality instruments in kit form featuring latest design and circuit developments. Completely detailed step-by-step construction manual — clear pictorials — complete schematics. All sheet metal work punched, formed and finished. Low kit prices include tubes, chassis, cabinet and all necessary constructional components.

Kits for the school — service shop — industrial laboratory — hobbyist, etc.

Write for free catalog for further information.

Now Sangamo presents

Telechief

THE PREMIUM MOLDED TUBULAR PAPER CAPACITOR

that will meet your most exacting demands

the only molded paper tubular that will *consistently* pass the moisture resistance requirements of MIL-C-91A (proposed)

Here is a paper tubular capacitor that combines remarkable capacitance stability during heat cycling and life with phenomenal resistance to moisture, even under extended exposure to high humidity and temperature.

The Telechief is brand new, inside and out. It combines a new solid dielectric impregnant, developed especially for this application, with Sangamo's famous Humiditite molding material.

A companion to the famous Sangamo Redskin, the new Telechief is a premium quality molded tubular, especially designed to meet rigid specifications so tough that no previously existing paper tubular could approach them.

These molded capacitors, when tested as prescribed by specification MIL-C-91A (proposed), have a final insulation resistance value which far exceeds specifications, and is 10 to 15 times greater than those molded in any other material.

Full information is given in our Engineering Data Sheet on Telechief. Send for your copy today.

SCS3-14

Those who know...choose Sangamo

SANGAMO ELECTRIC CO. MARION, ILLINOIS

the gages are given more fully than in the previous edition. Cements and waterproofing equipment are also included.

Vacuum-Tube Insulators. American Lava Corp., Chattanooga 5, Tenn. Bulletin No. 537 deals with internal insulators for electronic tubes. It gives the mechanical and electrical properties required in vacuum-tube insulators. Lava and synthetic ceramics are then described in relation to these requirements, as well as to necessary precision, design and quantity. The back cover is a property chart for these materials.

Portable Potentiometer. Minneapolis-Honeywell Regulator Co., Wayne and Windrim Aves., Philadelphia 44, Pa. Bulletin 1210 covers the Brown portable potentiometers, with direct reading temperature, millivolt and extended range scales. Wiring diagrams, instructions, specifications and special features are also included.

Strain Gage. Statham Laboratories, Inc., 12401 W. Olympic Blvd., Los Angeles 64, Calif. Bulletin No. 1.5 fully illustrates and describes the model SG-1 strain gage that incorporates the advantage of repetitive use and speed of application. Technical specifications included list strain ranges, gage lengths, gage factors, nominal resistance, input current, maximum input voltage and current, accuracy and linearity, resolution, electrical connection information, overall size and weight.

Tube Shield Evaluation. International Electronic Research Corp., 175 West Magnolia Blvd., Burbank, Calif. Technical Report 53-174, initiated by the Electronic Components Laboratory, Wright-Patterson AFB, Ohio, is an evaluation of shields for cooling miniature electron tube types. The relative cooling effected by JAN type nickel plated shields for JAN-S-28A, black finish JAN shields with window cutouts, and by tubes without shields is compared with a new Sample-X type shield. It

For Dependable Electronic Wiring Leading Manufacturers Choose UNILECTRIC Wiring Systems

Year after year . . . for over ten years . . . UNILECTRIC has produced millions of wiring systems for over 150 leading manufacturers of electric and electronic products. If you still fabricate your own electronic wiring it will pay you to investigate UNILECTRIC.

There is Only ONE Standard of Quality at UNILECTRIC

This intricate wiring harness for a jet auto pilot must meet the most rigid specifications. A pilot's life and perhaps a major battle depend on it.



The same workmanship . . . the same standards of quality protect your product wiring and your product's reputation for dependability.

To assure utmost dependability plus cost saving engineering assistance, low-cost production, and "on-schedule delivery", investigate UNILECTRIC today.

UNILECTRIC QUALITY Protects Your Products

Investigate UNILECTRIC Today!

UNILECTRIC WIRING SYSTEMS

Manufactured by

UNITED MANUFACTURING & SERVICE CO.

4[illegible] South 4th Street • Milwaukee 4, Wisconsin

the COMPLETELY NEW



HYCOR VARIABLE ATTENUATOR

. . . a revolutionary design in attenuators!

- PROOF against SHOCK — MOISTURE — TEMPERATURE
- Withstands ambient temperatures of —40°C. to +100°C.; 95% humidity.
- Resistive elements are accurate, noninductive, wire-wound and hermetically sealed in a special tough plastic compound.
- Greater power dissipation.
- Switch surface flat and smooth . . . easy to clean, BRUSHES CANNOT TRIP, exceptionally long life.
- QUIET . . . extremely low switch noise level . . . ideal audio mixer controls.
- "Lubricated for life" bearings.
- Stock types available with "LADDER," "T," "H," "L" and potentiometer configurations up to 32 steps.

Send for Bulletin A-2 for specifications and prices.

Representatives:
JACK BEEBE
5707 W. Lake Street, Chicago, Illinois
BURLINGAME ASSOCIATES
103 Lafayette Street, New York City

HYCOR SALES COMPANY of California
11423 VANOWEN STREET
NORTH HOLLYWOOD, CALIF.
SUnset 3-3860

Thor
leading users of
STEATITE
bobbins
SPECIFY
Thor
Steatite Bobbins are only one of the scores of standard and custom-made steatite products we manufacture to Jan-I-10 or Commercial Specifications.
Write for Details & Catalogs.
Thor Ceramics, Inc.
725 Belleville Avenue, Bloomfield, New Jersey

DANIEL KONDAKJIAN TUNGSTEN LEADS—TUBES BASES



TUNGSTEN LEAD-IN WIRES

Quality leads make quality tubes . . . and for over 30 years The Engineering Co., under personal supervision of Daniel Kondakjian, has been making quality precision lead-in wires for vacuum tight seals, for lamps, radio tubes, electronic devices and other special applications. Precision machines, capable of holding these fine wires so that they are accurately located and carefully spaced, assure high operating efficiency and uniformity in the finished product.

Parts are made to customer's blue prints or specifications. Specializing in leads of tungsten, moly, nickel, nickel clad copper and copper alloys. Send us your blue prints or specifications. Kovar leads and stampings.



ELECTRON TUBE BASES

The quality and performance of electron tubes depend upon quality bases and caps. We make all types, including an all-glazed ceramic base. Our hydrogen-tube bases go up to 6.25 diameter. Precision equipment and careful inspection in our plant assure the finest quality in caps and bases. Our engineers will be happy to serve you in any problem.

THE ENGINEERING CO. (DKE)
27 WRIGHT STREET, NEWARK 5, NEW JERSEY

was found that the design of the present military type shields does not adequately take heat dissipation from electron tubes into consideration. The new Sample-X type shield will provide better cooling and greater reliability than any other shields or mounting procedures for miniature tubes presently being used in military electronic equipments.

Paste Solder and Brazing Alloys. Fusion Engineering, 4504 Superior Ave., Cleveland 3, Ohio, announces a 4-page illustrated bulletin describing its line of flux-containing electrical, electronic and mechanical bond paste solder and brazing alloys, and covering the new two-part semiautomatic soldering technique. A chart is used to illustrate the melting ranges of each solder and brazing alloy type and is color-coded to indicate whether the paste alloy is designed for electrical or mechanical connection. Line drawings of a variety of parts show the two-part soldering method which involves preapplication of paste to the part with separate heat application. This semiautomatic technique, possible only because the flux is contained in the paste solder alloy, eliminates much of the hand operation formerly required, greatly reducing labor costs. An automatic paste applicator is also shown with a description of the company's engineering service available to mechanize production soldering operations.

Printed Circuit Controls. Chicago Telephone Supply Corp., Elkhart, Ind. A new line of variable resistors designed primarily for mass production radio or tv printed circuit applications is illustrated and completely described in data sheet 166 now available. Diagrams are included showing how ample spacing between printed circuit terminal openings provides adequate clearance for circuit paths for the miniature type U70 series, type U45 series, type GC-U45 series with spst switch and type WF-U45 series with dpst switch. Complete technical data are given, including resistance range, standard tapers,

JUST OUT!

INDEX

Volume 28 in The Massachusetts Institute of Technology

RADIATION LABORATORY SERIES

THE M. I. T. RADIATION LABORATORY SERIES has been acknowledged as a "monumental" work in its field; it is now made complete with the addition of an extensive and carefully prepared Index. Thousands of entries refer you to facts, research findings, and conclusions—a mine of raw material waiting to be used by today's engineers and technicians. The Index has been compiled with the needs of the practicing engineer in mind. It is more than a compilation of the 27 separate indexes; it's a comprehensive guide designed to give you the information you need quickly and correctly. Compiled by Keith Henney, Editorial Director, ELECTRONICS, NUCLEONICS. 160 pp., over 10,000 entries, available separately at $4.50.

Index completes and unifies this great Series of 28 volumes

1.	Radar System Engr.	3.50
2.	Radar Aids to Navigation	6.00
3.	Radar Beacons	6.50
4.	Loran	6.00
5.	Pulse Generators	9.00
6.	Microwave Magnetrons	10.00
7.	Klystrons & Microwave Triodes	8.00
8.	Prin. of Microwave Circuits	6.50
9.	Microwave Trans. Circuits	8.50
10.	Waveguide Hdbk	8.00
11.	Technique of Microwave Measurements	10.00
12.	Microwave Antenna Theory and Design	9.00
13.	Propagation of Short Radio Waves	10.00
14.	Microwave Duplexers	6.50
15.	Crystal Rectifiers	6.50
16.	Microwave Mixers	5.50
17.	Components Hdbk	8.00
18.	Vacuum Tube Amplifiers	10.00
19.	Waveforms	10.00
20.	Electronic Time Measurements	7.50
21.	Electronic Instruments	10.00
22.	Cathode Ray Tube Displays	10.00
23.	Microwave Receivers	3.50
24.	Threshold Signals	6.00
25.	Theory of Servomechanisms	5.50
26.	Radar Scanners and Radomes	7.00
27.	Computing Mechanisms and Linkages	5.50
28.	Index	4.50

SPECIAL PRICE

Save $22 on the total price of $217 for 28 volumes. Library price, when complete set is ordered, is only $195, payable in installments if you wish.

10-DAY FREE EXAMINATION

McGraw-Hill Book Co., 330 W. 42 St., NYC 36
Send me books circled below for 10 days' examination on approval. In 10 days I will remit for book(s) I keep, plus few cents delivery, and return unwanted book(s) postpaid. (We pay delivery if you remit with this coupon; same return privilege.)

1	2	3	4	5	6	7
8	9	10	11	12	13	14
15	16	17	18	19	20	21
22	23	24	25	26	27	28

☐ Send me the RADIATION LABORATORY SERIES, 28 Volumes, for 10 days' examination on approval. In 10 days I will send my first payment of $45, plus delivery, then $30 a month until the special price of $195 is paid. (We pay $2.94 delivery charge if you remit first payment with coupon; same return privilege.)

PRINT

Name .....

Address .....

City ..... Zone.... State.....

Company .....

Position L-11

Offer applies to U. S. only

U. G. CONNECTORS

Our Coaxial Cable Connectors Meet All Government Specifications

★ ALL ORDERS DELIVERED PROMPTLY ★

Manufacturers of Highest Quality Connectors

•

ALLIED INDUSTRIES, INC.

1023 S. 21st STREET
LOUISVILLE 10, KY.

Phone Arlington 4640

Dependable DC POWER

RAPID ELECTRIC SELENIUM RECTIFIERS



FOR GENERAL POWER NEEDS
RAPID Floor Models

- High Efficiency
- Single-knob Controls
- Built in Protective Circuits
- Easy to Install
- No Maintenance

Rapid Electric Co. makes Selenium Rectifiers in sizes from 10 to 10,000 amps. DC output at desired voltages.



FOR LABORATORY POWER
RAPID Bench Model

- Completely Self-Contained
- Portable
- Continuously Variable Controls
- Full Metering
- No Maintenance

ENGINEERING SERVICE

Our engineering department is available for consultation on any application of Direct Current Power Supplies. Avail yourself of this professional service without obligation.



THE NAMEPLATE THAT MEANS *"More Power to You!"*

RAPID ELECTRIC COMPANY

2895 Middletown Road • New York 61, N. Y. • Phone: Tuimadge 8-2200

TRANSFORMERS



HERMETICALLY SEALED TO MIL-T-27 SPECIFICATIONS

NYT offers a wide variety of transformer types to meet military and civilian specifications, designed and manufactured by specialists in transformer development.

Latest NYT service for customers is a complete test laboratory equipped and approved for on-the-spot MIL-T-27 testing and faster approvals.

NEW YORK TRANSFORMER CO., INC.
ALPHA, NEW JERSEY

angle of rotation, wattage, switches available, shaft diameter, shaft length, screwdriver slot dimensions, knob flat dimensions, mounting bushing dimensions and knurled and slotted shafts information.

Vibration Isolators. The Barry Corp., 807 Pleasant St., Watertown 72, Mass. Product bulletin 534 provides a complete technical description of vibration isolators of the knitted-wire type. Performance data are given without alteration from measurements made under stated JAN conditions. Organization and contents of the bulletin are explicitly designed to meet the full needs of application engineers concerned with vibration isolation of airborne equipment in military service. The information contained in the bulletin includes: transmissibility in all directions of motion; isolation curves for acceleration and displacements; the effect of load variation; the effect of extreme high and low temperatures; vibration isolation performance after severe shock; selection of isolators for unsymmetrical loads; detailed dimensions and construction data for unit isolators and complete bases; and complete load ratings.

Wire Forming and Intricate Stampings. PIX Mfg. Co., Inc., 22 Bedford St., Newark, N. J. A 16-page, 2-color illustrated catalog demonstrates the company's versatility in the production of wire formed parts and intricate stampings. It shows how PIX specializes in production for all industries, and can turn out delicate, intricate wire formings from 0.002-in. diameter to 0.156-in. diameter. The parts discussed are then used by the manufacturers for whom they are made as components for many complete products.

Drafting Machines. Charles Bruning Co. Inc., 4700 Montrose Ave., Chicago 41, Ill. Unusually realistic illustrations feature a new 2-color drafting machine booklet that presents a complete mechanical description of the various drafting machine models including gravity compensated, track type, civil engineering and detail machines. En-

STOP RF LEAKAGE ON THE DRAWING BOARD

. . . WHEN YOU DESIGN METEX ELECTRONIC WEATHERSTRIPPING INTO YOUR EQUIPMENT YOU GET ITS POSITIVE SHIELDING EFFECTIVENESS — AT MAXIMUM OVERALL ECONOMY

Plan *now* to take full advantage of *Metex Electronic Weatherstripping's* unusual effectiveness in shielding all types of electronic equipment. Because it is made of *knitted* wire mesh, *Metex Electronic Weatherstripping* is both conductive and resilient. It assures positive metal-to-metal contact between all mating surfaces. And being resilient it accommodates itself positively to surface inequalities.

In reality, *Metex Electronic Weatherstripping* can do more for you than just shield RF leakage. It can cut the cost of machining mating surfaces to close tolerances. It can eliminate the need for extra fasteners and many other costly means of making joints RF tight.

Applications in which *Metex Electronic Weatherstripping* has already proved its effectiveness include pulse modulator shields, wave-guide choke-flange gaskets, local oscillators on TV sets, dielectric heaters, etc.

For detailed information on METEX ELECTRONIC PRODUCTS, write for FREE copy of "Metex Electronic Weatherstrips" or outline your SPECIFIC shielding problem — it will receive our immediate attention.

METAL TEXTILE CORPORATION

ROSELLE, NEW JERSEY

encapsulated

PULSE TRANSFORMERS

wound to your requirements

SMALL IN SIZE

Weight—⅓ oz.

TYPE TE

TYPE TP



Write for Bulletin 166 E for additional information and specifications.

SMALL IN PRICE

As low as $5.00 each in quantity lots. One to three—$7.50 each.

TECHNITROL

ENGINEERING COMPANY

2751 N. 4th St., Philadelphia 33, Pa.

BECO DEKADIAL for accurate resistance, capacitance, inductance. Readings to four significant figures.

RANGE SELECTOR: seven positions

CIRCUIT SELECTOR: six positions

Universal BINDING POSTS connect to all bridge arms

DETECTOR SWITCH

GENERATOR SWITCH

DISSIPATION FACTOR and "Q" DIAL

7.5 μa-0-7.5 μa GALVANOMETER

BECO

IMPEDANCE BRIDGE

Wide Range

Resistance: 1 milliohm to 11 megohms
Capacitance: 1 mmf to 1100 mfs.
Impedance: 1 mh to 1100 henrys

Exceptional Accuracy

Resistance: ±0.1%
Capacitance: ±0.25%
Inductance: ±1.0%

◆

SHOWN MODEL 250-C1 $340

9"x11"x11" over-all. Convenient operation from battery, or from AC power lines with Beco accessory amplifier.

◆

Write to factory for literature and analysis of your needs.

BROWN ELECTRO-MEASUREMENT CORP.

4312 S. E. Stark St.
PORTLAND 15, OREGON

HOW MUCH ARE
JAMMED SWITCHBOARDS
COSTING YOU EACH YEAR?

The answer will surprise you!

The answer — they could cost you enough to *pay* for a RyCom CFD-B Packaged Carrier Telephone System in a year! These units immediately add *four* more voice channels to each of your present lines... and will quickly pay for themselves by *slashing* your long distance telephone costs!

Here's how the **RyCom CFD-B** *Cuts Costs!*



- **NO EXPENSIVE TEST EQUIPMENT NEEDED** . . . Built-in measuring panel provides fast over-all system line-ups, even by non-technical personnel. No more testing trips up and down the line.
- **EQUALIZATION OF NON-CONFORMING LINES** ... with built-in slope control.
- **EASIER INSPECTION AND MAINTENANCE** . . . with RyCom separate panel construction.
- **EASIER INSTALLATION IN LESS TIME** . . . The CFD-B is packaged in a single rack for space and labor savings. Shipped complete in one package.

Immediate Deliveries Now Being Made!

Order now for early delivery. RyCom engineers will be glad to talk over your specific installation needs. Write or phone today for complete details, specifications, prices!

Rely on **RyCom** *for Highest Quality at Minimum Cost*

RAILWAY COMMUNICATIONS, INC.
RyCom

Raytown, Missouri, U.S.A.
Phone: FLeming 2100

Export Office: 13 East 40th St.
New York 16, N. Y.

titled "The Finest In Drafting Machines", the new booklet offer detailed illustrations which have been so carefully prepared that even the vernier degree figures, as well as similarly small but highly important designed details, are perfectly legible. The booklet also pictures and describes the latest types of scales for all uses.

High Resolution Spectrometer. Varian Associates, 532 Hansen Way, Palo Alto, Calif. A new data bulletin illustrates and describes the model V-4300 high-resolution nuclear-magnetic-resonance spectrometer. Following an introduction characterizing the instrument as a basic lab research unit for rapid nondestructive analyses of chemical bonding situations leading to identification and measurement of components in a mixture and assignment of structural formulas. the publication includes further specific data on the spectrometer and suitable magnet system. Data are included on basic operating characteristics; general arrangement of subunits encompassing the probe, the r-f transmitter and receiver, sweep device, power supply and oscillograph.

Solenoid Valve. Valcor Engineering Corp., Carnegie Ave., Kenilworth, N. J. A 12-page illustrated catalog discusses the company's solenoid valve with the floating shear seal. Included are a history of the unit along with information on its absolute minimum pressure drop, lapping action and back pressure, dependability under adverse conditions, and design and construction data. Also given is a chart showing pressure drop vs fluid flow.

Soldering Fluxes. Mico Instrument Co., 80 Trowbridge St., Cambridge, Mass., has available a 4-page folder dealing with its Solderux fluxes, a group of very effective soft-soldering agents based upon sound chemical principles not used previously in soldering practice. The fluxes described are highly active at soldering temperatures, being comparable to the

AT LAST!

FUNGUS-PROOF NYLON LACING CORD and FLAT BRAIDED TAPE

No more problems from mold and micro-organisms! For Heminway & Bartlett's Nylon Lacing Cords and Flat Braided Tapes are completely fungus-proof. In addition, they have high abrasion-resistance and low moisture absorption. Their finish has the desirable malleability of wax and is non-toxic to humans. Samples gladly sent on request.

Meet Army, Navy and Civilian "Specs"

EST. 1888

HEMINWAY & BARTLETT

The Heminway & Bartlett Mfg. Co., 500 Fifth Ave., N.Y. 36, N.Y.
Sales Offices: Chicago, Phila., Boston, St. Louis, Cincinnati, San Francisco, Los Angeles, Charlotte, N. C., Gloversville, N.Y.
Foreign Agent: Turner, Halsey Co., Inc., 40 Worth Street, New York, N.Y. Cable Address: THECOTEX

Burlington

RUGGEDIZED
HERMETICALLY SEALED
INSTRUMENTS



LABORATORY APPROVED
Under MILITARY SPECIFICATION MIL-M-10304

- Will withstand Hi-Impact Shock Tests, extensive vibration and tumbling requirements, extreme thermal shock, humidity and temperature tests.
- Glass to metal type seal with molded vulcanized rubber terminal connections capable of carrying 30 amps for self-contained units.
- Magnetically shielded.
- Black satin anodized aluminum bezel.
- D'Arsonval permanent magnet type movement—for all D. C. Ranges.
- Available in 2-½" and 3-½" round case types.
- Guaranteed one year against defective workmanship and materials.

BURLINGTON INSTRUMENTS ALSO AVAILABLE IN HERMETICALLY SEALED OR BAKELITE CASES IN 1-½" THROUGH 4-½" SIZES.

BURLINGTON INSTRUMENT COMPANY
DEPT. F-113, BURLINGTON, IOWA

Principles of TRANSISTOR CIRCUITS

Edited by
Richard F. Shea
General Electric Co.

This is the first *full-length book* in the field. Written by nine G.E. experts, this pioneer book brings you basic theory *and* details on applicable techniques. It offers an integrated treatment of the most useful information scattered through the literature, plus new material published for the first time.

The treatment is general, built around generalized equivalent circuits which can be used conveniently to represent the great majority of transistors. Each chapter is self-explanatory, well documented and illustrated. Each section presents and analyses equivalent circuits, analyses the mathematical relationships, and develops applicable circuits. Resemblances to vacuum-tube circuits are pointed out, and the authors use current network theory modified to fit transistor circuits. The book treats both point-contact and junction transistors, and the analysis is applicable to both n-p-n and p-n-p units. PRINCIPLES OF TRANSISTOR CRCUITS gives you a solid background which will enable you to utilize new forms of transistors which appear as they are developed.

1953 535 pages Illus. $11.00

Ultra High Frequency Propagation

By H. R. REED and C. M. RUSSELL,
U. S. Naval Air Test Center
Patuxent River, Md.

This book brings you new data on the latest developments and experiments and provides a full understanding of such critical factors as: reflection, diffraction, turbulence, directivity and divergence. It shows the way to a closer approach to ideal installation practice and points up maintenance problems.

1953 562 pages 286 Illus. $9.50

Send today for your on-approval copies

JOHN WILEY & SONS, Inc.
440 Fourth Ave. New York 16, N. Y.

Eclipse-Pioneer

CORROSION-RESISTANT AUTOSYN* SYNCHROS

(AY-200 SERIES)

TYPICAL ELECTRICAL CHARACTERISTICS

	Type Number	Input Voltage Nominal Excitation	Input Current Milliamperes	Input Power Watts	Input Impedance Ohms	Stator Output Voltages Line to Line	Rotor Resistance (DC) Ohms	Stator Resistance (DC) Ohms	Maximum Error Spread Minutes
Transmitters	AY2019-25	26V, 400~, 1 ph.	133	0.8	40+j230	11.8	12	8.8	15
Control Transformers	AY2019-28	From Trans. Autosyn	Dependent Upon Circuit Design				40	10.2	20
Differentials	AY2219-25	From Trans. Autosyn	Dependent Upon Circuit Design				14	10.2	20
Receivers	AY2218-28	26V, 400~, 1 ph.	70	0.4	108+j440	11.8	80	11.4	24

PYGMY AUTOSYN SYNCHROS

(AY-500 SERIES)



TYPICAL ELECTRICAL CHARACTERISTICS

	Type Number	Input Voltage Nominal Excitation	Input Current Milliamperes	Input Power Watts	Input Impedance Ohms	Stator Output Voltages Line to Line	Rotor Resistance (DC) Ohms	Stator Resistance (DC) Ohms	Maximum Error Spread Minutes
Transmitters	AY503-4	26V, 400~, 1 ph.	220	2.5	45+j100	11.8	23.0	11.0	24
Receivers	AY503-2	26V, 400~, 1 ph.	220	2.5	45+j100	11.8	23.0	11.0	75
Control Transformers	AY503-3	From Trans. Autosyn	Dependent Upon Circuit Design				176.0	45.0	24
	AY500-5	From Trans. Autosyn	Dependent Upon Circuit Design				880.0	198.0	30
Differentials	AY533-3	From Trans. Autosyn	Dependent Upon Circuit Design				93.0	46.0	30
Receivers	AY523-3	26V, 400~, 1 ph.	55	0.8	290+j490	11.8	210.0	42.0	30
	AY543-5	26V, 400~, 1 ph.	11	0.12	900+j2200	11.8	880.0	165.0	30

Available for all applications is the new, *corrosion-resistant* AY-200 Series of Eclipse-Pioneer Autosyn Synchros (1.431″ dia. x 1.631″ lg.). Where space and weight are prime considerations, Eclipse-Pioneer offers the AY-500 Pygmy Autosyn Synchro Series (0.937″ dia. x 1.278″ lg.) with corrosion-resistant models available in sample quantities. Whatever your synchro requirements may be, our long experience, modern facilities and advanced production techniques can work to your advantage. For full details, write Department C.

*Registered trade-mark Bendix Aviation Corporation

THE NAME Bendix AVIATION CORPORATION MEANS MORE

ECLIPSE-PIONEER, Division of
TETERBORO, N. J.

Export Sales: Bendix International Division, 205 E. 42nd St., New York 17, N. Y.

highly corrosive zinc-chloride compounds in fluxing ability, and inert and quite noncorrosive at lower temperatures. Solderux paste and Solderux cream have had extensive use in industry, especially for soldering delicate parts and small wires. There are no zinc or other chlorides used in the Solderux described. A price list is included.

Meter-Positioner Bulletin. Texas Instruments Inc., 6000 Lemmon Ave., Dallas 9, Texas, has released a 2-page bulletin describing its instrument-size magnetic fluid clutch metering-positioning movement. The bulletin is complete with detailed performance specifications and curves and describes in detail both the movement and the component magnetic fluid clutches. The metering-positioning movement already is in operation in airborne military electronic systems. Ask for bulletin No. DL-C 311.

Pantograph Machine. Mico Instrument Co., 80 Trowbridge St., Cambridge 38, Mass., has published a 4-page folder illustrating and describing its engraver, a portable pantograph machine that can be used to produce models, molds, hobs, dies, templates and small parts requiring accuracy in three dimensions as well as the routine lettering tasks usually assigned to two-dimensional engravers. The addition of accessories make it ideally suited to the engraving of nameplates, dials, scales, panels and cabinets. One page of the folder is devoted to general information on the company's products.

High-Vacuum Applications. Central Scientific Co., 1700 Irving Park Road, Chicago 13, Ill. Completely revised and containing a great deal of additional information, charts and data, the new 60-page bulletin 10F on high-vacuum applications is now available. Included are many pages of factual data on such subjects as planning the high-vacuum system, connections and speed of evacuations, selection of high-vacuum pumping systems, low pressure technique, as well as illustrations and descriptions of various types of high-


Open type for surface mounting
Octal base type with snap-on dust cover
Sealed with header for solder connections
Unit with modified AN type connector

a rugged little space saver...

MIDGET TELEPHONE TYPE RELAYS SERIES (80)—OPEN TYPE FOR SURFACE MOUNTING, OR IN HERMETICALLY SEALED CONTAINERS.



This vibration and shock-proof Midget Type Relay is the answer to numerous applications where unfailing operation is necessary. In fact, it is built to meet rigid Army and Navy specifications. This "rugged little space saver" is a compact, multiple contact relay which has been developed over years of specialized engineering in the field by Signal Engineering and Mfg. Co., manufacturers of a comprehensive line of relays and signals of various designs and sizes.

Write for Bulletin MTR-6

Engineering Representatives in Principal Cities.

Wheelock RELAYS SIGNAL ENGINEERING & MFG CO

GLASS TURRET LATHE* saves TIME...LABOR

MODEL 2326

Great savings in time, labor and shrinkage or waste are obtained with Model 2326, a patented machine* produced by Kahle.

FEATURES:

- successive steps in glass work
- addition of successive pieces
- combination of pieces and operations with no cooling between processes; with no need for re-chucking

(The latter feature...re-chucking...insures absolue concentricity about the same axis.)

SPECIFICATIONS

- Chucks may be loaded at will
- Only chuck in operation rotates
- Entire turret moves back and forth
- Burner carriage moves back and forth
- Burners controlled by foot operated economizer
- Rotating speeds adjustable
- Air admission possible through operating chucks

The Glass Turret Lathe is one more in a succession of labor-saving, production speeders that Kahle offers to the glass and electronics industries. If interested in transferring your lathe work to special high or low production equipment requiring ordinary unskilled operators, consult Kahle. For a solution to any of your production problems where custom machines may provide the answer, write Kahle, the largest manufacturer of this equipment.

Kahle ENGINEERING COMPANY

for maximum economy... 5KW VACUUM TUBE BOMBARDER OR INDUCTION HEATING UNIT



$1535.

Simple...Easy to Operate...Economical Standardization of Unit Makes This New Low Price Possible.

Maximum economies can be obtained only by use of *correct frequency* and *power combinations* when applying the techniques of induction heating to manufacturing processes.

It is significant that only Scientific Electric in the present market, can offer you a selection of frequencies depending on power required, in wide power range. 2-3½-5-6-7½-10-12½-15-18-25-40-60 KW (all units above 60 KW are considered custom built). This means that electronic heating equipment produced by Scientific Electric is tailored to your needs... fitted perfectly to the task entrusted to it, enabling you to keep your initial investment in equipment to a minimum while affording you all the proven advantages of electronic heating.

Write now for complete information or send samples of work to be processed. Specify time cycle for your particular job. We will quote on proper size unit for your requirements.

DESIGNERS AND MANUFACTURERS OF HIGH FREQUENCY AND HIGH VOLTAGE EQUIPMENT SINCE 1921

Scientific Electric

105-119 MONROE ST SCIENTIFIC ELECTRIC GARFIELD, N. J.

precision electronic instruments by DeJUR

1½" SQUARE
WATERTIGHT
Panel Meter

ACTUAL SIZE

- From 1 to 100,000—DeJUR's 1½" meter sets the world's standard for quality, performance
- Available with 2 terminal designs
  1. Solder terminal
  2. 4-40 screw terminal
- Multi-color or luminescent scales and pointers
- Proven external pivot D'Arsonval movement
- From prototype to production on short notice

For further information write DeJUR-Amsco Corporation, Dept. EM-11, 45-01 Northern Boulevard, Long Island City 1, New York

YOU'RE SURE WITH DeJUR
POTENTIOMETERS · CONNECTORS · METERS
DeJUR AMSCO CORPORATION
45 01 NORTHERN BLVD., L.I.C. 1, N. Y.

vacuum pumps, oil-diffusion pumps, vacuum gages and vacuum accessories.

Point-Contact Transistors. Texas Instruments Inc., 6000 Lemmon Ave., Dallas 9, Texas. A new 4-page bulletin covers two types of hermetically sealed point-contact transistors. Of special interest to electronic design engineers is the 2-page section on the theory and application of point-contact transistors—complete with formulas, equivalent circuits and characteristic curves. The other two pages describe type 102 and 103 point-contact transistors, which differ principally in cutoff time. Mechanical specifications and complete electrical data are given, as well as hints on installation and operation. Ask for bulletin DL-S 312.

Subfractional H-P Motors. Air Marine Motors Inc., 3939 Merrick Rd., Seaford, L. I., N. Y., has published a bulletin covering the end applications and selection of subfractional h-p motors. Part I gives application data—specific applications, general information and outstanding characteristics of basic types. Part II deals with motor selection data—information that should be supplied to the design engineers to enable them better to evolve the best possible results pertaining to rotary-equipment problems.

Parts and Equipment Catalog. Allied Radio Corp., 100 N. Western Ave., Chicago 80, Ill. The 1954 general catalog contains 268 pages listing over 20,000 items. Special emphasis has been placed on equipment for industrial maintenance, research and production requirements. There are detailed listings of standard and special-purpose electronic tubes, test instruments, voltage stabilizers, transformers, resistors, capacitors, printed-circuit components, transistors, rheostats, relays, switches, rectifiers, fuses, tools, wire, cable, photoelectric components, counters, program clocks, batteries, sockets, generators, power supplies and a wide variety of other electronic equipment and components. A complete



PIX

Dependable • Precision Wire Forming and Stamping Specialists

Precision Parts to meet your Production and Engineering needs. From .002" dia. to .125" dia. Radio tube parts—Stampings—Drawings. Modern facilities, high-production equipment.

Send sketch or print for quotation and request complete new catalog.

PIX

MANUFACTURING CO., Inc.

24A Bedford Street
Newark 3, New Jersey

PRECISION • STABILITY • LOW NOISE LEVEL

S.S.WHITE TYPE 65X MOLDED RESISTORS

Rating—1 Watt.
Temperature Coefficient—From approx. + 0.1%/°F for 5000 ohm resistors to approx. − 0.2%/°F for 10 megohm resistors.
Voltage Coefficient—Less than 0.02%/Volt.
Upper Temperature Limit—170°F for continuous operation.
Standard Range—1000 ohms to 9 megohms. For general commercial service.
Noise Level—A low noise level is inherent in all 65X resistors. Where noiseless operation is essential, we are equipped to test and guarantee standard range resistors with "less noise than corresponds to a resistance change of 1 part in 1,000,000, for the complete audio frequency range."

EXTREME HIGH VALUE RANGE
Up to 10,000,000 megohms for specialized scientific and industrial service.

Send for Bulletin 4906. It gives full details on S.S.White Molded Resistors. Write for a copy.

THE S.S.White INDUSTRIAL DIVISION
DENTAL MFG. CO.
Dept. R, 10 East 40th St.
NEW YORK 16, N. Y.

Western District Office • Times Building, Long Beach, California

---

a midget in size....

a **GIANT** *in* **performance!**

KEYSTONE piezo crystals

Yes, they're tiny — but they carry a GIANT RESPONSIBILITY for critical frequency control in military and commercial equipment — where utmost accuracy and utmost stability are a "must".

Depend on KEYSTONE for the best in quartz crystals, plated or pressure mounted, to meet YOUR specific job!

KEYSTONE ELECTRONICS COMPANY
114 Manhattan Street Stamford, Connecticut

STANCOR
ULTRA-MINIATURE TRANSFORMERS for TRANSISTOR CIRCUITS . . .





If you are having space problems with your transistor circuitry, consider these Stancor transformers as a means of solving your difficulties.

In addition to the units shown below, special transistor transformers, designed and built to your specifications by Stancor engineers, can be supplied in quantities of five or more.

These five Stancor ultra-miniature transformers, designed especially for transistor applications, are available through your local Stancor distributor. The smallest weighs 0.07 ounce and measures ¼" x ⅜" x ⅜". The largest weighs only 0.10 ounce and measures ⅜" x ⅜" x ⅜".

Part No.	Application	Pri. Imp.	Sec. Imp.	Pri. DC Res.	Sec. DC Res.
UM-110	Interstage	20,000	1,000	1675	285
UM-111	Output or matching	1,000	50/60	120	9.0
UM-112	High imp. mic. input	200,000	1,000	4000	195
UM-113	Interstage	20,000	1,000	1350	205
UM-114	Output or matching	500	50/60	70	9.0

Write for Stancor Bulletin 462R listing complete data and performance curves on these units.

STANCOR

CHICAGO STANDARD TRANSFORMER CORPORATION

3578 ELSTON AVENUE • CHICAGO 18, ILLINOIS

EXPORT SALES: Roburn Agencies, Inc., 39 Warren Street, New York 7, N. Y.

section on recording equipment includes the Ampex line of tape recorders, Magnecorders and many popular-priced units. All recording accessories are listed. Included are a kit builders' section and an expanded technical-book section that includes leading publications covering the theoretical and practical aspects of radio, electronics and electricity.

Dictating Machines. Gray Mfg. Co., 16 Arbor St., Hartford 1, Conn. A profusely illustrated booklet, "How to Communicaté with People", sells are advantages of dictating machines by using humor to describe alternative methods of transferring ideas to the typed page. It describes seven possible, but awkward methods of business communication, and points out the chief features of the Audograph electronic soundwriter that witnesses telephone conversations, covers conferences and sits in on interviews.

Electric Generating Plants. D. W. Onan and Sons Inc., Minneapolis 14, Minn., has issued a Blue Book of general information concerning the selection of engine-driven electric generating plants. The pocket-sized booklet traces the history of electric-plant development from early stages where storage batteries were necessary to today's modern single-unit, engine-generator power plants. Described in simple, easy-to-understand language are the three general groups of electric plants: a-c, d-c and battery charging. Plant operation for each type is thoroughly discussed.

Dual-Beam C-R Voltmeter. Allen B. DuMont Laboratories, Inc., 760 Bloomfield Ave., Clifton, N. J., has released a bulletin on the type 322-A c-r oscillograph. It contains complete technical specifications, description and photo-recordings made with the new instrument. The type 322-A discussed is an improved, redesigned counterpart of the type 322 dual-beam c-r oscillograph with the added feature of built-in independent voltage calibration for both beams, and which also incorporates the new tight-tolerance type 5AFP crt.

let WILLIAMS help you apply

ferric oxides

to the manufacture of your

FERRITES

You'll be well repaid by getting the facts on a special group of Pure Ferric Oxides, developed by Williams especially for use in the manufacture of ferrites.

Williams Ferric Oxides analyze better than 99% Fe_2O_3. They contain a minimum of impurities. They are available in a broad range of particle sizes and shapes. Among them, we're certain you'll find one that's "just right" for your requirements. The proper application of Ferric Oxides to the manufacture of Ferrites is our specialty.

Tell us your requirements . . . we'll gladly send samples for test. Chances are good that our Ferric Oxide "Know How" can save you considerable time and money. Address Dept. 25, C. K. Williams & Co., Easton, Pa.

WILLIAMS
COLORS & PIGMENTS
C. K. WILLIAMS & CO.
Easton, Pa. • East St. Louis, Ill.
Emeryville, Cal.

P.S. We also produce IRN Magnetic iron powders for the Electronic Core industry, the Magnetic Tape Recording industry and others. Write for complete technical information.

Watch TENSOLITE for progress in ELECTRONIC WIRING!

For High Dielectric Strength, specify–

TENSOLON
TEFLON-INSULATED
WIRE & CABLE

- THIN WALL
- 14 COLORS
- FREE-STRIPPING
- EXTRA FLEXIBILITY
- TOUGH TEFLON INSULATION
- TEMPERATURE RATING: —90° to +250°C

For an extra margin of dependability at maximum operating temperatures, specify these rugged Teflon insulated hook-up wires. Available in stranded sizes from 20 to 30 AWG with shields and teflon jackets or lacquered braids. Constructed to meet highest government and commercial standards, Tensolon Wires feature the new Tensulated-Teflon covering that eliminates pin holes and other imperfections.

ASSORTED TENSOLON HIGH-TEMP WIRES IN LABORATORY AND TEST QUANTITIES

An economical sample kit for designers, engineers, testing departments and development laboratories. Prices on request.

WRITE FOR CATALOG TODAY

TENSOLITE INSULATED WIRE CO., INC., TARRYTOWN, NEW YORK

BIRNBACH
Electronic
COMPONENTS

Cut production costs — speed operations, by specifying BIRNBACH — your reliable Source of Supply for all requirements in Radio, Television, and Electronic Components, Accessories, Wire and Cables.

COMPLETE WAREHOUSE STOCKS
FOR PROMPT DELIVERY

- Govt. Spec. Hookup Wire
- JAN-C-76 SRIR-SRHV Plastic
- WL-Extruded Nylon Jacket
- Aircraft Wire—Nylon Jacket
- 105° C. UL Approved
- JAN-C-76 WL-Glass Braid
- Multiconductor Rubber Covered Cables, shielded, unshielded
- Tinned and Bare Wire
- Magnet Wire
- Heavy Formvar Wire
- Vinyl Extruded and Radio Grade Tubing
- Shielded Wires
- Insulated Hardware
- Plugs, Jacks, Sockets
- Test Leads, Switches
- Insulators, Steatite and Ceramic
- Terminal Strips

Quality Products for the Electronics Industries since 1923

BIRNBACH RADIO CO. INC.
145 HUDSON STREET
NEW YORK 13, N. Y.

WRITE FOR CATALOG 53-E

PLANTS AND PEOPLE

Edited by WILLIAM G. ARNOLD

OTHER DEPARTMENTS featured in this issue:

	Page
Electrons At Work	198
Production Techniques	244
New Products	298
New Books	453
Backtalk	464

RETMA Reorganization Moves Ahead

ELECTION OF Max F. Balcom as chairman of RETMA's Radio-Television Industry Committee and F. R. Lack as chairman of the Association's Electronics Industry Committee, along with the approval of a request for a paid general manager for electronics, highlighted RETMA meetings in New York.

During the meeting Fred D. Wilson, president of Capehart-Farnsworth, was elected a director of the set division. R. E. Cramer, Jr., vice-president of Radio Condenser, L. S. Racine, president of Chicago Standard Transformer, and W. M. Owen, president of Aerovox Corp., were elected directors of the parts division. A. L. Chapman, vice-president of Sylvania, was elected to the set division executive committee.

The tube division elected Max F. Balcom of Sylvania as chairman of its executive committee and N. B. Krim of Raytheon, R. T. Orth of RCA and I. G. Rosenberg of Du Mont as members of the committee.

At the first meeting of the Radio-Television Industry Committee, RETMA president McDaniel was authorized to register RETMA opposition to any proposed legislation designed to put subscription tv under regulation as a common carrier. Reports were made by the various divisions of the committee.

In the Electronics Industry Committee, chairman Lack was authorized to develop a plan for two or more divisions.

The set committee approved a proposal of the National Association of Better Business Bureaus that an informational booklet on color tv be published in the near future.

H. J. Schulman, chairman of the service committee, proposed production of a consumer educational film on tv set servicing. This was approved by the set committee but disapproved by the finance committee until sufficient funds were available.

In other actions, William L. Dunn of Raytheon was appointed chairman of the sales managers committee of RETMA's set division and E. L. Taylor of Stewart-Warner was reappointed vice-chairman.

Robert C. Sprague, chairman of RETMA's board, reappointed M. F. Balcom of Sylvania as chairman of the educational tv committee for the coming year.

John F. Giligan of Philco was reappointed chairman of the RETMA public relations and advertising committee by Robert S. Alexander, chairman of the Association's set division. Also reappointed were E. L. Redden of Motorola, Inc. as vice-chairman of advertising and S. H. Manson of Stromberg-Carlson as vice-chairman of public relations.

New Coast Electronics Company Is Formed

FORMATION OF The Ramo-Wooldridge Corp. of Los Angeles, a new company to be devoted to research, development and manufacturing in the general field of advanced electronics and guided missiles, was announced by the firm's officers and

Midget Jeep Designer Meets Computer



The fifteen-year-old boy, Donald Trumbull, who won Ford Motor Company's "industrial achievement" award for designing and constructing a radio-controlled midget jeep, is introduced to Remington Rand's newest computer by Jack Herron, assistant to the chief engineer at the company's advanced research lab

Working on complex VHF or UHF projects?

HERE'S EXPERT HELP YOURS FOR THE ASKING!

We've honestly earned our reputation as experts in electronic development, design and production . . . and our complete facilities are always at your service.

Our two plants have a production area of more than 122,000 square feet. They are laid out for peak efficiency in development, design, fabrication and assembly of every component in electronic projects from simple test equipment to complex radar systems.

Here are complete departments for metal working . . . welding . . . riveting . . . heat treating . . . plating . . . engraving . . . assembling . . . finishing . . . packaging and shipping. Approximately 500 trained employees and experienced electronic engineers assure accurate and efficient results.

Take advantage of our unique and complete ability to serve you, regardless of the size and scope of your electronic projects. Your inquiry will be expertly and promptly evaluated and our suggestions will be of interest and value to you. There is, of course, no obligation.



Lavoie Laboratories, Inc.

MORGANVILLE, NEW JERSEY

Want more information? Use post card on last page.

J. D. Wright, president of Thompson Products.

President of the new firm will be Dean E. Wooldridge, who for the past two years has been vice-president in charge of research and development for Hughes Aircraft.

Simon Ramo, who has served as vice-president of operations for Hughes, will be vice-president and executive director.

Thompson Products will have a stock interest in the new corporation which will provide Thompson with consulting services possibly leading to production programs for the Cleveland parts concern.

"Thompson Products and Ramo-Wooldridge have a mutuality of interests", said Mr. Wright. "They will bring us advanced engineering techniques, and Thompson will provide financing and production techniques."

Ramo-Wooldridge will specialize basically in new advanced system developments involving the general field of guided missiles, radar, computers, electronic controls and automatic intelligence devices.

Audio Engineering Society Elects Officers

JERRY B. MINTER, vice-president of Measurements Corp., was elected president of the Audio Engineering Society to succeed F. Sumner Hall, president of F. Sumner Hall, Inc., who became a governor of the Society.

Minter has been active in the audio equipment field since 1934 when he was employed by Boonton Radio in the development of bandpass intermediate-frequency transformers. In 1936 he participated in the development of aircraft radio receivers at Radio Frequency Laboratories. He subsequently became associated with the late Malcolm P. Ferris, working on development of a signal generator, a radio noise and field strength meter and other projects. Upon the death of Ferris, he joined with some associates in organizing Measurements Corp.

Other officers elected in the Society were: A. A. Pulley of RCA Victor, executive vice-president; R. C. Mayer of RCA Victor, central vice-president; Boyd McKnight of North American Aviation, western vice-president; R. A. Schlagel of WOR, treasurer; C. J. Le Bel of Audio Instrument and Audio Devices, secretary.

Elected to the board of governors were: R. H. Ranger of Rangertone; L. J. Scully of Scully Machine; W. O. Stanton of Pickering.

Jensen Names EP&PM Committees

APPOINTMENT of seven committees of the Association of Electronic Parts & Equipment Manufacturers was announced by Karl W. Jensen of Jensen Industries, chairman of the association. Committee chairmen named were:

P. N. Cook of Chicago Standard Transformer, chairman of the social committee; E. Van Deveer of Jensen, chairman of the credit committee; O. D. Jester of Standard Coil, chairman of the publicity committee; Roy S. Laird of Ohmite, chairman of the educational committee; Theodore Rossman of Pentron, chairman of the industry relations committee; Wilfred Larson of Switchcraft, chairman of the membership and attendance committee; Ben Boldt of Amphenol, chairman of the merchandising analysis committee.

Federal Labs Promotes Busignies And Hawk

APPOINTMENT OF Henri G. Busignies as vice-president and member of the management advisory board and Walter H. Hawk as manager of television operations was announced by Federal Telecommunications Laboratories.

Busignies has been associated with IT&T for nearly a quarter of a century. He joined the labs in 1941 and advanced from senior engineer to the post of technical director during the ensuing eight years. He is known chiefly as the inventor of the first automatic direction finder for aircraft. His contributions to the World War II

Managers Of GE's Electronics Laboratory Meet

FUNCTIONAL reorganization and new managerial appointments were made by Lloyd T. DeVore (right), manager of GE's electronics laboratory, as a result of a $3 million expansion, tripling the size of the lab at Syracuse, N. Y. Left to right are M. C. Evans, administration manager; B. R. Lester, advanced products development engineering manager; W. Hausz, manager of techniques and applications development engineering; R. N. Gillmor, manager of materials and processes; J. P. Jordan, manager of components development engineering. Two wings have added about 70,000 sq ft to the lab.

WEBBER

TRADE MARK REGISTERED

TEST CHAMBER

WITH HIGH-TEMPERATURE, LOW-TEMPERATURE AND HUMIDITY



★ This Webber test unit, designed for production and experimental testing, has a temperature range from +250°F., to −100°F. The pull-down to −100°F., is achieved in 45 minutes, and can be cycled from −100°F., to +250°F., in 30 minutes. 95% relative humidity is provided at temperatures between 75°F., and 95°F. Vacuum equipment can be added to simulate high altitudes. The test chamber, provided with a moisture-proof light for illumination, is 4½ cubic feet, 20 inches high, 20 inches wide, 20 inches deep. High and low temperatures are governed by a temperature controller with scale range from −200°F., to +400°F., with a 3 degree control point differential, 1½ degrees plus and minus. The humidity is regulated by a wet and dry bulb controller. Unit size is 60" long, 45" wide, 74" high. Apertures in left side of cabinet provide for electrical cables to energize equipment being tested. Webber offers a complete line of test units for various applications.

Write for more complete information

INDUSTRIAL FREEZER DIVISION

WEBBER MANUFACTURING COMPANY, INC.

(Formerly Webber Appliance Co., Inc.)

2745 MADISON AVENUE • INDIANAPOLIS 3, INDIANA

Is this your soldering problem, too?

Higher Speed with Smaller Tips?

The answer is—

HEXACON TRADE MARK

SUPER POWERED SOLDERING IRONS

Solder Faster with Lower Tip Cost!

For example, Cat. P-214 has more speed than conventional 200 watt iron, but takes ¼" tip instead of ⅝" *(only 1/6th the copper).*

SIX MODELS TO CHOOSE FROM			
Tip Dia.	Watts	Cat No.	List Price
1/4	100	P-114	$8.25
1/4	150	P-154	9.00
1/4	200	P-214	10.00
3/8	200	P-238	10.00
1/2	200	P-212	10.00
3/8	300	P-338	13.25

Write for Catalog showing 40 industrial soldering irons of every type and size; no obligation.

HEXACON ELECTRIC COMPANY

130 WEST CLAY AVENUE, ROSELLE PARK, NEW JERSEY

HEXACON — Industry's No. 1 Soldering Iron

SHURE

THE "Field-Proved" STANDARD IN COMMUNICATIONS... INTRODUCES A *NEW*

TELEPHONE HANDSET

...the first Handset specially engineered for two-way communications



- 2-Way Radio Communications
- Inter-Com Systems
- Airplane Announce Systems
- P. A. Systems

Specially Designed to Suit Your Specific Applications

Here is a truly modern functional handset specifically designed for 2-way communications! A product of the Shure Laboratories with many years of experience in safety mobile communications, the TH10 Handset brings you these features: ... the field-proved *controlled reluctance* assembly as a receiver ... high output *balanced response* carbon transmitter ... oversize switch cavity providing flexibility in stacking of famous Shure long-life leaf blades ... cored handle for maximum number of conductors ... no solder connections ... rugged shock resistant handle ... design smart to the eye, natural in the hand. The answer to your complex circuitry!

SHURE

For more complete information write to

SALES DIVISION

SHURE BROTHERS, Inc.

Manufacturers of Microphones & Acoustic Devices

225 W. HURON ST., CHICAGO 10, ILL.

Cable Address: SHUREMICRO

new! Integral core and coating design

castohm®

FIXED WIREWOUND POWER RESISTORS

OUTPERFORMS ALL CONVENTIONAL POWER RESISTORS

- Higher Wattage Ratings — smaller sizes
- 25% lighter in weight
- 350°C hot spot operation
- Closer Tolerances — to 1% (5% standard)
- Better heat conductivity
- Exceptional resistance to thermal shock
- Designed to MIL-R-10566 specifications

New Shallcross Castohm power resistors surpass all previous standards for high wattage fixed power resistors. Thoroughly tested and designed to MIL-R-10566 specifications, Castohms offer unique opportunities for saving space and weight while improving the reliability and efficiency of modern industrial and military equipment. Specifications on all types from 8 to 225 watts are yours for the asking. SHALLCROSS MANUFACTURING COMPANY, 522 Pusey Ave., Collingdale, Pa.

Shallcross

Henri G. Busignies

effort include the development of a shore-based direction finding system known as Huff Duff. In recognition of these activities he was awarded the U. S. Navy Certificate of Commendation for outstanding service to the U. S. Navy and the Presidential Certificate of Merit.

Hawk has been with FTL since 1948, serving successively as a division head, director of electronic production engineering and technical services manager. He will be in charge of the production and development of FTL's complete line of vhf and uhf tv broadcasting and studio equipment. He has been in the electronics industry since 1934, and was formerly with Federal Telephone and Radio Co., also a division of IT&T, serving successively as production line manager of the crystal division, and chief engineer of the rectifier and intelin division.

Luck To Receive Ballantine Medal

THE STUART BALLANTINE MEDAL of The Franklin Institute of Pennsylvania will be awarded to David G. C. Luck of RCA Laboratories "for his invention of the Omnidirectional Radio Range, an essential element in present-day air traffic control".

In 1932 he joined the staff of RCA-Victor as research engineer. Since 1942 he has been a member of the technical staff of the RCA Labs. He has been granted over

Ultraviolet Laboratory Equipment

UTILITY MODEL QUARTZ LAMP

A high pressure, quartz mercury arc lamp. It is ideally applicable for use with the microscope, polarimeter, spectrometer, and general laboratory applications.

INSPECTOLITE

A source of "black light" for making rapid qualitative analyses by visual observation.

1787

OPTOSIL

Fused quartz suitable for many optical uses. Hanovia's special manufacturing process greatly reduces the size and number of air bubbles as compared to general commercial grades. Higher optical grades available.

Write for technical data on these or other ultraviolet laboratory equipment.

HANOVIA
CHEMICAL & MFG. CO.
(Special Products Division)
100 CHESTNUT STREET, NEWARK 5, N. J. — Dept. E-1153

you can depend on
SECON for
PRECISION WIRE & RIBBON
if your product-need is here

SECON specializes in the development and production of base, rare and precious metals and alloys in all shapes and forms — to close tolerances and for highly engineered applications. Extremely close tolerances can be held on such important characteristics as: resistance, tensile strength, elongation, surface appearance, special spooling, purity, torque, linearity, composition, cross section, weight per unit length.

From initial selection of melt components through production and final completion, SECON puts a *complete metallurgical unit* at your service.

Tell us your wire and ribbon problems and we'll gladly submit prompt recommendations. Small quantity inquiries and orders specially invited. Write for Pamphlet (key).

- Fine Wire drawn to 0.0003" diameter. Smaller diameters by other processes.
- Ribbon rolled to 0.0001" in thickness.
- Electro-plated Wire and Ribbon
- Special Solder
- Enameled and Insulated Wire
- Pirani Gauge Wire
- Fuse Wire
- Galvanometer Suspension Strip
- Etched Wire
- Experimental Melts

SECON
For wherever the element calls for PRECISION
SECON METALS CORPORATION
7 Interv[illegible] Street, White Plains, New York
White Plains 9-4757

STOCK KNOBS IN ANY QUANTITY
...AND NEVER A TOOL CHARGE!

GEE-LAR—The House of Knobs —has hundreds of styles and patterns in stock at all times. Whatever your needs... whether for production, lab or experiment... you can get them faster and at lower cost from GEE-LAR.

WRITE TODAY
for Gee-Lar Catalog

THE HOUSE OF KNOBS

GEE-LAR MANUFACTURING COMPANY
1332 10TH AVENUE • ROCKFORD, ILLINOIS


First in
stainless steel
fastenings
ANTI-CORROSIVE
METAL PRODUCTS
behind this symbol is an on-hand inventory of *more than 9,000 items and sizes* of stainless steel fastenings. Ready for immediate shipment, this stock is the largest and most complete in the industry. In addition, a production capacity for large or small quantities of special orders is at your service! A good reason — when you think of stainless steel fastenings — to think FIRST of Anti-Corrosive! *Send for Catalog 53F today!*
ANTI-CORROSIVE METAL PRODUCTS CO., INC.
Castleton-on-Hudson, New York

sixty patents for devices in the radio field, most of which pertain directly or indirectly to direction finders or navigational aids. He has taken part in the work of RTCA committees studying various problems of air navigation and traffic control and has been active, as well, in the study of color tv systems.

Pilot Course For TV Technicians Opens

THE FIRST CLASS of RETMA's pilot training course for tv technicians at the New York Trade School has been held. Harold J. Schulman, chairman of the Association's service committee and service manager of Du Mont, explained that the program is based on a need by the nation's technical schools for an industry-approved syllabus for tv technician training.

The pilot course is being supported with both money and equipment donated by RETMA companies. A preliminary course of instruction, drawn up by the service committee, is open to revision on the basis of experience gained during the course. Following this, an industry-recommended course of training will be drawn for use in vocational schools throughout the country.

Erie Resistor Names Heibel And Shenk

Jerome D. Heibel

JEROME D. HEIBEL and Allen K. Shenk have been appointed vice-presidents of the Erie Resistor Corp., according to G. Richard Fryling, president.

Heibel has been named vice-

EPCO

TRANSFORMERS

" Fill Your Need to a "



For INDUSTRIAL and ELECTRONIC EQUIPMENT

•

Let us quote on your Specifications, no obligation

SAMPLE SHORT and LONG RUNS

•

Delivery as Promised!

DESIGNED TO COMMERCIAL AND MILITARY SPECIFICATIONS (MIL-T-27 and AN-E-19)

EPCO Products Inc.
2500 Atlantic Ave.
Brooklyn 7 New York

N.L. Instr't

UHF TV MEASURING INSTRUMENTS by New London

Write for Complete Catalog of our Measuring Equipment

UHF TV SWEEP GENERATOR MODEL 130 - $265 -

UHF GRID DIP OSCILLATOR MODEL 200 - $140 -

Designed for laboratory and production test use, the Model 130 has proven itself an ideal low cost instrument.

Frequency range:	450 to 900 mc
Output voltages:	0.01 to 1.0 volts into 75 ohm load
Sweep:	60 cycles, sine wave
Sweep width:	0 to at least 30 mc, continuously variable
Output:	Unmodulated, AM or swept

Markers and balun for 300 ohm load are available.

• • •

The only UHF Grid Dip Oscillator in the field, the versatile Model 200 is an extremely useful instrument for those who do UHF TV work. Featuring single range tuning and direct reading, the Model 200 has a remarkably smooth meter indication.

Frequency range:	400 to 900 mc, single range
Output:	CW
Size:	8½" high x 3" wide x 4" deep

New London Instrument Company
NEW LONDON 2, CONN.

For HIGHEST ELECTRICAL & MECHANICAL EFFICIENCY!

New

JONES SERIES 2400 PLUGS & SOCKETS

- Improved Socket Contacts—4 individual flexing surfaces. Positive contact over practically their entire length.
- Cadmium plated Plug and Socket, Contacts mounted in recessed pockets, greatly increasing leakage distance, INCREASING VOLTAGE RATING.
- Interchangeable with 400 Series.

P-2406-CCT



S-2406-SB

Send for complete Catalog No. 18. Plugs, Sockets, Terminal Strips.

Jones — HOWARD B. JONES DIVISION
CINCH MANUFACTURING CORPORATION
CHICAGO 24, ILLINOIS

Quality . . .

is Standard with Standard Piezo

Standard Piezo guarantees accurate and dependable quartz crystals to meet all private plane or commercial air carrier requirements.

Whether they are high or low in frequency, for use at low or high altitudes, you'll find Standard Piezo quality is consistently superior.

For your crystal requirements, standard or custom, write or call us.

Synonymous with Quality

Standard Piezo Co.
CARLISLE, PENNA.
Phone 1495

NOW READ VOLTAGE RATIOS OF 100,000 to 1



Direct Log-linear conversion over a 0 to 100 db. range makes this possible. The new Pickard & Burns Log-Linear Converter (Model 86*) produces a true logarithmic response between any 50 kc signal and its meter reading or recorder output. It does it electronically—not mechanically. This provides the user with a means of recording up to 100 db. on conventional linear recorders, or direct meter readings. For higher precision and easier readability, any portion of the 100 db. range may be quickly expanded by push-button selection to produce a full-scale reading of 20, 40, 60, 80 or 100 db. The overall accuracy is ±1 db. Sensitivity is 2 microvolts.

One of the uses of the Model 86 Converter is to operate in conjunction with the Pickard & Burns Model 100 Bolometer Amplifier to produce a logarithmic reading of the amplifier's 50 kc. I.F. The two units provide a remarkably wide-range combination to facilitate the measurement of RF field strengths of antenna systems and RF networks.

The Model 86 Converter is designed for either rack or cabinet mounting. Plug-in units for other frequencies will be available soon.

*Patent pending.

For further information write for Bulletin L-86

PICKARD & BURNS
INCORPORATED
240 Highland Avenue, Needham 94, Mass.

Allen K. Shenk

president in charge of research and engineering. He joined Erie in 1936, coming from Talon, Inc. of Meadville, Pa., and was manager of the capacitor division. In 1945 he became manager of sales engineering and since 1949 has served as director of research and engineering. He is chairman of the RETMA committee on ceramic dielectric capacitors.

Shenk was appointed vice-president in charge of sales. He joined Erie in 1942 as assistant sales manager of the electronics division. He was previously associated with the W. S. Hill Co. of Pittsburgh for 12 years.

These appointments, according to president Fryling, have been made coincidental with the company's expanded production facilities in Erie and the construction of a new plant in Holly Springs, Miss., and to strengthen the firm's entire sales program. He also stated that in line with these expansions, greater emphasis is also being placed on research in all phases of the company's activities.

Other promotions within the ranks of the company were also announced. J. C. Van Arsdell has been appointed assistant general manager of the electronics division. William Klevans advanced to manager of sales engineering, the post previously held by Van Arsdell. William J. Wervey moved up to field sales engineer, Klevan's former position.

Malcolm Young, formerly manager of quality control, has been named assistant general manager of the plastics division. Ralph L. Hathaway has been promoted from superintendent to works manager.

NEW! UHF TELEVISION
Standard Signal Generator



MODEL 84-TV
300—1000Mc.

SPECIFICATIONS

FREQUENCY RANGE: 300-1000 megacycles.
OUTPUT: .1 Microvolt to 1 Volt, across 50 Ohms.
OUTPUT IMPEDANCE: 50 Ohms coaxial.
MODULATION: Internal 400 cycle, continuously variable from 0 to 30%. Provision for external modulation of 50 to 20,000 cycles.
LEAKAGE: Negligible.
SIZE: Overall Dimensions: 11¾ inches high, 19 inches wide, 11 inches deep.
WEIGHT: Approximately 40 pounds.
POWER: 115 volts, 60 cycles, 120 watts.

Write for complete details

MANUFACTURERS OF
Standard Signal Generators
Pulse Generators
FM Signal Generators
Square Wave Generators
TV Standard Signal Generators
Vacuum Tube Voltmeters
UHF Radio Noise & Field Strength Meters
Megacycle Meters
Intermodulation Meters
TV & FM Test Equipment

MEASUREMENTS CORPORATION
BOONTON NEW JERSEY

where LESS is MORE
international instruments

1" and 1½"
SUB-MINIATURE AND MINIATURE
ELECTRICAL METERS

FOR AIRCRAFT, GUIDED MISSILES, ELECTRONIC and ATOMIC DEVELOPMENTS, COMMUNICATIONS and INDUSTRY

Wherever less weight and smaller size are vital, these sub-miniature and miniature meters allow more savings. They not only provide accuracy and dependability equal to that of larger models, but, in addition, the inherently strong construction withstands shock and vibration far better than conventional sized instruments. A D'Arsonval type movement of excellent design, precision workmanship and materials of selected quality permit miniaturization while retaining high performance standards.

Meters, testing devices and allied equipment are available for a wide variety of requirements and can be adapted for use wherever it is desired to measure quantities electrically. Instruments are engineered for unusual applications by our staff of skilled technicians. Efficient production insures good delivery and low cost on both regular and special jobs.

If smaller size and lighter weight can help solve your instrument problems, fill in and mail the attached coupon today.

international instruments
INCORPORATED
P. O. BOX 2954, NEW HAVEN 15, CONN.
LIAISON ENGINEERS IN PRINCIPAL CITIES

Please send me engineering data sheets covering the International line of instruments.

NAME_____
POSITION_____
CO. NAME_____
ADDRESS_____
CITY_____
ZONE_____ STATE_____

Fine Aluminum Wire

• To meet the growing demand from producers of light-weight, high-frequency Galvanometer movements, we have expanded our facilities designed to process Wire of 2S Aluminum. This wire can be supplied in diameters ranging from approximately .001 inch through .005 inch. Anodized with an exceptionally thin and flexible dielectric coating.

Also available: wires of aluminum alloys enameled as small as .001 inch diameter, to meet rigid specifications of resistance, size and straightness.

Write for Latest List of Products

SINCE 1901

SIGMUND COHN CORP. 121 So. Columbus Avenue • Mount Vernon, N.Y.

how to PICK UP 2,900,000 BTU without "wiggling" the flame

..solved by a KIRK AND BLUM ventilation system!



Above—Battery of RCA Sealex machines. Heat from glass sealing and evacuating operations on electron tubes is collected by aluminum hoods and duct-work.

Heat can be a headache in any plant. Here, in a midwestern tube plant of RCA Victor Division, Radio Corporation of America, glass sealing and forming operations require plenty of heat of all kinds—induced, radiated and reflected. For the comfort and safety of workers, this heat must be removed but without disturbing the play of gas flames on delicate parts.

KIRK & BLUM engineers achieved a fine balance, removing 2,900,000 BTU hourly and without distorting the delicate flames.



One of a number of batteries of roof-top fans which exhaust vented air from 10 identical systems.

Whatever your ventilation problem... heat, dust or fumes... the best, lowest-cost solution involves more than a fan, motor and some lengths of duct. Put it up to experts...The Kirk & Blum Mfg. Co., 3211 Forrer Ave., Cincinnati 9, Ohio.

KIRK AND BLUM
VENTILATION SYSTEMS

of the electronics division. Philip B. Ehrman has been promoted from assistant superintendent to superintendent of the electronics division. Horace S. Herrick has been promoted from division manager of quality control to manager of quality control of the electronics division.

Audio & Video Elects New Board Members

THE FOLLOWING new members were elected to the board of directors of Audio and Video Products Corp., according to Charles E. Rynd, president and chairman of the board:

Kenneth B. Boothe, vice-president and director of instrumentation and sales for the company; Martin V. Kiebert, Jr., formerly project director of Bendix and technical consultant in guided missiles; Bernard B. Smith, attorney, who is regarded as an expert on legal and economic aspects of radio and tv; Irving B. Buckley, executive vice-president of Trans-Caribbean Airways.

The following men were re-elected on the Board of Directors: Max Graff, Edward V. Otis, Charles E. Rynd, Sidney K. Wolf and Erwin S. Wolfson.

GE Established Control Department

G. E. BURENS, general manager of GE's switchgear and control division, announced the establishment of a specialty control department and the appointment of Louis T. Rader as its general manager.

The new department will be responsible largely for industrial electronic regulator and aircraft control equipment. Dr. Rader announced the following appointments to his staff: K. N. Bush, manager of manufacturing; H. L. Palmer, manager of engineering; J. P. Rutherford, manager of marketing; and C. S. Van Wormer, manager of finance.

Rader joined GE on the test course at Schenectady and completed the advanced engineering program a year later. Assigned to the control division, he worked as a design engineer until 1945 when he

BRIDGEPORT BRASS COMPANY

COPPER ALLOY BULLETIN

Bridgeport BRASS CO. MILLS IN BRIDGEPORT, CONN. AND INDIANAPOLIS, IND.—IN CANADA: NORANDA COPPER AND BRASS LIMITED, MONTREAL



Parts of ¼" diameter miniature volume controls used in hearing aids and in many other applications. Courtesy of Centralab, a Division of Globe-Union Inc., Milwaukee, Wisconsin.

Copper Alloys Play Important Role In Miniaturization Trend

Throughout the electronics industry, the trend is to smaller, lighter, more compact assemblies. Hearing aids, for example, must incorporate all the elements of a radio amplifier in a package not much larger than the average cigarette case. Portable communications equipment like radio sets for aircraft and automobiles, miniature personal radios, walkie-talkie units, airborne radar receivers all must be designed so that every possible extra inch of space and ounce of weight can be trimmed off the finished product.

Miniature Volume Control

Illustrated above with its copper-base alloy components is a volume control no bigger in diameter than a dime. This type of control has a rating of 1/10 watt and is obtainable with resistance ranges of from 0 to 500 ohms and on up through 10 megohms. It is probably one of the smallest volume controls commercially available. It is currently being used as a component in many hearing aids, test instruments, miniature radios, microwave sets and other miniaturized apparatus.

Copper-Base Alloys Excellent for Precision Parts

Copper-base alloys are preferred for many electrical and electronic applications because of their fine properties. Conductivity, good corrosion resistance, ability to withstand severe forming operations, high wear resistance, excellent plating and finishing properties explain their wide use in the many thousands of products with which we are familiar.

Many of the parts in this control are made of brass. Some are plated with either nickel or cadmium for increased wear resistance or silver for improved contact characteristics.

Among the parts made from brass rod are the contact blade pivot pin, the mounting studs, the shaft, rivet, hex screw and nuts. The terminals were made from yellow brass strip which is easily stamped and formed. The spacers and washers were also made from brass.

Phosphor Bronze Vital in Electronics Equipment

In complex assemblies like these volume controls and switches, satisfactory performance depends on each tiny part, especially those spring parts used in making mechanical and electrical contacts. For this reason, the selection of the correct alloy, temper, and gauge is most important.

The contact spring washer and spring pivot pin washer in the tiny volume control illustrated were made of Phosphor Bronze Grade C, approximately 92% copper, 8% tin, and 0.1% phosphorus. Supplied for these applications 8 B&S numbers hard, the material has a tensile strength of about 112,000 psi. It is widely used throughout the electronics industry because it combines superior spring properties as well as conductivity and high corrosion resistance.

Parts like contact springs must have high fatigue resistance to withstand millions of flexing cycles. Spring washers must withstand constant compression without taking a set if they are to be satisfactory. They must also be corrosion resistant under all climatic conditions. Phosphor Bronze meets all these qualifications and yet can be stamped and formed into precision parts. That is why Phosphor Bronze is in such wide use in the fields of radar, radio, television, sound reproduction and amplification, and in all types of electronic and electrical equipment and controls.

Bridgeport Brass Service

Bridgeport Brass supplies copper-base alloys—in strip, rod, tubing, and wire—used in the electronics field. Our Laboratory will be glad to assist you in the selection of proper alloys for your applications. Write for Bridgeport Brass Technical Handbook for properties and applications of copper-base alloys. Call or write the Bridgeport District Office nearest you. (714)



Parts of electronic switch and assembled switches. Courtesy of Centralab, Milwaukee, Wisconsin.

Want more information? Use post card on last page.

High-temperature, Wide-range

RADIO-NOISE FILTERS

for Bulkhead Mounting. Series 1515



TOBE FILTERETTES SERIES 1515

These compact, radio-interference filters are designed for use in low-current circuits. They are hermetically sealed in metal cases with threaded studs to mount the units on metal bulkheads or firewalls in such a way that input and output terminals are on opposite sides of the bulkhead, and the filter housing is connected to the bulkhead. Weighing only 0.17 pounds each, they are especially suited to aircraft service.

These units are available in various electrical ratings and frequency ranges; see table below.

Model No.	Amperes	Volts AC	Volts DC	Operating Temp.	Curve
1515	1.0	130	400	90°C	A
1515-1	1.0	130	500	90°C	B
1515-2	1.0	130	400	100°C	C
1515-3	1.0	130	400	100°C	D
1515-4	0.5	—	750	—	E



JUST OUT! Catalog on MIL-C-25A capacitors.
Write today for your FREE COPY.

TOBE DEUTSCHMANN
CORPORATION
NORWOOD, MASSACHUSETTS

left the company to become head of the electrical department at the Illinois Institute of Technology.

Two years later he returned to GE to manage the engineering laboratory of the control division. In 1949 he became assistant manager of engineering and was appointed manager of engineering in 1951.

Motorola Plans Plant Moves

TWIN ONE-STORY plants which cover an area of 150,000 sq ft on 300,000 sq ft of property, now under construction in Chicago, will soon be occupied by Motorola manufacturing and parts and service departments, according to Robert W. Galvin, executive vice-president of the company.

Most of the departments in the company's Washington Boulevard plant and Halstead Street plant in Chicago will move to the new buildings. Some departments, however, will be consolidated in the Franklin Park, Ill. tv assembly plant, also under construction.

Gagg Joins Bendix Executive Staff

Rudolph F. Gagg

RUDOLPH F. GAGG, recently president of Air Associates, has joined the administrative staff of Raymond P. Lansing, vice-president and group executive of Bendix Aviation Corp.

Gagg, who was assistant to the general manager of Wright Aero-

"INDUSTRIAL"
for
ELECTRONIC COMPONENTS



Precision engineered electronic components and connecting devices for all your needs.

- ANODE CONNECTORS
- INTERLOCK PLUGS
- LAMINATED TUBE SOCKETS
- TERMINAL STRIPS
- WIRED ASSEMBLIES
- BAKELITE STAMPINGS
- TERMINAL BOARD ASSEMBLIES

—NEW ITEMS—

- TUNER STRIPS, SOCKETS and BRACKETS for UHF

Our extensive design and production facilities are available for developing your special requirements and applications. Representatives in principal cities throughout U. S. A. Call or write for samples and information. ORegon 7-1681.

INDUSTRIAL HARDWARE Mfg. Co., Inc.
109 PRINCE STREET • NEW YORK 12, N. Y.

FORD control motors . . .

for extremely low inertia and high frequency response

HIGH VOLTAGE MOTORS

60 Cycle, 1½-5-10 watt models
Designed specifically for electronic systems—operate directly in the plate circuit of a vacuum tube amplifier.

LOW VOLTAGE MOTORS

60 and 400 Cycle, 2½-5-10 watt models
Recommended for normal two-phase applications.

advantages

- Linear torque—voltage characteristics
- Linear torque—speed characteristics
- Withstand continuous stalling
- High torque efficiency
- Flexibility of mounting

Write for Descriptive Brochure about all Ford Control Motors.

FORD INSTRUMENT COMPANY
Division of The Sperry Corporation
31-10 Thomson Avenue, Long Island City 1, N. Y.

THE MOST COMPLETE SOURCE
For Every IMPORTANT FASTENING
IN ALL METALS

BOLTS
NUTS
SCREWS
THREADED PRODUCTS
STAINLESS STEEL
NAVAL BRONZE · STEEL · BRASS
ALUMINUM · MONEL · EVERDUR
NICKEL ALLOY STEEL
IMMEDIATE DELIVERY
CATALOG ON REQUEST

KEYSTONE
BOLT & NUT CORP.
135 CHURCH ST., N. Y. 7, N. Y.
WOrth 4-4600

Every DANO Coil is Custom-Made

In electronic equipment success or failure is often determined by coil function. Every Dano coil is made to customer requirements and is delivered to you fit as a fiddle and ready to serve you and your products with perfect, trouble-free performance.

Send us samples or specifications with quantity requirements for our recommendations. No obligation!

- Form Wound
- Paper Section
- Acetate Bobbin
- Molded Coils
- Bakelite Bobbin
- Cotton Interweave
- Coils for High Temperature Application

Also, Transformers Made To Order

THE DANO ELECTRIC CO.
MAIN ST., WINSTED, CONN.

NO HEAT is required for BARCO
Metal Degreaser Fluid

. . . . for Electronic and Allied Industry

Removes all oil, grease, waxes, etc.
Does **NOT** burn. No heat required. Non-corrosive.
Used by leading electronic and Television manufactures for production and maintenance.

SAFE-UNDERWRITERS LAB. APPROVED.
Write for full information TODAY!

BARCO CHEMICAL PRODUCTS CO.
701-703 S. LA SALLE Chicago 5, Illinois

WHEN SPECIFYING A PREDETERMINED COUNTER

for any application, check the reasons why a *Potter Instrument is the only logical choice.* There are important differences among predetermined counters—basic differences in simplicity of operation, in ease of maintenance, in reliability, and in versatility.

THE SIMPLEST CIRCUIT

Potter Predetermined Counters use the "complement" circuit. Any count from one to ten can be set in the *simple, straightforward four tube decade.* A single output is operated when the predetermined count is reached. Other methods require the sensing of many "on" conditions. A typical three-sequence predetermined counter with four decades would require sensing 48 "on" conditions with separate tubes.

THE GREATEST RELIABILITY

The Potter system provides automatic indication of tube failure and stops automatically when failure occurs. *Rugged, approved industrial tube types and switches,* minimize maintenance, help assure trouble-free operation.

MAXIMUM VERSATILITY

Potter Predetermined Counter Decades are *especially adaptable to multiple-sequence counting.* Only 12 tubes, for instance, are needed for counting in a dual-sequence, 0 to 1000 count, unit. Other systems need up to 24 tubes, yet do not equal the Potter method in performance, in space and power economy, and ease of maintenance.

GET THE COMPLETE STORY

Get the complete story on Predetermined Counters for every application involving counting, sorting, batching, and measuring length, weight, volume, and speed. Along with it, let us prove, in detail, the superiority of Potter Instruments. For information on a unit or a system, write Department 11-C

POTTER INSTRUMENT CO., INC.

115 CUTTER MILL ROAD GREAT NECK, N. Y.

nautical Corp. before becoming president of Air Associates, will assist Lansing in the administration of seven Bendix divisions, which manufacture aircraft instruments, control and navigational equipment, starters, generators, special-purpose electron tubes, ignition systems, meteorological instruments, precision electrical units and many other products. These divisions employ some 22,000 employees, or about 45 percent of the corporation's total.

Gagg joined Wright Aeronautical as an experimental engineer in 1930. He became assistant chief engineer in 1934 and assistant general manager in 1940. He was named president of Air Associates in 1948.

Wilcox-Gay Establishes Scholarship At IIT

WILCOX-GAY CORP. established a scholarship at Illinois Institute of Technology that is designed to produce experts in the field of magnetic recording. It provides $650 tuition a year for students enrolled in studies preparing them for magnetic recording development.

In making the grant, Wilcox-Gay president L. H. Ashbach said, "We are establishing this scholarship because we want to help deserving students obtain expert knowledge in the magnetic recording field. By doing so, I believe we are advancing the interests of the entire industry."

In another move, the company announced the construction of two additional one-story buildings, adjacent to its plants in Charlotte, Mich. They will be devoted to increasing production of magnetic tape recorders and recorder accessories. The plants will add 25,000 sq ft of space to present facilities.

Clary Multiplier Appoints Gen. Davis

BRIG. GEN. MARLE H. DAVIS, who retired in August as chief of the Army Ordnance Industrial Ammunition Branch, has accepted a position as manufacturing and engineering consultant for Clary Multi-

HICKOK

Model 209A



true VTVM
and
CAPACITANCE TESTER

- Large 9" meter.
- Measures wide ranges of capacitance, inductance, resistance, current, voltage; both AC and DC.
- Includes matched high frequency probe to make this laboratory instrument a TRUE VTVM.
- Write for technical details . . .

THE HICKOK ELECTRICAL INSTRUMENT CO.
10527 DuPont Ave. Cleveland 8, O.

ZOPHAR

WAXES

COMPOUNDS

Zophar Waxes, resins and compounds to impregnate, dip, seal, embed, or pot electronic and electrical equipment or components of all types; radio, television, etc.

Cold flows from 100°F. to 285°F.

Special waxes non-cracking at –76°F.

Compounds meeting Government specifications plain or fungus resistant.

Let us help you with your engineering problems.

ZOPHAR MILLS 107 YEARS

ZOPHAR MILLS, INC.
112-130 26th Street,
Brooklyn 32, N. Y.

Linde
Trade-Mark

M.S.C.
(Mass Spectrometer Checked)
RARE GASES
HELIUM · NEON
ARGON · KRYPTON · XENON

LINDE Rare Gases are mass spectrometer checked to assure you gases of known purity and uniformly high quality. Available in commercial-size cylinders and glass bulbs.

LINDE, the world's largest producer of gases derived from the atmosphere, can meet your individual needs of purity...volume...mixture...containers...

LINDE AIR PRODUCTS COMPANY
A DIVISION OF UNION CARBIDE AND CARBON CORPORATION
30 East 42nd Street UCC New York 17, N. Y.
In Canada:
Dominion Oxygen Company, Limited, Toronto

The term "Linde" is a registered trade-mark of Union Carbide and Carbon Corporation

Spinning, forming and fabrication facilities can produce the shape or part you need for Electronics applications. If it includes shapes or sections like those shown here—if its a "headache item"—or needs engineering suggestions, send blue print or sample for quotations, or write for newest Brochure 53E.

ROLAND TEINER COMPANY, INC.
134 TREMONT ST., EVERETT 49, MASS. • EV 7-7800
Engineering Offices: Chicago, Cincinnati, Detroit, Fort Worth, Kansas City, New York, Los Angeles

TIC-TALKS FEATURE

PRECISION POTENTIOMETERS
of optimum accuracy meeting your space requirements



Technology Instrument Corporation potentiometers are designed for application in computing devices, instrumentation, electronic control and servo mechanisms — wherever extreme electrical and mechanical precision is an essential requirement.

As a result of years of custom manufacturing a complete line of standard sizes is available ranging from 7 inches in diameter to the sub-miniature ⅛" in diameter.

Custom design both mechanical and electrical is a featured TIC service. Precision non-linear pots may be designed to meet customer's requirements from either empirical data or implicit functions. Taps and special winding angles anywhere up to 360° continuous winding can be incorporated into both linear and non-linear precision potentiometers. Greatly expanded facilities plus mass production techniques meet customer volume needs yet maintain precision tolerances in both linear and non-linear potentiometers.

TYPE	DIAM	RESISTANCE	ELECTRICAL ANGLE	LINEARITY	POWER RATING	MOUNTING	EXAMPLE OF NON-LINEAR FUNCTION AVAILABLE AS STANDARD
RVP 7	7"	1,500,000 Ω tol. to ± 1%	320° tol. to ± 5°	As low as .05%	6 watts at 25° C	Servo	Type RVP7-S2 function: E out = sin (θ/2 + 0.1% peak amplitude E in
RVP 3	3"	Std. values to 200,000 Ω tol. to ± 1%	320° tol. to ± 5°	As low as ± 1%	6 watts at 25° C	Servo—tapped hole and precision pilot or threaded bushing	Type RVP3-S4 function: 50 db logarithmic; conformity ± 2%, constant fractional accuracy
RV-3	3"	Std. values to 200,000 Ω tol. to ± 1%	315° tol. to ± 1°	As low as ± .25%	8 or 12 watts	3 tapped hole	Available for non-linear functions. Note: Phenolic base precision potentiometer, stainless steel or bakelite shaft
RV2	2"	Std. values to 100,000 Ω tol. to ± 1%	320° tol. to ± 5°	As low as ± .2%	4 watts at 25° C	Servo—tapped hole and precision pilot or threaded bushing	Type RV2-S112 function: R = K conformity ± 5% over 64° to 320°
RV1⅝	1⅝"	Std. values to 100,000 Ω tol. to ± 1%	320° tol. to ± 1°	As low as ± .25%	3 watts at 25° C	Servo—tapped hole and precision pilot or threaded bushing	Type RV1⅝-S104 function: E out = sin (θ/2) ± 4% peak amplitude per quadrant E in
RV1	1"	Std. values 1/16" to 50,000 Ω tol. to ± 1%	320° tol. to ± 2°	As low as ± .5%	2 watts at 25° C	Servo or threaded bushing	Type RV1-S7 function: E out = sin (θ/1.78) ± 4% of E in peak amplitude
LINEAR TYPES ONLY:							
RV-⅝	⅝"	Std. values to 40,000 Ω tol. to ± 1%	320° tol. to ± 3°	As low as ± .5%	1 watt	Servo or threaded bushing	
RVT Translatory 1" x 1⅛"		10,000 Ω tol. to ± 15%	Stroke* 0/1"	± 1% total resistance	1 watt	Provides output proportional to a linear displacement rather than a rotary motion of a shaft	

* Special resistance values and stroke lengths from 5 inches to 15 inches can be provided on a custom basis

TECHNOLOGY INSTRUMENT CORP.

533 Main Street, Acton, Massachusetts, Phone Acton 3-7711

plier Corp. He will work with all phases of production operations, including business machines and electronic equipment as well as guided missile instruments and ammunition components, at the company's San Gabriel, Calif. plant. The firm has announced a new $6 million program for guided missile instruments and is expanding production of its electronic data handling equipment, office machines and other lines.

Marandino Appointed Sylvania Plant Head

Ned J. Marandino

NED J. MARANDINO has been appointed manager of the new Sylvania tv set plant in Batavia, N. Y., which is expected to be completed in February, 1954. The plant is the company's largest one-building facility and will employ approximately 2,700 persons.

Marandino joined Sylvania in 1950 as superintendent of test and inspection. In the same year, he was appointed superintendent of tv set production, a post he held until his present appointment.

Stromberg Enters Electronics Control

STROMBERG-CARLSON participated in the establishment of a new industrial process control firm in Los Angeles known as Electronic Control Systems.

The new firm, headed by Leonard Mautner as president and A. F. Brewer as executive vice-president

and secretary, will concentrate on problems in the fields of automatic process control and data handling. R. C. Tait, president of Stromberg, serves as a director of the company and helped to set it up.

Mautner, who was associated with the radiation laboratory of MIT during World War II, was formerly manager of Du Mont's tv transmitter division. He was president of Television Equipment Corp. and headed electronic research and development of guided missile laboratories for Hughes Aircraft.

Brewer has also specialized in radar and guided missiles for more than 13 years. He has carried on development work for the armed services at Sperry, Hughes and similar organizations.

National Electronics Expands Plant

NATIONAL ELECTRONICS, industrial tube manufacturers, have completed an addition to the Geneva, Ill. plant increasing floor space by more than 40 percent. The additional space will be used to expand production of thyratrons, rectifiers and ignitron tubes. Output this year is running 35 percent ahead of the 1952 rate, according to J. H. Hutchings, vice-president.

Aerovox Makes New Moves

W. MYRON OWEN, president of Aerovox Corp., announced the appointment of G. Milton Ehlers as chief research engineer. He has held positions as director of research with the Globar Corp. and chief ceramic engineer with Globe Union. From 1946 until his recent appointment, he was president of the Herlec Corp. of Milwaukee, a subsidiary of the Sprague Electric Co.

In another move, two of the largest divisions of Aerovox, the Wildor manufacturing operation and the ceramic capacitor operation of the Hi-Q division, were merged. Wildor has moved from Cleveland to three Hi-Q plants in New York and South Carolina. The combined

Measurement of

- Impedance
- Inductance
- Capacitance
- Resistance
- Dissipation Factor (D)
- Storage Coefficient (Q)
- Plot Impedance Functions



310A Z-Angle Meter

The type 310A Z-Angle Meter measures impedance directly in polar coordinates as an impedance magnitude in ohms and phase angle in degrees: Z/θ

Impedance Range: .5 to 100,000 ohms, covered by a single dial and a four position range switch.

Accuracy: ± 1%

Frequency Range: 30 cycles to 20 kc. for impedances below 5000 ohms, measurements can be made up to 40 kc. For frequencies from 100 kc. to 2 mc., write for specifications for the type 311A-RF Z-Angle Meter.

Phase Angle Range: 0° to 90° Direct reading on panel meter. Meter is also Calibrated in D and Q.

Phase Angle Accuracy: Within 2° of meter indication.

Internal Oscillator: 60 cycles and 400 cycles. Terminals are provided for an external, variable frequency signal generator for measurements at other frequencies.

In the field, the laboratory, the production test floor or the class room, the extreme accuracy and the simplicity of operation has proved the type 310A Z-Angle Meter to be a superb and reliable instrument.

Write now for more detailed information.

ENGINEERING REPRESENTATIVES

Chicago, Ill. — UPtown 8-1141
Cleveland, Ohio — PRospect 1-6171
Waltham, Mass. — WAltham 5-6900
Rochester, New York — Monroe 3143
Dayton, Ohio — Michigan-8721
Amprior, Ont., Can. — Amprior 400
Hollywood, Cal. — HOllywood 9-6305
Dallas, Texas — DIxon 9918
Roseland, New Jersey — Caldwell 6-4545
Wyncote, Pa. — Ogontz 8805
Silver Spring, Md. — Sligo 7-550

TECHNOLOGY INSTRUMENT CORP.

533 Main Street · Acton, Massachusetts · Tel. ACton 3-7711

HERMEFLEX*



Cut-away view of HERMEFLEX* approximately twice actual size.

. . . TRANSMITS ROTARY MOTION THROUGH A METAL-TO-METAL SEAL

Through the ingenious application of a toggle and metal bellows, the HERMEFLEX provides a positive metal-to-metal seal of shaft rotation through a wall of solid metal. Employing no gaskets nor sliding seals this device is a compact, unitized seal essential to the control of hermetically sealed instruments, electronic devices and high vacuum apparatus.

At present the HERMEFLEX is produced in two standard diameters—1-inch and ½-inch. These units are designed for the manual control of shaft rotation in pressure differentials up to 1 atmosphere. Your inquiries for HERMEFLEX developments to meet different duty cycles, special environmental conditions or other unusual problems, are cordially invited.

Bulletin will be sent upon request.

**PATENTED U. S. Patent Office. Trade name copyrighted.*

KEARFOTT COMPONENTS INCLUDE:

Gyros, Servo Motors, Synchros, Servo and Magnetic Amplifiers, Tachometer Generators, Hermetic Rotary Seals, Aircraft Navigational Systems, and other high accuracy mechanical, electrical and electronic components.

Kearfott

SINCE 1917

CREATIVE ENGINEERING
PRODUCTION ACHIEVEMENT

KEARFOTT COMPANY, INC., 1150 McBride Ave., Little Falls, N. J.
Midwest Office: 186 W. Randolph St., Chicago 1, Illinois
West Coast Office: 253 N. Vinedo Ave., Pasadena, Calif.
A General Precision Equipment Corporation Subsidiary

operations will be known as the Hi-Q division of Aerovox but the Wildor name will continue to be carried on all resistor products of the Hi-Q division.

Elwood Schafer Joins CBS-Hytron

Elwood W. Schafer

ELWOOD W. SCHAFER, former vice-president of National Union Radio, has been named assistant to Charles F. Stromeyer, vice-president in charge of manufacturing and engineering at CBS-Hytron.

Schafer was for seven years an engineer with GE and has served as chief factory engineer on receiving tubes for RCA.

His duties at CBS-Hytron will be to assist in planning expansion of the firm's tv tube manufacturing facilities, including operation of a color tube pilot plant.

Tinnerman Products Makes Changes

A. H. TINNERMAN, president of Tinnerman Products, announced five organizational changes in the engineering and sales departments of the company.

Lawrence H. Flora, director of engineering since early this year, has been appointed to the newly-created post of director of sales. He joined the Tinnerman engineering staff in 1942 and served as head of the product development department until 1949 when he became chief engineer.

In his new capacity, Flora will coordinate and integrate field activ-

Mark your own symbols, numbers, lettering, on your small parts, tools, identification and name plates . . . easily, simply, quickly . . . tracing from a master with the GREEN ENGRAVER.

Widely used in electronic and plastic fields, in machine tool shops and wherever permanent marking is needed. The GREEN ENGRAVER engraves equally well on metals, plastic, wood, hard rubber and glass.

✓ Fact-filled folder on request . . . showing how economies in costs, labor and time are achieved with the GREEN ENGRAVER.

✓ Routs ✓ Models ✓ Profiles ✓ Engraves

Etching attachment and other special equipment for industrial uses are available. ✓

Green Instrument Co.
INCORPORATED

363 PUTNAM AVE., CAMBRIDGE, MASS.



for lacings that stay put!

GUDELACE

BRAIDED NYLON LACING TAPE*

A New and Revolutionary Type of Lacing

- Saves time, saves money, greatly reduces the number of rejects
- Won't "bite through" insulation
- Won't cut wiremen's fingers or cause dermatitis
- Ties easier, ties tighter and cuts down on slipping of knots

Let GUDELACE answer your lacing problems.

Write for FREE samples and prices.

*Patent Pending.

GUDEBROD BROS. SILK CO., INC.
Electronics Division, Dept A
Main Office: 12 South 12th Street, Philadelphia 7, Pa.
225 West 34th Street, New York 1, N.Y.

BE SAFE WITH

Q-max

A-27

LOW-LOSS LACQUER & CEMENT

- Q-Max is widely accepted as the Standard for R-F circuit components because it is chemically engineered for this sole purpose.
- Q-Max provides a clear, practically loss free covering, penetrates deeply, seals out moisture, imparts rigidity and promotes electrical stability.
- Q-Max is easy to apply, dries quickly and adheres to practically all materials. It is useful over a wide temperature range and serves as a mild flux on tinned surfaces.
- Q-Max is an ideal impregnant for "high" Q coils. Coil "Q" remains nearly constant from wet application to dry finish. In 1, 5 and 55 gallon containers.

Communication Products Company, Inc.
MARLBORO, NEW JERSEY
(MONMOUTH COUNTY)
Telephone FReehold 8-1880
CPC

EEPCO

DC MOTOR OR GENERATOR
This small permanent magnet, ball-bearing unit—As a motor: 1/125 H.P. at 6000 RPM continuous duty. As a generator: output 4 watts at 6000 RPM—5 volts per 1000 RPM. Dimensions: 1-29/32" x 1-1/2" x 1-13/100".

SHADED POLE MOTOR — for sound recorders, air circulators, many other applications. 4-pole, 2 or 4 coil construction. Will operate from 115 volts, 60 cycle a.c.

The RIGHT power supply for mobile equipment is an EEPCO specialty

Outstanding experience in producing rotary electrical equipment to meet rigid specifications is an integral part of every EEPCO product.

Whether your problem involves an industrial or highly developed military unit, EEPCO's complete research and engineering facilities are at your disposal. Contact EEPCO today for special design assistance that can provide you with the best solution.



DYNAMOTOR OPERATES FROM 12-24-32 VOLTS
Output of this remarkably compact unit is 500 volts at .100 amperes. Dynamically balanced armature has 4 windings.

ELECTRO ENGINEERING PRODUCTS CO.
609 W. LAKE STREET, CHICAGO 6, ILLINOIS

• P-M DC MOTORS & GENERATORS • CAPACITOR TYPE MOTORS • UNIVERSAL MOTORS
• DC MOTORS & GENERATORS • SHADED POLE MOTORS 2-4-6 Pole • P-M AC GENERATORS



Unusual Applications demand GTC Transformers

The illustrated "electric fencer" is a product of Parker-McCrory Mfg. Company. More than 6,000,000 farmers save time, money and labor with this Parmak Electric Fencing.

Parmak Electric Fencers are guaranteed to perform exactly as represented. This emphasizes the need for "GTC" Transformers which will meet the most rigid requirements.

If your application is unusual or standard, we suggest you consider "GTC" — proven transformers where maximum performance is essential.



The illustrated, a typical "GTC" product, is used in the Parmak Electric Fencer...

We welcome your inquiries.

GENERAL TRANSFORMER COMPANY

serving industry since 1928

18240 Harwood Avenue, Homewood, Illinois

(Suburb of Chicago)

GTC

ities of the sales force and continue to direct policy of the engineering department.

Edward E. Griger, who joined the company in 1943 and was assistant sales manager, has been named sales manager. He absorbs many of the duties of William H. Taylor, Tinnerman's former general sales manager who resigned to become director of purchases for Packard Motor Car Co.

William L. Seitz, formerly in charge of development engineering, has been appointed chief engineer. He has been with the company for 12 years. Clarence Van Neil takes Seitz's former position.

John Balint, formerly in charge of product engineering, has been advanced to the post of new product manager. He joined the company in 1947, coming from Ford Motor Co.

Cook Names Anderson And Washburn

Alton D. Anderson

ALTON D. ANDERSON has been appointed chief engineer of the Cook Research Laboratories, succeeding D. C. McDonald who resigned. Earl L. Washburn has been named technical head of the systems development section.

Anderson spent over 10 years as research engineer with the Naval Ordnance Laboratory and as chief of the pressure mechanisms development section. Since coming to Cook in 1950, he has been director of the systems development section and most recently assistant chief engineer. He will continue to have responsibility for the company's

work in oceanographic instrument development, digital computer research and design, rocket instrumentation, and coordination of overall technical programs in addition to his new duties as chief engineer.

Washburn, who has worked for the past two years as a project engineer at Cook on atmospheric systems studies to determine the optimum organization, technique and equipment for use in such systems, was a senior project engineer for over seven years with Wallace Tiernan Products Co. In his new position, he will be in charge of all engineering phases of geophysical and physics research as well as digital computing equipment and special test instrumentation development.

Sprinkle Joins Ampex Corp.

MELVIN C. SPRINKLE, formerly chief engineer for Shrader Manufacturing, has been appointed audio sales manager of the Washington, D. C. office of Ampex Corp. For many years he was in the sales engineering department of Altec Lansing Corp.

Sarkes Tarzian Changes Personnel

G. EANNARINO, director of Sarkes Tarzian rectifier division, announced that Stanley Niciejewski has been named sales manager. Alfred D'Urso was promoted from sales engineering to assistant sales manager of distributor sales. Fred Lucas joined the division as assistant sales manager of industrial sales. He was previously employed by Federal Telephone and Radio in rectifier engineering and sales.

Du Mont Realigns TV Transmitter Division

ADDITION OF new sales engineers and revision of duties of the present staff have been made by the television transmitter division of Du Mont.

C. E. Spicer has been promoted

Pencil-Thin

FOR EASIER, FASTER SOLDERING OF:

- Electronic Circuits and Parts
- Aircraft Connectors
- Pin Type Plugs
- Wire-to-Wire
- Terminals
- Radio and TV Chassis
- Instruments
- Printed Circuits

Here is an all-new production tool expressly designed to make small and miniature soldering simpler and surer than ever before. It is so fast that some joints can now be soldered in less than 1 second! . . . so much lighter and easier to handle than soldering irons or guns that a woman can use it all day long without fatigue! Check this unique combination of features against your job requirements:

GETS INTO SMALL, TIGHT SPOTS because of smaller electrode pencil.

NO HEAT DAMAGE—instant resistance heating makes sound joints before resistors, condensers, printed circuits, terminal fibre, etc., can be damaged. Pinpoints the heat!

NO "COLD FLOW JOINTS"—resistance principle *requires* that metal be heated before the solder will flow. Tap switch adjust heat as needed.
SAFE—soldering pencil uses harmless (6v) voltage and high amperage from separate step-down transformer.

LESS FIRE HAZARD—electrodes are hot only when in use.

LESS REPLACEMENT COST—only low cost electrodes to buy.

TIPS FOR EVERY SMALL JOB
—2 sizes of double carbon, single carbon with ground clamp, double metallic. May also BE USED AS SOLDERING IRON —two sizes of chisel tip irons.

SOLD THROUGH LEADING DISTRIBUTORS

MAIL FOR FURTHER DATA

IDEAL INDUSTRIES, Inc.
1055 Park Avenue, Sycamore, Illinois

Please send catalog data on NEW IDEAL THERMO-TIP.

NAME.....
COMPANY.....
CITY.....ZONE....STATE.....
ADDRESS.....

Want more information? Use post card on last page.

No more worries about
FREQUENCY RESPONSE
or
WRITING SPEED.

The NEW and PHENOMENAL

HATHAWAY Type SC-16
OSCILLOGRAPH

with 6 elements is *flat from 0 to 200,000 cycles per second*, and its traces have a writing speed of *5 million inches per second.*

Fast transients and high-frequency phenomena now can be accurately recorded.

Several types of continuous-drive record magazines are available for 6-inch sensitized paper and film, and for 35-mm film. The magazine shown on the oscillograph at the left accommodates 100-foot rolls of record paper.



Drum-type magazines, both small and large, are valuable for short high-speed records. The large drum-type magazine at the left has a drum 3 feet in diameter and 6-inches wide. It can be driven at 3000 RPM for a *chart speed of 6000 inches per second* when high resolution is needed. It can be used to take one 10-foot record or a larger number of shorter records.



The ASC-10 6-element direct-coupled amplifier will drive the SC-16 oscillograph from potentials of millivolt level.

Useful for strain recording to 100 Kilocycles.

AUTOMATIC OPERATION Initiate a transient with the oscillograph, or let the transient start the oscillograph.

QUICK-CHANGE TRANSMISSION for wide range of record speeds.

PRECISION TIME LINES.

Z-AXIS MODULATION for timing to one-tenth millisecond.

QUICKLY-INTERCHANGEABLE LENS STAGES for different record and trace widths.

Write for Bulletin 2G1-K for details.

Write for FREE copy of Hathaway Engineering News

Hathaway
INSTRUMENT COMPANY
1315 SO. CLARKSON STREET • DENVER 10, COLORADO

to sales operations manager and manager of the sales engineering department.

Joining the division's staff are R. B. Bollen, formerly engineering supervisor for WDTV; F. D. Bonvouloir, formerly chief engineer of WAAB; L. O. Keys, formerly a Philco microwave engineer; F. Klimowski, former maintenance supervisor for the Stavid Engineering Co.; L. Litchfield, formerly a Du Mont research engineer; W. K. Terrell, an engineering supervisor for WABD and N. C. Ritter, formerly a Keith Electric Construction Co. engineer.

Morris A. Mayers, educational tv consultant, has been appointed general manager of Du Mont network closed circuit operations.

Stephen Pozgay, sales representative, has resigned to become manager of station WNAM-TV in Appleton, Wisc.

Audio Devices Acquires Advance

AUDIO DEVICES of New York has acquired the assets and goodwill of Advance Recording Products of Long Island City, N. Y., according to an announcement by William C. Speed, president of Audio.

Founded in 1941, Advance Recording was one of the oldest companies in the U. S. in manufacture of recording-disc blanks for radio stations, recording studios and phonograph record producers.

American Mica Moves

THE AMERICAN MICA Insulation Co. of Newark, N. J. has completed its move to Manasquan, N. J. where it will occupy expanded facilities for the manufacture of fabricated mica parts for the electronics industry.

Ford Names Assistant Chief Engineer

THEODORE JARVIS has been promoted to assistant chief engineer at the Ford Instrument Co., according to William Newell, vice-president for engineering. Jarvis, who is now responsible for engineering work connected with atomic energy

Priced Right!

WIRE FORMS

& Metal Stampings



High-speed, quality production with custom-made precision. Wire formed to any shape for every need.

IMMEDIATE CAPACITY FOR DEFENSE SUB-CONTRACTS

STRAIGHTENING & CUTTING
Perfect straight lengths to 12 ft.
.0015 to .125 diameter

WIRE FORMS
.0015 to .125 diameter

SMALL METAL STAMPINGS
.0025 to .035 thickness
.062 to 3 inches wide

Specializing in Production of Parts for Electronic, Cathode Ray Tubes & Transistors

Write for illustrated folder.
Send Blueprints or Samples for Estimate.

ART WIRE and STAMPING COMPANY
1 BOYDEN PLACE
NEWARK 2, N. J.



SCOPE DOLLY MODEL 1

- Convenient Height and Viewing Angle
- Lightweight Aluminum Construction
- Adjustable to Hold Portable Scopes
- Recommended by Laboratories Wherever Used
- Ball Bearing Swivel Rubber Tired Casters

$38.50
FOB Louisville, Ky.

TECHNICAL SERVICE CORP.
1404 W. Market St. Louisville 3, Kentucky



Pat. Applied for

ADJUSTABLE POLYSTYRENE PRECISION CAPACITOR

Capacitance Available—1 to 10 UFD.
Voltage Available—100 to 400 VDC.
Insulation Resistance—10^6 MEG./MFD.
Temp. Coeff.—100 P.P.M. Per °C (—20 °F to 140 °F)
Dialectric Absorb .015%; Dissipation .0002
1% Nominal Tolerance—Resetability: ±.0001 MFD.

Ideal as SECONDARY STANDARD or for TEST EQUIPMENT

NOW BEING USED BY LEADING ANALOG COMPUTER MFRS., *including* Reeves Inst. Corp.; Convair, Goodyear Aircraft; Beckman Inst.; Jet Prop. Lab.; Electronic Associates.

SOUTHERN ELECTRONICS COMPANY
239 W. Orange Grove Ave. Burbank, Calif.

Precisely fabricated to the most

Critical Tolerances

for electronic devices

Miniature and Subminiature Radio Tubes-Television Tubes Hearing Aid Tubes

Our technical skill will improve the performance of condensers, neon electrodes, soldering irons, electrical appliances, gauge glasses, diaphragms, stoves, mica washers, and for all other mica applications.

•

We guarantee that the quality of our mica will reduce your shrinkage costs!

•

Send for our "HANDBOOK on FABRICATED NATURAL MICA"

Quality— *Since 1929*

INDUSTRIAL MICA CORPORATION
225 So. Van Brunt St.
Englewood, New Jersey

PRECISION-MADE...FOR DEPENDABILITY

WIRE-WOUND RESISTORS

There are many makes of resistors—but there is only one I-T-E quality. I-T-E wire-wound power resistors and precision resistors are especially designed and *precision-built* to meet the exacting standards required for critical electronic applications.



I-T-E fabrication combines laboratory precision and close quality control with modern production methods. As a result, you can obtain the exact type of high quality resistor you want—in any quantity you need.

I-T-E POWER RESISTORS

Non-hygroscopic ceramic foundations are in accordance with JAN specifications.

Purest resistance wires are uniformly wound to prevent shorted turns and excessive hot spots. All connections silver-soldered.

Vitreous enamel coating (organic if required) provides a glazed moisture-repellent surface with fast heat-dissipation qualities.

Advanced production methods assure high stability, long life.

Standard Tolerance: ±10%. ±5% and less made to order.

Standard fixed resistors: 5-200 watts
Adjustable resistors: 10-200 watts
Oval resistors: 30-75 watts
Ferrule resistors: 12-200 watts
Special resistors: built to specifications

I-T-E PRECISION RESISTORS

High-quality wire alloys are used—free from particles of impurity and grain growth.

Automatic precision winding assures even tension—eliminates hot spots.

Hermetic or vacuum-impregnated sealing protects against destructive effects of salts, moisture, and atmospheric conditions.

Accelerated aging process prior to calibration assures accuracy.

Critical quality control eliminates all resistors which do not come up to high I-T-E standards.

Standard Tolerance: ±1%. Available in specified tolerances down to ±0.05%.

TYPE A: lightweight, hermetically sealed—for precision operation up to 125° C. Surpass JAN R-93 A, Characteristic A, and MIL R-93 A specifications.

TYPE B: vacuum-impregnated, moisture-resistant. For JAN R-93, Characteristic B, specifications.

RATINGS from 0.01 ohm—10 megohms, 0.125—5 watts.



High sensitivity Deflection Yokes and compact, high-quality Focus Coils are also available in many types and ratings

FOR DETAILS— WRITE FOR CATALOG R-100.

WIRE-WOUND RESISTORS

RESISTOR DIVISION OF I-T-E CIRCUIT BREAKER CO.

1924 HAMILTON ST. · PHILADELPHIA 30, PA.

projects, recently completed a year's study at the Oak Ridge School of Reactor Technology. Ford instrument specializes in the manufacture of computers for the armed services.

Cal-Tronics Moves

CAL-TRONICS CORP., manufacturer of test equipment, has moved to a new plant in Los Angeles. The building, containing 20,000 sq ft of floor space, provides executive offices and 3,500 sq ft for engineering, with the balance devoted to manufacturing and assembly. Employing 65 people at present, it is expected that employment will double with the new plant.

Williams Named Jensen Chief Engineer

Philip B. Williams

THOMAS A. WHITE, president of Jensen Maufacturing, announced the appointment of Philip B. Williams as chief engineer. He joined the company 11 years ago as a member of the engineering staff.

In his new position, he will be in charge of all product design, development and research for the company.

Bristol Expands

BRISTOL CO., manufacturers of automatic instruments, has completed an expansion of its socket screw division. New facilities include a new building equipped with the latest types of precision equip-

ment for screw manufacture.

The company also promoted three executives, according to announcements by Harry E. Beane, vice-president of sales.

D. C. Sanford, applications engineer, who joined the company in 1937, has been appointed manager of the applications engineering department.

F. W. Borchers, who joined Bristol in 1922 and was appointed assistant sales manager in 1948, has been named general sales manager.

Ernest Nuber has been appointed sales manager of the instrument division of th company. He joined Bristol in 1929 and, previous to his new post, held the position of manager of the applications engineering department.

Broadcast Engineers Attend RCA Course

A TOTAL OF 77 broadcast engineers from tv stations throughout the U. S. and Canada attended RCA's 17th Technical Training Program. The clinic, conducted by the Engineering Products Department, is designed to meet demands for instruction in operation and maintenance of new uhf and vhf tv broadcast equipment.

Stewart Appointed By Maico

W. E. Stewart

W. E. STEWART has been appointed director of engineering for the Maico Co., acording to an announcement by L. A. Watson, president.

Stewart spent the past 11 years

SPECIALISTS IN THE DESIGN AND MANUFACTURE OF

- Electro-Acoustic Devices
- Custom Printed and "Packaged" Circuitry
- Plastic Molding
- Coil Winding
- Transformers
- Electronic Component Assemblies

COMPONENT RELIABILITY and MINIATURIZATION

TELEX, INC. ELECTRO-ACOUSTIC DIVISION

CAN MEET YOUR MOST EXACTING DESIGN AND PRODUCTION REQUIREMENTS

The Electro-Acoustic Division of Telex, Inc., offers you an expertly staffed, modern laboratory, engineering know-how and the finest in production facilities. The variety of special skills at your disposal in Telex personnel and plant facilities means quick and cost-saving solutions for your design and production problems.





WRITE, WIRE OR PHONE:
J. R. Anderson
Electro-Acoustic Division
TELEX, INC.
Telex Park, St. Paul, Minn.
Phone — Nestor 7211

U.S.C.
M H (Miniature Hex)
CONNECTORS
feature VIBRA-SHOCK RESISTANCE
VISUAL INDEXING CONTACT DEPENDABILITY



1 Visual indexing boss provides visual as well as mechanical polarization.

2 U. S. C.'s miniature Hex type series with precision engineered lock spring (L S) and lock ring (L R) provides positive and dependable locking, eliminating disengagement possibility under shock or vibration conditions.


MH-5

MH-7

MH-9

MH-4 & 12 contact connectors now available.

We invite inquiries on your sub-miniaturization problems.

USC's complete engineering, tooling and production facilities are geared to produce quality connectors, allied components and assemblies. Our over 25 years experience is at your service.

MH-Brochures available on request.

U. S. COMPONENTS, Inc.

Want more information? Use post card on last page.

with RCA Victor and was in charge of broadcast audio and tv film engineering.

He was chief engineer for WOI in Ames, Iowa from 1934 to 1939 and spent two years in civil service before joining RCA Victor. He has been active in standardization of audio and magnetic recording equipment, serving on standarization committees of several industry associations.

Little To Establish Midwest Office

ARTHUR D. LITTLE, Inc. of Cambridge, Mass. will open a new midwest liaison office in Chicago, according to Earl P. Stevenson, president. The new office will maintain a staff to carry out technical-economic, technical-audit and market research surveys in that area.

J. R. Kirkpatrick will be manager of the office. He previously participated in the industrial development activities of the company on behalf of the Puerto Rican government.

National Research Appoints Moore

RICHARD S. MORSE, president of National Research Corp., announced the appointment of James H. Moore as general manager of Vacuum Metals Corp., a subsidiary.

Moore, formerly director of metallurgical research for National, has for several years been in charge of equipment and process development concerned with the vacuum melting, casting and fabrication of high-purity metals and alloys that are now being produced by Vacuum Metals.

An increased backlog of orders indicated the need for the appointment of a general manager to coordinate production and sales efforts of Vacuum Metals Corp., president Morse stated.

Nine Join Hughes Technical Staff

J. N. CONSTANT, R. L. Crone, G. M. Greene, E. E. Herman, C. S. McCormick, D. R. McKim, J. H. Parsons, M. Phister, Jr. and W. Rose have joined the technical staff

Miniature Connectors by U. S. C. means Contact Dependability



1 Individual processing of each contact assures quality control throughout with 100% dependability of contact.

2 Guide pins have the feature of a 1.16" D hole to provide easy assembly to chassis or hood with as simple a tool as a paper clip. This eliminates possible distortion of Guide pin.


MI-14 MI-21


MI-18 MI-34


MI-20

MI-50 contact connectors now available.

We invite inquiries on your sub-miniaturization problems.

USC's complete engineering, tooling and production facilities are geared to produce quality connectors, allied components and assemblies. Our over 25 years experience is at your service.

MI-Brochures available on request

U. S. COMPONENTS, Inc.

Want more information? Use post card on last page.

ALFAX UNIVERSAL RECORDING PAPER

For the first time there is available an indelible recording paper—ALFAX—that is NOT subject to humidity, temperature of capillary action problems usually associated with pen and ink or papers marked by arcing or heat.

ELECTRICITY IS THE INK THAT MARKS ALFAX

Alfax paper can be marked by current as low as one volt and is instantaneous, permanent and stable. Highly sensitive Alfax is capable of fourteen steps by simply varying the current through the paper.

Alfax is the only paper that is capable of high speed recording, stable before or after recording, is non-transferable, has low current consumption at high speeds, can record at high humidity over all temperature ranges, is smudge proof and non-toxic, widths from ¼" to 72".

Alfax opens a whole new field of monitoring and recording of phenomena which never before have been done easily and cheaply.

THIS MONTH'S EXAMPLE



Recording Directly Cathode Ray Tube Phenomena — One group using a new recorder employing Alfax Paper reports to us that they have been able to reproduce terrain, shore lines, harbors from cathode ray tube information in many cases better than photography.

Request Booklet—describe your problem

Alfax Paper & Engineering Co.

Alden Research Center, Westboro, Mass.
ENGINEERING SERVICE TO RECORDER MANUFACTURERS

1500 VOLT Regulated POWER SUPPLY
For Photo-Multiplier Tubes

Front View of Model 710-PR Power Supply

Continuously Adjustable from 600 to 1500 V.D.C. at 0-1 Milliamperes
POSITIVE TERMINAL GROUNDED

Regulation: Output voltage varies less than .01% per volt change of line voltage. Output voltage varies less than 1 volt with variations of output current between 0-1 milliampere. (Internal impedance less than 1000 ohms.)

Also available with 2 or 3 independently regulated and independently adjustable outputs.

Write for Descriptive Bulletin

MODEL 710-P
Cabinet Mounted
$190.00*

MODEL 710-PR
Standard Rack Mounting
$195.00*

Models Available With Negative Terminal Grounded (Substitute letter "N" for "P" in model designation)
*Prices not F.O.B. Chicago

FURST ELECTRONICS
3322 W. Lawrence Ave., Chicago 25, Illinois

XCELITE Hand Tools
PREFERRED BY THE EXPERTS

4 New "Good Right Hands" For You!

1. 10" TV STANDOFF INSULATOR PLIER, also a heavy-duty all-purpose plier, has grooved lower jaw, recessed upper jaw for non-slip grip to open or close standoff insulators.
2. 6" XCELITE DIAGONAL PLIERS, drop-forged, with keen, hand-honed blades, like all XCELITE cutters.
3. 7" DIAGONALS—this and the above added to our regular line by popular request.
4. 9" SIDE CUTTER, a rugged "right hand" for you on 1001 jobs.

XCELITE INC *Ask your supplier or write us today!*

(Formerly Park Metalware Co., Inc.)
Dept. C
Orchard Park, N. Y.

For Originality LOOK TO XCELITE

Saratoga Industries

STAR PERFORMANCE AS MANUFACTURERS OF TRANSFORMERS, REACTORS, FILTERS, TOROIDAL COILS FOR THE ELECTRONICS INDUSTRY

Now in its ninth year of operation, Saratoga Industries, Inc. has built a solid reputation for the manufacture of precision windings. Approved for in-plant testing under MIL-T-27, Saratoga Industries, Inc. is also prepared to handle all types of commercial production. Saratoga engineers invite your inquiry to help solve your problems relating to reactors, transformers, filters and windings of all types.

SARATOGA INDUSTRIES, INC. SARATOGA SPRINGS, N. Y.

Simplifying **HF** *Power Measurement*

Model 67 TERMALINE

DIRECT-READING R-F WATTMETER

30 mc to 500 mc
(to 1000 mc if specified)

50 ohms

Triple Range 0-25 watts
0-100 "
0-500 "

Type N Input Connector
(Adaptor for PL-259 supplied)



● Model 67 is a larger type Wattmeter than the well-known AN-ME-11/U (our Model 611) R-F Wattmeter. Specifically designed for fixed station transmitters to 500 watts output, it may be used nicely on low range for mobile gear. Provided with an aluminum cased, shock-mounted meter, Model 67 is as simple to use as a DC voltmeter. Now in general use throughout the industry, TERMALINE Wattmeters may be depended upon for fast, accurate and repeatable power readings

NON-RADIATING
... Accuracy — 5%

RUGGED CONSTRUCTION
... Size — 17" x 9" x 6"
Wght. — 30 pounds

BIRD ELECTRONIC CORP.
1800 EAST 38TH ST., CLEVELAND 14, OHIO
TERMALINE Coaxial Line Instruments

NEELY ENTERPRISES
Hollywood • San Francisco
Albuquerque

EARL LIPSCOMB ASSOCIATES
Dallas • Houston

MAGNATRAN

PRODUCTS ARE BETTER★

For HEAVY DUTY HIGH VOLTAGE



34 KW 17,000 V.D.C.

YES . . . WE BUILD BETTER EQUIPMENT BASED ON MANY YEARS OF EXPERIENCE

★While this word has been overworked in many instances, we will be pleased to demonstrate the extras built into our transformers to make them better.

← NEW UNITIZED RECTIFIERS

For high voltage D.C. sources . . . lower initial cost . . . minimum upkeep . . . convenient — ready to connect to AC. line and D.C. load . . . compact — requires minimum floor space.

Askarel Immersed Filter Reactor 50,000 Volt Test

AIR . . . OIL . . . ASKAREL

Plate Transformers . Filament Transformers . Filter Reactors . Modulation Transformers . Distribution Transformers . Pulse Transformers . Testing Transformers . Precipitation Transformers . General Purpose Transformers . Hi-Voltage Transformers.

WRITE FOR DETAILED INFORMATION

MEETS STANDARDS OF AIEE-NEMA

A NAME SYNONYMOUS WITH EXPERIENCE

MAGNATRAN INCORPORATED
TRANSFORMERS AND ELECTRICAL EQUIPMENT
WALTER GARLICK, JR., PRESIDENT
246 SCHUYLER AVE., KEARNY, NEW JERSEY

MAGNATRAN ®

of Hughes Research and Development Laboratories in Culver City, Calif.

Littlefuse Promotes Jack D. Hughes

Jack D. Hughes

JACK D. HUGHES has been promoted to the position of vice-president and operations general manager for Littlefuse of Des Plaines, Ill. He formerly served as vice-president in charge of sales. In his new post, he will continue to supervise sales and will assume responsibility for the purchasing, production, production control and time study departments of the company.

Rotron Appoints Berkeley Williams

BERKELEY WILLIAMS has been appointed assistant chief engineer of Rotron Manufacturing Co., according to an announcement by J. Constant van Rijn, president.

Williams, who has had 11 years of technical experience in development engineering at Sperry, will help promote the company's program of design and development in the field of cooling devices for electronic equipment.

Barth Manufacturing Undergoes Reorganization

BARTH MANUFACTURING CO. of Milldale, Conn. has been sold and reorganized and is now incorporated as Barth Engineering and Manufacturing Co. The new company will emphasize engineering development and production of electronic, electro-mechanical and elec-

tro-hydraulic control equipment and will continue to manufacture sheet metal working machinery.

Head of the new concern is Charles Russell, who was previously associated with the Eclipse Pioneer Division of Bendix as an engineering head.

John K. Mitchell, who is vice-president and general sales manager, was formerly connected with Sperry Gyroscope, serving for several years as that company's representative to the U. S. Navy.

Chief engineer of the new firm is Harvey M. Nilson, who was previously senior engineer with the Allen D. Cardwell Co.

Charles E. Gregory has been named plant superintendent.

Vitro Elects White Executive V-P

GEORGE WHITE, JR., has been elected executive vice-president of Vitro Corp. of America, according to an announcement by J. Carlton Ward, Jr., president.

Mr. White, with Vitro since 1946, has been a director and vice-president of its parent, the Vitro Manufacturing Co., and has served as chairman of the board and president of another subsidiary, Vitro Chemical Co. He is now executive vice-president, a director and member of the executive committee of the three companies.

CBS-Columbia Names Eight Engineers

ALBERT BECKMAN, Theodore H. Cook, Jr., Israel Melman, Frank J. Powers, Eugene W. Rose, Robert E. Savold, Fred T. Schick and Edward S. White have been named to engineering positions with CBS-Columbia.

Beckman, who has been named a mechanical project engineer on government assignments, was associated with Tele King as a mechanical project engineer and head of the drafting department.

Cook, who previously worked on the development of color tv receivers and studio equipment at RCA Laboratories, has been appointed

Attention!! • EXECUTIVES • SALESMEN • PUBLIC OFFICIALS • POLICEMEN • FIREMEN • OUTDOOR MEN REPORTERS • FIELD INSPECTORS • DOCTORS • LAWYERS, ETC.

DICTATE IN YOUR CAR with ATR INVERTERS

for changing your battery current to A.C. Household CURRENT Anywhere .... in your own car!!

INCREASE SALES EFFICIENCY! DICTATE SALES REPORTS ACCURATELY AND PROMPTLY! SAVE TIME!

$25.55 AND UP

ATR INVERTERS . . . especially designed for operating standard 110 volt A.C. Tape Recorders, Wire Recorders, Dictating Machines and Electric Razors IN YOUR CAR.

EASY TO INSTALL — EASY TO OPERATE

There is an ATR INVERTER for most applications for invert ng D.C. volts. ages (ranging from 6 volts D.C. to 220 volts D.C.) to 110 volts A.C. . . . Specially Designed for operating A.C. Radios, Tape Recorders, Wire Recorders, Dictating Machines, Electric Razors, Record-Changers, Television Sets, Amplifiers, Address Systems, Radio Test Equipment and most small electrical and electronic devices. FROM D.C. VOLTAGES IN AUTOMOBILES, BUSES, TRUCKS, SHIPS, TRAINS, PLANES AND IN D.C. DISTRICTS.

Additional information available upon request.

FREE! ATR INVERTER! . . . given away every 30 days to lucky registrant of preceding month. Mail a postcard as your registration request today!

A VALUABLE TIME SAVER FOR:

- TRAVELING SALESMEN—Dictate reports in your own car. Send your dictated reports in daily to your home office or sales manager.
- FIELD INSPECTORS & INVESTIGATORS—Dictate your field inspection reports in the field—on the spot. Give the complete story factually and completely. Include your clients recordings also.
- DOCTORS—Dictate and record your house calls on the completion of your call while everything is fresh in your mind. Have these records for transcription by your office girl.
- LAWYERS—Record evidence in the field at your client's premises. Obtain factual and complete witness reports, etc.
- EXECUTIVES—Dictate in your car all business matters while on trips for pleasure or business.
- PUBLIC OFFICIALS—Dictate complete field reports in your car. Obtain recorded opinions and expressions of Mr. Public in the field. Dictate your business reports while traveling.
- POLICE SQUAD CARS—Dictate accident reports right on the scene complete and factual. Include witness recordings at the same time. Have the complete story available by dictation.
- FIRE TRUCKS—Dictate your fire reports factually and complete on the scene and include witness reports. Have the complete story.
- AMBULANCES—Dictate complete reports of your ambulance run. Include witness recordings, etc.
- ADVERTISING AGENCIES—Use AC operated animated or illuminated displays in or on the car.
- FISHERMEN & HUNTERS—Use your electric razor on camping trips, operating in your car. Also small home radios and other electrical or electronic items.
- CAMPERS—Make your camping and outing trips more exciting using mix-masters, tape recorders, or wire recorders operating from your car battery.
- WAREHOUSE & MATERIAL HANDLERS—Dictate your inventory and material handling reports on the scene, in the warehouse, yard, or wherever you may be.

TYPE	Input DC Volts	AC Output 60 Cycles	Output Wattage Intermittent	Output Wattage Continuous	List Price	RECOMMENDED APPLICATIONS
6-LIF	6	110 volts	40	35	$25.55	For operating small fea-power AC motors, electric razors, small radios and small portable dictating machines having wattage consumption less than 35 watts.
12-LIF	12	110 volts	50	35	25.55	
6-RSD	6	110 volts	85	75	35.25	Recommended for operating small AC motors, Radio Sets, PA Systems, Amplifiers, and Radio Test Equipment having input wattage consumption within continuous output wattage ratings indicated.
12-RSD	12	110 volts	125	100	39.25	
6-ISQ-F	6	110 volts	85	75	49.95	Especially recommended for operating dicating machines, wire recorders, tape recorders, and small AC motors and electronic or electrical apparatus having input wattage consumption within continuous output wattage ratings indicated.
12-ISQ-F	12	110 volts	125	100	49.95	
6T-HSG	6	110 volts	175	150	86.45	For operating large tape recorders, wire recorders, P.A. Systems, amplifiers, and small TV sets having input wattage consumption within the continuous output wattage ratings indicated.
12T-HSG	12	110 volts	250	200	90.45	

See your jobber or write factory ✓ NEW MODELS ✓ NEW DESIGNS ✓ NEW LITERATURE

"A" Battery Eliminators, DC-AC Inverters, Auto Radio Vibrators

ATR AMERICAN TELEVISION & RADIO CO.

Quality Products Since 1931

SAINT PAUL 1, MINNESOTA—U. S. A.

Want more information? Use post card on last page.

GRC CUTS COST AND TIME!

TINY
INJECTION MOULDED
PRECISION
PLASTIC PARTS



Completely automatic . . . parts delivered trimmed, ready for use, in one operation, with Gries' speedy, specialized production facilities.
NYLON A SPECIALTY



INDIVIDUAL PARTS
No limit on smallness. Intricacy and precision — our unique features.

INDIVIDUAL INSERTS
Automatic insert feed permits wide variety of product possibilities.

Maximum Size:
.025 oz.—1¼" long
NO MINIMUM SIZE!

CONTINUOUS INSERTS
Small members accurately spaced on tape cord, wire, chain, etc.

LOW MOLD COSTS

Write Today for Demonstration Samples

GRIES REPRODUCER CORP.
151 Beechwood Ave., New Rochelle, N. Y.
Phone: NEw Rochelle 3-8600

ANOTHER BETTER TOOL...
for the ELECTRONIC ENGINEER and the RESEARCH SCIENTIST

A versatile instrument for research involving high repitition rates



MODEL B-2
PULSE GENERATOR

PULSE WIDTH: variable in 4 ranges from .2μs to 1,000μs
PULSE RISE TIME: .02 μs
PULSE AMPLITUDE: ± 80 volts open circuit
INTERNAL IMPEDANCE: 93 ohms
INTERNAL DELAYS: variable in 5 ranges from 0 to 10,000 μs with respect to synchronizing pulse
INTERNAL REPETITION RATES: variable in 4 ranges from 10 cycles at 100 KC
SYNCHRONIZING PULSES: 5—independently available at separate output jacks

- High duty factors
- Can be triggered externally and for single pulse operation
- Calibrating potentiometers are provided for each range

Write for complete data: our Bulletin E-B-2

Rutherford ELECTRONICS CO. 3707 S. ROBERTSON BLVD. CULVER CITY, CALIFORNIA

senior electronic engineer.

Melman, formerly engineer in charge of the advanced development laboratory, has been advanced to chief engineer of the special products division where he will be concerned with the development of CBS-Columbia color tv receivers.

Powers, who has been named head of the industrial engineering department, held a similar post at the Burndy Engineering Co. and also has had managerial posts with Federal and Sperry.

Rose, previously employed in a supervisory capacity by Western Electric, has been appointed electronic engineer for military equipment.

Savold, who has been appointed manager of field engineering, has been employed by the company for the past eight years, four of them as foreman of the test department and the last four as field engineer. In his new post he will coordinate all field engineering activity with the engineering and quality control departments.

Schick, formerly head of product design for Du Mont and assistant chief engineer of Emerson, has been named chief mechanical engineer for the company.

White, who has been named engineer in charge of the advanced development laboratory, will continue advanced circuit development work, as well as act as consultant on special engineering projects.

Rath Joins Jack & Heintz

WILBERT A. RATH has joined the purchasing department of Jack & Heintz of Cleveland and will serve as company buyer of special electrical items and fasteners. He replaces Jack Mills, who has established offices as manufacturers' representative. Rath has held buying and stock control positions with Clark Controller and Weldon Tool. His purchasing experience covers a period of 11 years.

Smith Named At Burroughs

JAMES W. SMITH has been named assistant to the director of the advanced development division at the

For SPECIFIED PERFORMANCE
Specify JELLIFF RESISTANCE WIRE

COMPLETE CONTROL OF MANUFACTURE . . .
A WIDE RANGE OF EXPERIENCE . . .
A WIDE RANGE OF ALLOYS . . .

make JELLIFF the ideal source of
Resistance Wire to assure your Product's

Performance According to Specs.

Precision resistors—rheostats—relays—thermocouples—ohmmeters—bridges—high-temperature furnaces can all benefit from the **PLUS-PERFORMANCE of JELLIFF RESISTANCE WIRE**

THE C. O. JELLIFF MANUFACTURING CORPORATION SOUTHPORT, CONN.

Detailed Enquiries Welcomed. Address Dept. 25

SEALING
DIPPING
POTTING
IMPREGNATING

INSULATING
FUNGUSPROOFING
MOISTUREPROOFING
HEAT CONDUCTING

WAXES BIWAX COMPOUNDS

Developed and produced for manufacturers of electronic components and other electrical units.

Specifications and samples available on request.

Information relative to your problem or application will enable us to make suggestions and recommendations.

BIWAX CORPORATION 3445 HOWARD STREET SKOKIE, ILLINOIS

Cosmic

CONDENSER SPECIALISTS SINCE 1923

ELECTROLYTIC and PAPER TUBULAR CONDENSERS FOR A.C. D.C. SETS PHONOGAPHS etc.

COSMIC RADIO CORPORATION
853 Whittier St., Bronx, N. Y.
Phone LUdlow 9-3360

HIGH QUALITY- LOW COST

the new Brown-Hill 18 and 24 position

18-Position Switch

SELECTOR SWITCHES

24-Position Switch

ONLY in these new, precision 18- and 24-position selector switches do you get . . . contacts and rotor blades made of solid, fine silver providing constant low-resistance contact . . . a 20° positive detent mechanism with beryllium copper springs and stainless steel detent rollers . . . wiper blades made of laminated fine silver to phosphor bronze for added springiness and more positive contact . . . low-loss Dow-Corning-200 impregnated steatite (grade L-5 or better) . . . voltage breakdown, 4000 Volts A.C. (peak at 60 cycles) . . . current carrying capacity at 60 cycles, 30 amps. . . . available in 1 to 6 gangs.

If yours is a switching problem where constant stability in conductivity is critical and where resistance, inductance, capacitance and low initial cost must be kept to a minimum, it will pay you to investigate Brown-Hill switches. R-F engineers will be glad to cooperate on your switching problems. Samples for inspection and test are available on a 30 day memo.

AVAILABLE SOON! Miniature & Subminiature, top quality Brown-Hill Versions with fine silver contacts.

WRITE FOR DATA

R. F. ELECTRONICS, INC.
291 N.E. 61st St. - Miami 37, Fla.

QUALITY • QUANTITY • *QUICKLY*



The Right Connection . . . right now!

Dage RF connectors are designed *right*, engineered *right*, built *right*—and available *now*. Each part is carefully made—Dage connectors are precision assembled to assure a sure connection.

Check your specifications—be sure you're *right*—ask for Dage radio frequency connectors

ALWAYS SPECIFY

DAGE

Dage is versatile . . . any standard or special RF connector can be quickly produced at Dage. Write for Catalog 101.

RADIO FREQUENCY CONNECTORS

DAGE ELECTRIC COMPANY, INC., 67 NORTH SECOND STREET, BEECH GROVE, IND.

FREQUENCY STANDARDS

MICROMETER HEADS

JOB TESTED!

- Precision Built
- Positive Resetting
- Automatic Compensation for Spindle Wear
- Positive Spindle Lock
- Anodized Finish

FIELD CHECKED!

AVAILABLE IN SEVERAL MODELS —WRITE FOR LITERATURE

This new precision instrument affords the highest degree of accuracy in reading. Elimination of backlash assures positive resetting in either direction of rotation and automatically compensates for wear of spindle and nut thread. Calibrations are large, legible, easy to read. Features include temperature compensation construction, thimble stop to prevent thread jamming and a positive spindle lock. The instrument is easily reset for calibrated instruments.

Frequency Standards

General Offices: ASBURY PARK, NEW JERSEY
PLANTS AT NEW SHREWSBURY AND ASBURY PARK, N. J.

Telephone:
ASBURY PARK 1-1718

Research Center of Burroughs Corp. He was formerly administrative assistant to the vice-president in charge of research.

William Sage Acquires Sealtron

William C. Sage

WILLIAM C. SAGE acquired the name and a substantial portion of the assets of the Sealtron Co. of Cincinnati, manufacturers of hermetic seals and subassemblies, for over $250,000.

Officers of the new corporation are: W. C. Sage, president; H. G. McKnight, vice-president; L. M. Paul, secretary and treasurer. Directors are L. M. Paul, chairman; F. Bader, O. W. Hirschfield, W. H. Nieman and William C. Sage.

Warwick Names Chief Designer

WILLIAM A. WAGNER, formerly chief divisional designer for Montgomery Ward, has been named chief product designer for Warwick Manufacturing, according to John S. Holmes, president. He will be in charge of product design for the company's Chicago and Zion, Ill. plants and for its Chicago research and development lab.

Nuclear-Chicago Elects Chairman

E. B. TILTON, formerly president and treasurer of Vilter Manufacturing, has been elected chairman of the board and chief executive

officer of the Nuclear Instrument and Chemical Corp. of Chicago.

Before joining Vilter, he was a vice-president of the Bank of America and of the Central Trust Company of Illinois.

Sterling Names Howard Meuche

HOWARD O. MEUCHE has been named production superintendent of Sterling Engineering Co. of Laconia, N. H., according to an announcement by Morehead Patterson, chairman and president of American Machine and Foundry, the parent company. In his new position, Meuche is responsible for general coordination and all production activities.

Prior to joining Sterling, he was assistant plant manager of National Union Radio Corp. for three years. From 1947 to 1950 he was associated with Tevel Laboratories as production manager. He previously was with RCA as quality control engineer.

Scott Elects New Officers

JOHN S. MECK, president of Scott Radio Laboratories, announced that Russell Eggo, previously secretary-treasurer, has been elected executive vice-president and secretary of the company. Samuel W. Block has been elected to the newly created position of assistant secretary.

Scott officers re-elected for the fiscal year are Meck, president and treasurer; C. E. Palmer, vice-president in charge of production; and Louis Woycke, vice-president in charge of engineering.

Re-elected by stockholders to the board of directors were: John S. Meck, Hugh Conover, S. W. Black and Russell Eggo. Newly elected to the board is Daniel Gibson, Indiana insurance executive.

New Firm Formed In Philadelphia

RESE ENGINEERING CORP., a new company that will specialize in the design and production of test equipment and components for the computer field, has been established in

is this your timing problem?
Sorry! A. W. Haydon Company
Can't Help Your Timing Here.
Only a "pro" and practice can straighten you out!
But - - -
We are the "pro's" for precision timing. Come to us with these timing problems. You'll find that we have solved more complex A.C. and D.C. timing problems than just about anybody else. Maybe we have already solved yours. It costs you nothing to find out. Write for catalog.
A.W. HAYDON COMPANY
235 NORTH ELM STREET
WATERBURY 20, CONNECTICUT
Design and Manufacture of Electro Mechanical Timing Devices

NOISE and FIELD INTENSITY METER Model NF-105

(Commercial Equivalent of AN/URM-7)



CONFORMS TO
MIL-I-6181B
MIL-I-16910

ENGINEERING DATA

- Frequency range 20 MC to 1000 MC by means of three quick-change tuning heads. At least one RF amplifier with tuned input is employed for each tuning range.
- Easy frequency scanning by means of single tuning knob.
- Built-in impulse noise calibrator flat to 1000 MC (Output externally available).
- 4½" logarithmic indicating meter reads carrier or true peak.
- Aural slideback operation.
- Input VSWR better than 1.2 to 1.
- Built-in regulated "A" and "B" supply.
- Complete line of accessories available.

Write today for additional information and our complete catalog

edp EMPIRE DEVICES PRODUCTS CORPORATION
38-15 BELL BOULEVARD • BAYSIDE 61 NEW YORK

MANUFACTURERS OF
FIELD INTENSITY METERS • DISTORTION ANALYZERS • IMPULSE GENERATORS • COAXIAL ATTENUATORS • CRYSTAL MIXERS

THE MIGHTY MIDGET

Guarantees His Product Precision

made in all shapes, sizes and alloys with or without self-flux

SOFT SOLDER PREFORMS

MADE BY ALPHA

Alpha's preformed solders, in any shape or size, cut many hours from your production time. You can select washers, rings, coils, cut shapes, drops, pellets, solder foil, to fit your specific needs. They save you considerable money and materials in repetitive soldering processes.

Speed Automatic Soldering

for flame, oven or induction heating

Increase Production • Melts Faster • Guarantee Product Precision • With Or Without Self-Flux Save Labor Costs • Designed For Your Application • All Sizes, Shapes, Alloys • Stronger, Smoother Joints.

AVAILABLE IN

★ CEN-TRI-CORE *ENERGIZED* ROSIN-FILLED
★ TRI-CORE *LEAK-PRUF* ACID-FILLED
★ SINGLE-CORE
★ SOLID WIRE
★ SHEET SOLDER

Please consult us on your soldering problems. Trained Field Engineers always available to assist you. Small or large quantities.

for further information

write . . .

ALPHA METALS, INC.

59 Water St., Jersey City 4, N. J.

Specialists IN SOLDER For Over 50 Years

Want more information? Use post card on last page.

Philadelphia, Pa. Other activities of the company will include the development of specialized apparatus for industrial and scientific applications.

Jerome Rovins, formerly associated with Philco, has been appointed president. Julian Saltz is vice-president of the firm.

Pyroferric Buys Manufacturing Plant

Pyroferric plant

PYROFERRIC Co. of New York City has purchased the building that houses its manufacturing plant.

Expansion of both production and laboratory facilities is now in process. The additional space now available will enable the company to meet increasing demands for iron cores and other powdered metal components.

Timberlake And Wallack Join RCA Field Sales

FLOYD A. TIMBERLAKE and Chester A. Wallack have joined the Engineering Products Department of RCA Victor.

Timberlake, who previously served as tv operations supervisor of ABC in Chicago, was, at one time, chief engineer of the city of Gary, Indiana. In his RCA post he will be the broadcast field sales representative in the company's central region with headquarters in Chicago.

Wallack, who becomes field sales representative of the broadcast marketing division for the Denver

To Readers Outside North America

● All Tektronix products are fully warranted against defective materials and workmanship for one year. Such a warranty is possible because a continuing effort is made to select "long-life" materials, control the design for maximum component life, and sufficiently test the completed product so that any latent defects will appear prior to shipment. Tektronix transformers, manufactured in our own plant, carry an indefinite warranty.

In the event of failure, please contact the Tektronix Distributor in your country. Your Tektronix Distributor has complete engineering data to provide valuable assistance in repair, maintenance, and application; and in some cases maintains a stock of replacement parts. Where an authorized distributor has not yet been established, please contact the Tektronix Field Maintenance Department at the address below.

Television Oscilloscope



Variable delayed sweeps at the frame rate let you examine any portion of the television picture—from complete frames to small portions of individual lines. Any one of the picture lines may be located and observed in minute detail. A touch on the Field Shift button provides a quick switch to corresponding line or lines in the opposite field. Sweep magnifier expands the image 3x or 10x for detailed examination of synchronizing pulses. Internal markers are available to check timing accuracy. All other features meet Tektronix standards for laboratory-type oscilloscopes.

Sensitivity dc to 10 mc—0.15 v/cm to 50 v/cm; 2 cps to 10 mc—0.015 v/cm to 50 v/cm
Risetime—0.04 μsec
Signal Delay—0.25 μsec
Time Base Range 0.1 μsec/cm to 0.01 sec/cm continuously variable, accurate within 5%
4 KV Accelerating Potential 5" flat-faced crt
Amplitude Calibrator Variable duty cycle square wave
Line-Indicating
Video Output Lines being observed on the Type 524-D are brightened on picture monitor
All DC Voltages Electronically Regulated
Supply Voltage 105 to 125 v or 210 to 250 v, 50 to 60 cycles

Type 524-D Oscilloscope—$1180
f.o.b. Portland, Oregon

Tektronix, Inc.
P. O. Box 831A
Portland 7, Oregon
Cable: TEKTRONIX

Want more information? Use post card on last page.

Phaostron

RUGGEDIZED, GLASS-TO-METAL HERMETICALLY SEALED INDICATING INSTRUMENTS

Provides accurate and sensitive means for electrical measurement under extreme conditions of shock, vibration, weather conditions and climate. They meet the dimensional requirements of JAN-1-6 and are completely interchangeable with existing types in AC and DC ranges.

The component parts of these instruments are fabricated, assembled, adjusted, tested and hermetically sealed under controlled and exacting conditions free from contamination in our *Air-conditioned, Temperature-Controlled* plant.

ENVIRONMENT FREE ELECTRICAL EQUIPMENT by Phaostron

PHAOSTRON COMPANY, 151 PASADENA AVENUE, SOUTH PASADENA, CALIF.

"Nielsen" COMPRESSION SPRING DRAW PULL CATCHES

WITH SPRINGS CONCEALED



SIZE: 2¾" LONG X 1⅛" WIDE

SIGNAL CORPS NO. SC-B-83314

70-Pound Tension at ⅛" Deflection, the established application dimension.

Withstands 600-Pound Pull Test.

Nielsen Catches Carry "Certification of Compliance".

Get our Folders on Standard Catches and Draw Bolts and other Compression Spring Catches

NIELSEN HARDWARE CORP. 770 Wethersfield Ave., HARTFORD 14, CONN.

AFFILIATED WITH NIELSEN TOOL & DIE CO.

FOR QUALITY HARDWARE — GOOD SERVICE TO YOUR SPECIFICATION

Ferrites

Purified synthetic products of reagent quality. Controlled particle size and shape contribute to effective control of packing and shrinkage. Our know-how can help you accomplish best results.

Manufactured by highly modern processes under rigid laboratory control. This ad clipped to your letterhead will bring a working sample.

made with **HIGH PURITY**

MAPICO

RED FERRIC OXIDES

are TOP performers

COLUMBIAN CARBON COMPANY
MAPICO COLOR DIVISION
MANUFACTURER

BINNEY & SMITH CO., Distributor
41 EAST 42nd STREET, NEW YORK, N. Y.

PRECISION

SYNCHROS SERVO MOTORS RATE GENERATORS

Infra Electronic Corporation is playing an important part in the precision manufacture and assembly of electronic and electro-mechanical system components for the Military.

We invite your inquiry when commercially available units will not meet your system demands.

Custom design, development, and manufacture of Test Sets, Kits and Consoles for preflight check out and ground maintenance of airborne systems.

INFRA

Electronic Corp.

Roseland, New Jersey

Manufacturers of Precision Synchros

Want more information? Use post card on last page.

interested in **H-E*?.....**

Investigate

NOTHELFER "NWL" SPECIAL TRANSFORMERS

For ELECTRONICS, RESEARCH and SPECIAL INDUSTRIAL FIELDS

***HIGH EFFICIENCY**

Over 28 years' experience in the manufacture of special transformers to meet individual requirements. Built in quality proved by years of actual use.



From 10 VA to 300 KVA Dry-Type only. Both Open and Encased. 1, 2, and 3 Phase. 15 to 400 cycles.



NWL

NOTHELFER WINDING LABORATORIES

NEMA

9 ALBEMARLE AVE., TRENTON 3, N. J.

Bird COMPLETE JEWEL ASSEMBLIES WILL SPEED YOUR PRODUCTION



You'll be time and money ahead if you specify Bird complete jewel assemblies for your product. Rejects are eliminated, jewel breakage is minimized, and Bird jewel assemblies will keep your production running smoothly.

Bird Jewel Assemblies are furnished in the right mounting, rigidly inspected according to your specifications, ready for your assembly operations. Make a test — find out how Bird Jewel Assemblies can help your production. Send us a print of your specifications, and we'll provide samples for your own testing.

Our engineering staff is at your service for all small bearing problems.

Over 40 years of serving industry with Quality jewel bearings

Richard H. Bird & Co., Inc.

Sapphire and glass jewels · Precision glass grinding · Ferrite precision products · Sapphire stylii

1 Spruce Street, Waltham 54, Mass.

region, was formerly chief engineer of station KVGB in Great Bend, Kansas, where he served since 1948.

Heising Retires From Bell Labs

Raymond A. Heising

RAYMOND A. HEISING, president of the IRE in 1939, has retired from the Bell Telephone Laboratory after 39 years of service. Entering Western Electric in 1914, he conducted their first carrier experiments and constructed their first radio transmitters. He invented and developed transmitter circuits for the SCR 68 and CW 936 which were made for the military in World War I. He participated in engineering the pioneer transoceanic commercial radiotelephone circuits. For the last nine years he has been engaged in patent engineering and other patent work.

Dr. Heising plans to continue his professional activities as a consulting electronic engineer and patent agent.

Smith And Jagmin Advance At Varo

JACK G. SMITH assumed the duties of chief engineer and Walter J. Jagmin, general counsel, took over duties vacated by Smith as plant manager, according to an announcement by Robert L. Jordan, vice-president of Varo Manufacturing Co.

Smith began with Varo as project engineer in the electrical design section in 1947. Jagmin joined Varo in 1949 as patent at-

torney and general counsel.

Jordan explained that the moves were made to fill the vacant chief engineer position and to further Varo's commercial production. In the past, the firm's production has been largely military and was concentrated on the development of precision electronic power supplies for use with airborne equipment.

Harrison To Receive Cresson Medal

GEORGE RUSSELL HARRISON, dean of science of MIT, will receive the Elliott Cresson Medal at the annual medal day ceremonies of the Franklin Institute of Pennsylvania.

In making the announcement, Henry B. Allen, executive vice-president and secretary of the Institute, stated that the award was being made for his valuable work in spectroscopy.

Largely responsible for the ten International Spectroscopy Conferences held at MIT, Dr. Harrison developed ingenious machines which automatically determine spectroscopic data. His work has culminated in the development of the MIT wave length tables.

Air Force Needs More Engineers

THE ROME AIR Development Center has jobs at salaries from $5,040 to $9,600 a year in all phases of electronic research and development, and in the installation and maintenance of radio, radar and wire-communications equipment.

Write the Professional and Scientific Recruiter, Rome Air Development Center, Griffiss Air Force Base, Rome, N. Y., or phone Rome-3200.

GPL Shifts TV Sales Organization

BLAIR FOULDS, vice-president, announced four changes in the sales organization of General Precision Laboratory.

E. Arthur Hungerford, Jr., returning from a leave of absence for special work with the Joint Com-

Why LAMBDA laboratory power supplies are among the most FREQUENTLY RECOMMENDED

RACK MODEL 28
Standard rack mounting.
Panel size 5¼" x 19".
Weight 16 lbs.

SPECIFICATIONS:

Input: 105-125 Volts AC, 50-60 cycles, 120 watts.

DC Output: Continuously variable from 200 to 325 Volts DC regulated from 0 to 100 ma max. Either postive or negative side of supply may be grounded.

DC Voltage Regulation: Output constant to better than 1% for loads from zero to full load and line voltage variations from 105 to 125 volts.

Noise and Ripple Output: Less than 10 millivolts rms for above ratings.

AC Output: 6.3 Volts AC at 3A unregulated.

ALSO AVAILABLE NOW: Model 28-M, with voltmeter and milliammeter.

Lambda power supplies are made by engineers who pioneered in this field and have continued to specialize in it. Used by many of the country's leading laboratories, Lambda units are recommended by them for value, versatility and dependable performance. Models for many purposes. Conservatively rated, constructed for long, trouble-free service, priced moderately. Fully guaranteed.

LAMBDA
ELECTRONICS CORP.
103-02 NORTHERN BOULEVARD
CORONA 68, NEW YORK

SEND FOR NEW CATALOG. Comprehensive, authoritative, up-to-the-minute. An important addition to your power supply reference library.

only one-tenth micro ampere
ACTIVATES
These Ultra-Sensitive Electronic RELAYS



Devtronics engineers have developed three new outstanding basic relay circuits. The sensing elements use activating currents of .1, .01 and .001 microamperes with input resistances as high as 500 megohms. Can be furnished with open or hermetically sealed snap-action relays with varying load carrying capacities up to 30 amperes non-inductive. Circuit response time may be varied from .004 seconds to .125 seconds.

Thermoregulation • Liquid Level Control • Pressure Control • Flame Sensing
Counting-Gauging • Safety Indicator • Position Indicator

Write TODAY for Detailed Bulletin

DEVTRONICS
INCORPORATED
221 N. HERMITAGE AVE.
TRENTON, N. J.
TRENTON 2-4029

Want more information? Use post card on last page.

DURANT
MFG. CO.
Specials
For RADAR, ELECTRONIC and INSTRUMENT APPLICATIONS

High speed, non-reset, direct reading counter to indicate increment of measurement in radar navigation instruments.

High speed degree-type counter to indicate degrees, minutes and tenths of minutes for navigating equipment.

"Y" 2-figure Rotary Counter used in navigating instruments.



Special counter for use on Tape Recorder to indicate the position of tape passing through the recorder.

Special high speed Y-type counter for Goniometer application.

WRITE FOR LITERATURE

DURANT MANUFACTURING CO.
1912 N. Buffum St,. Milwaukee 1, Wis.
112 Orange Street, Providence 3, R. I.

PRODUCTIMETERS SINCE 1879 *Count Everything*

Want more information? Use post card on last page.

mittee on Educational Television, has been named manager of the tv department.

Nathaniel M. Marshall has been designated as eastern district manager. He has been a field representative for GPL since 1950.

Edward Manzo, who has been assigned as southeastern district manager, has a background of tv studio design for the Navy.

Robert F. Johnston, formerly chief engineer of radio station WILL, has joined the company as manager of the midwest district.

Avien-Knickerbocker Appoints Frary

RUSSELL H. FRARY has been named director of service engineering for Avien-Knickerbocker, according to Leo A. Weiss, president.

Frary was formerly with Northwest Bell Telephone and was, for many years, associated with sales and service engineering for Minneapolis Honeywell and Associated Air Services.

"Mr. Frary will be in charge of Avien's rapidly growing sales and field service engineering force", Mr. Weiss stated, "which now comprises 10 percent of our total work force."

Van Horn Elected Telecom President

John Van Horn

JOHN VAN HORN has been elected president of Telecom, a new company in Kansas City, Mo. that will

HUMPHREY LINEAR POTENTIOMETER

ABSOLUTE PRECISION LINEARITY
Gives noise-free, sharp out-put when subjected to vibration, dither and other environmental conditions. Rugged, lightweight, with exclusive internal design.

Dual element construction

Resistance Values to 13,000 ohms/inch, higher in special units.
½" diam. for strokes up to 3"
¾" diam. for strokes over 3"

SPECIAL CONSTRUCTION AVAILABLE FOR HIGH TEMPERATURE APPLICATIONS

NEW HUMPHREY ACCELEROMETER

Readily adapted to wide selection of g ranges.

Accuracy: From plus or minus 1% at zero, to plus or minus 2% at maximum acceleration.

A RUGGED, COMPACT ACCELEROMETER with integral Potentiometer take-off, giving amazing accuracy under adverse conditions, due to the rugged construction. No "cross-talk".

FULLY TESTED AND QUALIFIED FOR MILITARY APPLICATIONS

Pacific SCIENTIFIC CO.
1430 Grande Vista Ave., Los Angeles 23, Calif.
25 Stillman Street, San Francisco 7, California
1915 1st Avenue South, Seattle 4, Washington
806 East Abram Street, Arlington, Texas
EASTERN REPRESENTATIVE: AERO ENGINEERING INC.
Mineola L.I., N.Y. • Indianapolis • Baltimore • Montreal
Want more information? Use post card on last page.

DEPENDABLE *Miniature*
RADIO FILTERS



Type 111

—Saves space !
—115 V ac/dc, 20 amp.
—Excellent attenuation
—Feed through installation
—Flange mounting bracket
—Corrosion & fungus resistant

If you have radio interference problems, write or wire us, TODAY !

HOPKINS *Engineering Co.*

FACTORY: 2082 Lincoln Ave., Altadena, Calif. *SYcamore 8-1185*
Offices in WASHINGTON, D. C. and DETROIT

IF IT'S NEW . . . IF IT'S NEWS . . . IT'S FROM ELCO



Illustrated here, is Elco Corporation's new 7-pin printed-circuit socket, which in addition to its electrical and mechanical efficiency and stability, incorporates many advantages never previously available. Aware for a long time of the growing importance of printed circuitry, Elco engineers have been busy in their laboratories on the development of sockets for practical commercial application of this new technique. And again, Elco introduces a quality product.

Positioning of the Elco printed circuit socket in the chassis is quick, easy, positive. No strains or stresses are transmitted to the chassis or to the socket insulator; yet electrical contact is excellent at all times. The improved contact design automatically centers tube pins in position; resulting in positive contact retention with low resistance, producing optimum circuit performance. Contacts are made of brass or phosphor bronze, cadmium plated or beryllium copper silver plated. Insulators are of general purpose phenolic or ceramic materials. These Elco sockets are also available with shield clamps. Complete technical data is yours upon request; as is full information concerning Elco's complete quality-line of tube-sockets, shields, and sensational new Varicon connectors.

For Catalog Sheets, Call GArfield 6-6620 or Write ELCO Corp., 190 W. Glenwood, Phila. 40, Pa.

A NEW FAST 10 mc SCALER

0.1 Microsecond Resolution

SPECIFICATIONS Model 410

INPUT CIRCUIT:
POLARITY: Positive pulses only.
AMPLITUDE: Minimum amplitude of 5 volts required at low counting rates, increasing to 10 volts minimum at the maximum counting rate.
REQUIRED RATE OF RISE: Minimum of 10 volts per μsec.
INPUT IMPEDANCE: Greater than 5000 ohms.
RESOLVING TIME: 0.1 μsec.
MAXIMUM ACCEPTABLE UNIFORM RATE: 10mc or 10^7 counts/second, no lower limit on counting rate.
SCALING FACTOR: Neon light interpolation for reading residual counts.
OUTPUT:
POLARITY: Positive or Negative pulse selected by front panel switch.
PULSE CHARACTERISTICS: Triangular pulse of approximately 1 μsec. rise time, 4 μsec. width and 50-60 volt amplitude.
POWER REQUIREMENTS: 105-125 volts, 50-60 cycles, approximately 175 watts.
SIZE: 10-1/2" x 19" x 13" deep

Complete literature on request

EPIC **ELECTRICAL & PHYSICAL INSTRUMENT CORP.**
42-19 27th Street, L.I.C. 1, N. Y

PRECISION TRANSFORMERS



...built to fill your exact requirements... and to all government specifications.

No job too big or too small.

Development and design facilities available.

We specialize in

MAGNETIC AMPLIFIER development

YOU can improve the performance, life and reliability of your circuits . . . eliminate costly equipment maintenance and replacement part costs by using ATLAS Magnetic Amplifiers for:

1. Low level amplification
2. Regulated DC power supplies
3. Motor drive controls
4. Thermocouple and photocell to relay applications

We welcome inquiries. Send sketches of your circuit and list desired performance characteristics . . . we'll do the rest.

CONSTRUCTION TYPES:

- **Hermetically sealed**
- **Fosterite**
- **Scotch Cast**
- **Open types**

ATLAS *ATLAS ENGINEERING CO., Inc.*
3 EDGEWOOD ST., ROXBURY, MASS.

BOESCH
Window Winding Attachment

Provides fast and practical means for winding longitudinally along sides of core form.



BOESCH
Continuous Winding Attachment

Quick installation to provide continuous winding on toroidal to 360°. Adjustable for core size.

Designers and Builders of coil winding machinery, special machinery and equipment. Write for brochure.

WORLD'S MOST VERSATILE WINDING MACHINES

BOESCH
MANUFACTURING CO., INC
DANBURY, CONN.

NOW
Transistor Test Set

Plots all Parameters & D.C. Characteristics

This new Model T-61B Transistor Test Set not only measures parameters but it can be used with an X-Y Recorder to permanently plot these parameters as a function of any of the D.C. variables as well as any of the usual D.C. characteristics. Additional equipment to make it more convenient to measure grounded emitter parameters is also available.

The Model T-61B tests the small signal behavior of all point contact and junction transistors by measuring the four independent parameters of the four terminal equivalent circuit of the transistor — carrying out the measurements over the complete operating range. Permanent plotting of the parameters and D.C. characteristics under test is accomplished by adding a T61B105 Recorder Panel to permit attachment of a standard X-Y Recorder. A T61B106 Adapter provides a convenient method of measuring grounded emitter parameters.

For data sheets and complete information on Transistor Products diodes, transistors and transistor test sets, write Dept. E11.

TP
TRANSISTOR PRODUCTS, INC.
SNOW AND UNION STREETS, BOSTON 35, MASSACHUSETTS
AN OPERATING UNIT OF CLEVITE CORPORATION

manufacture telephone switchboards and other electrical and electronic specialties in the communication field. Marketing will be handled through established distributor channels.

Van Horn has been associated for the past five years with Midwest Research Institute, specializing in instrumentation and remote control applications. He has also been active as a consultant in industrial control design and specialized telephone engineering projects. He has devoted the past 14 years to the design and manufacture of telephone, electronic and electrical equipment.

Smith Moves To New Brooklyn Plant

New Smith plant

THE HERMAN H. SMITH Co. has moved to a new plant in Brooklyn, N. Y., according to an announcement by Herman Smith, president. The building, newly designed and constructed, is equipped with modern machinery for maximum efficiency in the production of plugs, jacks, switches, test leads and other electronic hardware for both commercial and military users.

Smith Named By Gray Research

NEWLAND F. SMITH has been appointed general manager of Gray Research and Development Co. of Manchester, Conn., according to an announcement by Walter E. Ditmars, president.

Smith was named assistant general manager earlier this year. He was previously director of general engineering for the Mutual Broadcasting System and WOR. He has also been associated with the television engineering group at RCA and has been with Philco Corp.

YOUR Professional Plans and SRI

Stanford Research Institute, an independent scientific organization, has a number of challenging opportunities for high-caliber engineering and technical people to join an expanding program. Work is currently under way on a wide range of advanced research projects.



ELECTRONIC ENGINEERS

experienced in circuitry, magnetic amplifiers, mechanical layout, product design, or miniaturization.

MECHANICAL DESIGNERS

having experience in layout, packaging or miniaturization techniques.

MACHINE-DESIGN ENGINEERS

for the development of automatic machinery to fabricate electronic equipment, with experience on automatic machinery for handling small parts.

PLASTICS TECHNICIANS

to process and apply plastic materials for fabrication of electronic equipment. Laboratory experience is essential.

The Institute is located on the San Francisco Peninsula. It is central to a growing electronic region; yet situated in an area of attractive homes, good schools and pleasant living.

Send full background details to Lucien G. Clarke, Department of Engineering Research, Stanford Research Institute, Stanford, California.

Want more information? Use post card on last page.

NEW BOOKS

Dielectric Aerials

BY D. G. KIELY, *foreword by Professor H. M. Barlow. Methuen's Monographs on Physical Subjects. Methuen & Co., Ltd., London; John Wiley & Sons, Inc., New York,* 132 *pages,* 1953, $2.00.

THIS IS A most interesting monograph on a subject about which too little is known. The author, according to Professor Barlow, has made considerable contributions to this subject. The references to his own work indicate that he, along with those others mentioned in the bibliography of some 29 citations, are working in a vitually virgin field.

For the most part the monograph deals with the mathematical attempts to analyze the action of nonmetallic rod, cylinder and horn antennas. Many pages are intensely mathematical, but for the reader not interested in these attempts to come to a full understanding of the radiation phenomena from dielectric antennas, there is much of interest and value. The experimental results of the investigators are described. The electrical, mechanical advantages and disadvantages of dielectric aerials make for thoughtful reading and cogitation.

There are five chapters and the bibliography; the chapters deal with the general introductory and historical remarks, wave propagation along a dielectric rod, dielectric rod aerials, dielectric tube aerials and other dielectric aerials. The nonmathematical portions are easily readable; in fact, the only portion of these passages which this reviewer could not fathom was this statement: "Short dielectric rods have been used in the apertures of hog-horns feeding cheese aerials."—K.H.

Sound Reproduction

BY G. A. BRIGGS. *The Wharfedale Wireless Works, London,* 368 *pages,* 1953, *Third Edition,* 17*s* 6*p.*

MR. BRIGGS has established himself as one of the most popular writers on the reproduction of

they're here!

TELEWAVE'S

Micropads

ATTENUATOR PADS — CALIBRATED WITH EXCEPTIONAL ACCURACY — MINIATURIZED — FREQ. RANGE: DC THROUGH MICROWAVE (X BAND) LOW VSWR

PAD TYPE	db drop	L (inches)
3D	3	2 1/8
6D	6	2 1/2
10D	10	2 1/8
20D	20	3 1/8

SPECIFICATIONS

Impedance	50 OHMS
Accuracy	±0.2 db calibrated at 1, 10, 100 MC and 1, 2, 3, 4, 5, 6, 7, 8, 9, 10 KMC
VSWR Ratio	Better than 2:1 throughout entire frequency range
Finish	Rhodium Flash over silver plate for optimum corrosion resistance and electrical conductivity
Power	¼ watt continuous duty at 25° C
Mating Connector	Mates with AN type UG-21B/U plug on one end and with AN type UG-23B/U jack at other

TELEWAVE LABORATORIES, Inc.

100 Metropolitan Avenue, Brooklyn 11, N. Y.

Export Dept., 13 E. 40th St., N. Y. 16

REPRESENTATIVES: Albuquerque · Atlanta · Boston · Chicago · Cleveland · Fort Worth · Kansas City · Los Angeles · New York · Ontario · Philadelphia · San Francisco · Seattle · Syracuse

Want more information? Use post card on last page.

WAVEGUIDE

Components

TO SPECIFICATIONS SINCE 1943

Tees	Bends
Mixers	Ratraces
Duplexers	Cavities
Rotating Joints	Pads
Filters	Phasers
Attenuators	Flanges

Electronic Assemblies
Special Purpose Components

For the complete story on *Premier's* fully integrated engineering, production and testing facilities, write Dept. *E* today for our new brochure.



PREMIER
INSTRUMENT CORP.
52 West Houston Street
New York 12, N. Y.

Want more information? Use post card on last page.

sound. His material is at a level accessible to the advanced amateur, usually with a sufficient base of engineering so that it is useful to the professional in the field. This third edition of his "Sound Reproduction" is greatly enlarged with new material, and has all his virtues of a concise style interspersed with a reasonable amount of chattiness. The book therefore assays out a very high percentage of useful information.

Among the valuable features of the book are oscillograms showing the frequency response of loudspeakers under many different conditions of loading, construction and magnetic field strength. These bring out clearly a lot of information that the seeker for loudspeaker perfection will find helpful. For instance, the prime importance of solidity in a loudspeaker mounting, to eliminate panel vibrations, is demonstrated. The ultimate solution, the brick or concrete enclosure, shows its superiority in the tests, but some less drastic recourses are offered, especially the double-front enclosure with sand between the panels. The fact that Mr. Briggs has a note on how to get a bag of sand thoroughly dry is an amusing reminder of the fantastic range of techniques a man gets mixed up with, when he loses his head about the reproduction of sound.

Mr. Briggs sums up his oscillographic investigation of reflex boxes with a set of rules for the experimeter, among which are: use a speaker with the lowest possible resonance; use the biggest possible enclosure, up to 9 cubic feet; use the lowest convenient cross-over in dual systems; avoid a tall shape, to reduce resonance effects.

Besides loudspeaker enclosures, Mr. Briggs covers the physics of the ear, room acoustics, crossover networks and intermodulation. In a second part, he reviews briefly present-day recording systems. There are some excellent microphotographs of record grooves under various conditions of wear. As he admits in his introduction, the book is "patchy", but this is a virtue: given the ground Mr. Briggs has set himself to cover,

YOUR OWN KNITTING COMES FIRST

You can usually profit most by sticking pretty close to your knitting. One aspect of our business is that of proving new designs with pilot runs. We can help you stick to your knitting by ironing the bugs out of new products for you. This will save you the extravagance of tying up your expensive equipment before you are all set to GO.

CONRAD & MOSER

Workers in Aluminum, Brass, Steel & Plastics

DESIGNING
ENGINEERING • MANUFACTURING
MECHANISMS • MACHINES
PARTS • TOOLS • DIES • MOLDS
STAMPINGS • CASTINGS
MACHINING • SHEET METAL
ENCLOSURES & CHASSIS
⅛ to ⅛ NAVY SPEC ALUMINUM
SPOT WELDING AND HELIARC WELDING.

2 Borden Ave.
Long Island City 1, N. Y.

CONRAD & MOSER · ESTABLISHED 1925 · APPLIED PRECISION

Want more information? Use post card on last page.

for PROVEN RESULTS *specify*

McGRAW-HILL

Mailing Lists

You can save time, avoid needless expense, increase your results by having McGraw-Hill Lists do your mail advertising job!

Three quarters of a century of practical experience is made available to you when you turn your direct mail jobs over to McGraw-Hill. And these seventy-five years of leadership in the development and perfection of lists *assure you the maximum results at the lowest cost* per order or inquiry.

Those who are acquainted with mailing lists know that year-after-year acceptance of lists does not come by chance or luck. Accepted lists, like McGraw-Hill's, hold their places by merit alone. Nor does success one day guarantee success the next. Vigilant eyes must constantly add new names, delete, change, check, recheck, etc. Inferior lists are dropped as soon as shortcomings are noticed . . . "good lists" yield to better lists.

For seventy-five years expert list users have preferred McGraw-Hill by long odds. No matter how few names you use—whether your business is large or small—the best lists, McGraw-Hill Lists, are the most economical in the long run.

The world-wide reputation McGraw-Hill has earned as builders of the finest mailing lists was born of constant research in our office and in the field—constantly adding new names . . . developing new markets, new avenues of revenue for direct mail list users.

McGraw-Hill Mailing Lists are built—and constantly maintained—to provide, as accurately as humanly possible, complete rosters of the industries we serve.

Investigate their tremendous possibilities in relation to your own product or service. Your specifications are our guide in recommending the particular McGraw-Hill lists that best cover your market. When planning your industrial advertising and sales promotional activities, ask for more facts or, better still, write today. No obligation, of course.

McGraw-Hill Publishing Co., Inc.

DIRECT MAIL DIVISION

330 W. 42nd Street, New York 36, N. Y.

Direct Mail Division, McGraw-Hill Publishing Co.
330 West 42nd Street, New York 36, N. Y.

Please send me, **at no cost,** mailing list information that will cover my markets.

Name ..... Title.....

Company .....

Address .....

City and State.....

Product or Service.....

Want more information? Use post card on last page.

GLUTTONS for PUNISHMENT
CORNISH
CUSTOM
CORD SETS
RUBBER . . PLASTIC . .
NEOPRENE . . .
Also
"NOFLAME-COR"
The Television
Hookup Wire
Designed, engineered and produced for YOUR products! For a delicate "walkie-talkie" or a huge arc welding unit . . . put your wire problems up to CORNISH experts!
"MADE BY ENGINEERS FOR ENGINEERS"
CORNISH WIRE CO., INC.
50 Church St. New York 7, N.Y.

Facts you should know about
HEYCO STRAIN RELIEFS!
the Nylon Bushings that Anchor cord to housing
CHASSIS
HEYCO
1. Absorb cord pull, push and torque
2. Insulate wire from housing
CUT PRODUCTION COSTS
IMPROVE PRODUCT QUALITY
APPROVED
SAMPLES? Send wire size and chassis information—
Try HEYCOS at no cost to you—today!
MADE IN ALL SIZES FOR CLOCK WIRE TO S-10/3 CABLE
HEYMAN MANUFACTURING COMPANY
KENILWORTH 2, NEW JERSEY
HEYCO ELIMINATES STRAIN ON TERMINALS
THE HEYMAN ORGANIZATION WITH 25 YEARS STAMPING EXPERIENCE HAS MODERN PRESS CAPACITY FOR OVER 2,000,000 FINISHED STAMPINGS PER DAY.
ASK FOR BULLETIN 33
HEYCO

and the high degree of usefulness to the experimenter that he imposes on his material, a wide range of topics is the natural result.—R. S. LANIER, *20th Century Fund.*

Industrial Electronic Engineering

BY W. L. DAVIS AND H. R. WEED. *Prentice-Hall, Inc., New York,* 1953, 514 *pages;* $11.35.

THIS BOOK is typical of a number of works with similar ambitious titles which contain selected discussions of a few topics in this broad field. The contents of the eleven chapters are briefly summarized below, but broadly speaking, the book may be considered to treat primarily the "power" or "large-current" aspects of industrial electronics.

A stated purpose of the book is "to present basic methods of analyzing and solving problems," and the authors have included many useful techniques. Nevertheless, this reviewer has the impression that too many topics have been covered somewhat too briefly to make the book outstanding. Many discussions are sufficiently detailed to demand the reader's careful attention, but topics are only rarely covered in a manner completely satisfying to an advanced student. The outstanding lack of references will be a disappointment to the general reader.

Line drawings and graphs are used freely, and most of them are clear and adequately labeled. Technical, grammatical, and typographical errors are relatively few. The index is notably adequate.

The early chapters described the general characteristics of gas tubes emphasizing power thyratrons and ignitrons, and the more common methods of control. There is a good and reasonably extensive treatment of single phase and polyphase rectifiers including controlled types.

The nature, characteristics and uses of semiconductor rectifiers are covered briefly with emphasis on copper oxide and selenium cells. The theoretical explanation of metal-to-crystal rectification is con-

IMMEDIATE DELIVERY!

S190A

REGULATED OUTPUT AMPLIFIER

Holds output level constant despite 40 db input level variations

- Adjustable noise threshold
- 75 db gain
- Low distortion
- 25/50/250/600 Ohms input
- 600 Ohm output
- $295.00 FOB Washington, D. C.

SCHUTTIG and CO.
INCORPORATED
9th and Kearny St., N.E.
Washington 17, D. C.

IMMEDIATE DELIVERY!



S178A

ANTENNA MULTICOUPLER

Operates 10 Receivers from One Antenna

- Antenna Impedance 50-1000 ohms
- Frequency Range 2-20 Mc
- Rack Mounting
- Used and Approved by many Government Agencies
- $308.00 FOB Washington, D. C.

SCHUTTIG and CO.
INCORPORATED
9th and Kearny St., N.E.
Washington 17, D. C.

Want more information? Use post card on last page.

fused by the supposition that the potential difference between two materials is the potential between their surfaces (here called the zero-energy levels) rather than between their Fermi levels as is actually the case. While the resulting energy-level diagrams permit a plausible explanation of rectification, it is unfortunate that they are misleading.

The treatment of phototubes appears to be an "extra" in this book, but does concisely assist a general reader to understand the principles of light measurement. Light is defined as "the visual sensation produced by that portion of radiant energy that is known as luminous flux." However, light is actually not visual sensation, but radiant energy evaluated in terms of its ability to produce this sensation; and luminous flux is analogous not to energy but to power. The derivation of an incremental equivalent circuit for a phototube is highly commendable. No mention is made of the effects of grid current in phototube amplifier circuits, even though these effects often constitute a design difficulty.

The chapter on Industrial Timing Circuits deals almost exclusively with the principles and operation of resistance welders and the *R-C* timing circuits used to control them. The sections on Servomechanisms and Regulation give a conventional mathematical treatment of first- and second-order systems, system stability, and the use of simple derivative and integral control, and offer a few examples in the area of voltage control of d-c generators. All-electronic voltage regulators are only briefly mentioned. A short chapter is devoted to the study of thyratron-controlled d-c motors.

Much of the basic mathematical theory of radio-frequency heating is presented. The material is adapted primarily from the book by Brown, Hoyler, and Bierwirth, and is perhaps excessively mathematical; the empirical nature of practical design problems is not stressed, and actual design equations are difficult to locate. The discussion of X-rays in the last chap-

for high permeability applications

now—the first time available . . .

PERFORMANCE GUARANTEED

TAPE WOUND CORES

ONLY MAGNETICS, INC.

offers Performance-Guaranteed Tape Wound Cores. Guaranteed performance to specifications means truly economical production of high permeability magnetic devices in your plant . . . and controlled buying by your purchasing department. If you haven't investigated Performance-Guaranteed Tape Wound Cores, why not let us send you the complete story?

FACTORY CORE MATCHING

For applications in which closely matched characteristics are required, save time and money by using the Magnetics, Inc. factory core matching service.

free engineering design service for high permeability magnetic applications

Magnetics, Inc. engineering is second to none in the field of high permeability magnetics. Services are free to customers.

Write for full information

MAGNETICS, inc.

Specializing in High Permeability Magnetics

Dept.E-2 BUTLER, PA.

Want more information? Use post card on last page.

New Technitrol Variable Pulser

* Wide pulse repetition frequency range from 20 cps. to 2.0 mcs.
* Pulse rise and fall times are symmetrical at 0.05 μs.
* Duration of pulse variable from 0.2 μs to 5.0 μs in steps of 0.1 μs.
* Stable pulse duration controlled by electric delay lines.
* Low impedance output, amplitude continuously variable from 0 to 40 volts without distortion.
* Trigger pulse precedes output pulse.

This reliable and versatile instrument, developed for our own use, has wide possibilities for application in many laboratories.

Write for Bulletin 186E.

TECHNITROL
ENGINEERING COMPANY
2751 N. 4th St., Phila. 33, Pa.

NEY'S SMALL PARTS PLAY A **BIG** PART IN PRECISION INSTRUMENTS



The Ward Leonard Electric Company's New Plunger Potentiometer-Type Rheostat, illustrated at the right, uses a sliding contact made of one of Ney's Precious Metal Alloys.

Paliney #7* Slider

The J. M. Ney Company has developed a number of precious metal alloys which are fabricated into contacts, wipers, brushes, slip rings, commutator segments, and similar components for use in electrical instruments. These Ney Precious Metal Alloys have just about ideal physical and electrical properties, high resistance to tarnish, and are unaffected by most corrosive atmospheres. Consult the Ney Engineering Department for help in selecting the right Ney Precious Metal Alloy which will improve and prolong the life and accuracy of your instruments.

*Reg. trade-mark

18NY838

THE J. M. NEY COMPANY • 179 Elm St., Hartford 1, Conn.
Specialists in Precious Metal Metallurgy Since 1812

ter is a good brief summary of the physics of production of X-rays and of some of their physical characteristics.

This book could serve as a text for those primarily large-current portions of the field of industrial electronics which it covers. In 500 pages, the coverage is frequently too brief for the inexperienced engineer, and the unfortunate lack of references limits the value of the work.—ELERY F. BUCKLEY, *Assistant Professor of Electrical Engineering, Massachusetts Institute of Technology, Cambridge, Mass.*

Fundamentals of Electronic Motion

BY WILLIS W. HARMAN. *McGraw-Hill Book Co., New York*, 315 *pages*, 1953, $6.50.

THIS BOOK deals with the mathematical processes and physical reasoning which are fundamental to an understanding of the principles of operation of the wide variety of electron tubes in existence today. There are several chapters devoted exclusively to the analyses of a few types of microwave tubes. This text will be very useful to any engineer who is entering the tube engineering field, as it will supply him with the fundamentals of the analytical approach to a great many problems in this area.

The author's primary objective, as quoted from the preface, is "to nurture the ability to deal wih new problems and new situations." Toward this end he has covered a large number of diverse problems. There is essentially no new material in this book. There are other texts on electron tubes, some specialized to certain tubes and some general, which treat the same material in greater detail on a slightly higher level. Professor Harman, however, gives a very clear presentation of the material which he covers. He explains not only the steps of the mathematical analyses but also conveys the physical meaning of the equations. After the completion of a section the reader is left with a feeling of a fairly complete understanding of the subject matter.

One of the most important assets

WANT THE BEST IN CAPACITORS?



Type UMP

Many, many notable advances in the art of capacitor design and manufacture have been made by the ILLINOIS CONDENSER COMPANY. As an example, ILLINOIS CONDENSER COMPANY has recently been awarded a patent on their unique and exclusive molded capacitor construction as featured in the UMP types.

For almost two decades, ILLINOIS CONDENSER COMPANY has been building quality capacitors and regular users include most all of the largest manufacturers of TV and radio sets. Their names literally compose the "blue book" of electronics.

To meet the ever increasing demand for ILLINOIS electrolytic capacitors, ILLINOIS CONDENSER COMPANY has built new plants and greatly increased production. Why don't you, too, discover why ILLINOIS capacitors are "first choice" of so many!

Write for Catalog!

ILLINOIS CONDENSER CO.
1616 NORTH THROOP STREET • CHICAGO 22, ILL.

PROTECTIVE COVERING

When you design or redesign a coil unit, remember: Proper covering is a coil's first line of physical defense. Have our design engineers recommend the correct covering to protect your coil. Coto-Coil Company, 65 Pavilion Avenue, Providence 5, R. I. New York Office: 10 E. 43rd Street, New York 17.

Coto PRECISION WOUND **Coils**

PHAZOR Pat. Pend. **PHASE METER MODEL 200A**

$349.50 F.O.B. New York, N. Y.

Measures phase shift in transformers, amplifiers, filters, and phase displacement networks.

- Measures from 0 to 360 degrees.
- Readings not affected by noise and harmonics.
- Phase shifts of the order of .01 degree can be measured employing special circuit techniques.
- Measures in-phase and quadrature components separately.

SPECIFICATIONS

Accuracy—Basic accuracy plus or minus 2 degrees. Plus or minus 1 degree due to meter error.
Noise and Harmonic Rejection ..... 40 db. down
Sensitivity ..... 6 millivolts full scale
Maximum Input Voltage ..... 125 volts RMS
Peak Input Signal ..... 400 volts
Frequency Range ..... 20 to 20,000 cps.
Input Impedance
High Gain ... 2.0 megohm shunted by 25 mmfd.
Low Gain ... 2.5 megohm shunted by 10 mmfd.
Reference Input Impedance ..... 4000 ohms
Power Supply ... 105 to 125 volts, 60 cps., 25 watts
Dimensions—Length 15 in., Hgt. 9 in., Depth 8 in.
Weight ..... 25 pounds

INDUSTRIAL TEST EQUIPMENT CO.
55 EAST 11th ST., N. Y. 3 - Tel. GR. 3-4684

MINIATURE SADDLE HEADER

FEATURES:

- Glass to metal compression sealed
- Miniaturized — vacuum tight
- Saddle design permits locking to standard saddle socket
- Other standard types from stock — special designs available



SCIENTIFIC ELECTRONIC LABS, INC.
866 Bergen Street — Bigelow 8-6553 — Newark 8, N. J.

TYPE VC-1258 ZERO BIAS
MINIATURE HYDROGEN THYRATRON
for generation of peak pulse power up to 10 KW

- max. peak forward anode potential — 1000 volts
- max. peak anode current — 20 amps
- max. avg. anode current — 0.05 amps
- max. heating factor (epy x prr x ib) — 1.0×10^3
- nominal Filament Power — 12.6 watts
- prr in excess of 10,000 pps possible at reduced ratings
- no hydrogen reservoir

write or phone

MERCURY TUBE CO.
JERSEY CITY, N. J.
26 JOURNAL SQUARE
JERSEY CITY 2-2663

of this book, as the author points out in the preface, are the numerous problems included in each chapter. At the end of each major section are offered problems based on the principles presented. For full comprehension of a subject, problems which stimulate thought and reasoning are essential, and the problems which Professor Harman uses in this text are well integrated with the reading material. The insight and understanding gained from faithful performance of the problems is invaluable.

The book begins with a discussion of units and basic electric field equations, such as Laplace's and Poisson's equations. Methods of solution of these equations are discussed. The equations of motion of electrons in a uniform electric field are then developed. The paraxial ray equation for an electric field is derived and some general properties of electrostatic electron lenses are considered.

The third chapter discusses the wave-particle quality of electrons, and interference phenomena resulting from electron diffraction are explained. The chapter concludes with a discussion of thermionic photoelectric and secondary emission and applications to electron tubes.

Electron motion in magnetic fields is considered next. The general equations of motion in an axial magnetic field are derived. The paraxial ray equation is obtained and general properties of magnetic lenses are presented. Space charge effects and motion in time-varying fields are treated in Chapters 5 and 6. The analyses contained in these first six chapters are utilized and extended in three of the remaining four chapters, which give operating principles of the klystron, the electron wave tube, the traveling wave tube, the traveling wave magnetron and the magnetron oscillator.

The final chapter deals with the relativistic effects in electron dynamics. These effects are applied briefly to some of the electron tubes treated above and to particle accelerators.

Professor Harman's book provides the mathematical tools and the physical analyses necessary for

VECO Stands for



ADVANCED DESIGN . .

A recent development in sensing elements provides the basis for a new and better approach to problems in measurement and control. VECO THERMISTORS have an extremely high negative temperature coefficient of electrical resistance. Their small size and extreme sensitivity to thermal changes offer engineers a circuit element to utilize in new applications, and for the improvement of older methods.

BEADS • WASHERS • DISCS • RODS

SOME PRACTICAL USES:

Time delay • Gas analysis • Volume limiting • Surge protection • Vacuum manometry • Flow measurement • Temperature control • Temperature measurement • Radar power measurement • Temperature compensation Oscillator stabilization • and many new applications being developed.

SEND FOR—
VECO THERMISTOR DATA BOOK

VECO VARISTORS react instantaneously to current or voltage changes, and have innumerable uses such as arc suppressing and regulating source voltages.

VECO GAS ANALYSIS CELLS employ Veco glass-coated Thermistors as sensing and reference elements (no open wires, therefore no corrosion).

Victory ENGINEERING CORPORATION
MANUFACTURERS OF:
Electronic & Thermal Control Instruments
Temperature Sensing Devices
Combustion Analyzers

Springfield Road, Union, N. J. Tel. UNionville 2-7150
Want more information? Use post card on last page.

HERE'S WHAT We MEAN BY—

Miniature BEARINGS!



Type CI Pivot Type Ball Bearings .043"-OD.

Smallest Ball Bearing Ever Manufactured Commercially

An RMB First

These bearings, developed by RMB, are not toys. Type C1, and the other ten sizes in the C series, are hard-working components of—

- Delicate Instruments
- Small Motors
- Scales and Gauges
- Small gear trains for clockwork
- Vibration Pick-ups
- Aircraft Instruments

—anywhere a miniature bearing is needed to reduce friction, where space is at a premium. Bring your miniature bearing problems to RMB. A complete line of over 250 miniature and instrument bearings including radial and roller types available for prompt delivery. Experimental quantities from stock.

Write for Catalog 11

RMB LANDIS & GYR, INCORPORATED
45 West 45th St. • New York 36, New York
Want more information? Use post card on last page.



RAWSON METERS

MULTIMETERS and REGULAR METERS
AC and DC types, multiple ranges, accuracy — ½ of 1%. 2 microamperes to 1 ampere DC. 2 milliamperes to 3 amperes AC.

ELECTROSTATIC VOLTMETERS
Ranges 100 V to 35,000 V, AC or DC. Resistance exceeds million megohms. Can measure static electricity.

FLUXMETERS
Laboratory and production measurements on magnets and magnetic circuits. Single push button return-to-zero.

ROTATING COIL GAUSSMETERS
Our most recent development for measuring magnetic field strengths. Measures from a few gausses to 120 kilogausses.

SINE-COSINE POTENTIOMETERS
Now available, popular type RL11C, for radar and computor circuits — *write for new bulletin.*

Rawson
ELECTRICAL INSTRUMENT CO.
111 Potter Street, Cambridge, Mass.

F·C·I
Teflon Capacitors

- Operation to 200° C
- Ultra High IR
- High Stability
- Low Power Factor .01%
- Low Soakage .01%
- Low Temp. Coefficient –50 ppm/°C

Available in many different types of housings, in ratings from .001 MF up, and 100 volts up.

Excellent delivery on standard and special types.

Capacitors made to your specifications
Write for Catalogue F

film capacitors, inc.
3400 PARK AVENUE, N.Y., N.Y.
Telephone CYpress 2-5180

Want more information? Use post card on last page.

an understanding of the fundamentals of electron tube operation. While the material herein has been more fully treated in numerous other texts which precede it, perhaps no single book covers the breadth of the electron tube field as does this one. It is a valuable contribution to this field.—DARYL W. SHIPLEY, *Physics Laboratories, Sylvania Electric Products Inc., Bayside, New York.*

THUMBNAIL REVIEWS

Principles of Television Servicing. By C. V. Rabinoff and M. E. Wolbrecht. McGraw-Hill Book Co., New York, N. Y., 1953. 560 pages, $7.50. Combined textbook and practical field reference text assuming only a basic knowledge of electronic circuits and superheterodyne radio principles. The absence of mathematics and unnecessary complex theory greatly enhances the value of the book to those for whom it is intended. In addition, much is of real value to the engineer who seeks to fix his own television receiver.

Materials Handling. By John R. Immer. McGraw-Hill Book Co., New York, N. Y., 1953, 591 pages, $8.00. General principles as applied to all industry. Although only a few specific examples are taken from the electronic industry, there is much basic information in almost every chapter that can readily be adapted to expedite production in electronic plants. Major sections include coverage of motion and time study, materials handling equipment, packaging, handling procedures and organization of personnel.

The Saturday Review Home Book of Recorded Music And Sound Reproduction. By E. T. Canby, C. G. Burke and I. Kolodin. Prentice-Hall, Inc., New York, N. Y., 1952, 308 pages, $4.50. Three major sections, each by one of the authors. Canby provides interesting background information and basic knowledge by tracing recording and playback equipment and techniques from Edison's 1877 tinfoil gadget through to modern magnetic tape. Burke deals with home reproduction and its improvement, telling how to choose, install and operate the units of a modern high-fidelity audio system; examples of systems in five price categories are given and analyzed, ranging from about $225 to $2,000 for the basic elements. Kolodin covers the musician's interests with his "Learning to Listen and Listening to Lean".

Simplified Drafting Practice. W. L. Healy and A. H. Rau. John Wiley & Sons, Inc., New York, N. Y., 1953, 156 pages, $5.00. Tested techniques for eliminating unnecessary work in

VINYL SLEEVING

A picture of Resinite insulation sleeving cannot show the superior qualities that enable it to fully meet Military and Air Force specifications.
Nor, can we graphically portray our service—a service that eliminates most of your purchasing and inspection headaches.
But an order will make it crystal clear why a majority of the Nation's largest users prefer to do business with Resinite. Write for specification data and samples.

Resinite
RESIN INDUSTRIES, INC.
315 olive st • box 1589 • santa barbara, cal
SPECIALISTS IN VINYL SLEEVING AND TUBING FOR THE AIRCRAFT, ELECTRONICS AND MEDICAL FIELDS

F·C·I
Polystyrene Capacitors

- Low Power Factor .01%
- Low Soakage .01%
- Low Temp. Coefficient –100 ppm/°C
- High Insulation Resistance 10^{12} ohms/mf
- High Stability

Available in many different types of housings, in ratings from .001 MF up, and 100 volts up.

Excellent delivery on standard and special types.

Capacitors made to your specifications
Write for Catalogue F

film capacitors, inc.
3400 PARK AVENUE, N.Y., N.Y.
Telephone CYpress 2-5180

Want more information? Use post card on last page.

NEW AIRCRAFT SERVO COMPONENT

The Type 71-5 Baroresistor is a pressure actuated potentiometer designed for operational use in aircraft. It features:

HERMETICALLY SEALED MECHANISM

The potentiometer winding and operating parts are hermetically sealed in a vacuum. Pressure is applied inside the bellows only. Therefore, the Type 71-5 Baroresistor is not affected by dust, fungi, or moisture.

RUGGEDIZED CONSTRUCTION

A special high force mechanism was developed for the Trans-Sonics Baroresistor to avoid the necessity for employing micro force potentiometer elements. Shock of 30g in any direction will not cause electrical discontinuity.

MACHINE CALIBRATION

Each instrument is calibrated by machine and its performance is automatically recorded as a graph of resistance versus pressure. Every turn of the winding is inspected. All electrical characteristics are automatically checked in an eleven stage inspection cycle.

Condensed Data

Range: 0-15 psi, absolute
Resistance: 7500 ohms
Maximum voltage: 75 volts
Resolution: ¼%
Accuracy: 2% of full scale

Typical Applications

Servos—Vary servo loop gain as a function of altitude.
Computers—Voltage divider, P total/P static.
Fire Control—Air density measurements.
Telemetering—Pressure transducer.
Recording—Pressure transducer.

TECHNICAL REPRESENTATIVES

Los Angeles, Calif. Telephone: Cumberland 3-4183
San Carlos, Calif. Telephone: Lytell 3-2189
Boston, Mass. Telephone: Capitol 7-9797
St. Louis, Mo. Telephone: Sweetbriar 2175
Detroit, Mich. Telephone: Broadway 3-2900
Dayton, O. Telephone: Hemlock 1254
Seattle, Wash. Telephone: Main 7005
Houston, Tex. Telephone: Monroe 5-5624
Cleveland, O. Telephone: Yellowstone 2-7849
Home Office: Telephone Lexington 9-2508

Write for Bulletin No. 71-5 for further details

Price: $225.00 Short delivery

TRANS SONICS, INC.
5 Forest Street Bedford, Mass.



SELENIUM RECTIFIER POWER SUPPLIES
for
Aircraft - Mobile - Marine Electrical Equipment

D.C. OUTPUT		CATALOG NO.	
VOLTS	AMPERES	115 V.A.C. 60 ~ 1ϕ	230 V.A.C. 60 ~ 1ϕ
O-6	25.0	K38	—
	50.0	K47	K48
	100.0	K56	K57
O-12	12.5	K65	—
	25.0	K74	K75
	50.0	K83	K84
O-28	10.0	K92	—
	20.0	K101	K102
	40.0	K110	K111

Typical Applications
- Aircraft Motors
- Dynamotors & Inverters
- Relays & Solenoids
- Battery Charging
- Electro-plating

These OPAD-GREEN General Purpose Power Supplies are designed to furnish an adjustable source of rectified D.C. from single phase 50 or 60 cycle A.C. power lines. Step-less output control, overcurrent protection, 2% accuracy meters, aging taps and exclusive Poly-Koated Rectifiers are among the many features of these units.

Opad-Green COMPANY

For additional information write for Bulletin No. 147

71-2 WARREN STREET, NEW YORK 7, N. Y.

preparing working drawings, including greater use of freehand drawing, symbols, mechanical aids, abbreviations, arrowless dimensioning, typewriters for lettering, and modern reproduction processes. The greater part of the material definitely applies to electronic drafting. The book is the result of a comprehensive study of drafting practices throughout General Electric Co.

Planseeberichte für Pulvermetallurgie. A new German magazine in the field of powder metallurgy, corresponding in aims and style to the American Powder Metallurgy Bulletin. Available in U. S. through the latter publication, 320 Yonkers Ave., Yonkers, N. Y. About 3 issues per year are planned; $3 for six issues; checks should be made payable to Planseeberichte für Pulvermetallurgie.

UHF Television. By Edward M. Noll. Paul H. Wendel Pub. Co., P.O. Box 1321, Indianapolis, Ind., 1953, 72 p, $1.00. Practical technical information on uhf and vhf tuners and antennas, propagation characteristics and converters.

Glossary of Terms Used in Methods, Time Study and Wage Incentives. Booklet No. 104, Society for Advancement of Management, 411 Fifth Ave., New York, N. Y., 32 pages, $1.00. Definitions of 332 terms, prepared by 93 management leaders as a serious attempt to cut down aimless discussion and hair-splitting interpretations of contract language.

High-Fidelity Design, Construction, Measurements. Gernsback Publications, Inc., New York, N. Y., 1953, 128 pages, $1.50. Compilation of articles from *Radio-Electronics* by 21 different audio experts, edited by Martin Clifford for maximum reading and reference value to high-fidelity audio enthusiasts who prefer to design and build their own equipment.

Atmospheric Noise at High Frequencies. H.M.S.O., London, 1953, 45¢. A survey of existing data based on measurements from 2.5 to 20 mc during the period 1945-1951.

Master Index to Supreme Publications. 3727 West 13 St., Chicago 23, Ill. 1953, 32 pages, 25¢. Index to servicing data for radios and television sets arranged by manufacturers.

NARDA TV Blue Book. National Appliance Trade-in Guide Co., 2142 Fordem Ave., Madison 1, Wisc., $5.00, 1953. Trade-in values on over 4,000 tv sets, the products of over 50 manufacturers, including the majority of sets produced between 1946 and 1953.

Metal Powder Association, Proceedings 9th Annual Meeting. Metal Powder Association, 420 Lexington Ave., New York 17, N. Y., 111 pages, 1953, $2.50. All papers, illustrations and discussion, giving an up-to-the-minute commentary on the latest developments in this field.

A Full Line

● Terminal Lugs ● Insulated Terminals ● Electronic Hardware ● Handles ● Captive Screws ● Brackets ● Dial Locks ● Spacers ● Shaft Locks ● Binding Posts

Completely assembled terminal boards to meet all government specifications.

Immediate delivery from stock or to order on all items.

Write for Catalog E

CITATION PRODUCTS CO.
233 EAST 146th ST., NEW YORK 51, N.Y.

MAGNETIC, VACUUM TUBE and TRANSISTOR-MAGNETIC *Servo Amplifiers*



MODEL 434-B (400 cps)
- TRANSISTOR-MAGNETIC circuits,
- Absolute Reliability.
- Hermetically sealed.
- For MK 14 & MK 7 servo motors.

MODEL 410-A (60 cps)
- Adjustable gain, damping & phase.
- Matches any A.C. data system.
- Drives Diehl FPE-25-11 servo motor.

Our complete catalog on servo amplifiers and test equipment available on request.

ICO INDUSTRIAL CONTROL COMPANY
Wyandanch Long Island, New York
MIDLAND 3-7548

Over 85% of the torque wrenches used in industry are

STURTEVANT TORQUE WRENCHES

Read by Sight, Sound or Feel.

- Permanently Accurate
- Practically Indestructible
- Faster—Easier to use
- Automatic Release
- All Capacities

in inch ounces . . . inch pounds . . . foot pounds (All Sizes from 0-6000 ft. lbs.)

Every manufacturer, design and production man should have this valuable data. Sent upon request.

PA STURTEVANT CO.

MOLDED POWDERS
TO YOUR SPECIFICATIONS



- Powdered glass of all types for IRON and KOVAR hermetic seals
- Cold-mold plastics, sintered powders
- Precision work to close tolerances
- Immediate deliveries

For Prompt Quotations Write

ELECTRONIC CERAMICS CO.
868 Bergen Street Newark 8, N. J.

WHAT MAKES A MAILING CLICK?

Advertising men agree . . . the list is more than half the story. McGraw-Hill Mailing Lists, used by leading manufacturers and industrial service organizations, direct your advertising and sales promotional efforts to key purchasing power.

In view of present day difficulties in maintaining your own mailing lists, this efficient personalized service is particularly important in securing the comprehensive market coverage you need and want. Investigate today.

McGraw-Hill Publishing Co., Inc.
DIRECT MAIL DIVISION
330 West 42nd Street New York 36, New York

The Van Nostrand Series in Electronics and Communications

MICROWAVE THEORY AND TECHNIQUES

By Herbert J. Reich, Herbert L. Krauss, Philip F. Ordung, and John G. Skalnik

This comprehensive treatment of present-day microwave theory and techniques covers the entire microwave field—defined as extending upward from 300-400 megacycles per second, and applying to devices operating at frequencies at which distributed-element circuits are generally used. Features of special interest are the emphasis upon underlying physical principles, as in the treatment of the operation of microwave amplifiers and oscillators, the many hundreds of clarifying illustrations, and the extensive selection of exemplifying problems, laboratory experiments and bibliographical references.

914 Pages $12.50

MEASUREMENTS AT CENTIMETER WAVELENGTH

By Donald D. King, Ph.D.

This book on the principles, methods, and laboratory techniques of measurement in the V.H.F. and microwave regions, emphasizes the importance in this work of transmission-line theory, and achieves a unified presentation relating the practical formulas to basic line equations. There are complete schematic diagrams of the experimental equipment for each type of measurement. Graphs and line charts illustrate the various methods, and antenna measurements are covered most thoroughly, including material on surface currents.

330 Pages $5.50

FUNDAMENTALS OF RADIO COMMUNICATIONS

By Abraham Sheingold

A comprehensive and clearly-written account of both the principles and techniques of present-day radio-communication systems. From basic principles this book develops a broad treatment of the operational features of a-m and f-m sound-communication systems: television, and facsimile, frequency-sharing and time-sharing multiplex systems; loran, radar and other aids to navigation. The important characteristics of the components and circuits used in such equipment are fully explained. The description and analysis of each circuit shows its capabilities and limitations when used in the radio-system applications. Basic circuits are analyzed in a detailed, quantitative fashion by algebraic and trigonometric methods. Examples, numerous references, and more than 300 illustrative figures add materially to the clarity and thorough coverage of this important new work.

442 Pages $5.25

free-examination coupon

D. VAN NOSTRAND CO. INC.
250 Fourth Ave., New York 3, N. Y.

Please send me for 10-day free examination the book or books I have checked below. After ten days I will either return the book or books and owe nothing, or I will send you the full purchase price plus postage.

☐ Microwave Theory and Techniques
☐ Measurements at Centimeter Wavelength
☐ Fundamentals of Radio Communications

Name .....
Address .....
City ..... *Zone* ... *State* .....

SAVE! (If you enclose full purchase price with this coupon, we will pay the postage. Same return privilege if not entirely satisfied.)

Want more information? Use post card on last page.

BACKTALK

"Complaint"

DEAR SIRS:

I HAVE READ your *"Crosstalk"* editorials for some time and have found them to be both interesting and informative. In the August issue of ELECTRONICS, I took particular interest in your editorial titled "Complaint". I agree wholeheartedly.

My organization, Electronics Engineering Corporation, is devoted entirely to the industrial field of electronics. Four of us in the organization left the engineering field some years ago to enter the service field. Each one of us managed separate successful television service organizations in the city of Baltimore. Upon investigation over the past three years, we discovered that there was no organization in this large industrial area devoted to the service of industrial electronic equipment. The larger industrialists can afford to have their own service and engineering departments. The smaller industries must do one of two things—either do without time-and-labor-saving equipment or depend on factory service. This latter service is slow and costly, due to travel involved. Hence, the inception of Electronics Engineering Corporation.

Manufacturers of industrial equipment realize the importance of these time-saving devices and, if given the opportunity, can design a circuit to do almost anything. However, their consideration of saving time and production costs stops there on the original design. They fail to take into consideration the thing which will make their product and future product sales a success—service. Very few manufacturers take this item into consideration. A breakdown of an electronic device is very costly to a manufacturer. Very often, as we have found, an entire assembly line must quit production until the machine is repaired. With inadequate schematics, wiring and parts without coding, the service engineer is hampered in his work.

Your "Complaint" to manufac-

Model VS-500. 50 to 3000 Cycles

INPUT:
Volts—115v 2 wire or 230v 3 wire single phase; Frequency— 50 to 3000 cycles/sec. Power-1600 V.A.

OUTPUT:
Volts—115v or 230v, regulated; Frequency—50—3000 cycles/sec; Power—500 watts.

WAVEFORM:
Standard—sine wave; Optional—variable waveform with amplitude factor variation of 1.16 to 1.68. Square wave through sine wave to peaked wave.

REGULATION OF OUTPUT VOLTAGE:
Better than 3% from no load to full load.

SIZE:
75" H. 26" W. 27" D. Weight Net: 535 lbs.

Furnished with caster base to provide an easy means of moving equipment to desired location.

Write for descriptive literature now.

TRAD
TELEVISION
CORPORATION
1001 FIRST AVENUE
ASBURY PARK, N. J.

Want more information? Use post card on last page.

turers of electronic equipment is well put. By supplying clear, informative schematics and service manuals and by color-coding wiring and component parts, the service engineer's job would be greatly simplified. Manufacturers using electronic equipment would benefit due to less lost time of breakdown and less cost for service. Manufacturers of electronic equipment would benefit due to increased acceptance of easily maintained equipment. This could very easily work into a good sales item for the salesmen contacting a customer—ease and simplicity of maintenance.

I realize that color-coding of wiring would probably increase the production cost of original equipment; but it would pay off.

Design engineers must realize that equipment they design is only as good as the maintenance so far as the user is concerned. By simplifying circuit tracing, the design engineer aids his concern. As mentioned earlier in this letter, there is a tremendous shortage of skilled maintenance personnel in the industrial electronics field. Unless training programs are set up as in television and proper service information is supplied, industrial electronics will lag far behind the rest of the electronics industry.

I would appreciate comments from some of the major manufacturers. Incidently, a representative in this area of one of the major manufacturers of electronic control panels has stated that, in many instances, his department has spent more time in maintenance than an item costs. This is due not to faulty design or engineering, but in large part to the fact that their own service personnel are unable to read the schematics. Is this sound business?

J. EDWIN PARRISH
Vice-President
Electronics Engineering Corp.,
Baltimore, Maryland

Frequency Stability

DEAR SIRS:

WITH REFERENCE to the article entitled "Wide-Band Data Transmitter" appearing on page 168 of the September, 1953 issue of ELECTRONICS, the writer would like

☆ model 1200
☆ continuous duty
REVERSIBLE DC MOTORS

18 to 30 volts with or without brake . . .

- Ambient temperature: — 55° C to + 105° C.
- Size: 1.25 in. diameter, 2.18 in. long.
- Weighs 5.3 ounces . . . without brake.

We can manufacture these motors to meet your specifications. This particular motor is used on an actuator for aircraft use.

Let's discuss your need!
Write or wire us, TODAY

MOTORS
GENERATORS
RELAYS
TRANSFORMERS
SPEED CONTROL GOVERNORS
MAGNETIC SERVO AMPLIFIERS
MAGNETIC CONTROLS & CIRCUITS

MOTORDYNE INC.
Dept. J, 2661 S. Myrtle Ave.
MONROVIA, CALIFORNIA

AEROCOM MEANS TROUBLE-FREE SERVICE!
From Ground To Air or Point to Point

The model 12GLX-M, 1KW Beacon Transmitter illustrated, operates on a single frequency in the range 200-415 Kcs. Oscillator coil can be supplied crystal-controlled or self-excited. Tone oscillator provides 30% high level modulation for identification when keyed with Aerocom's model AK-3B automatic keyer. The unit can also be voice modulated. Power supply . . . any stable voltage in the range 200-240 volts, 50/60 cycles, single phase. Overall dimensions in CM, 56W x 62D x 177H. Net weight 286 kilos.

AER-O-COM
3090 DOUGLAS ROAD MIAMI 33, FLA.

Want more information? Use post card on last page.

Rockbestos says: "thanks for KULGRID"

ROCKBESTOS PRODUCTS CORPORATION

NEW HAVEN 4 CONNECTICUT

August 18, 1953

Mr. Philip Pritchard, Division General Sales Manager
Sylvania Electric Products Inc.
Parts Division
2nd Avenue
Warren, Pennsylvania

Dear Phil:

I have been meaning to write you this letter for quite some time, but up till now I just haven't had the opportunity.

Primarily, I would like to say "Thanks for Kulgrid."

As you are well aware, we have been using Kulgrid wire ever since we ran into some problems in the manufacture of components for aircraft engines and in the making of galley ranges for the Navy.

What we were looking for was a wire which had good conductivity yet was able to withstand high temperature without flaking or corroding. We found the answer with "Kulgrid" and have used it ever since.

We are extremely grateful for your assistance in helping us clear the hurdles on this problem and we are sure that Sylvania Kulgrid and Rockbestos Products will have a very happy association for many years to come.

Very truly yours,

ROCKBESTOS PRODUCTS CORPORATION

H. O. Anderson

H. O. Anderson
Vice President in Charge of Sales

HOA:hmf

Rockbestos Products Corporation is another important modern manufacturer that appreciates the fine performance and durability of KULGRID . . . Sylvania's nickel-clad copper wire.

Kulgrid's tough nickel coating resists corrosion and guards the copper core from deterioration, while assuring excellent electrical conductivity. You'll find Kulgrid ideal for high-temperature wiring in electric furnaces, stoves, industrial ovens, and many aircraft applications. Available in single or stranded forms. New illustrated booklet gives full details. For your file copy, address: Sylvania Electric Products Inc., Dept. 3A-1011, 1740 Broadway, New York 19, N. Y.

SYLVANIA

LIGHTING • RADIO • ELECTRONICS • TELEVISION

In Canada: Sylvania Electric (Canada) Ltd., University Tower Bldg., St. Catherine St., Montreal, P. Q.

to add the following comments to the frequency stability discussion by the authors of the double phantastron.

It is pointed out in this article that the frequency of operations of the double phantastron is directly proportional to the voltage E_{cc}'. This voltage is the difference between the input voltage E_{cc} and the average grid bias during plate rundown, E_p. Now the voltage E_p is not only a function of the phantastron gain, but is also dependent upon the initial emission velocity potential of the cathode. This potential will vary with tube aging and with line voltage if the heater supply is unregulated. Heater voltage variations of ± 10 percent can be expected to produce a variation in this potential of about ± 0.1 volt, or since $f \sim E_{cc}'$ and $\Delta f/f$ expressed as a percentage is equal to 100 times $\Delta E_{cc}'/E_{cc}'$, approximately ± $10/E_{cc}$ percent variation in frequency.

At a center-frequency voltage of 150 this can only amount to about ±0.06 percent. However, at a value of E_{cc} which will give an operating frequency of 1 kc for which a modulation linearity of 0.1 percent is reported, the frequency drift caused by line-voltage fluctuations can be as much as ± 2 percent.

It is felt that these are relatively insignificant for the application reported; however, the inference that heater supplies need not be regulated may be misleading to those unfamiliar with this problem, and who might wish to employ the double phantastron in critical applications with low center values of E_{cc}.

ROBERT G. ROUSH
The Johns Hopkins University
Baltimore, Maryland

Credit

DEAR SIRS:

THE UNDERSIGNED would appreciate it if you would put the following erratum in the next issue of Electronics.

In the article by MacQuistan entitled, "Determining Properties of Bulk Semiconductors (p 150, June, 1953), the acknowledgement should read, "The method used here for

CONTACTS

FOR THE FIELD OF ELECTRONICS

ELECTRICAL

COILS

Bobbin, spool, form, layer, interleaved, interwoven types. Made of any material, any finish, for any application.

Send blue-prints and specifications for prompt quotation.

THE FIVE STAR COMPANY
West Main Street
Plantsville, Conn.

Auricon Hollywood

16mm SOUND-ON-FILM EQUIPMENT FOR TELEVISION NEWSREELS, TV FILM INSERTS AND KINESCOPE RECORDINGS...SOLD WITH A 30-DAY MONEY-BACK GUARANTEE. YOU MUST BE SATISFIED!

CINE-VOICE $695.00 · AURICON-PRO $1310.00 · SUPER 1200 $4652.15 · TRIPOD $325.00 · PORTABLE POWER UNIT $369.50 · SOUND RECORDER $1149.50

WRITE FOR FREE ILLUSTRATED INFORMATION

BERNDT-BACH, Inc.
7373 Beverly Blvd., Los Angeles 36, Calif.

MANUFACTURERS OF SOUND-ON-FILM RECORDING EQUIPMENT SINCE 1931

6751 BRYN MAWR AVE.



EISLER MANUFACTURES COMPLETE EQUIPMENT
WELDERS FOR SPOT & WIRE BUTT
RADIO, TV TUBE EQUIPMENT & REPAIR UNITS
INCANDESCENT, FLUORESCENT MFG EQUIPMENT
NEON SIGN MAKERS EQUIPMENT, GLASS LATHES
ELECTRONIC EQUIPMENT, VACUUM PUMPS, Etc.
Wet Glass SLICING & CUTTING MACHINES for Lab. Use
TRANSFORMERS, SPECIAL & STANDARD TYPES

EISLER ENGINEERING CO., INC.
751 So. 13th St. Newark 3, N. J.

Shorted Turn Indicator

Sensitive, rugged, non-shocking for unmounted coils; $150. f.o.b. HUNTINGTON BEACH, CALIF.

KKARTRON

WALKIE-RECORDALL BATTERY RECORDER PLAYBACK

Continuous, permanent, indexed recording, up to 4 hrs., only 3¢ hr. Instantaneous, permanent playback. Picks up sound up to 60 ft. Records conferences, lectures, dictation, 2-way phone & sales talks; while walking, riding or flying. Records in closed briefcase with "hidden mike"! Write for Detailed Literature.

MILES REPRODUCER CO., INC.
812 BROADWAY Dept. E-11 NEW YORK 3, N. Y.

Have you problems in

Metal to Glass Seals?

NAME IT . . . WE'LL MAKE IT!
TERMINALS
HEADERS
END SEALS . . . SPECIAL ITEMS

QUALITY PRODUCTS CO.
387 Charles St., Providence, R. I.

CRYSTALS FOR ALL PURPOSES

LOW FREQ.—FT 243A for 560, lattice filter, ½" spc. 56th or 72nd harm channels listed by fund. Fractions omitted.

370	398	422	447	513	480	497
372	397	423	448	514	480	498
374	398	424	449	514	481	499
375	400	425	449	515	482	500
376	403	426	442	516	483	501
377	403	427	443	516	484	502
378	404	428	444	517	485	503
379	405	429	444	518	486	504
380	406	430	445	518	487	505
381	406	431	446	519	488	506
382	407	431	447	520	489	507
383	408	432	447	521	490	508
384	409	433	448	522	491	509
385	410	434	449	523	492	510
386	411	435	450	524	493	511
387	412	436	451	525	494	512
388	413	437	452	526	495	513
389	414	438	453	527	496	514
390	415	439	454	528	497	515
391	416	440	455	529	498	516
392	417	441	456	530	499	517
393	418	442	457	531	500	518
394	419	443	458	532	501	519
395	420	444	459	533	502	520
396	421	445	460	534	503	521
397	422	446	461	535	504	522

49c EA—10 for $4.50

BC.: 623 3rd OT, MW sp. 6439 to 6847.9 in 7.5 kc steps. 6850 to 7350 in 25 kc steps. 7350 to 7930 in 30 kc steps. 90c each 10 for $8.00

BC-610 2 banana plugs ½" spc.

7010 7200 7011 7211 7012 7212 7013 7213 7014 7214 7015 7215 7016 7216 7017 7217 7018 7218 7019 7219 7020 7220 7021 7221 7022 7222 7023 7223 7024 7224 7025 7225 7026 7226 7027 7227 7028 7228 7029 7229 7030 7230

$1.29 EA

265 A HOLDER ½" SPC. $1.95 EA

PT 243 — ½" P IN SPC.

6390	6579	7006	6640	6840	6273	6450	6680	7040	7250
6400	6586	7046	6646	6846	6279	6473	6686	7046	7273
6406	6773	7073	6673	6873	6286	6480	6693	7073	7280
6440	6779	7079	6679	6879	6293	6486	6700	7079	7286
6473	7040	7140	6740	6940	6377	6573	6773	7140	7373
6540	7773		6773	6973	6386	6579	6779	7146	7379

49c EA—10 for $4.50

3013	3740	5040	5273	6450	6680	7440	7650
3020	3746	5046	5279	6473	6686	7446	7673
3040	3773	5073	5286	6480	6693	7473	7680
3046	3779	5079	5293	6486	6700	7479	7686
3073	3940	5140	5373	6573	6740	7486	7693
3079	3946	5146	5379	6579	6746	7493	7700
3140	3973	5173	5386	6586	6773	7500	7740
3146	4040	5179	5393	6593	6779	7540	7746
3173	4046	5240	5473	6600	6786	7546	7773
3179	4073	5246	5479	6606	6793	7573	7779
3240	4079	5273	5486	6613	6800	7579	7786
3246	4140	5279	5493	6640	6806	7586	7793
3273	4146	5286	5500	6646	6813	7593	7800
3279	4173	5293	5506	6653	6840	7600	7806
3286	4179	5340	5513	6673	6846	7606	7813
3293	4240	5346	5540	6679	6853	7613	7840
3340	4246	5373	5546	6686	6873	7640	7846
3346	4273	5379	5573	6693	6879	7646	7853
3373	4279	5386	5579	6700	6886	7653	7873
3379	4286	5393	5586	6706	6893	7673	7879
3386	4293	5440	5593	6713	6900	7679	7886
3393	4340	5446	5600	6740	6906	7686	7893
3440	4346	5473	5606	6746	6913	7693	7900
3446	4373	5479	5613	6753	6940	7700	7906
3473	4379	5486	5640	6773	6946	7706	7913
3479	4386	5493	5646	6779	6953	7713	7940
3486	4393	5500	5653	6786	6973	7740	7946
3493	4440	5506	5673	6793	6979	7746	7953
3500	4446	5513	5679	6800	6986	7753	7973
3506	4473	5540	5686	6806	6993	7773	7979
3513	4479	5546	5693	6813	7000	7779	7986
3540	4486	5553	5700	6840	7006	7786	7993
3546	4493	5573	5706	6846	7013	7793	8000
3573	4500	5579	5713	6853	7040	7800	8006
3579	4506	5586	5740	6873	7046	7806	8013
3586	4513	5593	5746	6879	7053	7813	8040
3593	4540	5600	5753	6886	7073	7840	8046
3600	4546	5606	5773	6893	7079	7846	8053
3606	4573	5613	5779	6900	7086	7853	8073
3613	4579	5640	5786	6906	7093	7873	8079
3640	4586	5646	5793	6913	7100	7879	8086
3646	4593	5653	5800	6940	7106	7886	8093
3673	4600	5673	5806	6946	7113	7893	8100
3679	4606	5679	5813	6953	7140	7900	8106
3686	4613	5686	5840	6973	7146	7906	8113
3693	4640	5693	5846	6979	7153	7913	8140
3700	4646	5700	5853	6986	7173	7940	8146
3706	4653	5706	5873	6993	7179	7946	8153
3713	4673	5713	5879	7000	7186	7953	8173
3740	4679	5740	5886	7006	7193	7973	8179
3746	4686	5746	5893	7013	7200	7979	8186
3773	4693	5753	5900	7040	7206	7986	8193
3779	4700	5773	5906	7046	7213	7993	8200
3786	4706	5779	5913	7053	7240	8000	8206
3793	4713	5786	5940	7073	7246	8006	8213
3800	4740	5793	5946	7079	7253	8013	8240
3806	4746	5800	5953	7086	7273	8040	8246
3813	4753	5806	5973	7093	7279	8046	8253
3840	4773	5813	5979	7100	7286	8053	8273
3846	4779	5840	5986	7106	7293	8073	8279
3853	4786	5846	5993	7113	7300	8079	8286
3873	4793	5853	6000	7140	7306	8086	8293
3879	4800	5873	6006	7146	7313	8093	8300
3886	4806	5879	6013	7153	7340	8100	8306
3893	4813	5886	6040	7173	7346	8106	8313
3900	4840	5893	6046	7179	7353	8113	8340
3906	4846	5900	6053	7186	7373	8140	8346
3913	4853	5906	6073	7193	7379	8146	8353
3940	4873	5913	6079	7200	7386	8153	8373
3946	4879	5940	6086	7206	7393	8173	8379
3953	4886	5946	6093	7213	7400	8179	8386
3973	4893	5953	6100	7240	7406	8186	8393
3979	4900	5973	6106	7246	7413	8193	8400
3986	4906	5979	6113	7253	7440	8200	8406
3993	4913	5986	6140	7273	7446	8206	8413
4000	4940	5993	6146	7279	7453	8213	8440
4006	4946	6000	6153	7286	7473	8240	8446
4013	4953	6006	6173	7293	7479	8246	8453
4040	4973	6013	6179	7300	7486	8253	8473
4046	4979	6040	6186	7306	7493	8273	8479
4053	4986	6046	6193	7313	7500	8279	8486
4073	4993	6053	6200	7340	7506	8286	8493
4079	5000	6073	6206	7346	7513	8293	8500
4086	5006	6079	6213	7353	7540	8300	8506
4093	5013	6086	6240	7373	7546	8306	8513
4140	5040	6093	6246	7379	7553	8313	8540
4146	5046	6100	6253	7386	7573	8340	8546
4153	5053	6106	6273	7393	7579	8346	8553
4173	5073	6113	6279	7400	7586	8353	8573
4179	5079	6140	6286	7406	7593	8373	8579
4186	5086	6146	6293	7413	7600	8379	8586
4193	5093	6153	6300	7440	7606	8386	8593
4240	5100	6173	6306	7446	7613	8393	8600
4246	5106	6179	6313	7453	7640	8400	8606
4253	5113	6186	6340	7473	7646	8406	8613
4273	5140	6193	6346	7479	7653	8413	8640
4279	5146	6200	6353	7486	7673	8440	8646
4286	5153	6206	6373	7493	7679	8446	8653
4293	5173	6213	6379	7500	7686	8453	8673
4340	5179	6240	6386	7506	7693	8473	8679
4346	5186	6246	6393	7513	7700	8479	8686
4353	5193	6253	6400	7540	7706	8486	8693
4373	5240	6273	6406	7546	7713	8493	8700
4379	5246	6279	6413	7553	7740	8500	8706
4386	5253	6286	6440	7573	7746	8506	8713
4393	5273	6293	6446	7579	7753	8513	8740
4440	5279	6300	6453	7586	7773	8540	8746
4446	5286	6306	6473	7593	7779	8546	8753
4453	5293	6313	6479	7600	7786	8553	8773
4473	5340	6340	6486	7606	7793	8573	8779
4479	5346	6346	6493	7613	7800	8579	8786
4486	5353	6353	6500	7640	7806	8586	8793
4493	5373	6373	6506	7646	7813	8593	8800
4540	5379	6379	6513	7653	7840	8600	8806
4546	5386	6386	6540	7673	7846	8606	8813
4553	5393	6393	6546	7679	7853	8613	8840
4573	5440	6400	6553	7686	7873	8640	8846
4579	5446	6406	6573	7693	7879	8646	8853
4586	5453	6413	6579	7700	7886	8653	8873
4593	5473	6440	6586	7706	7893	8673	8879
4640	5479	6446	6593	7713	7900	8679	8886
4646	5486	6453	6600	7740	7906	8686	8893
4653	5493	6473	6606	7746	7913	8693	8900
4673	5500	6479	6613	7753	7940	8700	8906
4679	5506	6486	6640	7773	7946	8706	8913
4686	5513	6493	6646	7779	7953	8713	8940
4693	5540	6500	6653	7786	7973	8740	8946
4740	5546	6506	6673	7793	7979	8746	8953
4746	5553	6513	6679	7800	7986	8753	8973
4753	5573	6540	6686	7806	7993	8773	8979
4773	5579	6546	6693	7813	8000	8779	8986
4779	5586	6553	6700	7840	8006	8786	8993
4786	5593	6573	6706	7846	8013	8793	9000

49c EA—10 for $4.50

99c EA—10 for $9.00

• Add 20¢ for each 10 xtals or less for postage and handling

Sun

PARTS DISTRIBUTORS, LTD.

520 TENTH ST., N.W. - WASHINGTON, D.C.

"SEARCHLIGHT" IS Opportunity Advertising

—to help you get what you want.
—to help you sell what you no longer need.

Take Advantage Of It

For Every Business Want

"Think SEARCHLIGHT FIRST"

REX RHEOSTAT CO.
BALDWIN, L. I. N. Y.



NEW REX DOUBLE RHEOSTATS
and RESISTORS UP TO 2000 WATT.
WRITE FOR NEW CATALOG NO. 5

MICROMETER FREQUENCY METER

Measures center frequency of any number of transmitters, AM or FM. 0.1 to 175 MC., 0.0025% accuracy. Price $220.00.

LAMPKIN LABORATORIES, INC.
BRADENTON FLORIDA

MILITARY-SUB-CONTRACTING-COMM.
Electronic—Mechanical Devices
Full Metal, Machine Shop Facilities
From Raw Metal to Finished Device
No Order Too Small
UNIVERSAL MANUFACTURING CO.
196 Bowery
Rector 2-1997 New York 12, N. Y.

SUB-CONTRACTING
MILITARY and COMMERCIAL
receivers—test equipment
transmitters—controls
sub-assemblies
TELETRONICS LABORATORY, INC.
Westbury, L. I., N. Y. Westbury 7-1028

Want more information? Use post card on last page.



The average member of "The Representatives" has been selling electronic products and components to jobbers and manufacturers for 10.15* years. He is a member of the association formed to promote better internal relations in the industry between the manufacturer and his customers and through the years has bent all efforts to maintaining this spirit of sincere cooperation, and a high code of ethical selling. Since the early beginnings of the electronics industry, "The Representatives," by building up channels of distribution have been a large factor in the growth of the industry. Each member of "The Representatives" has been approved by a jury of his peers as a salesman dedicated to upholding both the standards and the expansion of your market.

*25% of all members of "The Representatives" have been selling in the industry for over 20 years.

Call on The Representatives for assistance in activating your sales program.

National Headquarters Office
"THE REPRESENTATIVES"
of Electronic Products Manufacturers, Inc.
[illegible] S. Michigan Avenue, Chicago 5, Illinois
HArrison 7-2402

Because Teflon by Ethylene is processed under rigid control in new equipment designed especially for the processing of this material, you are assured of a satisfactory product. It is uniform in density and dimension and free from cracks, voids, and porosity.

Teflon by Ethylene is available in rods, sheets and tubing, in the following size ranges:

Molded Sheets	1/16" to 2" thick by 29¼" x 29¼"*
Extruded, Centerless Ground Rod	3/16" to 1"
Extruded Tubing	3/16" to 4" OD inclusive 1/16" to 3½" ID 1/16" Minimum Wall
Molded Rod	1½" to 6"
Molded Tubing	1½" x ⅛" to 20" x 18¾"
Shaved Tape	.0025 to .060 thickness and 12" wide

Also economical production of accurately machined parts or special moldings in small experimental quantities or production runs.

ETHYLENE CHEMICAL CORP
250 BROAD STREET
SUMMIT, N. J.

* Du Pont Trade-Mark for tetrafluorethylene resin

the measurement of bulk resistivities of semiconductors with pulse heating, and the method of temperature measurement has been designed by J. Hirsch during his stay at Purdue University. We are also indebted to H. M. Bath, who prepared the manuscript for print."

DR. K. LARK-HOROVITZ
Head, Dept. of Physics

R. B. MACQUISTAN
Mechanical Engineering Department
Purdue University
West Lafayette, Indiana

Predestination

DEAR SIRS:

I, TOO, WAS disturbed by Norbert Wiener's essay on Ashby's Design For A Brain (p 368, June, 1953), but only to the extent that I have ordered the book!

From a philosophical point of view I find that Fred Hoyle, etc. of the cosmologists, and Erwin Schrödinger, of the physicists, would seem to agree, basically, with Dr. Wiener rather than Dr. van Slooten (*Backtalk*, p 444, Sept, 1953). His premise that even so prosaic a thing as the Model T *might* not have been the result of randomness does not weigh against the recorded facts of even that machine: it was trial and error!

I had thought that predestination, which seems the advocacy of Dr. van Slooten's letter, was also a baseless delusion: a proposition not pure nonsense, however, any more than man's current preoccupation with his own transmutability into galactic hydrogen!

D. VON RUYSDAEL DRENNER
Engineer, KGGF
Coffeyville, Kansas

Sub or Super?

DEAR SIRS:

IN THE Parallel-Resistor Chart article by Mitchell Aron in the July 1953 issue of ELECTRONICS (p 192), there is an error in Eq. 6. As it now stands, it reads

$$\frac{E_1}{R}\,x = \frac{E^2}{R^2}\,A$$

whereas it should be

$$\frac{E^2}{R}\,x = \frac{E^2}{R_1}\,A$$

RICHARD W. PLAHN
Mechanical Engineer
Aircraft Radio Corp.
Boonton, New Jersey

PROFESSIONAL SERVICES

ANNIS ELECTRIC RESEARCH LABORATORY, INC

CONSULTING — RESEARCH — DEVELOPMENT AND DESIGN OF RADIO AND ELECTRONIC EQUIPMENT

Antennas, Wave Propagation, Information Storage, Computers, Impedance Matching, and Variable Speed A-C Motors.

P. O. Box 581 — 1401¼ S. Neil St.
Champaign, Ill. — Tel. 6-1740

READERS MAY CONTACT

the consultants whose cards appear on this page with the confidence justified by the offering of these special services NATIONALLY.

MAURICE I. PARISIER & CO.

Communications Experts

International Engineering Consulting
RADIO BROADCASTING & COMMUNICATIONS
Planning & Installation Supervision
Communication Equipment for Armed Forces
1475 Broadway New York 36, N. Y. LOngacre 4-5434
Offices: Paris-Buenos Aires — Sao Paulo-Bombay

CROSBY LABORATORIES, INC

Murray G. Crosby & Staff

Radio - Electronic
Research Development & Manufacturing
Communications, FM & TV
Robbins Lane, Hicksville, N. Y.
Hicksville 3-3191

HIGHLAND ENGINEERING CO.

William R. Spittal & Staff

DESIGN, DEVELOPMENT AND MANUFACTURE OF TRANSFORMERS, CHOKES, ETC. FOR THE ELECTRONIC, INDUSTRIAL & ALLIED FIELDS
Main & Urban, Westbury, L. I., N. Y.
WE-7-2083

PICKARD AND BURNS, INC.

Consulting Electronics Engineer

Analysis and Evaluation of Radio Systems
Research, Development and Production of Special Electronic Equipment
240 Highland Ave. — Needham 94, Mass.

EDGERTON, GERMESHAUSEN & GRIER, INC.

Consulting Engineers

Research, Development and Manufacture of Electronic and Stroboscopic Equipment
Specialists in High-Speed Photography
160 Brookline Avenue — Boston 15, Mass.

HOGAN LABORATORIES, INC.

John V. L. Hogan, Pres.

Applied Research, Development, Engineering

Est. 1929. Electronics, Optics, Mechanisms, Facsimile Communication, Digital Computers (Circle). Electro-sensitive recording media. Instrumentation.
155 Perry Street, New York 14. — CHelsea 2-7855

ALBERT PREISMAN

Consulting Engineer

Television, Pulse Techniques, Video Amplifiers, Phasing Networks, Industrial Appliances
Affiliated with
MANAGEMENT-TRAINING ASSOCIATES
2303-14th St., N. W. — Washington 10, D. C.

Eldico of New York, Inc.

Pioneers of Television Interference Elimination from Transmitters, Induction Heaters, Diathermy and etc.

Donald J. S. Merten & Engineering Staff
44-31 Douglaston Pkwy — Douglaston, N. Y.
Bayside 9-8686

INTERFERENCE MEASUREMENT LABORATORY

Interference Study per Government Specifications
Shielded Space for Interference Investigation
Field Surveys for F.C.C. Certification of Induction and Dielectric Heating Equipment
748 McDonald Avenue — Brooklyn 18, New York
Gedney 5-2488

JOSEPH RACKER COMPANY

Radar Consultants & Editors

Technical Manuals
Research and Development
140 Nassau Street, — New York 38, N. Y.
Worth 4-1463

ELECTRONIC RESEARCH ASSOCIATES, INC.

TRANSISTORIZE YOUR PRODUCT!

Complete Service in consulting, research, development, and production on Transistor circuitry, products, and instrumentation.
715 Main Street — North Caldwell, N. J.
Caldwell 6-6739

THE KULJIAN CORPORATION

Consultants • Engineers • Constructors

Electronic Control Specialists
Utility • Industrial • Chemical
1200 N. Broad St., — Phila 21, Pa.

ROTRON RESEARCH CORPORATION

Research and Development

Fluid Dynamics and Heat Transfer.
Exclusively Electronic Applications

Cooling Problems, Heat Exchangers, Fans, Turbines and Pump Designs
Woodstock, N. Y. — Phone 2468

ERCO RADIO LABORATORIES, INC.

Radio Communications Equipment

Engineering - Design - Development - Production
Pioneers in Frequency Shift Telegraph
Garden City • Long Island • New York

MAGNETIC INDUSTRIES, INC.

Development & Manufacture

Servo Magnetic Amplifiers and Special Relays
2640 Huldy — Houston 6, Texas

SKINNER, HARLAN AND IRELAND, INC.

Consulting Engineer

Specializing in Magnetic Materials and Their Application
1123 E. 23rd St. — Indianapolis 7, Indiana

HARRIS GALLAY

Consultant

Electronic Project Development for Industry
Day, Week and Duration of Project Services
Our Laboratory Facilities Optional
Plymouth 9-4237 — 60 Perry St., Belleville 9, N. J.

Measurements Corporation

Research & Manufacturing Engineers

Harry W. Houck — Jerry B. Minter
John M. van Beuren

Specialists in the Design and Development of Electronic Test Instruments
Boonton, New Jersey

THE TECHNICAL MATERIEL CORPORATION

Communications Consultants

Systems Engineering
General Offices and Laboratory
121 Spencer Place, Mamaroneck, N. Y.

GORDON ASSOCIATES, INC.

Government Contract Liaison and Consulting

Specializing in Signal Corps Electronic Requirements, Technical Manuals, Tabular List of Parts, Drawings.

L. Gordon, Pres. — P. Treston, Ch. Engr.
157 Broad Street — Telephone
Red Bank, New Jersey — Red Bank 6-2743

NEW ROCHELLE TOOL CORP.

FOR CERTIFICATION OF INDUCTION AND DIELECTRIC HEATING EQUIPMENT IN ACCORDANCE WITH F.C.C. RULINGS
320 Main St., — New Rochelle, New York
Phone NE 2-5555
Mobile Test Unit Available Entire U. S.

WHEELER LABORATORIES, INC.

Radio and Electronics
Consulting—Research—Development
R-F Circuits—Lines—Antennas
Microwave Components—Test Equipment
Harold A. Wheeler and Engineering Staff
Great Neck, N. Y. — Great Neck 2-7806

HANSON-GORRILL-BRIAN INC.

Products & Mfg. Development

ELECTRICAL - ELECTRONIC
HYDRAULIC - MECHANICAL
One Continental Hill — Glen Cove, N. Y.
Glen Cove 4-7300

NIAGARA ELECTRON LABORATORIES

CONSULTATION - DESIGN - CONSTRUCTION
MFG. THE THERMOCAP RELAY

Specializing in solution of problems of electronic and electro-physical instrumentation for the research of analytical laboratory. Industrial plant problems also invited.

Andover, New York Cable Address: NIATRONLAB

YARDNEY LABORATORIES, INC.

Research - Design - Development

Electro-Chemical Generators of Energy
105 Chambers Street — Worth 2-3534, 35, 36
New York 7, N. Y.

CLASSIFIED SEARCHLIGHT SECTION ADVERTISING

EMPLOYMENT • BUSINESS • OPPORTUNITIES • EQUIPMENT—USED or RESALE

UNDISPLAYED RATE

$1.80 a line, minimum 3 lines. To figure advance payment count 5 average words as a line. POSITION WANTED & INDIVIDUAL SELLING OPPORTUNITY WANTED undisplayed advertising rate is one-half of above rate, payable in advance.
BOX NUMBERS count 1 line additional.

INFORMATION

DISCOUNT 10% if full payment is made in advance for four consecutive insertions of undisplayed ads (not including proposals).

EQUIPMENT WANTED OR FOR SALE Advertisements acceptable only in Displayed Style.

DISPLAYED—RATE PER INCH

The advertising rate is $16.10 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

AN ADVERTISING INCH is measured ⅞ inch vertically on one column, 3 columns—30 inches —to a page. ELECT.

Send NEW ADVERTISEMENTS to N. Y. Office, 330 W. 42 St., N. Y. 36, for the *December issue closing Nov. 2nd.* The publisher cannot accept advertising in the Searchlight Section, which lists the names of the manufacturers of resistors, capacitors, rehostats, and potentiometers or other names designed to describe such products.

FIELD ENGINEERS

Pacific Division, Bendix Aviation Corporation, needs electronic field engineers to form a new Field Engineering Group offering excellent opportunities for growth. The job requires supervision of installation and maintenance, and instruction in the operation of Bendix airborne radar at aircraft plants and Air Force Bases within U. S. limits.

Positions are open at several levels, and inquiries are also invited from recent graduates. Salaries based on ability, experience, and education. Travel allowance in addition to salary.

Address inquiries to W. S. Leitch, Chief Electronics Engineer, 11600 Sherman Way, North Hollywood, California.

ELECTRONICS ENGINEERS

This established electronics manufacturer located in the heart of western New York requires men with design experience. Permanent positions available for senior and junior men with EE degree or equivalent experience.

ALSO TELEVISION AND RADIO DESIGN ENGINEERS

Fine cultural community in which to live with good schools, homes, and progressive associates. Please write to:

Chief Electronics Engineer

STROMBERG-CARLSON COMPANY

Rochester 3, N. Y.

ENGINEERS

SYSTEMS
RADAR
SERVO
COMPUTER

BACKGROUND: Responsible positions open for top level development and project engineers with practical and research experience in:

Advanced Electronic Circuits and Systems
Microwave Radar
Microwave Receivers and Transmitters

Requirements emphasize advanced analytical and/or management experience on highly complex electronic and electro-mechanical systems.

Kindly send resume and salary requirements to

The W. L. MAXSON Corp.
460 W. 34th St., NEW YORK 1, N.Y.

REPLIES (Box No.): Address to office nearest you
NEW YORK: 330 W. 42nd St. (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITIONS VACANT

ELECTRONICS ENGINEERS and Physicists interested in Research and Development on trigger circuits and high speed sweeps. Opportunity to do original work on transducer applications to specialized problems in shocks and detonations. P-8766, Electronics.

SALES ENGINEERS—Openings available with large industrial instrument manufacturer for field Sales Engineers in New York, Chicago, Houston, and St. Louis areas. Graduates of recognized engineering colleges with training in electronics preferred. Mechanical and Chemical Engineers will also be considered. Excellent opportunity for young engineers with sales aptitude who wish to enter the fast-growing industrial instrument field with a long established and rapidly growing manufacturer of industrial instruments. P-9321, Electronics.

ELECTRONIC ENGINEER or Electronic Scientist, GS-12, $7,040.00 per annum. Permanent assignment at the Naval War College, Newport. The incumbent will be Resident Engineer in charge of a technical group responsible for the operation, maintenance, and continuous modernization of a complex electronic system. Qualifications: Must meet minimum Civil Service requirements, developmental experience, administrative, and technical development abilities and academic training or experience at least equivalent to a B.S. degree in Electronic Engineering or Physics. Interested persons should obtain a Standard Form 57 from any first or second class Post Office and file it with the Employment Office, Navy Electronics Laboratory, San Diego 52, California before 31 October 1953.

SELLING OPPORTUNITIES OFFERED

ELECTRICAL CONTACT manufacturer seeks representative in Chicago area. Outstanding Eastern company engaged in manufacture of electrical contacts, contact materials, and electronic parts wishes high grade representative to call on electrical manufacturers in Wisconsin, Illinois, and some surrounding territory. Salary and commission, all expenses paid. Excellent opportunity for man either with experience in this line or suitable background combined with connections to learn and progress in this business. Write giving particulars of past experience, age, education, and salary history and requirements. RW-9223, Electronics.

SALES-ENGINEERS for leading electronics manufacturer to cover Northern New Jersey except New York City; New York State east of Rochester except New York City; Missouri, including St. Louis and Kansas City. Practical engineering background desirable. Give complete information concerning experience, education, previous employment, salary requirements. Write to SW-9236, Electronics.

EXCELLENT OPPORTUNITY FOR PLANT MANAGER

We are looking for a man between 35-45 years of age who has been connected with electronics or instrument manufacturing in a supervisory capacity for a number of years to take full charge of engineering and production of electrical apparatus. He should have a technical background with an M.E. or E.E. degree. He should be thoroughly versed in engineering and factory procedure. The plant is located in New England—the compensation is in the top-level brackets. Mail complete background information to:

Cory Snow
CORY SNOW INC.
655 Beacon St. Boston 15, Mass.

LIKE TO LIVE IN SAN FRANCISCO?

Well established agency with substantial clients in electronic and mfg. fields wants competent technical copywriter. Must have minimum five years agency writing experience, largely on electronic products. Send full history and work samples to

TECHNAGRAPH COMPANY
301 Broadway, San Francisco.

WANTED

APPARATUS-PRODUCTION ENGINEER

Western manufacturer desires graduate engineer with 5 to 7 years of practical apparatus production experience. Must be able to engineer designs and models of electrical, optical and electromechanical devices for production; be familiar with precision machine-tools, with foundry and die-casting methods, plastic molding, press forming, finishing processes and electronic assembly, and be able to design tooling and fit production quantities consistent with economy, demand and timing.

Opportunity of advancing to position of head of Production Planning Department for individual with good background, cooperative disposition and good personality. Attractive working and living conditions.

Send full particulars with details of training, practical experience, references, salary expectations and photograph (if available) to:

P-9512, Electronics
520 N. Michigan Ave., Chicago 11, Ill.

Public Auction Sale
San Diego, Calif.
NOV. 5, 1953
See Page 479

Exceptional Opportunities for...

electrical engineers
mechanical engineers
mechanical designers

•

in the field of electronic computers and associated equipment for use in business machines.

Write, giving education and experience to Employment Manager.

Reply to Department A.

THE NATIONAL CASH REGISTER COMPANY, Dayton 9, Ohio

POSITIONS WANTED

PATENT ATTORNEY—Electronics—27; **BEE;** NY Bar; 2 yrs prosecuting applications; 4 yrs eng exp. PW-9483, Electronics.

ENGINEERING PHYSICIST, Field test, evaluation, development experience electronic equipment. Age 29, desires position which will further develop administrative and technical capacities. PW-9309, Electronics.

BI-LINGUAL COMMUNICATIONS Engineer desires responsible position in Latin America. 17 years experience design ground, airborne, and marine equipment and systems. PW-9451, Electronics.

FIELD ENGINEER, experienced in radar and communications installation, maintenance and instruction. Prefer overseas assignment. PW-9286, Electronics.

BUSINESS OPPORTUNITY

For Rent—In Hempstead, Long Island—5,000 Sq. ft. sales room and work shop for distributor. Mr. P. Dobler, 447 Maxwell Street, L. I., N. Y. HE 7-7185.

WANTED

ANYTHING within reason that is wanted in the field served by Electronics can be quickly located through bringing it to the attention of thousands of men whose interest is assured because this is the business paper they read.

LIFETIME OPPORTUNITY FOR A CREATIVE ENGINEER

PARTNERSHIP

Successful Sales and Business Manager, EE, wants to start manufacturing company in the electronics field, and seeks capable, experienced Electrical Engineer as partner. Applicants should be in a position to contribute full time, plus sound ideas or a completely developed, marketable product. Limited investment may be required, but integrity, competence and ability to work together will be paramount considerations. Location: New York Area. Replies will be fully confidential.

BO-9431, Electronics
330 W. 42 St., New York 36, N. Y.

Bell Telephone Laboratories

has career openings for experienced

electrical engineers
mechanical engineers
physicists

For work on Guided Missiles, Radar, Fire Control and Underwater Systems in New Jersey *(20 miles from New York City).*

The company that has pioneered many of the major developments in the fields of communications and electronics now offers you an opportunity to join its staff. Here you will gain invaluable experience and great satisfaction through the challenging diversified nature of the work. To qualify, you must be a college graduate (preferably not over 40 years of age) with related experience of the following types:

Systems Engineering	*Systems Development*
Analysis	**Fundamental Development**
Coordination	**Circuit Design**
Evaluation	**Mechanical Design**
Planning	**Equipment Development**
Studies	**Field Testing**

Write, giving full details of education and experience to:

BELL TELEPHONE LABORATORIES Inc.
Employment Director, Box 2, New York 14, N. Y.

ENGINEERS DESIGNERS

ELECTRONIC SERVO

ELECTRO— MECHANICAL

AC QUALITY PRODUCTS

"AC" OFFERS *A Challenge to Men of Resourcefulness*

FIELD ENGINEERS

• For recent college graduates, here are positions with a challenge—

ASSIGNMENT — you will assist in the installation, operation, and maintenance of our equipment at aircraft plants and Air Force bases. The work will include liaison between AC and the customer, training of customer personnel, analysis of problems, and recommendations for improvements. Many of these outstanding openings are one-year overseas assignments.

YOUR BACKGROUND — your educational background can be in any of the fields of AE, EE, ME, Physics, or equivalent. To be successful in these positions you should have a definite interest in people as individuals and be willing to relocate to field assignments. Single men given preference.

TRAINING — our theoretical and applied in-plant training (here in Milwaukee) will prepare you for these assignments.

In addition to your salary, you will receive a field allowance — and a substantial bonus if selected for overseas assignment . . . if you're looking for an opportunity with a "present" and a *future* write us for further facts.

We need men of high caliber, experienced in the field of airborne automatic electro-mechanical control equipment. You will be engaged in the manufacture and development of highly complex equipment of the most advanced type in a steadily expanding division of our company—a division with 20 years of successful operation in the precision instrument field. We offer many advantages to those who join our organization— SALARY increases are based on merit and initiative . . . two weeks VACATION with pay . . . HOSPITALIZATION BENEFITS . . . LIVING and RECREATIONAL FACILITIES are among the best anywhere along Lake Michigan . . . POSITIONS ARE PERMANENT due to long-range manufacturing and development programs . . . in short—here at our "AC" Milwaukee plant you get small company advancement opportunities with large company employe benefits . . . EXPENSES incident to interviews are all absorbed by us.

For less experienced engineering graduates, we have a Junior Engineer Training Program which makes it possible for you to become acquainted with all phases of our company . . . you can also take advantage of educational opportunities for advanced degrees at Marquette University and the University of Wisconsin.

We answer ALL inquiries . . . write or apply

AC SPARK PLUG DIVISION

GENERAL MOTORS CORPORATION

1925 E. KENILWORTH PLACE • MILWAUKEE 2, WISCONSIN

IMAGINATION

Got more than your share? Like to have the freedom to use it, with commensurate recognition? Then, you've come to the right ad!

That is, if you're an electronic or mechanical engineer with practical experience in the electronic industry.

We need engineers with imagination. We're growing and going . . . you're just in time to go with us. You'll enjoy the job plus the advantage of pleasant living conditions in a large, modern city . . . without the disadvantage of big city pressure.

The man to contact is Arthur E. Harrison, Vice-President of Engineering. The time is now! You'll never regret it!

wilcox

Aviation Communications and Navigation

Fourteenth & Chestnut,
Kansas City 27, Mo.

ENGINEERING OPPORTUNITIES WITH A GROWING ELECTRONICS FIRM

Positions open for Senior and Junior Engineers experienced in

COMMUNICATIONS
RADAR
TEST EQUIPMENT
TELEVISION

Attractive Living Conditions, and Pleasant Working Environment

WRITE TO:

CHIEF ENGINEER

HARVEY-WELLS ELECTRONICS, Inc.

NORTH STREET
SOUTHBRIDGE, MASSACHUSETTS

SALES ENGINEER

Man with following among electronic, instrument or aviation companies. Excellent opportunity with AAA-1 manufacturer of electro-mechanical assemblies. Salary commensurate with ability. Please send resume including names of companies you are presently calling on. Box E 1430, 221 W. 41 St., N. Y. 36

Help Build Tomorrow's World TODAY!



GOODYEAR AIRCRAFT CORPORATION, pioneer and leader in lighter-than-air craft, offers you a new employment opportunity with a well-established and fast-growing company where "careers are planned."

DESIGN AND DEVELOPMENT engineering opportunities are available for capable and imaginative men and women in the field of airships, aircraft and aircraft components.

RESEARCH AND DEVELOPMENT projects — missiles, electric and electronics systems, servomechanisms, new special devices, fiber resin laminates — all present an urgent need for engineers with fresh talent, aptitude and ambition.

POSITIONS ARE OPEN at several levels in various fields with salaries based on education, ability and experience.

Physicists	Civil engineers
Mechanical engineers	Electrical engineers
Aeronautical engineers	Technical editors
Welding engineers	Technical illustrators

AKRON, THE HOME OF GOODYEAR AIRCRAFT, is located in the lake region of northeastern Ohio. Cosmopolitan living, year-round sports and recreation, cultural and educational advantages make this thriving city an ideal spot for a pleasant home.

YES, BUILD YOUR FUTURE — TODAY! Write, giving your qualifications, or requesting an application form.

C. G. Jones, Salary Personnel Department

GOODYEAR AIRCRAFT CORPORATION, 1210 MASSILLON RD., AKRON 15, OHIO

ENGINEERS...

Tie in your future with Admiral

. . . . at the steadily expanding electronics engineering activity of our Chicago, Illinois, plant.

Can *your* professional experience be more fully recognized? Think of *your* future . . . . investigate these opportunities at Admiral.

Openings exist in all classifications for Junior, Intermediate and Senior Project Engineers.

They are for Research, Development, and Product Development in the following fields:

MONOCHROME AND COLOR TV RECEIVERS
COLOR GENERATING TEST EQUIPMENT
UHF SYSTEMS
RADIO RECEIVERS
RADAR SYSTEMS
LABORATORY TEST EQUIPMENT

All with the security and possibilities for advancement inherent in this type of work.

Chicago is foremost among cities in supplying unsurpassed educational and recreational facilities. Individuals with a technical educational background will have the opportunity of furthering their experience and education by working with qualified engineering personnel. Excellent opportunities exist in the Chicago area for further study and education including post-graduate work.

We suggest you write Mr. Walter Wecker, Personnel Division, giving educational qualifications and related experience. Interviews will be arranged at your convenience.

Admiral Corporation
3800 W. Cortland St.
Chicago 47, Illinois

ELECTRONIC ENGINEERS

EE or ME degree, minimum 3 years' experience in research and development work involving microwave circuits and antennas, circuit development, servo-mechanisms, analogue computers or related equipment.

FIELD REPRESENTATIVES

A few openings for graduate engineers only with backgrounds similar to above. Continental U.S.A.

3 ***good reasons for choosing***
General Precision Laboratory

1. **OPPORTUNITY** . . . Because we are a comparatively small company with a close working relationship between management and staff, recognition and advancement are more rapid—as evidenced by the number of young men in top positions today.
2. **STABILITY** . . . GPL provides interesting work with a great measure of stability due to our association with a large, diversified parent organization.
3. **GOOD LIVING** . . . Consider the opportunity to live in a fine suburban community in Westchester County, N. Y., known throughout the country for its high standard of living.

Expenses will be paid for qualified applicants who come for interviews. Please submit complete resume to:

Mr. H. F. Ware

GENERAL PRECISION LABORATORY, Inc.
A subsidiary of General Precision Equipment Corp.
63 Bedford Road, Pleasantville, New York

WANTED
ENGINEER WITH EXPERIENCE IN
VHF OR UHF

Interesting creative work with the most resourceful and progressive firm in the field of television equipment.

This position is permanent. It will offer every opportunity for unlimited advancement and for developing a successful career. The plant is now housed in a newly-acquired larger building, only 22 miles from downtown New York City. The surroundings and atmosphere are stimulating and congenial.

Attractive Salary
Write stating qualifications.

BLONDER-TONGUE LABORATORIES
526-536 NORTH AVENUE
WESTFIELD, NEW JERSEY

What means most to an Engineer?

PROFESSIONAL RECOGNITION

GOOD SALARY

UNEXCELLED FACILITIES

SUBURBAN LIVING

A Career at RCA offers all Four!

RCA offers opportunities now—real career opportunities—for qualified ELECTRONIC, COMPUTER, ELECTRICAL, MECHANICAL and COMMUNICATIONS ENGINEERS . . . PHYSICISTS . . . METALLURGISTS . . . PHYSICAL CHEMISTS . . . CERAMISTS . . . GLASS TECHNOLOGISTS.

Positions are open in research, development, design and application. Long range work in many fields is being carried on both for commercial developments and military projects for war and peace.

At RCA you'll work in an exciting professional atmosphere, with technical and laboratory facilities unsurpassed anywhere in the radio-electronic industry. You are in close and constant association with leading scientists and engineers. Individual accomplishment is not only recognized, it is sought out. Delightful suburban living is easily available for your family. And there's ample opportunity for income and position advancement.

Plus, Company-paid hospitalization for you and your family . . . accident and life insurance . . . progressive retirement plan . . . fine recreational program . . . modern tuition-refund plan at recognized universities for advanced study.

Join the team at RCA, world leader in electronic development, first in radio, first in recorded music, first in television. Rest easy in the knowledge that your future is secure, the rewards many and varied.

Positions Open In: **RESEARCH—DEVELOPMENT—DESIGN—APPLICATION**

in any of the following fields:

RADAR—Circuitry—Antenna Design—Servo Systems—Information Display Systems—Gear Trains—Stable Elements—Intricate Mechanisms

COMPUTERS—Digital and Analog—Systems Planning—Storage Technique—Circuitry—Servo Mechanisms—Assembly Design—High Speed Intricate Mechanisms

COMMUNICATIONS—Microwave—Aviation—Mobile—Specialized Military Systems

MISSILE GUIDANCE—Systems Planning and Design—Radar and Fire Control—Servo Mechanisms—Vibration and Shock Problems

NAVIGATIONAL AIDS—Loran—Shoran—Altimeters—Airborne Radar

TELEVISION DEVELOPMENT—Receivers—Transmitters and Studio Equipment

COMPONENT PARTS—Transformer—Coil—Relay—Capacitor—Switch—Motor—Resistor

ELECTRONIC TUBE DEVELOPMENT—Receiving—Transmitting—Cathode-Ray—Phototubes and Magnetrons

ELECTRONIC EQUIPMENT FIELD ENGINEERS—Specialists for domestic and overseas assignment on military electronic communications and detection gear.

Personal interviews arranged in your city.
Please send a complete resume of your education and experience to:

MR. JOHN R. WELD
Employment Manager, Dept. 200K
Radio Corporation of America
30 Rockefeller Plaza, New York 20, N.Y.

RADIO CORPORATION of AMERICA

ENGINEERS, E E

- Development of radio and radar components and systems.
- Design of components for the magnetic deflection of Cathode Ray Tubes.
- For component and system development work in airborne navigational equipment.

DESIGNERS

- For work in the design of electro-mechanical navigational computers.

YOU'LL FIND THESE ADVANTAGES AT KOLLSMAN:

- An organization small enough to provide diversity and recognition of achievement, large enough for stability.
- Intricate design and development work on America's finest aircraft instruments.
- An informal friendly atmosphere, and the best facilities available in modern laboratories.
- Convenient location in a quiet residential area only 20 minutes from the heart of New York.
- Free life, hospitalization, surgical, accident and health insurance.

Why not find out what Kollsman has to offer you?

KOLLSMAN INSTRUMENT CORP.

80-08 45th Avenue — Elmhurst, Long Island, N. Y.

Electrical Engineers and Physicists

- Radar Simulation
- Advanced Circuitry
- Analog Computers
- Ballistics
- Mapping
- Telemetering

Senior and Junior Engineers

*Opportunities Ltd.**

We offer you an opportunity to grow with us . . . an opportunity: for steady advancement . . . individual recognition by working closely with technical management . . . rapid individual development by contact with all phases of projects . . . an interesting and stimulating association with other engineers . . . a suburban location for working and living . . . to ally yourself with a firm with a future. If you are looking for *opportunities unlimited* . . . write:

Industrial Research Laboratories
Hilltop and Frederick Roads
Baltimore 28, Maryland

* Unlimited

---

senior engineers . . .

in whose hands is your future?

MELPAR has an unparalleled opportunity to offer you—rapid progress and sound future—varied project assignments under the guidance of nationally known engineers. In addition to numerous and challenging projects—both military and industrial—Melpar is Research Headquarters for the Westinghouse Air Brake Company and its affiliates.

If you can qualify—high achievement, financial security and gracious living await you here! Melpar is located in the beautiful Virginia suburbs, just a few minutes from the Nation's Capital. A grand place to build a grand future! Let's discuss it all in detail.

THREE TO FIVE YEARS EXPERIENCE IS REQUIRED IN ONE OR MORE OF THE FOLLOWING FIELDS

Radar • Sonar • Fire Control Systems • Micro-Wave Techniques • Pulse Circuits • Servo Mechanisms • Electro-Mechanical Design • Speech Compression • Small Mechanisms • Antennae Design • Flight Simulators

FOR PERSONAL INTERVIEW

in your area, write Personnel Director, Dept. E-11

melpar INCORPORATED

440 SWANN AVENUE, ALEXANDRIA, VIRGINIA

THE RESEARCH LABORATORY OF WESTINGHOUSE AIR BRAKE CO. AND ITS SUBSIDIARIES

HOUSTON, TEXAS

Precision equipment manufacturer needs qualified experienced engineer for audio and sub-audio transformer design and development. Experience with high permeability alloys desirable. Knowledge of magnetic circuitry must be sufficient for development work on magnetic amplifiers. Salary commensurate with ability.

SOUTHWESTERN INDUSTRIAL ELECTRONICS CO.

P. O. BOX 13058, HOUSTON 19, TEXAS

ELECTRONIC ENGINEERS

for design & development work
WITH A YOUNG PROGRESSIVE COMPANY

√ digital techniques
√ computers
√ radar

SEND RESUME OF EXPERIENCE AND EDUCATION, WITH SALARY REQUIREMENTS, TO

Electronic Engineering Company

180 SOUTH ALVARADO STREET
LOS ANGELES, 57, CALIFORNIA
DUNKIRK 2-7353

Bendix Aviation Corporation

●YORK *Division* . . .

This NEW division of our nationally-famous corporation has openings for . . . .

ENGINEERS
PHYSICISTS

Top-flight men in advanced fields of electronic research, development and product engineering are needed for challenging work under ideal conditions in our new, modern plant.

You benefit at Bendix York from our location in the heart of a beautiful suburban area, from high wages, paid vacations and holidays . . . and excellent opportunities for advancement.

Openings at all levels.

Write, Wire or Phone
Department Y-1

Bendix

AVIATION CORPORATION
YORK DIVISION
Phone: York 5521 York, Penna.

SPECIAL OPPORTUNITIES FOR

SENIOR ENGINEERS

Convair in beautiful, sunshiny San Diego invites you to join an "engineers" engineering department. Interesting, challenging, essential long-range projects in commercial aircraft, military aircraft, missiles, engineering research and electronics development. Positions open in these specialized fields:

Electrical Design	Servo-mechanisms
Mechanical Design	Aerodynamics
Structural Design	Thermodynamics
Structures	Operation Analysis
Weights	System Analysis

Generous travel allowances to those accepted. For free brochure, write Mr. H. T. Brooks, Engineering Dept. 900

CONVAIR
IN BEAUTIFUL
SAN DIEGO
3302 PACIFIC HIWAY
SAN DIEGO 12, CALIFORNIA



RAYTHEON

WANTS

FIELD ENGINEERS

FOR INSTRUCTION AND SUPERVISORY WORK ON THE INSTALLATION AND MAINTENANCE OF RADAR AND SPECIAL EQUIPMENTS

EE graduates or equivalent with 3 years experience in the field given preference. Excellent starting salary and opportunity for rapid advancement based on merit. Many other attractive benefits. Don't delay. Write now.

Government Field Engineering

RAYTHEON
MANUFACTURING COMPANY
Waltham 54, Massachusetts

"An Unexcelled Opportunity For Professional Growth . . . . . "

ELECTRONIC ENGINEERS & PHYSICISTS

IN RESEARCH AND DEVELOPMENT

GUIDED MISSILES • RADAR • SOLID STATE PHYSICS •
VACUUM TUBES • ELECTRONIC NAVIGATION •
TELEVISION • MICROWAVES • ANTENNAS •
RADIO • COMPUTERS • TRANSISTORS •

DIRECT INQUIRIES TO:
THE EMPLOYMENT DEPT.

CAPEHART-FARNSWORTH
CORPORATION
FORT WAYNE, INDIANA

AN IT&T ASSOCIATE

EXCELLENT OPPORTUNITIES FOR GRADUATE ENGINEERS

Electronic & Mechanical

Experience in Design and Development of Radar and Sonar necessary.

Senior Engineers with Degree or equivalent and at least 5 years experience in any one of following fields: Microwave, circuit design, filter network design, precision components (capacitors - resistors), and communications.

Broad knowledge of Search and Fire Control Systems; Servo Mechanisms, Special Weapons, Microwave, Antennas and Antenna Mounts, etc. Mechanical Engineer should also have experience in packaging of Electronic Equipment to Gov't. specifications including design of complex cabinets, shock mounts and sway brace structures.

Field Engineers

Qualified to instruct in the operation and supervise installation, maintenance and repair of Radar, Sonar and allied electronic equipments in the field.

Senior engineers with degree or equivalent and at least 5 years experience in flight simulators, radar, sonar, and associated trainers.

A chance to grow with a young and progressive company; salary and advancement commensurate with ability; liberal vacation, sick leave, 9 paid holidays, group life, sickness and accident insurance plans, and a worthwhile pension system.

STAVID ENGINEERING, INC.

PERSONNEL: 312 PARK AVENUE — PLAINFIELD, N. J. - Pl. 6-4806

ELECTRONIC DEVELOPMENT IS MOVING WEST*

ENGINEERS—Take this opportunity to join the staff of a Western electronics pioneer & leader.

Creative ability finds expression with us!

- **RESEARCH**
- **DEVELOPMENT**
- **PRODUCTION**

Broad project variety in special receivers, transmitters & other devices. Advanced design techniques.

* Figures show 20% U. S. activity in So. California

Relocation expenses—excellent working conditions—Central location. Scheduled reviews & advances. Fine insurance plan. Move should not disturb urgent military projects.

Send complete resume with income history & requirements to engineering employment mgr.

Hoffman LABORATORIES, Inc.

3761 SO. HILL ST. — LOS ANGELES 7, CALIF.

(A Subsidiary of Hoffman Radio Corp.)

Electronic Research Opportunities

The Cook Research Laboratories, division of the Cook Electric Company, one of the nation's foremost research organizations requires the services of several outstanding scientists. Positions are permanent:

STAFF ENGINEERS

• ELECTRONICS •
• MECHANICS •

Openings also exist for top level personnel in the following fields:

RADAR & PULSE SYSTEMS
(VHF-UHF Development Experience)

SERVO
(Hydraulic Background)

AERODYNAMICS AERO DESIGN

Excellent Starting Salaries
Ideal Working Conditions
A Technical Turnover of Less Than 1/6 the National Average

• A staff composed of a group of engineers and scientists eminently qualified in their respective fields, and with whom you would be proud to be associated.

Contact or write Mr. D. M. Halliday

COOK RESEARCH LABORATORIES
8100 N. Monticello Ave.
Skokie, Illinois

COOK ELECTRIC CO.
2700 N. Southport — Chicago, Ill.
(Electrical and mechanical engineering and manufacturing since 1897)

Public Auction Sale

ENTIRE INVENTORY OF
POWER ELECTRONICS CO. — Jack Levinson
of San Diego, California
"NO LIMIT" "NO RESERVE"
One of the largest, cleanest stocks ever auctioned!

TRANSMITTERS & RECEIVERS
400 APS—13 Transceivers complete
Arc 1 & 3 Transceivers (checked out)
150 ARB Receivers comp. (checked out)
Command Equipment: Arc 5—274N
3000 Com. Transmitters 4-5.3, 5.3-7, 7-9
Command Receivers 190—550 KC
400 MN 26C Radio Compass Sets comp.
RTA 5-B Transmitters and Receivers
TCS Transceivers
Large assort. Transmitters & Receivers
BC-602 BC-603 BC-604 BC-522
BC-474A TVK-5 TVJ-8
BC433G & BC433F Radio Compass
Receiver Units (partial listing only)

SHORT WAVE & INTERPHONE
150 BC347C Amplifiers, T24 Microphones
T30 Throat Mike, HS30 Head Sets
BC365 12V Interphone Amplifiers
BC367 Interphone Amplifiers
10 National Ship-to-Shore Receivers
Short Wave Receivers
Walkie-Talkies & Handie Talkies
SDS Pulse Timers
Hand Mikes & Head Sets

Model BA Radio MG Sets
Directional Loops
Field Phones—Phone Equipment
Large quantity of Coaxial & Power Cable
250 APS Antenna Drive Motors
(Thousands of component parts)

RADAR EQUIPMENT
5 SG-1 Radar Complete
SA Radar Console
SC Radar Transmitters
SF & SL Radar Unit
RC-100 Radar Unit Complete
1500 3-CM Radar Wave Guide Sections
150 SCR 518 Radar Altimeters complete
SF Radar Domes. Radar Indicators
Radar Screens. SC Radar Transmitters
APQ13 Component Kits

ELECTRONIC COMPONENTS
4000 Transformers
MC385 Head Set Adjusters
PE237 Vibrators 5000 Tubes
BC434F Control Boxes
5000 CD343 Cord Sets
1200 Dynamotors 12 to 28V
Amphenol and Cannon Plugs
1000's Switches—Relays—Condensers

Power Supplies
Chokes
Circuit Breakers
Selsyn & Autosyn Motors
Hi Fi Speakers
B2 Intervoltmeters
Volt. Regulators BC 937-B
Inverter Motors
Motor Generator Sets
Gunnery Trainers
Instruments, Meters, Ind.
Thousands of Misc. items

TEST EQUIPMENT
RCA, Jackson, Supreme,
Hallicrafter & Western
Pulse Generators
Volt Meters, Volt Ohmeter
Oscillographs
Tube Analyzers, etc.
Audio Chanalyst
Frequency Meters
15 Kohler Power Plants
1M21A (New)
Maintenance Tools

Cut Out This Memo Now:

POWER ELECTRONICS CO.
AUCTION
Thursday, November 5, 1953,
starting at 10:30 A.M. P.S.T.
on premises
534 Market St., San Diego, Calif.

NOTE: Above is only a partial listing of merchandise to be auctioned.
Write, wire or phone to address below for descriptive literature or hotel accommodations.

DAVID WEISZ CO. *Auctioneers*
840 SAN JULIAN ST Michigan 8005 LOS ANGELES CALIF

Applications ENGINEER

An engineer is needed to study circuitry problems involving the use of small electron tubes and semi-conductor devices; in the applications laboratory of major radio tube manufacturer. A degree in electrical engineering, electronic engineering or physics is required. Salary commensurate with experience and ability. Applicants without experience will be considered. We offer good pay and many employee benefits. Send resume to or apply at

TUNG-SOL ELECTRIC INC.
200 Bloomfield Avenue, Bloomfield, N. J.

WANTED

WILL BUY
All ART-13/type T-47A $200.00; ART-13/type T-47, $150.00; BC-348 unmodified $45.00, BC-348 modified $50.00; APN-9 $200.00; ARC-3 complete $600.00; B77 Receivers $300.00; ARC-1 $300.00; BC-312 $60.00; BC-342 $60.00.
Ship via Express C.O.D., subject to inspection to:
H. FINNEGAN
49 Washington Ave. Little Ferry, N. J.

ELECTRONIC TUBES
URGENTLY NEEDED
CASH PAID FOR:
Radio, TV, Special Purpose, all types, small and large quantities. State types, quantities, prices.
WRITE NOW to
W-9166, Electronics
330 W. 42 St., New York 36, N. Y.

WANTED
BC-1016
TAPE RECORDERS
COMMUNICATION DEVICES CO.
2331 Twelfth Ave. NYC 27, N. Y.
Cable: Communidev Tel: Ad 4-6174

SALES ENGINEER

Must have successful record of sales to electrical and electronics industry in Midwestern states and be desirous of working in that area.

Excellent opportunity for qualified man to become affiliated with long range program to expand sales of coil winding machinery.

Send complete resume to Personnel Director

UNIVERSAL WINDING CO.
P. O. Box 1605
PROVIDENCE 1, RHODE ISLAND

WANTED TO BUY:
One—General Radio Type 667-A Inductance Bridge.
One—Boontar Type 160A "Q" Meter.
They must be in A-1 Condition.
DELUXE COILS, INC.
First & Webster Sts. Wabash, Indiana

If there is anything you want
or something you don't want that readers can supply—or use—advertise it in the
Searchlight Section

WILL PAY FOR
BC 348R—$110.
BC 348L, K & H—$90.
ID-17/APN3
T-11/APN3
T-12/CPN2
CM-3/APN3
Other equipment wanted
What have you?
RADALAB
1964 Webster Ave. Bronx 57, N. Y.
Tel: WE 3-3232-3

Want more information? Use post card on last page.

Weston offers modern facilities for the PRODUCTION, MODIFICATION & DEVELOPMENT of PRECISION EQUIPMENT

ENGINEERING

Staffed by experienced engineers and skilled technicians, Weston Laboratories is constantly at work with customers, in problems relating to microwave and allied products. No problem is too large or too small for our consideration.

STOCK

Having one of the largest stockrooms in New England, Weston is prepared to "draw from stock" for quick assembly of its production and "custom made" units. It serves as the important link between customer requests and the finished product.

ASSEMBLY

Our production assembly departments are equally prepared for short or long-run contracts. The section shown here illustrates a production run of some of our "stock" units.

Here, in the Research and Development Laboratories, the know-how of our engineers and laboratory technicians is put to the test. With a practically complete complement of standardizing and testing equipment for measurements from D-C to 45,000 MC, we are prepared to tackle a great variety of problems advanced by the customer. Research and development is also being carried on in an effort to improve our own line of test equipment, and keep abreast of the latest developments.

LABORATORIES

Our Machine shops reflect the quality, precision and workmanship that characterizes the New England machine tool industry. These people, skilled in their trades, have been schooled in the art of microwave fabrication, and are equipped with the tools and the "know how" to do the job speedily and correctly.

MACHINE SHOP

• QUOTATIONS PROMPTLY SUBMITTED •



LABORATORIES, INC.
HARVARD, MASS.
Tel: HARVARD 250—AYER 300—TWX HARV 193
Cable: WESLAB

Want more information? Use post card on last page.

Weston HIGH QUALITY TEST EQUIPMENT

WL-117 WAVEMETER

A precision wavemeter having a range from 2400 mc to 3400 mc with an accuracy of better than 0.1% over the entire range. The resonant cavity has a Q of not less than 1000 and normally from 1000 to 2000. The unit, supplied with a pickup dipole interconnecting cable and adapters, may also be used for relative field strength measurements.

PRICE: $390.00

WL-62 ECHO BOX

A portable ringing cavity for microwave research; the unit has a frequency range from 9320 to 9420 mc, with a Q of 50,000 to 80,000. The echo box is used for relative power measurements, spectrum analysis, frequency checks, tests for unstable operation and a host of other applications in the laboratory.

PRICE: $350.00

WL-108 TERMINATION

This 1" x ½" waveguide hi-power load is capable of dissipating a peak power of 200 kilowatts and an average power of 150 watts. The VSWR is less than 1.10 over the entire frequency range of 9300 to 9450 mc. All accessories including carrying case and coupling adapters are supplied with the unit.

PRICE: $90.00



WL-13 SIGNAL GENERATOR

A versatile x-band signal generator providing a source of pulsed or CW power and having provisions for square-wave and sawtooth modulation. Accurate monitoring of the RF output is accomplished with a thermistor bridge and a calibrated attenuator. The power supply is electronically regulated to insure stable operation of the 723A/B Klystron oscillator.

PRICE: $1278.00

WL-89 VOLTAGE DIVIDER

An indispensable aid in high power radar and transmitter measurements this unit has provisions for 100:1 and 10:1 voltage division. It can be used with an oscilloscope to measure video pulses between 200 and 20,000 volts in high-impedance circuits. The ratio accuracy is within +15% and transmission is within 2 db from 150 cycles to 5 megacycles.

PRICE: $45.00

WL-102 PULSE GENERATOR

Equivalent to the TS-102/AP Range Calibrator, this crystal controlled pulse generator produces a square-topped, 50 volt synchronizing pulse of .8 microseconds at a prf of 400, 800, 1600 or 2000 cps, and a triangular marker pulse of 0.4 microseconds duration at a prf corresponding to a pulse-echo distance of 1500 ft. The phase between the marker and sync. pulses is continuously variable from −180 to +180 degrees.

PRICE: $350.00



WL-125 POWER METER

This instrument is a compact, battery operated thermistor bridge designed to measure power in the range of 2400 to 3335 mc., and having a full-scale sensitivity of 2 milliwatts. Among other applications, it can be used to measure antenna patterns, check standing wave ratio and determine average or peak powers. A complete set of accessories, including a 10 db and 16 db attenuator pad for measuring higher power levels, are supplied with the unit.

PRICE: $390.00

SG-8/U NOISE GENERATOR

This popular model, employing a 5722 temperature limited diode as the R.F. noise source, can be used as an absolute means of receiver noise measurements as well as for fundamental studies. The normal input impedance is 270 ohms but a 50 ohm adaptor is supplied with the unit as a standard accessory.

PRICE: $250.00

WL-90 DUMMY LOAD

Provides a 50 ohm termination in the form of a 50 to 1 ratio voltage divider for making over-all performance tests on radar units such as the AN/APQ-7, 13, 13A, 23 and a host of other equipments in this frequency and power range. The 49 and 1 ohm resistor elements are carbon coated ceramic rods in helium filled glass tubes and are capable of dissipating up to 500 watts at a peak voltage of 5000 volts.

BC-221 FREQUENCY METER

This universally used and time-tested instrument is a precision meter designed to measure or radiate R.F. impulses between 125 and 20,000 KC. The overall accuracy of the unit is 0.034% over the entire operating range. It is portable and completely self contained or, if desired, it can be obtained with a power supply for 115 volt operation.

PRICE:

Without Modulation	$125.00
With Modulation	165.00
115v Power Supply	35.00



TS-100 OSCILLOSCOPE

This instrument can be used with a linear sweep as a general purpose test oscilloscope or it can be used with a circular sweep as a precision range calibrator. It has a PRF rate of 300 to 1500 per second. Trigger input — 15 volts at 100 volts per microsecond rise. Trigger output — 120 volts (+ 20 volts). It can be used for detecting "jitter" in trigger divider circuits and modulator trigger pulse, and also for determining and adjusting division rate.

PRICE: $850.00

WL-268B/U CRYSTAL RECTIFIER TEST SET

A combination ohmmeter-ammeter designed to measure the electrical characteristics of microwave crystal rectifiers such as the 1N21 and 1N23 series. The instrument is completely self contained and requires only a single 1½ or 3-volts cell for operating power.

PRICE: $83.75



LABORATORIES, INC.

HARVARD, MASS.

Tel: HARVARD 250—AYER 300—TWX HARV 193

Cable: WESLAB

SPECTRUM ANALYZER

T S 148/UP

Most versatile instrument in the Microwave field for frequencies from 8470 mc/s to 9630 mc/s all directly calibrated.

It will measure within the above frequencies spectra of radar transmitters, receivers, echo boxes, local oscillators, resonant cavities, T R boxes, magnetrons, klystrons and test sets.

This instrument is manufactured to the highest standards of the industry and is used by the largest radar and aircraft manufacturers as well as the services of the United States.

Specifications

Power Supply.....50-1200 Cps; 105-125 Volts; 125 Watts
Frequency-meter Range....Calibrated directly from 8470 mc/s to 9630 mc/s
Sweep Frequencies.....Continuously Variable from 10 to 30 Cps
Attenuation (Spectrum Amplitude).....Uncalibrated, Variable from 3 to 70 db.
Operating Temperature Range.....—40°C. to +55°C.
Frequency swing of analyzer r-f oscillator (sawtooth FM).....40 to 40 mc/s
Overall i-f bandwidth at half power points.....50 kc/s
Sensitivity to CW — Spectrum Amplified Pos. — 80 db. below 1 watt for 1 inch of deflection on Oscilloscope Screen.
— Spectrum Position — 55 db. below 1 watt for 1 inch of deflection of Oscilloscope Screen.
Maximum dispersion of spectra.....1.5 mc/s per inch
Maximum error .....+ 5 megacycles

We will gladly furnish all details regarding specifications prices and delivery.

Other test equipment, used checked out, surplus.

TSK1/SE K Band Spectrum Analyzer
TS3A/AP Frequency and power meter S Band
RF4A/AP Phantom Target S Band
TS12/AP VSWR Test Set for X Band
TS13/AP X Band Signal Generator
TS14/AP Signal Generator
TS33/AP X Band Power and Frequency Meter
TS34/AP Western El Synchroscope
T35/AP X Band Signal Generator
TS36/AP X Band Power Meter
1-96A Signal Generator
TS45 X Band Signal Generator
TS47/APR 40-400 MC Signal Generator
TS69/AP Frequency Meter 400-1000 MC
TS100 Scope
TS102A/AP Range Calibrator
TS108 Power Load
TS110/AP S Band Echo Box
TS125/AP S Band Power Meter
TS126/AP Synchroscope
TS147 X Band Signal Generator
TS270 S Band Echo Box
TS174/AP Signal Generator
TS175/AP Signal Generator
TS226 Power Meter
TS239A Synchroscope
TS239C Synchroscope

SURPLUS EQUIPMENT

APA10 Oscilloscope and panoramic receiver
APA38 Panoramic Receiver
APS 3 and APS 4 Radar
APR4 Receiver
APR5A Microwave Receiver
APT2 Radar Jamming Transmitter
APT5 Radar Jamming Transmitter

MINIMUM ORDER
25 Dollars

YOU CAN REACH US ON TWX NY1-3235

Cables:
TELSERSUP

SPECIAL

Wide Band S Band Signal Generator 2700/3400MC using 2K41 or PD 8365 Klystron, Internal Cavity Attenuator, Precision individually calibrated Frequency measuring Cavity. CW or Pulse modulated, externally or internally.

Large quantities of quartz crystals mounted and unmounted.
Crystal Holders: FT243, FT171B others.
Quartz Crystal Comparators.
North American Philips Fluoroscopes Type 80.
Large quantity of Polystyrene beaded coaxial Cable.

LIBERTY ELECTRONICS, INC.
135 LIBERTY STREET NEW YORK 6, N. Y.
PHONE WORTH 4-9262

Want more information? Use post card on last page.

Hard-to-get

X-BAND SIGNAL GENERATOR

Now Available



Model 385A
(Equivalent to TS-147 C/UP TEST SET)

ESPEY Model 385A (Equivalent to Test Set TS 147 C/UP) is a Portable Microwave Signal Generator designed for testing and adjusting beacon equipment and radar systems which operate within the frequency range of 8500 MC to 9600 MC.
COMPACT — SELF-CONTAINED — WEIGHS ONLY 40 LBS. COMPLETE WITH ACCESSORIES AND COMBINATION CASE.

GENERAL SPECIFICATIONS:

FREQUENCY RANGE: 8500 MC to 9600 MC. Selection is accomplished by a tuneable klystron which is set to an accurate absorbtion wavemeter.
FREQUENCY ACCURACY: ± 2 MC.
OUTPUT POWER RANGE: — 42 dbm to —82 dbm.
INPUT POWER RANGE: + 7 dbm to + 30 dbm.
ATTENUATOR ACCURACY: ± 1 db with calibration chart provided.
INPUT AND OUTPUT COUPLING: Type N female fitting (UG 21B/U).
MODULATION AVAILABLE ON OUTPUT: FM signal internally generated.
MODULATION OF INPUT SIGNAL ACCEPTED: CW or any other wave shape including pulse. Minimum pulse width accepted is .5 microseconds. Meter will read average power of input signal.
FM MODULATION: Carrier can be modulated through klystron mode at any frequency in range. (Minimum mode is 30 MCS). The sweep rate is continuously adjustable from 0 to 6 MCS. per microsecond.
EXTERNAL SYNC. PULSE REQUIRED: Amplitude of video input 10-50 volts positive polarity pulse .5 to 20 microseconds wide. Unit may also be synchronized from RF input pulse provided peak RF input power is at least 5 watts.
POWER SOURCE: 115 ± 10 volts A.C. 50 to 1600 cycles, single phase.
POWER CONSUMPTION: 135 watts.
SIZE: Width 11 inches.
Length 18¾ inches.
Height 12¾ inches.
WEIGHT: 40 lbs. including accessories.

ACCESSORIES AND SPARES PROVIDED:

ACCESSORIES: 1 R.F. Cord assembly. Consists of 3 ft. of RG-9A/U cable fitted with two UG-21B/U connectors. Calibrated to an accuracy of ± 0.3 db.
1 Trigger cord assembly. Consists of six ft. of RG-11/U cable fitted with two type 49195 connectors.
1 Power cord assembly. Consists of six ft. of rubber covered two-conductor cord with male plug and female receptacle.
1 Pick-up antenna.
1 coaxial cable fitting (right angle).

SPARES, OPERATING:
1 thermistor mount.
5 fuses, 2 amp.
9 wave guide flange joint gaskets.
3 panel lamps, 3.0 volt.
2 IN 23 B rectifier crystals.

THE ACCESSORIES AND SPARE PARTS ARE CONTAINED IN THE REMOVABLE PROTECTIVE COVER.

NEW YORK'S RADIO TUBE EXCHANGE

TYPE	PRICE	TYPE	PRICE	TYPE	PRICE	TYPE	PRICE	TYPE	PRICE	TYPE	PRICE	TYPE	PRICE
OA2	$1.40	2J22	17.95	3GP1	5.50	NE16	.66	371B	1.95	7286	99.00	884	1.95
OA3	1.10	2J26	27.75	4A21	2.75	FG17	6.95	385A	4.95	728AY	27.00	885	1.75
OB2	1.35	2J27	29.95	4B26	6.95	KY21A	8.75	388A	2.95	730A	24.00	889R	199.50
OC3	1.25	2J31	29.95	4C27	25.00	FG33	12.95	394A	5.00	861A	1.00	914	75.00
OD3	1.25	2J32	69.95	4C28	35.00	35T	3.50	MX408U	.75	862	4.25	931A	5.00
C1B	1.95	2J36	185.00	4E27	17.50	45 Special	.35	417A	17.95	863	7.95	954	.35
1B21A	2.75	2J38	17.95	4J25	199.00	RK39	2.95	434A	19.95	865	5.95	955	.55
1B22	3.95	2J39	12.50	4J26	199.00	HF50	1.75	446A	1.95	867	1.69	956	.89
1B23	9.95	2J40	35.00	4J27	199.00	VT52	.25	446B	5.40	868	3.50	957	.79
1B24	17.95	2J42	150.00	4J31	199.00	RK72	1.10	450TL	45.00	870	11.00	958A	.69
1B26	2.95	2J49	199.00	4J32	199.00	RK-75	1.95	464A	7.95	811A	3.95	991	.65
1B27	11.50	2J50	95.00	4J33	199.00	100TH	9.95	471A	2.75	813	9.95	F1148	.35
1B35	4.10	2J61	45.00	4J35	199.00	FG95	24.95	527	35.00	814	1.95	1J26	1.25
1B36	33.00	2J63	45.00	4J37	199.00	FG105	24.00	WL530	3.50	815	3.50	1611	1.95
1B42	19.95	2K25	29.50	4J38	189.00	203A	8.95	WL531	22.50	816	1.45	1615	1.38
1B51	9.95	2K28	37.50	4J39	199.00	211	.95	WL533	17.50	829	12.95	1616	2.95
1B56	49.95	2K29	37.50	4J40	199.00	217C	18.00	700A/D	25.00	829A	13.95	1619	.89
1B60	69.95	2K39	150.00	4J41	199.00	242C	16.00	701A	7.50	829B	15.95	1622	1.75
1N21	1.35	2K41	150.00	4J42	250.00	244A	12.95	703A	5.00	830B	2.50	1624	2.00
1N21A	1.75	2K45	149.50	4J51	350.00	249C	4.95	705A	3.95	832	7.95	1625	.45
1N21B	4.25	2K48	170.00	4J53	350.00	250TH	22.50	707A	17.95	832A	9.95	1851	1.95
1N22	1.75	2K50	350.00	C5B	3.95	250TL	19.95	707B	17.95	833A	49.95	2050	1.85
1N23	2.00	2K54	200.00	5BP1	6.95	274A	3.00	714AY	17.95	834	7.95	2051	1.89
1N23A	2.75	2K55	200.00	5BP4	6.95	274B	3.00	715A	7.95	836	4.95	8012	4.25
1N23B	4.25	2K56	180.00	5CP1	6.95	304TH	10.00	715B	12.00	837	2.95	8013	2.95
1N34A	.95	2V3G	2.10	5D21	21.00	304TL	12.00	715C	25.00	838	6.95	8013A	5.95
1N43	2.50	3BP1	7.50	5JP1	27.50	307A	4.95	717A	1.95	845	5.50	8014A	89.00
2B22	1.95	3B24	6.50	5JP2	19.50	310A	8.95	718AY/EY	48.00	849	52.50	8019	1.75
2B26	3.75	3B24W	7.50	5JP4	27.50	311A	6.95	719A	29.50	851	88.50	8020	3.50
2C34	.35	EL3C	5.95	WE6AK5	2.50	313A	3.95	721A	3.95	860	4.95	8025	6.95
2C40	10.00	3C22	120.00	C6A	12.50	323A	15.00	722A	3.95	861	29.50	PD8365	9.00
2C43	20.00	3C24	1.95	C6J	10.95	327A	3.95	723A/B	24.95	866A	1.79	9001	1.75
2C44	.50	3C31	1.95	7BP7	7.95	328A	6.95	724A	4.95	869B	57.50	9002	.95
2D31	1.75	3DP1A	10.95	7DP4	10.00	350A	10.00	724B	6.95	869BX	35.00	9003	1.75
2E22	2.75	3DP1B2	12.50	12AP4	55.00	350B	5.95	725A	9.95	872A	3.95	9004	1.75
2K30	2.75	3E29	15.50	15E	1.95	357A	15.00	726A	24.00	878	1.95	9005	2.90
3J21A	17.95	4A21	2.75	15R	.95	368AS	5.00	726B	56.00	880	300.00	9006	.35

Thousands of other tubes

CRYSTALS

. . . in FT 241-A Holders—½" Pin SPC. Marked 54th OR 72nd Harmonic MC Freq. Listed below by fundamental frequency with fractions omitted.

370	390	405	422	438	454	470	487	504	520
372	391	406	423	440	455	472	488	505	522
374	392	407	424	441	456	473	490	506	523
375	393	408	425	442	457	474	491	507	526
376	394	409	426	443	458	475	492	508	527
379	395	411	427	444	459	476	493	509	529
380	396	412	429	445	461	477	494	513	530
381	397	413	430	446	462	479	495	512	531
383	398	414	431	447	463	480	496	513	533
384	400	415	433	449	464	481	497	514	534
385	401	416	434	450	465	483	498	515	536
386	402	418	435	451	466	484	501	516	537
387	403	419	436	452	468	485	502	518	538
388	404	420	437	453	469	486	503	519	540

10 for $8.00 Postpaid

$1.00 EACH

MINIMUM ORDER 25 Dollars

YOU CAN REACH US ON TWX NY1-3235

Cables: TELSERSUP

LIBERTY ELECTRONICS, INC.
135 LIBERTY STREET NEW YORK 6, N. Y.
Phone WOrth 4-6363

WRITE FOR OUR FREE BULLETIN MORE GOOD ITEMS — GUARANTEED BRAND NEW

LECTRONIC RESEARCH TUBE SPECIALS

STANDARD BRANDS ONLY — WRITE FOR OUR FREE BULLETIN MORE GOOD ITEMS

Receiving Tubes

Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price	Type No.	Price
0A2	$1.50	6AC7	.65	6S7G	.90	12BE6	.66	75	.69	2J32	36.50	5JP2	26.50	VU-111A	1.69	471A	149.20	815	5.25	1633	.75	5855	75.40
0B2		6AC7W	2.25	6SA7GT	.75	12BF6	.67	76	.69	2J33	26.50	5JP7	26.50	VU-120A	1.75	482A	4.67	826	1.25	1634	1.25	5863	10.50
0C2		6AD5G	.75	6SA7GT	.75	12BH7	.90	77	.89	2J34	27.50	5JP11	26.50	HY-114B	.75	502AX	1.25	829A	1.25	1635	1.25	5870	1.72
0D3		6AD7G	1.25	6S8GT	1.04	12BH8	.90	78	.89	2J37	13.75	5JP16	15.75	WE-117A	.95	503AX	1.25	832A	9.50	1636	1.25	5871	10.50
0G3		6AE5G	.75	6SC7GT	.80	12BL6	.80	80	.89	2J38	16.50	5JP19	26.50	WE-124A	3.00	504AX	1.47	836	1.25	1638	1.25	5872	10.50
0Z2		6AG5	.75	6SF7	.82	12D7GT	.67	82	1.15	2J48	34.50	C6A	6.75	WE-124A	3.00	507AX	1.47	838	1.25	1639	1.25	5875	1.72
0Z4A	.45	6AG7	1.45	6SF7GT	.75	12DA8	.67	83	1.25	2J49	65.00	C6B	6.75	WE-205A	12.50	AR-180	12.50	845	2.50	1640	1.25	5876	1.72
1A1		6AH6	1.25	6SF7Y	.75	12DC7	.80	84	1.15	2J49	65.00	C6C	6.75	WE-211C	12.50	VR-105	.90	852A	9.75	1641	1.25	5879	1.72
1A3GT	.72	6AJ5	1.25	6SG7	.75	12DF7	.79	84/6Z4	.70	2J50	39.50	GC21	27.50	VR-150	.90	872A	1.75	861	9.50	1642	1.25	5881	1.72
1A7GT	.72	6AK5	.84	6SH7GT	.75	12DQ6	.80	85	.69	2J51	65.00	GC22	48.50	FG-32	48.50	873	3.50	866	1.25	1643	1.25	5886	1.72
1A05	1.30	WE-6AK5		6SH7GT	.75	12DT7	.80	89	.89	2J52	65.00	GP4	5.00	FG-172	29.50	882	2.20	872A	2.25	1644	1.25	5886A	1.72
1B3GT	.90		1.45	6S17	.71	12SQ7	.80	117N7GT	1.49	2J61	45.25	C6J	6.00	FG-178	14.50	885	1.50	873	2.25	1645	1.25	5887	1.72
1B5/25S	.90	6AK5W	2.00	6SJ7GT	.65	12SR7	.80	117P7GT	1.89	2J62	165.00	C6K	6.00	FG-180	15.50	954	.75A	874	2.25	1646	1.25	5893	1.72
1B8	.76	6AK8	.90	6SJ7Y	.65	12SW7	.80	117Z3	1.45	2J63	36.50	C6L	6.00	FG-190	14.50	955	.75A	878	14.50	1651	.90	5894	1.72
1C5GT	.88	6AL5	.90	6SK7GT	.72	12SJ7GT	.65	117Z6GT	.80	2K25	75.50	7BP1	6.00	KF200	6.00	KU616	11.50	884	.90	1652	1.25	5899	1.72
1C6	.80	6AL5W	2.45	6SK7GT	.72	12SK7GT	.65	FM-1000	1.00	2K26	75.50	7BP3	6.00	2B21	6.00	KU617	11.50	885	.90	1653	1.25	5902	1.72
1C7G	.80	6AQ5	.72	6SL7GT	.81	12SL7GT	.92			2K28	75.50	7BP12	14.50	2B31	6.00	AR-140	12.50	887	1.50	1654	1.25	5903	1.72
1D5GP	.90	6AQ6	.79	6SN7GT	.75	12SN7GT	.84			2K29	27.50	7BP14	14.50	2D21A	47.50	KU-623	39.50	893	67.00	1655	1.25	5904	1.72
1D8GT	.90	6AQ7GT	1.45	6SQ7	.75	12SQ7GT	.80	Trans-mitting and special Purpose Tubes		2K31A	165.00	7BP15	14.50	2E26	6.00	826	1.25	894	67.00	1656	1.25	5905	1.72
1E5GP	.71	6AR5	.75	WGT.	2.10	12SR7	.79			2K32	165.00	7GP7	11.75	231	.95	KU-627	15.00	895	67.00	1657	1.25	5908	1.72
1F4	.80	6AS6	.90	6SQ7	.65	12SR7GT	.80			2K33	165.00	9LP7	4.00	WE-		KU-628	22.50	898	494.00	1658	1.25	5914	1.72
1F5G	.80	6AS7G	2.25	6SR7	.65	12V6	.80			2K34	165.00	12BP4	12.50	211D	12.50	KU-629	11.50	900	1.25	1659	1.25	5915	1.72
1F8	.71	6AS7G	4.25	6SR7	.65	12X5	.80			2K35	165.00	12BP4	12.50	WE-		KU-630	1.00	902	22.50	1660	1.25	5916	1.72
1G4GT	.80	6AT6	.63	6S7T	.90	14A7	.97			2AP1	8.25	10T1	.88	211E	12.50	832B	26.50			1661	1.25	5919	1.72
1G6GT	.80	6AU5GT	1.25	6ST7	1.25	14A8	.74	Type No.	Price	2B22/	10.25	12DP7	14.50	2K42	6.00	KT61	1.45	931A	1.45	1662	1.25	5920	1.72
1G6GY	.80	6AU6	.65	6T7G	1.25	14B5	.80	0A2	$ .95	EL-1C	2.60	12DP7	14.50	2K43	6.00	KT66	2.45	954	.75A	1663	1.25	5921	1.72
1H4G	.80	6AV6	.65	6T8	.90	14B6	.80	0A3	1.25	2B24	1.50	12DP7	14.50	2K45	6.00	2C17C	8.95	955	62.50	1664	1.25	5922	1.72
1H5GT	.80	6AV6	1.20	6U7G	.80	14B8	.90	0A4G	1.15	2B25	4.50	12DT7	14.50	2K46	6.00	WE-		954	.75A	1665	1.25	5923	1.72
1H6GT	.70	6AV6	1.20	6U7G	.80	14C7	.80	0B2	1.10	2B26	4.50	12DT7	.85	211F	12.50	WL-6544/		955	62.50	1666	1.25	5924	1.72
1H6GY	.70	6AV6	.60	6V6	1.40	14E6	.90	0B3	1.10	2B27	4.50	12DT7A	.85	211G	12.50			956	62.50	1667	1.25	5925	1.72
1J5G	.80	6BA6	.70	6V6GT	.67	14F7	.80	0C3	1.10	2B31	4.50	12E5	.85	211H	12.50	WL-679A	5.75	958A	133.40	1668	1.25	5926	1.72
1J6G	.80	6BC5	.70	6V6GT	.67	14F7	.80	0C4	1.10	2B32	4.50	12E6	.85	211J	12.50	WL-6772	22.50	959	1.25	1669	1.25	5927	1.72
1L4	.80	6BA6	.60	6W4GT	.64	14H7	.80	0D3	.95	2B33	4.50	12F5	.85	5C27	4.00	672A	1.25	1616	1.25	1670	1.25	5928	1.72
1L4A4	.80	6BC5	1.20	6W6GT	.80	14J7	.80	0D21A	2.00	2B34	4.50	12F8GT	.85	WE-211D	2.25	KU-676	12.25	976	1.25	1671	1.25	5929	1.72
1L4A5	.80	6BC5	.60	6X4	.60	14N7	.80	1A3	2.00	2B35	4.50	12H6	.85	212CH	240.00	677	1.25	1613	1.25	1672	1.25	5930	1.72
1L4A6	.80	6BC5	.60	6X5GT	.60	14N7	.80	1B22	9.00	2C21	9.85	12J5	.85	WE-212E	12.50	WL-681/		1614	450.00	1673	1.25	5931	1.72
1L4A7	.80	6BC5GT	.60	6X5GT	.60	14N7	.80	1B22A		2C21/1615	9.85	12J7GT	.85	213A	4.95	5868	45.00	1615	1.75	1674	1.25	5932	1.72
1L4G	.80	6BE6	.60	6Z5GT	.60	14W7	12.00	West	12.00	2C22	9.85	REL-31	1.95	WE-214A	2.25	708A	24.50	1616	1.25	1675	1.25	5933	1.72
1L4H5	.80	6BE6	.65	7A4	.70	14W7	.80	1B24		2C31/		REL-21	1.95	WE-215A	2.25	708B	24.50	1617	1.25	1676	1.25	5934	1.72
1L4H6	.80	6BE6	.65	7A5	.70	14W7	.80	Sylv	10.95	EL-C1B	3.95	23D4	1.15	WE-245B	3.50	708C	24.50	1618	179.00	1677	1.25	5935	1.72
1L4I3	.80	6BE6	.65	7A6	.70	15E	.80	1B24A	30.50	2C31	12.50	24G	1.15	WE-245C	3.50	708D	24.50	1619	1.25	1678	1.25	5936	1.72
1L4N4	.80	6BF5	.60	7A7	.70	15Y6	.80	1B24A	30.50	2C34	12.50	RK-25	1.15	28D	1.15	708E	24.50	1620	1.25	1679	1.25	5937	1.72
1L4N5	.80	6BG6G	.80	7A7	.70	22		1.15	1B25	1.75	2C36	12.50	FG-27A	8.25	250TH.	22.50	701A	6.95	1621	1.25	1680	1.25	5938	1.72
1M1GT	.80	6BG6G	.80	7A8	.70	19AQ5		1.15	1B26	2.75	2C39	14.00	FG-32		250TL	22.50	701B	6.95	1622	1.25	1681	1.25	5939	1.72
1N5GT	.80	6BJ6	.80	7AD7	1.44	26A		1.15	1B31	2.75	2D21	2.25	35B	6.75	WE-254A	5.00	701C	6.95	1623	1.25	1682	1.25	5940	1.72
1P5GT	.90	6BK7A	1.60	7AH7	1.00	25L6GT		.90	1B32	2.75	2DP1A	4.95	FG31	22.84	WE-257A	3.77	703A	2.25	893AR		1683	1.25	5941	1.72
1P10GT	.90	6BL7GT	1.45	7B5	.70	25Z6	.80	1B33	2.75	2E22	13.75	45	1.15	WE-275A	4.00	704A	45.00			1684	1.25	5942	1.72
1Q6	.80	6BN6	1.50	7B6	.70	27		.90	1B34	2.75	2E24	13.75	51	4.95	5551	62.50	704B	45.00			1685	1.25	5943	1.72
1R4	.80	6BQ6GT	1.25	7B7	.70	27		.90	1B35	2.75	2EP1	4.75	1ST IGN		WE-276A	5.50	704C	45.00			1686	1.25	5944	1.72
1S4	.71	6C4	.70	7B8	.70	26D7	.90	1B36	2.75	2E25	13.75	Source	5.95	274B	240.00	704D	45.00			1687	1.25	5945	1.72
1S5	.71	6C5	.70	7B8	.70	30		.90	1B40	4.50	2EP7A	5.95	2F2G	4.95	WE-275A	2.25	704E	45.00			1688	1.25	5946	1.72
1S4	.80	6C6	.70	7C4	.70	30 Spec.		.65	1B41	51.50	3QP1	1.95	REL 36	.45	WE-203A	4.25	707A	7.95	1612	1.25	1689	1.25	5947	1.72
1T4	.80	6C8G	.70	7C5	.70			.65	1B42	51.50	3QP1	1.95	T-40	1.75	WE-205A	8.75	707B	14.95			1690	1.25	5948	1.72
1T6GT	.71	6CB6	.70	7C6	.70	31		.80	1B43	50.00	3JP1	165.00	FG-41	122.50	WE-206A	8.75	708A	6.95	1625	1.25	1691	1.25	5949	1.72
1U4	.71	6CD6G	1.25	7C7	.70	32L7GT		.87	1H29	.60	4-125A	29.50	RK-47	4.92	304TH.	8.75	708A	6.95	1626	1.25	1692	1.25	5950	1.72
1U5	.71	6CG6	.80	7C8	.70	33		.69	1P21	35.00	4-250A/		CE-48	4.92	307A	4.25	708B	6.95	1627	1.25	1693	1.25	5951	1.72
1V	.65	6CG6	.80	7E6	.80	33		.69	1P22		5D22	35.00	CF-48	.98	311A	4.25	708C	6.95	1628	1.25	1694	1.25	5952	1.72
1X2	.95	6D6G	.83	7E7	.83	35/51		.69	1P24	1.27	4A1	1.15	VT-52	.65	WE-310A	6.25	714AY	10.75	925	1.25	1695	1.25	5953	1.72
2A3	1.45	6E5	1.20	7F7	.80	35L6GT		.69	1P28	2.25	4AP10	6.45	51A	2.60	311A	6.25	715A	8.25	926	1.25	1696	1.25	5954	1.72
2A5	.75	6F5GT	.75	7F8	1.30	35Z3		.69	1P39	2.85	4B22/		RK59		WE-313C	4.95	715B	8.25	927	1.25	1697	1.25	5955	1.72
2B7	.79	6F6G	.99	7G7	.99	35L6GT		.67	1Q21	122.50	EL-5B	5.95	QK-60	60.00	311A	.80	715C	19.50	928	1.25	1698	1.25	5956	1.72
2C5	.80	6F6G	.80	7H7	.80	35W4		.67	1R22		4B24	6.45	SK-60	6.00	313A	4.25	715CX	19.50	929	1.25	1699	1.25	5957	1.72
2X2	.90	6F7	1.00	7J7	1.30	35Y4		.67	1T22		4B26/		QK-61	63.00	327A	4.25	715AY	45.00	930	1.25	1700	1.25	5958	1.72
2X2A	1.05	6F8G	.91	7K7	1.30	35Z4GT		.67	2A4G	1.22	EL-6CF	5.95	QK-62	65.00	WE-311A	5.75	715BY	45.00	931	1.25	1701	1.25	5959	1.72
2X2A	.85	6F8G	.80	7N7	.97	35Z5GT		.67	2A5	1.22	4B32	10.50	VT-62 Br	10.50	WE-		715CY	45.00	932	1.25	1702	1.25	5960	1.72
2A5	.85	6H6G	.50	7N7	.97	36		.69	2AP1	8.95	4C27/		RK-62	22.50	343A	185.00	721A	5.95	933	1.25	1703	1.25	5961	1.72
2A6GT	.80	6H6GT	.65	7Q7	.77	37		.69	2B4	2.20	4C35	27.50	FG-67	14.50	WE-		722A	2.25	958A	.65	1704	1.25	5962	1.72
2A7	.80	6J5	.60	7Q7GT	.77	38		.69	2B6	2.20	4C39	27.50	VT-67		346A	2.75	723A/B	2.25	959	2.25	1705	1.25	5963	1.72
2B6	.75	6J5GT	.60	7S7	.80	39/44		.69	2C22	.69	4J30	150.00	RK-69	2.25	WE-		723A/B	2.25	960	2.25	1706	1.25	5964	1.72
2B6	.67	6J5GT	.60	7V7	1.41			.69	2C23	.69	4J32	170.00	72	1.32	350A	6.95	724A	1.22	961	.65	1707	1.25	5965	1.72
2B7	.79	6J7G	.70	7W7	1.41	41		.79	2C24	.69	4J35	170.00	75	1.32	350B	6.95	724B	1.22	CK-1005		1708	1.25	5966	1.72
2D6GT	.82	6J7GT	.70	7Y4	.73	42		.79	2C26A	.69	4X150A	35.00	RK-70	1.32	WE-350B	6.45	724C	1.22	CK-1006		1709	1.25	5967	1.72
2E5	.77	6J7GT	.70	7Z4	.73	45		.79	2C31A	4.95	4X500A	110.50	75T	5.00	356A	6.95	724A	14.50	E-1148		1710	1.25	5968	1.72
2E6	.77	6K6GT	.70	7Y4	.73	42Y5GT		.79	2C34	.69	VX		VR-75	1.54	371A	6.95	724B	14.50			1711	1.25	5969	1.72
2E24	.90	6J5G	1.20	8A	.88	50		.97	2C36	22.50	1000A	129.50	VR-78	1.54	371B	.95	726C	65.00	1293	.65	1712	1.25	5970	1.72
2E26	.94	6K6GT	.80	12A6	.84	47		.79	2C39A	29.00	5AP1	5.95	FG-81A	3.95	388A	2.00	730A	25.00	1291	.65	1713	1.25	5971	1.72
2E30	.94	6K7GT	.70	12A7	.84	47		.79	2C40	22.50	5AP4	5.95	VR-90	1.54	394A	4.00	730B	25.00	1292	.65	1714	1.25	5972	1.72
2E32	.94	6K7GT	.70	12A8GT	.77	50A5		.80	2C42	22.50	EL-C5B	3.75	02A	14.50	394A	4.00	731A	1.75	1293	.65	1715	1.25	5973	1.72
2E35	.94	6K7GT	.70	12A8GT	.77	50B5		.80	2C43	17.75	5BP1	5.50	FG-95/		WE-399A	4.70	801A	1.75	1602	2.25	1716	1.25	5974	1.72
2E36	.94	6K7GT	1.45	12AH7GT	1.30	50C5		.80	2C43	17.75	5BP4	6.00	304TL	25.00	410R	185.00	802	1.25	1603	2.25	1717	1.25	5975	1.72
2E42	.94	6K8G	1.40	12AL5	.80	50L6GT		.80	2C44	21.50	5C22	47.75	VT-94/		410	110.00	803	4.50	1614	2.25	1718	1.25	5976	1.72
2E44	.94	6L6G	1.40	12AQ5	.80	50X6GT		.80	2C45	21.50	5C24	47.75	Be	19.50	GL-446/		804	4.50	1615	2.25	1719	1.25	5977	1.72
2E46	.94	6L6GA	1.40	12AT6	.80	53		.80	2C51	13.75	5CP1	6.95	C1100A	2.30	5548/	39.50	805	4.50	1616	2.25	1720	1.25	5978	1.72
2E50	.94	6L7G	.80	12AU6	.71	55		.80	2D21	1.55	5D21	19.50	C1099	2.30	417A	16.50	807	1.25	1617	2.25	1721	1.25	5979	1.72
2E51	.94	6L7G	.80	12AU7	.84	56		.80	2E22	1.85	5D22/		1092	2.30	434A	24.50	808	2.25	1618	2.25	1722	1.25	5980	1.72
2E52	.94	6L7GT	.80	12AV6	.80	56		.80	2E24	1.85	4-250A	35.00	100TH.	2.30	446A	1.95	809	2.25	1619	2.25	1723	1.25	5981	1.72
2E56	.94	6N7GT	.85	12AV7	.80	57		.80	2E26	1.75	5FP7	1.95	WE-301A	3.50	446B	1.95	810	10.50	1620	1.25	1724	1.25	5982	1.72
2E57	.94	6P1GT	.96	12AW6	1.30	58		.80	2J21	8.75	5HP1	1.50	WE-302A	2.25	446C	1.95	811A	3.25	1621	2.25	1725	1.25	5983	1.72
2E62	.94	6Q7	.70	12AX7	.84	59		.80	2J22	8.75	5JP1	26.50	WE-304A	4.00	450TH.	42.50	811A	3.25	1622	2.25	1726	1.25	5984	1.72
2E63	.94	6Q7	.70	12AZ7	.84	70L7GT		.80	2J26	24.75	5JP2	221.00	5563/	24.50	450TL	46.50	812A	3.50	1623	2.25	1727	1.25	5985	1.72
2E64	.94	6S4	.72	12BA7	.93	71A		.70	2J27	22.50	5JP5	14.50	FG-105	19.50	451A	1.75	813	5.95	1624	2.25	1728	1.25	5985	1.72
2AC5GT	1.10	6S7	1.04	12BD6	.99	75		.69	2J31	27.00	5JP11	26.50	VR-105	2.30	471A	2.65	814	3.95	1625	2.25	1729	1.25	5998	1.72

GENERATORS AND INVERTERS

Pioneer 716-3A GENERATOR (NAVY NEA-3A)—Out—AC 115V 10.4A 800 to 1400 cy. 1 ph.—DC 30V 60A. Brand New $38.50

Pioneer 1215-3A GENERATOR—Out—30VDC 15A. Brand New—original packing $16.50

Pioneer 12112-1A INVERTER—28VDC to 115VAC 400 cy. 3 ph. 250VA 0.8PF—Volt & Freq. Regulated $228.00

Pioneer 12117-1A INVERTER—24VDC to 115VAC 400 cy. 3 ph. 250 VA Volt & Freq. Regulated $228.50

PE-109D INVERTER—12.5VDC to 115VAC 400 cy. 175VA 1 ph. Brand New $79.50

PE-218 INVERTER—28VDC to 115VAC 400 cy. 1600VA New $45.50

Pioneer 866-1B INVERTER—28VDC to 130VAC 800 cy. 7A. Brand New $22.50

G.E. INVERTER—28VDC to 130VAC 800 cy. 750VA 1 ph. $39.50

ATR INVERTER—400 cy. to 110VAC 90 cy. 75 w. $22.50

Pioneer 12121-1A INVERTER—24VDC 18A. Input—AC output 115V 400 cy. 3 ph. 250 VA 0.7A. Volt & Freq. Regulated—New $228.00

Pioneer 12114 INVERTER—28VDC to 115VAC 400 cy. 1 ph. 80VA. $79.50

Pioneer 12115 INVERTER—28VDC to 26VAC 400 cy. ph. 61VA $33.50

Leland 28983 INVERTER—28VDC to 115VAC 400 cy. 3 ph. 115VA. $75.00

MIDGET D.C. MOTORS

G.E. 5BA16AJ52—Dense 5D63230—FM 27VDC 14.6RPM .7A 1/4 oz-in. Dim. 1¾D.x2¾L. ..... Ea. $12.50

G.E. 5BA16AJ51—27VDC 160RPM .66A. 12 oz-in. Reversible Dim. 1¾D.x4¾L. ..... Ea. $12.50

Delco 9003760—27VDC 160RPM Reversible Dim. 1¾D.x4¾L. ..... Ea. $22.50

G.E. 5BA16AJ57—27VDC 260RPM .8 A. 8 oz-in. Reversible Dim. 1¾D.x2¾L. ..... Ea. $19.50

Delco 9003820—FM 27VDC 260RPM Dim. 1¾D.x3¼L. ..... Ea. $22.50

Delco 9003739—FM 27VDC 260RPM Dim. 1¾D.x5¼L. ..... Ea. $22.50

G.E. 5BA16AJ49—27VDC 260RPM .75A. 6 oz-in. Reversible Dim. 1¾D.x2¾L. ..... Ea. $19.50

Delco 9003820—FM 27VDC 260RPM Dim. 1¾D.x3¼L. ..... Ea. $22.50

G.E. 5BA13BA372—27VDC 1/25 HP. 2.2 A. 6000RPM Shunt Wound Reversible Dim. 5¼"D.x9"L. ..... Ea. $8.75

OHIO Electric D-26436—27VDC 1/20 HP. 3A. 6000RPM shunt wound Reversible Dim. 1¾D.x4L. ..... Ea. $8.75

Stewart-Warner 671584 24VDC 1.7A. 6800RPM Full load—a. Series Wound Dim. 2½D.x5M. ..... Ea. $2.50

TACHOMETER GENERATOR

Klinge type PM-2M.
DC Tachometer Generator-New **$27.50**

OIL FILLED CONDENSERS

MFD	VDC	Price	MFD	VDC	Price
1	400	$ .61	1	2000	$1.40
1.5	400	1.65	1	3000	2.25
1	600	.70	3 x .2	3000	2.25
2	400	.63	2	3000	2.95
2-2	400	R'd 1.65	.2	3000	1.75
4	400	1.65	4	3000	3.75
4	600	1.65	4	3000	12.50
4	600	R'd 1.65	4	3000	23.50
4	600	1.75	.01-.03	5KV	1.25
6	400	1.65	1	5000	3.95
6	600	R'd 1.65	1	7500 R'd	14.50
8	400	1.65	.1	7500	1.25
8-8	450	2.50	.1-.1	7500	2.25
4-4-4	450	2.50	.1	7500	2.95
4 x 2	450	2.50	.1	7500	3.75
10	450	3.25	.1-.1	7500	5.50
50	450	7.95	.075-.075	8KV	6.50
1	1000	.90	1	12KV	28.50
1	1000 R'd	.95	1	12KV	47.50
.5-.5	1000	1.65	.25	20KV	24.50
1	1000	1.75	1	20KV	35.00
2	1000	2.50	1	25KV	65.00
4	1000	3.50	.002	30KV	24.50
1	1200	.95	.005	30KV	24.50
1-1-1	1200	1.65	.025	30KV	42.50
1	1500	.90	.1	30KV	65.00
2	1500	1.65	.25	30KV	95.00
4	1500	2.95	7.5	220VAC	1.95
1-.5	2000	1.65	.25	220VAC	1.95
.25	2000	1.50	1-1	330VAC	1.95
.5	2000	1.50	12.75	330VAC	4.10
1	2000	1.65	2	330VAC	2.95
2	2000	2.95	1	440VAC	1.10
1	2000	3.25	2.5	660VAC	1.95
1-1	2000	2.75	1	660VAC	2.95
2	2000	3.50	1	660VAC	4.50
.5	3000	2.40			

OILMITES

MFD	V.	TYPE	Price
.47	600	OM-6S07	$ .45
.01	600	OM-6S05	.45
.05	600	OM-6S10	.55
.1	600	OM-6S15	.55
.5	600	OM-6S17	.65
1.0	600	OM-6S21	.65

2 ϕ LOW INERTIA SERVO MOTORS

Diehl FPE-25-11—75V 60 cy. .11 Amp 4 Watts. Each $34.50

KOLLSMAN—26 Volt 60 cycle 4 watts 1800 RPM—new $22.50

PIONEER—28V11-2-A 28 volt 400 cycle with 40:1 reduction gear $14.50

Minn. Honeywell type—115V 60 cy. 11.5W—Brown instr. 76750-1 162 RPM; 76750-2 14 RPM; 76750-3 27 RPM. Any Type ..... $19.50 ea.

LECTRONIC RESEARCH LABORATORIES

715-19 ARCH ST. PHILA. 6, PA.

Telephones - MARKET 7-6771-2-3

COAXIAL CONNECTORS

83-1AC	$ .42	83-1RTY	$ .45	83-22J	$1.40
83-1AP	.36	83-1T	.48	83-22R	.98
83-1J	1.10	83-1TPH	.46	83-22SP	.98
83-1M	.32	83-1U	1.38	83-22T	1.25
83-1MP	.32	83-1UP	1.38	83-22U	.32
83-1T	.73	83-22AP	1.40	83-1BR	.32
83-1R	.40	83-22F	2.10	83-76S	.32
				83-77S	.32

UG-7

Reliance Specials

SOUND POWERED HANDSET

Brand New

TS-10 Type—includes 5 ft. cord. USES NO BATTERIES OR EXTERNAL POWER SOURCE
PAIR—$18.95

SOUND POWERED HEAD & CHEST SET

Navy Type M Head and Chest Set. Brand New For Work Requiring Free Use of Hands. Heavy Duty—Consists of Headset with 2 Phones and Chest Mike. Includes 20 Ft. Rubber Cord ..... EACH $14.88

TELEPHONE FIELD WIRE

W-110-B

1/2 MILE COIL.... $7.95
1 MILE REEL.... $14.95

HAYDON TIMING MOTOR

1 R.P.M. 115 V., 60 Cycle. $1.95

TIMING MOTOR

8 RPM 115 V. 60 cyc
E. Ingraham Co.

$1.79

Timer—Industrial Timer Corp. 15 min. on 15 min. off continuous 115 V. A.C. Fully cased Plugs into octal socket $8.50

TIME DELAY RELAY

Raytheon CPX 24156
1 Min. Delay. 115 V., 60 Cycle

2½ second recycling time spring return • Microswitch contact, 10A • Holds ON as long as power is supplied • Fully Cased •
ONLY $6.50

JONES BARRIER STRIPS

2-140Y	$0.17	2-141	$0.17	7-141½W	$0.56
3-140	.18	3-141	.20	8-141	.44
5-140½W	.21	3-141½W	.27	8-141½W	.64
4-140	.20	3-141W	.27	9-141Y	.71
6-140	.28	4-141	.24	3-142	.26
10-140W	.59	5-141	.29	2-150	.43
10-140½W	.59	5-141½W	.41	3-150	.60

Brand New Meters—Guaranteed

0-10 ma. D.C. 3½" $3.95
0-1 Ma D.C. 3½" Dejur (Scale Reads 0.4 KV) $5.75

SELENIUM RECTIFIERS

Full Wave 200 MA 115V $1.70
Half Wave 100 Ma 115V ..... .91

3 AG FUSES

Amp.	Per 100	Amp.	Per 100	Amp.	Per 100
½	$4.00	¾	$4.00	8	$3.00
¾	4.00	1	3.00	10	3.00
½	4.00	4	3.00	15	3.00
		5	3.00		

3 AG FUSE HOLDERS (Finger) 25¢

RESISTORS

Type EB	½W 10%	6¢ ea.	$4.00 per C
EB	½W 5%	12¢ ea.	8.00 per C
Type GB	1W 10%	9¢ ea.	7.00 per C
GB	1W 5%	18¢ ea.	14.00 per C
Type HB	2W 10%	12¢ ea.	9.00 per C
HB	2W 5%	24¢ ea.	18.00 per C

AVAILABLE IN ALL STANDARD RMA VALUES

POSTAGE STAMP MICAS

AVAILABLE IN ALL STANDARD RMA VALUES
PRICE SCHEDULE

5 mmf to 910 mmf	5¢
.001 to .0013 mfd	5¢
.0015 to .0056 mfd	15¢
.0062 to .0091 mfd	20¢
.01 mfd	25¢

SILVER MICA—POSTAGE STAMP

AVAILABLE IN ALL STANDARD RMA VALUES
PRICE SCHEDULE

10 mmf to 910 mmf	15¢
.001 mfd to .002 mfd	20¢
.0022 mfd to .0091 mfd	55¢
.01 mfd	95¢

ASSORTMENTS

GEARS—100 SMALL GEARS, BUSHINGS & SHAFTS. $6.50
RESISTORS—200 ½ WATT ALL INSULATED AMERICAN MADE $2.50
HARDWARE—5 lbs. BOLTS—NUTS—LUGS—WASHERS ETC $2.00

PULSE TRANSFORMERS

UTAH—9262 9278 9289 9318 9340 9350
WESTERN ELECTRIC—D166173 D161310
K58696, K59169, K59462, K51216;
GENERAL ELECTRIC—90-G-S
JEFFERSON ELECTRIC—C-12A-1118
DINION COIL—TR1048 TR1049
also 552-7250-2A: 552-7251-2A: T-1229621-60



UNIVERSAL JOINTS ALUMINUM

¼" hole, ½" O.D. 1-¼" long with two 6/32 tapped set-screw holes EACH 85¢
⅝" O.D. 1-½" long with 3/16" hole, two 6/32 tapped set-screw holes EACH ..... 90¢

OIL FILLED CONDENSERS

MFD	V.D.C.	Price	MFD	V.D.C.	Price
5.2	50	$0.89	0.5	3,000	$2.40
6	400	.85	2	3,000	4.98
3 x 3	400	1.00	2	4,000	7.95
4	500	.85	0.01	5,000	.95
1	600	.65	1	5,000	4.88
0.5-0.5	600	.40	0.03-0.03	6,000	1.50
2	600	.75	1	6,000	9.95
4	600	1.75	0.02-0.02	7,000	1.55
8	600	1.85	0.1	7,000	1.79
10	600	3.25	0.1-0.1	7,000	5.95
4 x 3	600	2.50	0.1	7,500	2.25
8-8	600	1.95	0.075-0.075	8,000	6.50
1	800	.60	0.15-0.15	8,000	6.95
1	1,000	.69	0.25	20,000	19.95
2	1,000	.95			
3	1,000	1.70			
1	1,500	1.45			
0.02	2,000	.65			
0.1-0.1	2,000	1.30			
0.1-0.5	2,000	.95			
0.5	2,000	1.85			
3	2,000	3.75			
8	2,000	7.95			
0.25	3,000	2.25			

1 mfd
6,000
V.D.C.
G.E.

$9.95

OIL FILLED AC CONDENSERS

MFD	V.A.C.	Price	MFD	V.A.C.	Price
7.5	220	$2.00	15	440	$4.25
20	220	4.95	1	660	2.95
1	236	.49	2.9	660	4.35
4	236	1.40	3	660	4.45
8	236	1.95	4	660	4.95
3	330	1.45	5	660	5.45
4	330	2.25	6	660	5.95
20	330	6.75	8	660	7.50
25	330	7.50	0.2	750	.69
4.4	375	2.15			

COAXIAL CABLE CONNECTORS

A full line of jan approved connectors in stock

83-1AC	$0.42	PL-274	$1.10	UG-88/U*	$ .30
83-1AP	.30	PL-275	2.10	UG-99/U*	1.10
83-1BC	.35	SO-239	.40	UG-102/U	.30
83-1F	1.10	UG-13/U	1.70	UG-103/U	.48
83-1H	.12	UG-18B/U	1.05	UG-104/U	1.40
83-1HP	.22	UG-20B/U	1.60	UG-105/U	1.50
83-1J	.73	UG-21/U	.85	UG-106/U	.15
83-1R	.48	UG-21B/U	1.60	UG-107B/U	2.75
83-1RTY	.45	UG-21C/U	1.85	UG-146/U	2.00
83-1SP	.45	UG-21D/U	1.45	UG-167/U	3.75
83-1SPN	.50	UG-22/U	1.30	UG-175/U	.12
83-1T	1.30	UG-22A/U	1.60	UG-176/U	.12
83-2AP	1.95	UG-22B/U	1.20	UG-185/U	.35
83-2J	2.10	UG-23/U	1.20	UG-196/U	1.65
83-2R	1.65	UG-23B/U	1.50	UG-203/U	.65
83-2SAP	1.40	UG-23C/U	1.10	UG-224/U	1.15
83-22F	2.10	UG-24/U	1.30	UG-255/U	1.95
83-22J	1.40	UG-27/U	1.25	UG-260/U	.85
83-22R	.68	UG-27A/U	2.25	UG-261/U	1.10
83-22SP	.50	UG-27B/U	2.95	UG-262/U	1.10
83-2ZT	1.95	UG-28A/U	2.95	UG-273/U	1.45
83-168	.12	UG-29B/U	1.75	UG-274/U	2.30
83-185	.12	UG-30/U	2.30	UG-290/U	.90
CW-123A/U	.45	UG-57B/U	1.85	UG-291/U	.35
M-358	1.30	UG-58/U	.70	UG-306/U	2.65
M-359	.30	UG-58A/U	.90	UG-414/U	1.95
M-359A	.45	UG-59A/U	1.90	UG-499/U	1.25
PL-258	.75	UG-88/U	1.75	UG-625/U	1.35
PL-259	.45	UG-85/U	1.65		
PL-259A	.50	UG-87/U	1.40		

NEW COAXIAL CABLES Jan approved

	Price per 1000 ft.		Price per 1000 ft.
RG5/U*	$140.00	RG22/U*	$150.00
RG6/U	180.00	RG22A/U	285.00
RG7/U*	85.00	RG24/U	675.00
RG8/U*	180.00	RG26/U	475.00
RG9/U*	250.00	RG29/U*	50.00
RG9A/U	275.00	RG34/U*	300.00
RG10/U	240.00	RG35/U	900.00
RG11/U*	190.00	RG41/U*	295.00
RG11A/U*	150.00	RG54A/U	97.00
RG12/U	240.00	RG55/U*	110.00
RG13/U*	215.00	RG57/U*	125.00
RG17/U	650.00	RG58/U*	60.00
RG18/U	900.00	RG58A/U*	70.00
RG19/U	1250.00	RG59/U*	60.00
RG20/U	1450.00	RG62/U*	75.00
RG21/U*	220.00	RG71/U*	160.00

Add 25% for orders less than 500 feet.
* No minimum order—other 250 minimum.

NEW RG-8/U Unmarked 100 Ft. Coil.. Special $5.95

SELSYN MOTORS

Army Ordnance Type C-78248 115V, 60 Cy. Transmitter. Approx. 3-⅝" dia. x 5-⅝" L. Like new.. EACH $27.50

SELSYN MOTORS

50 V. 50 Cy. High Torque. Connect in Series For Use On 110 V. 60 Cy. Approx. 3-⅝" dia. x 5-⅝" L. Like New ..... ONLY $12.95 PAIR

DIFFERENTIAL Used $4.95

115 V., 60 Cycle #C78249 New $9.95

3⅝" dia. x 5⅝" long
Used between two C78248's as a dampener. Can be converted to 3600 RPM Motor in 10 minutes. Conversion sheet supplied. (Converted) $8.50
Mounting Brackets—Bakelite for selsyns, and differentials shown above ..... 35¢ pair

PRECISION RESISTORS

(WIRE WOUND SPOOL TYPE)

½ watt one percent tolerance WW3 or Equal 35¢ ea.

.250	7.4	19.37	105.8	400	5000	20K
.334	9.1	20	123.8	414.3	5900	25K
.502	10.48	25	125	705	6500	30K
.557	10.84	30	130	723	7000	32.99K
.627	11.1	46	147.5	750	7500	33.3K
.760	11.25	50	190	855	8000	35.99K
1	11.74	52	210	2193	8500	36K
1.01	12.32	55.1	220.4	2200	8800	37K
1.53	13	62.54	235	2250	10K	40K
2	13.02	75	260	3500	12K-2%	47K
2.04	13.15	79.81	270	3850	14.82K	50K
2.5	13.52	87	298.3	3427	15K	59K
3.5	13.89	97.8	301.8	4000	15.75K	59.15K
5.26	14.98	100	366.6	4300	16.7K	79.01K
				4451	17K	125K

1 watt one percent tolerance WW4 or Equal 45¢ ea.

.851	3.39	20	270	2000	7000	50K
1.01	5.1	28	425	2300	8000	55K
2.55	5.21	38	1250	3300	9000	80K
2.58	12	50	1750	6000	20K	

1 watt one percent tolerance WW4 or Equal 60¢ ea.

100K	128K†	150K	240K	320K	600K
130K†	130K		250K		

1 watt WW5 or Equal 65¢ ea.

64K-2% 522K-1% 645K-1% 700K-1% 1 meg-5%

1 MEGOHM 1 WATT 1% $1.50

TYPE "J" POTENTIOMETERS

Ohms	Shaft	Ohms	Shaft	Ohms	Shaft
100	SS*	2.5K	SS	100K	7/16
150	SS	3.0K	3/8	200K	SS
150	SS*	4.0K	3/8	250K	5/8
500	1/4	15K	3/8	250K	SS
1.0K	9/16	25K	SS	1.0 Meg	1/4
1.5K	5/16	75K	SS		
2.0K	1/4	100K	3/8		

SS: Screw-driver slot.
*: Split locking bushing.

$1.25 EACH

TYPE "JJ" POTENTIOMETERS

Ohms	Shaft	Ohms	Shaft	Ohms	Shaft
10K-10K	5/16	30K-10K	¼†	90K-3K	¼
15K-15K	SS	†With switch.			

PRICE—$2.50 EACH

High Current Filament Transformer

Amertran type W Pri. 105-125 V. 60 cy. 1 Phase—Sec. 5V. 190 amps.—.97 KVA 35 KV. RMS Insul. Test 7x10x 13; Wt. 80 lbs. Ideal For Use As Arc Welder.
SPECIAL $29.99 ea.
Kenyon S-14040 R.C. #2Z9943-1073 Pri. 105-125 V. 60 Cy. Sec. 5V. 115 Amps. ..... $19.50 ea.
Kenyon S-13277, R.C. #2Z9943-7 Pri. 115 V. 60 Cy. Sec. 5V. 60 Amps. ..... $15.25 ea.

RAYTHEON PLATE TRANSFORMER

TYPE U8355A

PRI. 110V/220V/440V/60 cy.
SEC #1 300V @ 4 AMPS. SEC. #2 300V @ 4 AMPS.
1780 RMS TEST, 9¾"x8½"x8¾" HIGH. $19.95

Choke

10 hy
400 MA
90 OHMS
HERMETICALLY SEALED



$4.88

2J1G1 SELSYNS $8.50

400 CYCLE BRAND NEW

400 CYCLE INVERTERS

Leland Electric Co.

#10800 in; 20-28 V.D.C., 22 A. 8000 R.P.M. Out: 115V. 400 Cyc. 1 phase, 1500 V.A. .90 PF $225.00

Minimum Orders $3 ... ... Get on our Mailing List

AN CONNECTORS

See Our Ad February, 1953 Electronics
PHONE! WIRE! WRITE! YOUR NEEDS

TERMS — Cash with Order or 25% Deposit — Balance C.O.D. Net 10 Days to Rated Accounts. All Prices are Net F.O.B. Our Warehouse.

RELIANCE MERCHANDIZING CO.

Arch St., Cor. Croskey Phila. 3, Pa. Telephone Rittenhouse 6-4927

Want more information? Use post card on last page.

RELAYS RELAYS RELAYS

SIGMA RELAYS

4F8000S: 1 ma; SPDT; 8000 ohm; #R287...5.95
41FS7: 2 ma; SPDT; 10,000 ohm; #R914....2.95
41F8000S: 2.5 ma; SPDT 8,000 ohm; #R1002..2.95
41FZS7: 115VAC; SPDT; Will Operate Continuously on 220VAC; #R909..2.95
41FR: 6VDC; SPDT; 62 ohm; Will Operate on 1½ VDC; #R924.....1.75
41FR: 12VDC; SPDT; 340 ohm; Will Operate on 6 VDC; #R925.....1.95
4AH: 4 ma pull-in, 2.5 ma hold; SPDT; 2000 ohm; Air Tight Seal, RTMA 5-prong Plug Base; #R444 .....4.25
4RJ-47G: 3VDC; SPDT; 47 ohm; Hermetically Sealed; Solder Head Terminals; #R448 .....5.95
5F150G: 20 ma; SPDT; 150 ohm; #R1003 .....2.95
5RLP150G: Same as #R1003 (Sigma 5F150G) except with dust cover; #R1004 4.50
5RJ100S: 1.5VDC; SPDT; 100 ohm; Hermetically Sealed; Solder Head Terminals; #R1001 .....6.95
5RJ2000G: 2.3 ma; SPDT; 2000 ohm, Hermetically Sealed; #R1005.....7.50
5RJ5000G: 1.4 ma pull in, 0.4 ma hold; SPDT; 5000 ohm; #R281.....6.95

COAXIAL RELAY

ARC 3 55476 (K101); 12-34V, DC; SPDT; 275 ohm; #R751 .....8.95

IMPULSE DIAL

To open a normally closed circuit. Ten holes — capacity: 1-10 impulses. Has 3 shunt springs, arranged to make when dial is moved off normal. #D101 ... ...4.95

TRANSFORMERS

#TX240

2:1 AUTOTRANSFORMER 220-110V, 50-60 cyc., Open Frame
40W #T106 .....$2.49
250W #T107 .....$4.75

LINE TO VOICE COIL, RAYTHEON 30418, Ratio 600 ohms to 6 ohms (100:1) POWER LEVEL +17db, Hi Fidelity #TX-240 .....$2.95

#T39

PREAMP OUTPUT (TRIODE PLATE) TO LINE OR PHONES G.E. 400 to 4000 cyc. #TX214 $1.49

P.P. INTERSTAGE P. P. PLATES to P. P. Grids, Stancor #87A15 or Kenyon T54, Ratio 1.2 to 1, Hi Fidelity, T112 $2.50

4:1 INTERSTAGE FERANTI Single Plate to Grid, Hi Fidelity T39 $1.89

CLASS B DRIVER, Driver Plate to P. P. Class B Grids, Ratio Pri. to ½ sec, 1 to 0.9 #238 $1.95

#T38

3000V, 10Ma, 115V, 50-60 cyc., W. E. #D161913 #T109 .....$4.95

3000V 50Ma Constant Current Xfmr, 115V 50-60 cyc., Westinghouse ST96, for "Sterilamp" or Neon #T110 .....$7.95

JOBBERS—EXPERIMENTERS LABORATORIES

WRITE OR PHONE YOUR RELAY REQUIREMENTS

We have a large variety of standard types of relays and solenoids for a multiplicity of uses which for various reasons are not listed in our advertising. When inquiring concerning your needs give as much information as possible. Catalog numbers are **not** sufficient. Give coil voltage; specify AC or DC; give current or resistance; contact current and arrangement.

CHOKES

#T111

SWINGING CHOKE Thoardson T74C29, 5 to 20 hys, 125 ma., 200 ohms, S.C. #4G1668c/R1 2000V Test, #T111 .....$3.49

#T78

DELUX FILTER Amertran #L218, 60 ma 45 hy, 600 ohms, Heavy Cast Case, S.C. #2C2770/R2 #T78A $2.95
25 Hy, 20 Ma, 975 ohms, G.E. K54J115 Hermetically Sealed, 2500V insul #T78 .....$3.95

4 Hy, 60 Ma, 200 ohms, Rola KS8729 Hermetically Sealed, Hi Q, Very Compact #T92 .....$1.19
3 Hy, 10 Ma, 325 ohms, ARL 5634 Compact Shielded #T74 .....$3.69

#T74

1 Hy, 25Ma, 100 ohms, Westinghouse 3 3 2 8 2 6, Shielded #T71 .....$3.49

600 Hy, 1 Ma, 6000 ohms, Raytheon CRP 30330 Hermetically Sealed. Hi Q. #T76 .....$1.95

#T76

200 Hy, 10 Ma, 5260 ohms, Westinghouse CAY301161 Shielded #T73 .....$2.49
325 Hy 3 Ma, 5500 ohms, G. E. 400V Insul. #T35A $1.25

SERVO OUTPUT

PP6L6 to Servo mechanism with 10% feed-back winding. Mu metal core .....$3.50 ea.

DUAL unit PP6V6 to Servo mechanism with 10% feedback winding and 6SN7 to Servo mechanism. Both in 1 can. Mu Metal Core.....$3.95 ea.

120 CYCLE FILTER

Input Impedance: 1000 ohm, Output Impedance: 1000 ohm, Kenyon 213104-1. Shielded. #T289.....$3.95

FILAMENT TRANSFORMERS

110V 50-60 cyc. Primary

Stock #	Volts	Amps	Insul.	Price
T154	6.3 CT	1	2500	$1.35
T155	5	2	2500	1.65
T156	6.3 CT	2	2500	1.80
T157	6.3 CT	6	2500	3.00
T158	2X6.3 CT	3+3	2500	3.29
T159	6.3V	16	1500	3.49
KENYON Shielded; 6.3V; 2.5A; 2500V Insul; #T153.....				2.25
T250	7.5V	7	1500	3.49
T251	6.3V	4	1500	2.49

AUDIO XFMRS

Multiple Line & Voice Coil to Multiple Line & Voice Coil. Good Fidelity. Kenyon S20130. Shielded. #T287.....$2.25

Input Line to Single or P.P. Grids. 500-ohm C.T. Primary. Overall Ratio 1:13.7, Kenyon 213089-1. Shielded. #T288....$2.25

Multiple Line or Mike to Single Grid. 300-ohm C.T. Primary. Overall Ratio 600:1. Kenyon 213307-2. Shielded. #T289.$2.25

P.P. INTERSTAGE. Single or P.P. Plates to P.P. Grids. Ratio 1:1.2 Hi-Fidelity. Stancor 87A15. Shielded. #112.....$2.50

VOLTAGE REGULATOR



Amertran Transtat

103 to 126 V, 50-60 cyc, 2.17 Amps, #T283.$9.95
W. E. D122855, 92 to 115 V, 400 cyc, 5.5 Amps, #T281 .....$6.75
10 for $60.00

2.5 AMP H.D. FILTER REACTOR

Amertran Type PBN 0.5 Hy, at 2.5 A, 2.3 Ohm, 2.5 KV insul, 5½ x 7 x 8" overall, Heavy Shield, #T284.....$12.95

TRANSFORMERS

110/220 V 50-60 cycles

STEP-UP-DOWN

40W, #T106, 2.49; 150W, #T113, 5.95; 250W, #T114, 7.49; 350W, #T115, 8.95; 500W, #T116, 11.95; 750W, #T117, 17.95; 1000W, #T118, 25.00; 1500W, #T119, 37.50.

CARBON MONOXIDE DETECTOR SIGNAL ASSEMBLY

MINE SAFETY APPLIANCES CO. Type K-1 and K1-N—Manufacturer's Part No. SK 1557 and SK 1557-1—Spec. No. 27493

NEW! REG. PRICE $300

89.00 each

3 for $250.00
10 for $825.00

TERMS:—All prices F.O.B. Our Plant. Rated Firms Net 10 Days: All Others Remittance with Order.

Delivery From Stock While They Last!

Orders Under $10 Remittance With Order. Plus Approximate shipping charges (coverage will be returned.)

324 CANAL ST., N.Y.C., 13, N.Y. WAlker 5-9642

Universal general corp.

SWEEP GENERATOR CAPACITOR
Magnavox Part #XC-260048-G1

Rotating split stator capacitor. Cylindrical silver plated rotor concentric to silver plated stator on inside of Bakelite housing. Housing diameter 1⅝". Square end bells 1⅝" sq. Shaft extension ¼" x 0.1875 dia. High speed ball bearings. Capacity 5 to 10 mmf. Ideal for motor driven high frequency sweep generator.
BRAND NEW $2.50

G. E. GENERATORS

General Electric Type 5-ASB-31JJ3; 400 cycles out at 115 volts; 7.2 amps; 8,000 rpm.; size 6" long x 6" dia. ..... $99.50 ea.

SINE-COSINE GENERATORS
(Resolvers)

Diehl Type FJE43-9 (Single Phase Rotor). Two stator windings 90° apart, provides two outputs equal to the sine and cosine of the angular rotor displacement. Input voltage 115 volts, 400 cycle.. $30.00 ea.
Diehl Type FPE-43-1 same as FJE-43-9 except it supplies maximum stator voltage of 220 volts with 115 volts applied to rotor ..... $25.00 ea.
Arma Resolver Type 2138144: equal in size to size 5 synchro; 55-60 cycle; single phase primary, 3 phase secondary $79.50

VOLTAGE GENERATORS (RATE)

ALNICO MIDGET D.C. VOLTAGE GENERATOR Type B-35-D $17.50
ALNICO MIDGET D.C. VOLTAGE GENERATOR Type B-44-D $17.50
A.C. GENERATOR: 67 V., 30 Cyc., 2-Phase, .015 Amps. Type PM-1, 1200 R.P.M. $18.00

SYNCHRONOUS SELSYNS

110 volt, 60 cycle, brass cased, approx. 4" dia. x 6" long. Mfg. by Diehl and Bendix.
Quantities Available.
REPEATERS ..... $20.00 ea
TRANSMITTERS ..... $20.00 ea.

AUTOSYN MOTOR TYPE 1

115 VAC; 60 cycle; 1-phase; DR. & CB 4270 Foot Mounted; Mfg. Bendix Aviation Corp. ..... $22.50 ea.

SELSYN GENERATOR

General Electric MOD. 2J15M1; 115-57.5 Volts 400 Cycle ..... $22.50 ea.

SYNCHROS

AUTOSYN MTR. KOLLSMAN Type #403; 32 VAC; 60 cycle; single phase $22.50
AUTOSYN MTR. BENDIX Type #851; 32 VAC; 60 cycle; single phase $22.50
SYNCHRO TRANSMITTER, KEARFOTT Type R-312-1A-A Rotor: 26 Volts; single phase; Stator: 11.8 Volts; 3-phase; 400 cycle $25.00
MICROSYN UNIT, Type 1C-006-A $35.00
1F Special Repeater (115V-400 Cy.) ..... $15.00 ea.
2JIF 3 Generator (115-400 cyc.) ..... $10.00 ea.
5CT Control Transformer: 90-50 Volt; 60 Cy.. $45.00
5F Motor (115/90 Volt—60 cyc.) $45.00
5/DG Differential Generator (90-54 volts—400 cyc.) ..... $30.00 ea.
TRANSMITTER, BENDIX C-78248: 115 Volt, 60 Cycle ..... $25.00 ea.
Differential—C-78340: 115 V., 60 Cy. $5.00
5N MOTOR (115 Volts/60 Cycle) $22.50
REPEATER, BENDIX C-78410; 115 Volt, 60 Cycle ..... $37.50 ea.
REPEATER. AC synchronous 115 V., 60 cycle. C-78863 ..... $15.00 ea.
REPEATER. DIEHL MFG. No. FJE 22-2: 115 Volt; 400 Cy.; Secondary 90 V. $27.50
5G GENERATOR (115/90) 60 cycles $45.00
7G Synchro Generator (115/90 volt; 60 cycle) $75.00
6G Synchro Generator (115/90 volt; 60 cycle) . $60.00
6DG Synchro Differential Generator (90/90 volt; 60 cycle) $50.00
2-1F5-1 Selsyn Control Transformer: 105-55 Volts; 60 Cycle $50.00
5JD5HA1 Selsyn Generator: 115-105 Volts; 60 cycle $50.00
2JIFI GENERATOR: 115—57.5 Volt; 400 cycle. ..... $12.50 ea.
2JIHI DIFFERENTIAL GENERATOR: 57.5—57.5 Volt; 400 cycle ..... $12.50 ea.
2JIGI CONTROL TRANSFORMER: 57.5—57.5 Volt; 400 cycle ..... $7.50 ea.

PIONEER TORQUE UNITS

TYPE 12606-1-A: Contain CK5 Motor coupled to output shaft through 125.1 gear reduction train. Output shaft coupled to autosyn. follow-up (AY43). Ratio of output shaft to follow-up Autosyn is 15.1. ..... $70.00 ea.
TYPE 12604-3-A: Same as 12606-1-A except it has a 30:1 ratio between output shaft and follow-up Autosyn ..... $70.00 ea.
TYPE 12602-1-A: Same as 12606-1-A except it has base mounting type cover for motor and gear train ..... $70.00 ea.

Immediate Delivery

ALL EQUIPMENT FULLY GUARANTEED

All prices net FOB Pasadena, Calif.

INVERTERS

10563 LELAND ELECTRIC
Output: 115 VAC; 400 cycle; 3-phase; 115 VA; 75 PF. **Input:** 28.5 VDC; 12 amp. $89.50

PIONEER 12126-2-B
OUTPUT: 26 Volts; 3 Phase; 400 cycle; 10 Volt Amperes; .6P.F. **INPUT:** 27.5 Volt DC; 1.25 Amp. $30.95

PIONEER 12117
OUTPUT: 26 volts; 400 cycles; 6 volt amperes, 1-Phase. **INPUT:** 24 VDC; 1 amp. ..... $25.00 ea.

ALTERNATOR, CARTER
Mfg. Carter Motor Co.; OUTPUT: 7 VAC; 9.7 amp.; 650 cycles, and 295 VDC, 200 amps. INPUT: 24.5 VDC; 10.5 amps; 6500 rpm. ..... $49.50 ea.

PE 218 LELAND ELECTRIC
Output: 115 VAC; Single Phase; PF 80; 380/500 cycle 1500 VA. **INPUT:** 25-28 VDC; 92 amps; 8000 RPM; Exc. Volts 27.5.
BRAND NEW ..... $99.95 ea.

PE 109 LELAND ELECTRIC
Output: 115 VAC, 400 cyc; single phase; 1.53 amp.; 8000 RPM; **Input:** 13.5 VDC; 29 amp. $69.00

MG-0-75 ONAN
Navy Type PU/11 . . . **Output:** 115 VAC; 480 cyc.; single phase; 5.3 amp and 26 VDC @ 3.8 amp. **Input:** 115/230 VAC; 60 cyc.; single phase. . . $225.00

MG 153 HOLTZER-CABOT
Input: 24 V. DC, 52 amps; **Output:** 115 volts—400 cycles, 3-phase, 750 VA. and 26 Volt—400 cycle, 250 VA. Voltage and frequency regulated $95.00 ea.

PIONEER 12130-3-B
Output: 125.5 VAC; 1.15 amps. 400 cycle single phase, 141 VA. **Input:** 20-30 VDC, 18-12 amps. Voltage and frequency regulated $75.00

12116-2-A PIONEER
Output: 115 VAC; 400 cyc.; single phase; 45 amp. **Input:** 24 VDC 5 amp. $65.00

10285 LELAND ELECTRIC
Output: 115 Volts AC, 750 V.A., 3 phase, 400 cycle, .80 PF, and 26 volts, 50 amps, single phase, 400 cycle, .40 PF. **Input:** 27.5 VDC, 60 amps. cont. duty, 6000 RPM. Voltage and Frequency regulated. $95.00

10486 LELAND ELECTRIC
Output: 115 VAC; 400 Cycle; 3-phase; 175 VA; .80 PF. **Input:** 27.5 DC; 12.5 amp; Cont. Duty. $90.00 ea.

PIONEER 10042-1-A
DC INPUT 14 Volts; **OUTPUT:** 110 Volts; 400 Cycle 1-Phase; 50 Watt. $75.00

94-32270-A LELAND ELECTRIC
Output: 115 Volts; 190 VA; Single Phase; 400 Cycle; .90 PF, and 26 Volts; 60 VA; 400 Cycle; .40 PF. **Input:** 27.5 Volts DC; 18 amps; cont. duty, voltage and freq. regulated $95.00

PIONEER 12147-1-B
OUTPUT: 115 VAC; 400 cycle; Single phase. **INPUT:** 24-30 VDC; 8 amps. $79.50

MG 149F HOLTZER-CABOT
OUTPUT: 26 VAC @ 250 VA; 115V @ 500VA; Single Phase; 400 cycle. INPUT: 24 VDC @ 36 amps. $75.00

EICOR CLASS "A" NO. 1-3012/08-7
OUTPUT: 125 VAC; 400 cycle; single phase; 100 VA. **INPUT:** 24-30 VDC; 11 amps; Duty Int. Voltage and Frequency Regulator $99.50

PIONEER AUTOSYNS

AY-1 ..... 26 Volt—400 Cycle $6.95
AY-5 ..... 26 Volt—400 Cycle $7.95
AY27D $12.50
AY6—26 Volt—400 cyc. ..... $4.95 ea.
AY30D—26 Volt—400 cyc. ..... $25.00 ea.
AY14D $10.00
AY24 ..... $20.00
AY20—26 Volt—400 cyc. ..... $12.50 ea.

MIDGET TYPE
NT-6 WILLARD 6V. STORAGE BATTERIES
Dry Charged

3 Amp-Hour rating. Transparent plastic case. SIZE: 2⅝" x 1-13/16" x 2¾". Weight approx. 1¼ lbs. Uses standard electrolyte. Regularly lists at $12.00 each. **NOW** ..... New, unused ..... $2.49 ea.; Four for $8.50; Quantities: 20 or more $1.85 each.

ALNICO FIELD MOTORS

(Approx. size overall . . . 3¾" x 1¾" diameter)
DELCO TYPE #5069080: 27.5 volts DC; 250 RPM $19.95
PM Motors Delco Type #5069371: 27.5 volts; DC Alnico Field; 10,000 r.p.m.; dimensions 1" x 1" x 2" long; shaft extension ⅛" diameter 0.125" . . . $15.00

PIONEER GYRO FLUX GATE AMPLIFIER
Type 12076-1-A, complete with tubes ..... $27.50 ea.

AC CONTROL MOTOR
A. C. SYNCHRONOUS MOTOR Type RBC 2565; Volts 115; Cycles 60; RPM 2; Mfg. HOLTZER CABOT ELECT. Approx. size: 2⅝" x 2⅝" x 2⅝" . . $15.00 ea.

400 CYCLE MOTORS

PIONEER: TYPE CK5 2 Phase; 400 cycles $25.00 ea.
EASTERN AIR DEVICES TYPE J49A: 115 V; 0.1A; 7000 r.p.m. Single phase 400 cycle ..... $17.50 ea.
AIRESEARCH: 115V; 400 CPS; Single phase 6500 RPM; 1.4 amp; Torque 4.6 in. oz.; HP .03. ..... $10.00 ea.
EASTERN AIR DEVICES TYPE JMGB: 200 VAC; 1 amp; 3 phase; 400 cycles, 6000 RPM. . . . $12.50 ea.
EASTERN AIR DEVICES, TYPE J31B: 115 V, 400-1200 Cycle. Single Phase ..... $12.50 ea.
AIRESEARCH: AC induction, 200 V; 3 Phase, 400 Cycle, 2 H.P.; 11,000 RPM; 8 amps. . . . . $75.50 ea.
AIRESEARCH: AC induction. 200 V; 3 Phase, 400 Cycle, 12 H.P. 6500 RPM; 1.5 amps. $25.00
Electric Motor: PNT—1400—A1—1A Serial No. 207, 208 V., 400 Cycles, 3 Phase Kearfott Co., Inc. ..... $17.50 ea.

SERVO MOTOR 10047-2-A; 2 Phase; 400 Cycle, with 40-1 Reduction Gear

SYNCHRONOUS CAPACITY INDUCTION MOTOR
Mfg. Eastern Air Devices; 1/40th HP; Single Phase; Current .7 amperes; 115 VAC; 60 Cycle 3800 RPM; Shaft length 2¼"; impeller cooled; Includes starting condenser. **BRAND NEW** $9.95

SMALL DC MOTORS

DELCO #5072000: 27.5 VDC; 11.75 rpm. $15.00
DELCO #5068750: constant speed; 27 VDC; 160 RPM; built-in reduction gears and governor. ..... $17.50 ea.
J. OSTER: series reversible motor; 1/50th H.P.; 10,000 RPM; 27½ VDC; 2 amps; **SPERRY #806069:** approx. size 1⅝" x 2¾" ..... $7.50 ea. (Approx. size . . . 4" long x 1¾" dia.)
General Electric Type 5AB10AJ37: 27 volts, DC; 5 amps. 8 oz. inches torque; 250 RPM, shunt wound; 4 leads; reversible ..... $15.00 ea.
General Electric. Mod. 5RA10PJ33: 12 oz. inches torque, 12 DC, 50 RPM, 1.02 amp. ..... $15.00 ea.
General Electric Type 5BA10AJ52C: 27 volts DC; 5 amps. 8 oz. inches torqque; 145 RPM; shunt wound; 4 leads; reversible ..... $15.00 ea.
GENERAL ELECTRIC DC MOTOR Mod. 5RA10AJ64. 100 r.p.m.; 65 amp; 12 oz.-in. torque; 27V DC. ..... $19.95 ea.
2½ H.P. MOTOR—Mfg. LEECE-NEVILLE Co; Type 1454-MO; 24VDC; 4000 RPM; 100 amp. $35.00

115 VOLT GENERATORS



Brand new Eclipse generators: 115 VAC; 9.4 amp; 1000 watts; single phase; 800 cycles. 2400-4200 rpm. DC output is 30 volts at 25 amp. Unit has spline drive shaft and is self-excited $29.95

MICROPOSITIONER
Barber Colman AYLZ 2133-1 Polarized D.C. Relay: Double Coil Differential sensitive, Alnico P. M. Polarized field. 24V contacts: .5 amps; 28 V. Used for remote positioning, synchronizing, control, etc. ..... $12.50 ea.

BLOWER
Eastern Air Devices, Type J31B; 115 volt; 400-1200 Cycle; single phase; variable frequency; continuous duty; L. & R #2 blower; approx. 22 cu. ft./min. $15.00

BLOWER ASSEMBLY
115 Volt, 400 Cycle, Westinghouse Type FL, 17CFM, complete with capacitor. New ..... $12.50 ea.

SENSITIVE ALTIMETERS
Pioneer Sensitive altimeters, 0-35,000 ft. range . . . calibrated in 100's of feet. Barometric setting adjustment. No hook-up required. ..... $12.50 ea.

BENDIX AIRCRAFT TYPE GENERATOR
Bendix-Eclipse Aviation; Type 1235 . . . Counter-clokwise rotation. Speed 2500-4500 RPM; 28.5 VDC @ 15 A. A. Two-Brush ball bearing generator suitable for any application where 28 volt output is required. Field and armature taps for adjustment of voltage from 13 to 28 volts. ..... NEW $15.00

C and H Sales Company

BOX 356-X EAST PASADENA STATION • PASADENA 8, CALIFORNIA

Want more information? Use post card on last page.

COMMUNICATIONS EQUIPMENT CO.

MICROWAVE COMPONENTS

MICROWAVE MIXER

CV-12/APR-6: Waveguide/mixer unit, 4000-6000 mc. Designed for use with microwave receiver. Has pick up loop for coupling to lighthouse cavity local oscillator. RF input is to 1" x 2" waveguide (contact flange). Output (thru 1n21 xtl.) is from standard 50-ohm coax connector. Brand new, complete with crystal. As shown $35.00

APS-2 SPARE PLUMBING

Z-601C: Elevation Joint.....$9.50
Z-601B: Transmission Line from El. Jt. to antenna feed $4.50
Z-601A: Antenna and Dipole feed assy.....$12.50
Z-601E: Azimuth Rotating Joint.....$15.00
Z-911: Long Rt. Angle Bend, 90 Deg.....$4.50
Z-910: Short Rt. Angle Bend with pressure fitting $3.50

"S Band," RG48/U Waveguide

POWER SPLITTER for use with type 726 or any 10 CM Shepherd Klystron. Energy is fed from Klystron antenna through dual pick-up system to 2 type "N" connectors .....$22.50 EACH
DIRECTIONAL COUPLER. Broadband type "N" Coupling, 20 db. with std. flanges. Navy #CABV 47AAN-2 .....$37.50
LHTR, LIGHTHOUSE ASSEMBLY. Part of RT39 APG 5 & APG 15. Receiver and Trans. Cavities w/assoc Tr. Cavity and Type N CPLG. To Recvr. Uses 2C40, 2C43, 1B27, Tunable APX 2400-2700 MCS. Silver Plated $49.50
BEACON LIGHTHOUSE cavity 10 cm. Mfg. Bernard Rice, each $47.50
MAGNETRON TO WAVEGUIDE Coupler with 721-A Duplexer Cavity, gold plated.....$45.00
RT-39 APG-5 10 cm. lighthouse RF head c/o Xmtr.-Recvr-Tr, cavity compl. recvr. & 30 MC IF strip using 6GK5 (2C40, 2C43, 1B27 lineup) w/Tubes. .....
721A TR BOX complete with tube and tuning plungers $12.50
McNALLY KLYSTRON CAVITIES for 707B or 2K28 .....$4.00
WAVEGUIDE TO ¾" RIGID COAX "DOORKNOB" ADAPTER CHOKE FLANGE, SILVER PLATED BROAD BAND $32.50
AS14A AP-10 CM Pick up Dipole with "N" Cables $4.50
OAJ ECHO BOX, 10 CM TUNABLE.....$22.50
HOLMDELL-TO-TYPE "N" Male Adapters, W.E. #D167284 .....$2.75
I.F. AMP. STRIP: 30 MC, 30 d.b. gain, 4 MC Bandwidth, uses 6AC7's—with video detector. A.F.C. less tubes $24.50
POLYROD ANTENNA, AS31/APN-7 in Lucite Ball, Type "N" feed $22.50
ANTENNA, AT49A/APR: Broadband Conical, 300-3300 MC Type "N" Feed $12.50
"E" or "H" PLANE BENDS, 90 deg. less flanges $7.50

X Band— RG 52/U WAVEGUIDE

VSWR Measuring Section. Consisting of 6" straight section, with 2 pick-up, Type "N" Output Jacks. Mounted ½ Wave apart.....$8.50
UG 40A/U Broadband Choke Flanges.....$1.65
1" x ½" waveguide in 5' lengths, UG 39 flanges to UG40 cover .....per length $7.50
Rotating-joints supplied either with or without deck mounting. With UG40 flanges.....cash, $17.50
Bulkhead Feed-thru Assembly.....$15.00
Pressure Gauge Section 15 lb. gauge and press nipple $10.00
Pressure Gauge, 15 lbs. $2.50
Directional Coupler, UG-40/U Take off 20db..$17.50
TR-ATR Duplexer section for above $8.50
Waveguide Section 12" long choke to cover 45 deg. twist & 2½" radius, 90 deg. bend.....$4.50
Waveguide Section 2¼ ft. long silver plated with choke flange $3.75
Rotary joint choke to choke with deck mounting $17.50
90 degree elbows. "E" or "H" plane 2½" radius $12.50
45 degree twist.....$8.00
Microwave Receiver, 3 CM. Sensitivity: 10-13g Watts. Complete with L.O. and AFC Mixer and Waveguide Input Circuits. 6 I.F. Stages give approximately 120 DV gain at a bandwidth of 1.7 MC. Video Bandwidth: 2 MC. Uses latest type AFC circuit. Complete with all tubes, including 723A/B Local Oscillator $175.00
ADAPTER, waveguide to type "N", UG 81/U. p/o TS 13, TS-15, Etc. $27.50
ADAPTER, UG-163/U (1¼" x ½" cover) special bil. Flange for TS-45, etc.....$2.50 ea.

1¼" x ⅝" WAVEGUIDE

CG 98B/APQ 13 12" Flex. Sect. 1¼" x ⅝" OD $10.00
X Band Wave guide, 1¼" x ⅝" O.D. 1/16" wall aluminum .....per ft. 75¢
Slug Tuner Attenuater W.E. guide, old plated $6.50
Bi-Directional Coupler, Type "N" Takeoff 25 db. coupling $27.95
Bi-Directional Coupler. UG-53. Takeoff 25 db. coupling $24.95
Waveguide-to-Type "N" Adapter. Broadband $22.50

RADAR SETS

SO-1 10 cm. with a range of 4, 20, and 80 miles. PPI presentation on a 5 inch screen. 360 deg rotation of antenna with a pattern 8 deg in horiz. and 15 deg in vert. plane. Operates from 115 vdc. Set consists of following: antenna, m/g—modulator, xmtr—rcvr, PPI unit, accessory control, and rectifier power unit.....POR*

MK 10 GUN RADAR. Extremely accurate, rugged and compact. Designed for ship board use to direct naval gun turrets. Antenna utilizes conical scanning for accurate pointing. Max. range is 20,000 yards with an error of pm 15 yds pm .1% of range. Pointing accuracy is pm .25 deg. Pulse dur. 0.5 usec. at prr of 3600 cps. Pk. power output is 25 Kw. Primary power consumption is 1300 watts. Operates from 115V, 60 CPS source. BRAND NEW, COMPLETE WITH SPARES AND INSTRUCTION MANUAL .....POR*

SQ Portable radar with type PP1, "A", or "B" Scope. Frequency is Approx. 3000 Mcs. 3 ranges: 3, 15, and 45 miles. Operates from 115v, 60 cycles.....$850

SE 10 cm radar for use on small surface craft for Sea-Search use. Max. range 80,000 yards, with an accuracy of 100 yards ± 1% of range. Bearing accuracy 2 degrees. Operates from 115 VDC. Complete Equipment. Brand new, in original matched sets @.....$850.00

SN Portable, lightweight, 10 cm set with ranges of 4 and 20 Mi. Presentation is on 5" "A" Scope. Operates from 115V, 50-60 Cy. Ideal for labs, Classrooms, and small boats $850.00

IFF SETS RC 148 RC 184 Navy BM
RC 145 RC 186

*PRICE ON REQUEST

COMPONENTS

• AIA*	• APN-1*	• MK IV
• ABA-1	• APN-2*	• MK 10
• APA-9	• APN-3*	• SCR 545
• APG-5*	• APN-4*	• SCR 515
• APG-15*	• APN-7*	• SCR 585
• APQ-13*	• APN-9*	• SG-1
• APS-2*	• APN-19*	• SJ-1
• APS-3*	• ASB-7	• SO-8
• APS-4	• ASD*	• IFF

*Major Components and/or Spare Parts

SCR 584 PARTS

• BC 1088 • BC 1096
• BC 1094 • BC 1058

MAGNETRONS

Type	Price	Type	Price
2J51	$6.75	2J55	$24.50
2J22	7.50	2J49	33.50
2J27	19.95	2J61	34.50
2J31	24.50	2J62	34.50
2J32	28.50	2J31	45.00
2J17	12.50	725-A	Write
2J16	16.50	730-A	24.50

QK 60, 61, 62—$85 ea.

KLYSTRONS

723A .....$12.50 | 2K25/723A/B ..$27.50
723A/B ..... 19.50 | 417-A (Sperry).. 17.50

10 CM R.F. HEAD

Complete R.F. Head and Modulator delivers 50 KW Peak R.F. at 3000 MC. Pulser delivers 12KV pulse at 12 Amp. to magnetron of .5, 1, or 2 microsec. duration at duty cycle of .001. Unit requires 115V, 400-2400 Cycles, 1 phase @ 3.5A. Also 24-28 VDC @ 2A. External sync. Pulse of 120V Req'd. Brand New. Complete with schematic and all tubes $375.00

THERMISTORS

D-164699	Bead Type DCR: 1525-2550 Ohms @ 75 Deg. F. Coefficient: 2% Per Deg. Fahr. Max. Current 25 MA AC/DC.	$2.50
D-167332	Bead Type, DCR is 1525-2550 Ohms. Rated 25 MA at .625-1.175 VDC.	1.50
D-167613	Disk Type DCR: 355 Ohms @ 75 Deg. F. P. M. 2.5%, 1 Watt.	1.50
D-166228	Disk Type 7120 Ohms @ 60°F. 4220 Ohms @ 80°F 2550 Ohms @ 100°F. 1640 Ohms @ 120°F.	1.50

PULSE EQUIPMENT

MIT. MOD. 3 HARD TUBE PULSER: Output Pulse Power 144 KW (12 KV at 12 Amp). Duty Ratio: .001 max. Pulse duration: .5, 1.0, 2.0 microsec. Input voltage: 115 v, 400 to 2400 cps. Uses: 1-71B, 4-89-B, 3-'72's, 1-'73. New.....Less Cover—$135
APQ-13 PULSE MODULATOR. Pulse Width .5 to 1.1 Micro Sec. Rep. rate 624 to 1248 Pps. Pk pwr. out .35 KW Energy 0.018 Joules.....$49.00
TPS-3 PULSE MODULATOR. Pk. power 50 amp. 24 KW (1200 KW pk); pulse rate 200 PPS. 1.5 microsec. pulse line impedance 50 ohms. Circuit series charging version of DC Resonance type. Uses two 705-A's as rectifiers, 115 v. 400 cycle input. New with all tubes $49.50

PULSE TRANSFORMERS

GE #K-2449A
Primary: 9.33 KV, 50 ohms Imp.
Secondary: 28 KV, 450 ohms
Pulse length: 1.0/5 usec @ 635/120 PPS. Pk. Power Out: 1,740 KW
Bifilar: 1.5 amps (as shown)..$62.50
GE #K-2748-A. 0.5 usec @ 2000 Pps. Pk. Pwr. out is 32 KW impedance 40:100 ohm output. Pri. volts 2.3 KV Pk. Sec. volts 11.5 KV Pk. Bifilar rated at 1.3 Amp. Fitted with magnetron well.....$39.50
K-2748. Primary: 3.1/3.8 KV, 50 ohms Z. Secondary: 14/13.6 KV 1025 ohms Z. Pulse Length: 0.25/1.0 usec @ 600/800 PPS. Pk. Power 200/150 KW. Bifilar: 1.3 Amp. Has "built-in" magnetron well $42.50
K-2461A. Primary: 3.1/2.6 KV—50 ohms (line). Secondary 14/11.5 KV—1000 ohms Z. Pulse Length: 1 usec @ 600 PPS. Pk. Power Out: 200/130 KW. Bifilar: 1.3 Amp. Fitted with magnetron well $39.75
UTAH X-151T-1: Dual Transformer, 2 Wdgs. per section 1:1 Ratio per sec 13 MH inductance 30 ohms DCR $7.50
UTAH X-150T-1: Two sections, 3 Wdgs. per section. 1:1:1 Ratio, 3 MH, 6 ohms DCR per Wdg.....$7.50
6962711: Ratio: 4:1 Pri: 200V. Sec. 53V. 1.0 usec Pulse @ 2000 PPS, 0.016 KVA.....$4.50
TR1049: Ratio: 2:1 Pri. 230 MH, 50 Ohms, sec. 0.75 H. DCR 100 Ohms.....$6.75
K-901695-501: Ratio 1:1, Pri. Imp. 40 Ohm, Sec. Imp. 40 Ohms. Passes pulse 0.6 usec with 0.05 usec rise $6.95
Ray UX 7896—Pulse Output Pri. 5v. sec. 41v...$7.50
Ray UX 8442—Pulse Inversion—40v + 40v.....$7.50
PHILCO 352-7250, 352-7251, 352-7287
RAYTHEON: UX8693, UX5986.....$5 ea.
W.E.: D-166310, D-166638. KS 9900, KS9948.
UTAH #9262, with Cracked Beads, but will operate at full rated capacity $3.00
UX 3693 (SCS #229627-54): 3 Wdgs. 32 turns #18 wire. DCR is: .32Ω/.37Ω/.4 ohms. Total voltage 2500 vdc $5.00
D-166173: Input: 50 ohms Z. Output: 900 ohms 3 Wdgs. Freq. range 10 kc-2mc. P/O AN/APQ*-13 .....$12.50

PULSE NETWORKS

15A—1.400-50: 15 KV, "A" CKT, 1 microsec. 400 PPS, 50 ohms imp. $37.50
G.E. #3E (3-84-810) (8-2.24-405) 50P4T: 3KV "E" CKT Dual Unit; Unit 1, 3 sections, 0.84 Microsec. 810 PPS ,50 ohms imp.; Unit 2, 8 Sections, 2.24 microsec. 405 PPS 50 ohms imp.....$6.50
7-5E3-1-200-67P. 7.5 KV "E" Circuit, 1 microsec. 200 PPS, 67 ohms impedance 3 sections.....$7.50
7-5E4-16-60, 67P. 7.5 KV "E" Circuit, 4 sections 16 microsec. 60 PPS. 67 ohms impedance.....$15.00
7-5E3-3-200-67P. 7.5 KV, "E" Circuit, 3 microsec. 200 PPS, ohms imp. 3 sections.....$12.50
K58665 CHARGING CHOKE: 115-180 H @ .02A. 32-40H @ .08A. 30,700V Corona Test. 21KV Test $37.50
G.E. 2SE5-1-350-50 P2T. "E" SKT, 1 Microsec. Pulse @ 350 PPS. 50 OHMS Impedance.....$62.50
K58623 CHARGING CHOKE: 16H @ 75 MA. 250 Ohms DCR. 9000 Vac test.....$14.95
G.E. 2SE3-5-2000 50 P2T: 6 KV. "E" Circuit. 0.5 usec/2000 PPS/50 ohms/2 sections.....$7.50

MAIL ORDERS PROMPTLY FILLED. ALL PRICES F.O.B. NEY YORK CITY. SEND M.O. OR CHECK. ONLY SHIPPING SENT C.O.D. RATED CONCERNS SEND P. O. ALL MDSE SUBJECT TO PRIOR SALE AND PRICES SUBJECT TO CHANGE WITHOUT NOTICE. PARCELS IN EXCESS OF 20 POUNDS WILL BE SHIPPED VIA CHEAPEST TRUCK OR RAILEX

131 Liberty St., New York 7, N. Y. Dept E-11 Chas. Rosen Phone: DIgby 9-4124

COMMUNICATIONS EQUIPMENT CO.

D.C. RELAYS

CR2792B116A3

SPST—50 Amp Contracts. Operates from 22-30 VDC. Coil Res. 200 Ohms. Completely enclosed in transparent plastic case, which may be removed for adjustments. $1.50

GE #CR2791B116W3

Same as above, except additional terminal brought out from contact arm.....$1.74

GE #CR2791-F100D3

Differential: DPST. Norm. open. Dual coil. 1500 ohms per coil—25 Ma. Operating Current. Contacts: 20 Amp. $2.25

GE #CR2791F100G3

Same as above, except has extra 1A contact. Rated 5 Amp. $2.35

GE #CR2791D101F3

All Ceramic Insulation, DPDT, Coil—12VDC. 100 Ohms DCR. Contacts designed for fast operation. Rated at 5 Amps. $1.25

GE #CR2791B106J3

3PDT, 5 Amp. contacts. Coil rated 22-30VDC. 150 Ohms DCR. Contacts are designed for fast operation, and enclosed by clear plastic cover.....$1.35

GE #CR2791B106C3

8PDT, Dual Contacts will handle 20 Amps. Coil: 18-28VDC 125 Ohms DCR.....$1.25

DYNAMOTORS

TYPE	INPUT VOLTS	INPUT AMPS	OUTPUT VOLTS	OUTPUT AMPS	PRICE
DM 416	14	6.2	330	.170	$6.75
DM 31A	28	7	540	.250	3.95
BD AR 93	24	3.25	375	.150	7.50
23350	27	3.75	295	.075	3.95
B-19 Pack	12	9.4	275	.110	6.95
			500	.050	
DA-3A*	28	10	300	.260	6.95
			150	.010	
5053	28	14	14.5	5.	
PE 73 CM	28	19	250	.060	3.95
BD 69†	14	2.8	1000	.350	22.50
D-4021	13.5	13.2	220	.08	12.95
			300	.200	
SP 175	12	3.2	6.3VAC		12.50
DM 28‡	12	2.5	450	.06	4.45
			250	.005	6.95

‡ Less Filter † Used, Excellent * Replacement for PE 94.

INVERTERS

PE-218-H: Input: 25/28 vdc, 92 amp. Output: 115v, 350/500 cy 1500 volt-amperes. NEW $37.50

PE-206: Input: 28 vdc, 36 amps. Output: 80 v 800 cy, 500 volt-amps. Dim: 13"x5½"x10½". New $22.50

NAVY COR-211005: Input 22-30 VDC/75-80A. OUTPUT: 115V/400 CY. 1 KVA/8.7A. RPM: 4800. With coupling provision for motor. Brand New. Original packing $150.00

SELENIUM RECTIFIERS

Current (Continuous)	18/14 Volts	36/28 Volts	54/42 Volts	130/100 Volts
1 Amp.	$1.35	$2.15	$3.70	$8.50
2 Amps.	2.20	3.60	5.40	10.50
2½ Amps.			6.00	13.00
4 Amps.	4.25	7.95	12.95	25.25
6 Amps.	6.75	9.80	17.50	33.00
10 Amps.	6.75	12.75	20.00	44.95
12 Amps.	8.50	16.25	20.50	49.00
20 Amps.	13.25	25.50	38.00	79.50
24 Amps.	16.25	32.50	45.00	90.00
30 Amps.	20.00	38.50		
36 Amps.	25.00	48.50		

* F. W. Bridge

EE-89 REPEATER

Extends range of EE-8 field phone up to 20 miles of dry or wet wire operation. Extremely rugged, portable and lightweight. Uses hybrid coils and V.T. Amplifier, with extreme long-life characteristics. Brand new, complete with tube and teeb. Manual, only .....

$12.75 EACH

HELMHOLTZ PHASE-SHIFTER

Stator consists of 4 loops oriented at 90 degrees to each other. Total stator inductance is 40MH. Rotor: 10MH. Total phase shift 0-360 deg. Designed for range unit of SCR-268 .....

3.95 EACH

POWER TRANSFORMERS

Comb. Transformers—115V/50-60 cps Input

CT-766	300-0-300V/120MA, 2 x 5V/3A, 2.5V/3A			$3.95
CT-125	550-0-550V @ 150 MA, 6.3V/4A, 2.5VCT/5A			5.79
CT-813	450-0-450V @ 200 MA, 10V/1.5A, 2.5V/3.5A 5V/3A			6.95
CT-15A	550VCT .085A 6.3V/.6A, 6.3V/1.5A			2.85
CT-341	1050 100MA—525V @ 5 MA, 36V @ 4.5A 2x2.5V/3A, 6.3V @ 1A			9.95
CR 825	360VCT	.340A	6.3VCT/3.6, 6.3VCT/3A	3.95
CT-426	1500V	.160A	2.5/12, 30/100	9.95
CT-671	115V	.200A	13/.200, 5V/10, 2.5/10	4.95
CT-367	550VCT	.030 A	5VCT/3A	2.25
CT-483	350VCT	.026 A	5V/1A	2.75
CT-311	385VCT	.086 A	5V/3A, 6.3V/6A	4.25
CT-456	390VCT	80 MA	6.3V/1.3A, 5V/3A	3.45
CT-531	385VCT	86 MA	5V/3A, 6.V/6A	4.95
CT-442	525VCT	75 MA	5V/2A, 1 CT/2A, 50V/200 MA	3.95
CT-43A	600-0-600V/.08A, 2.5VCT/6A, 6.3VCT/1A			6.49
CT7-501	650VCT/200MA, 6.3V/8A, 6.3V/5A			6.49
CT-444	230-0-230V/.085A, 5V/3A, 6V/2.5A			3.49

Filament Transformers—115V50-60 cps Input

Item	Rating	Each
FT-140	5VCT @ 10A 25KV Test	$22.50
FT-157	4V/16A, 2.5V/2.75A	2.95
FT-181	6V/.25A	.79
FT-824	5.25A/21A, 2x7.75V/6.5A	14.95
FT-824	2x25V/2.5A, 16V/1A, 7.2V/7A, 6.4V/18A, 6.4V/2A	6.95
FT-463	6.3VCT/1A, 5VCT/3A, 5VCT/3A	6.49
FT-55-2	7.2V/21.5A, 6.5V/6.85A, 5V/6A, 5V/3A	8.95
FT-38A	6.3/2.5A, 2x2.5V/7A	4.19
FT-A27	2.5V/2.5A, 7V/1A, TAP 2.5V/2.5A, 16 KV TEST	18.95
FT-606	6.3V/3A 750V Test	1.79
FT-873	4.5AV/.5A, 7V/7A	2.19
FT-899	2x5V 45A, 29KV Test	24.50

Special Fil. Transformers—60 cps

Item	Pri. Volts	Secondaries	Price
STF-370	220/440	3x2.5V/5A, 3KV Test 2.5V/15A	6.95
STF-11A	220V	2x48V/.05A, 2x5V/6A 12.6V/1A	4.49
STF-688	220V	24V/6.6A, 5V/3A, 6.3V/1A, 6.3V/1A	3.45

Transformer Special

#766: Primary: 115 V, 60 cy, 1ϕ. Secondary: 300-0-300 V @ 120 MA. D.C. 2-5V WDGS @ 3 A ea. Also 2.5 VCT @ 5 A. Ruggedized. Herm. Sealed. Size: 4½" H x 3½" x 4½". 11 Solder Tmls. M.F.D. W.E. **$3.95**

400 CYCLE TRANSFORMERS

(All Primaries 115V, 400 Cycles)

Stock	Ratings	Price
352-7102	6.3V/2.5A	1.45
M-7472426	1450V/1.0MA, 2.5V/.75A, 6.4V/3.5A, 5V/2A, 6.5V/.3A, P/O ID-39/APG-13	4.95
352-7039	640VCT @ 280MA, 6.3V/.5A, 6.3V6A 5V/6A	5.49
702724	9800/3600 @ 32MA	8.95
K59584	5000V/200MA, 5V/10A	22.50
K59687	714VCT/.177A, 1710VCT/.177A	6.79
352-7273	700VCT/350MA, 6.3V6.9A, 6.3V 25.A 6.3V/.08A, 5V/CA	6.95
352-7070	2x2.5V/2.5A(2KV TEST) 6.3V/2.25A, 1200/100/750V. @ .005A	7.45
352-7196	1140/1.25MA, 2.5V/1.75A, 2.5V/1.75A —5KV Test	3.95
352-7176	329VCT/50MA,4.5V/3A,6.3VCT/20A, 2x6.3VCT/6A	4.75
RA6400-1	2.5V/1.75A, 6.3V/2A—5KV Test	2.39
901692	13V 9A	2.49
901695-501	2.77V @ 4.25A	3.45
901692-501	900V/75MA, 100V/.04A	4.25
Ux8855C	900VCT/.067A, 5V/3A	3.79
RA6405-1	800VCT/65MA, 5VCT/1A	3.69
T-48852	700VCT/305MA5V/3A, 6V/1.75A	4.25
352-7098	2500V/MA, 300, VCT, 135MA	5.95
KS 9336	1100V/50MA TAPPED @25V 2.5V/5A	3.95
M-7474319	6.3V 2.7A, 63.V/.66A, 6.3VCT/21A	4.25
KS58984	27V/4.3A, 6.3/2.9A, 1.25V/.02A	2.95
52C080	650VCT/50MA, 6.3VCT/2A, 5VCT/2A	3.75
32532	400VCT/35MA, 6.4V/2.5A, 6.4V/.35A	3.95
68G611	1150-0-1150V	2.75
80G198	6VCT/.0006 KVA	1.75
302433A	6.3V 3.1A, 6.3VCT/6.5A, 2.5V/3.5A, 2.5V/3.5A	4.85
KS 9445	592VCT/115MA, 6.3V/6.1A, 5V/2A	5.39
KS 9685	6.4/7.5A, 6.4V/1.5A, 6.4/2.5A ALL CT	4.79
79G30G1	600VCT/30MA	2.65
M-7474318	2100V/.027A	4.95
352-7069	2-2.5V Wdgs. at 2.5A, Each Lo-Cap., 22Kv Test	5.95
352-7096	2.5V/1.75A, 5V/3A, 6.5V/6A, 6.5V/1.2A, P/O BC-939	2.95
352-7099	350VCT/20MA, 1350V/1MA 2.5V/1.75A, 6.1V/2.5A, 6.3V/.6A, P/O BC-939	6.45
D162253	5200V/.002A, 2.5V/5A	5.35
M-7471957	2.5V/20A, 12KV Test	4.85
352-7179	250V/100MA, 6.5V/12ACT 5V/2A	3.45

SPECIALS

DC RELAYS
- ALLIED TYPE "AR", SPST, N.O. COIL 3 VDC, 77 OHMS MIDGET $5.95
- LEACH 1257, DPDT, 10 AMP CONTACTS COIL: 60 VDC, 2400 OHMS, 25 MA $2.85
- COL. RAD #55351, FOR ARC-5 .....$1.35
- COL. RAD #55528, FOR ARC-5 .....$1.35
- PHILCO 452-1127, SPST, N.O. COIL, 28 VDC, 300 OHMS $5.95

SWITCHETTES
- CR1070C122A3 .....$2.95
- CR1070C130D3 .....$2.95

TEST SET I-104 For testing 274-N, ARC-4, ETC $47.50

TEST SET, IE-30, FOR TESTING SCR-522, Meter $47.50

SPARE ARMATURES FOR GENERATORS:
- GN-35, GN-45, GN-37, BD 86 .....$4.95

EE-89A Telephone repeater, New $12.50

PHOTOTUBE 932: Infra-red, but may be used with incandescent light. Complete with data .....75¢

ID-24/ARN-9 Cross Point. Indicator. Contains 2—0-200 U AMP MOVEMENTS $6.95

MP-22 Mast Bases, original packing $4.95

COILS, C-387-D, For BC 610 transmitter $3.95

COILS, C-390-A For BC 610 transmitter $2.79

DYNAMIC MIKE and HEADSET COMBO, as used in B-19 TANK TRANSMITTERS $3.75

OSCILLOGRAPH Photo Recording paper, HIGHLY SENSITIVE, 35 mm x 250 Ft. Rolls $1.00

BRUSH CAPS For BD77 Dynamotor SCS #3H1777/8 ea. .....12¢

POWER SUPPLY For Super-Pro Receiver, #RA-74, NEW $69.50
- Driver Transformer, for ART-13, T-202 .....$1.29
- Side-Tone Transformer, for ART-13, T-203 .....$1.19
- Modulation Transformer, ES-69102S for BC 456 .....$1.19
- AN-104A Antennas for SCR-522 .....95¢
- BC 929 Indicators, p/o APN-2 .....$32.50
- BC 151 Trans. Control Box, p/o SCR 274N $1.85
- C-30/ARC-5 Control Box $1.85
- FT-225-A Mounting Racks $1.65
- FT 227-A Shock Mount Racks $1.65

MD7/ARC-5 Modulators, all Tubes $5.95

MC 211 Right Angle Drives .....21¢

BC 433 Compass Rcvrs., Used, Excellent $32.50

ART-13 Barometric Limit Switches $8.75

BC 306 Antenna Loading Unit for BC 375 .....$5.00

RL-7 Interphone Amplifiers, Used, Excellent, Less Tubes $3.75

SA-4A/APA-1 Meter Driven (28 VDC) Yagi-Antenna Switch $24.50

MT-36-C Ant. Loading Unit for TA-2J XMTR $35.00

A-62 Phantom Antennas, for use with Mobile XMTRS. 20-38.9 MC 40 Watts $3.95

RT-19/ARC-4 Trans-receivers, 24 VDC, covers Amateur 2—Meter Band. Complete with Tubes and Crystals $30.50

Radar Trainer, Type 15-C. Consists of 4 separate XMTRS. Operating 380-500 MC. 1—Pulse Gen. 1—Power Supply, all Cables, 2 Inst. Books. $215.00

Rubber Inserts, M-300 for HS-30 Headsets $3.25/M

BC 406A Dual Control Boxes (Receiver) for SCR 274N $1.95

T-30 Throat Microphones .....69¢

National XS-3 Double-Bewn Insulators, fits 2¾" Hole. All Hardware included .....65¢

IN-64 Double Cone Insulations .....12 for $1.00

ARC-5 PLUGS

#5842	35¢	#7027	45¢
#5577	35¢	#7025	45¢
#PL 154	70¢	#PL 152	85¢
#PL 154A	70¢	#6418	35¢

C-114 Loading Coils .....85¢

VOLTAGE REGULATORS

CARBON—PILE TYPES

LELAND TYPE "A": Coil: 245 ohms. Current 108-116 MA. Reg. Resistance: 1.5-2.5 ohms with 1.2-2.3 Amps. For 80 V.

LELAND TYPE "B": Volts In: 21-30 V. Volt Out: 18-25 V DC. at 5 A.

LELAND TYPE "C": Spec. VR 9000—2 C. Input: 22-30 VDC. Coil: 300 MA. Output: 19 V @ 2 A.

WEBSTER: 35x025: Philco 451-1035 Input: 21-30 V. D.C. Output: 18 VDC/4.75 A.

Price, Any Model..... $2.25 ea.

GN 35 HAND GENERATORS

BRAND NEW. IN ORIGINAL CARTONS. WILL DELIVER 8 V @ 2.5A AND 325-368 V @ 100 MA OR 16 V 1.25A AND 380-420 V @ 70 MA. LESS HAND CRANKS. A GREAT VALUE.....$17.50

CIRCUIT BREAKERS

HEINEMANN: .01A, 2340 V — Insulated for 5000 V. Separate Tmls. for coil and contact $1.95

#1510-M-7: 7 A. 24 VDC SCS #3H900-7-8 .....$1.65

#AM 1614-100: 100 Amps, 24 VDC $1.65

#AM 1614-80: 80 Amps. 24 VDC $1.45

#AM 1610-.5: 500 MA, 1000 VDC. Curve 3. SCS #3H900A-50 .....$2.25

SCS #3H900-10-3: 40 VDC, 10 Amps $1.65

MAIL ORDERS PROMPTLY FILLED. ALL PRICES F.O.B. NEW YORK CITY. SEND M.O. OR CHECK. ONLY SHIPPING SENT C.O.D. RATED CONCERNS SEND P. O. ALL MDSE SUBJECT TO PRIOR SALE AND PRICES SUBJECT TO CHANGE WITHOUT NOTICE. PARCELS IN EXCESS OF 20 POUNDS WILL BE SHIPPED VIA CHEAPEST TRUCK OR RAILEX.

131 Liberty St., New York 7, N. Y. Dept E-11 Chas. Rosen Phone: Digby 9-4124

Micro-Wave Lavoie Freq. Meter 375 to 725 MCS

Model TS-127/U is a compact, self-contained, battery powered, precision (± 1 Mc) frequency meter which provides quick, accurate readings. Requires a standard 1.5V "A" and 45V "B" battery. Has 0.5 MIN. time switch. Contains sturdily constructed HI-"Q" resonator with average "Q" of 3000 working directly into detector tube. Uses 957, L36 and 954 Tubes. Complete, new with inst. book, probe and spare kit of tubes. Less batteries.

Full data on request

$79.50

G.E. Servo Amplifier

Used in B29 planes for Central Station Fire Control Systems B2, B3 and B4. Used to drive Amplidyne 5AM31NJ9A and Control Motor 5BA50LJ3A. New less tubes. $29.50

Telrad Frequency Standard

Complete self contained, dual 100/1000 kc crystal, multivibrator and harmonic amplifier. Calibrates with WWV and provides 1000, 100, and 10 kc check points from 100 to 45,000 kc. 115V. 60 cycle. New with instructions. $29.50

TS-47/APR Test Oscillator



Provides calibrated CW, mod. or pulse signal source from 40 to 500 mc. Operates on 80, 115 or 230 V. from 50 to 2600 cy. or battery supply. New with tech. manual. $245.00

REPAIR PARTS FOR BC-348 RECEIVERS (H, K, L, R, Only)

Also BC 224 Models F. K., Coils for ant., r.f., det., osc., I.F., b.c. osc., xtal filters, 4 gang cond., vol. conts., etc. Write for complete list and free diagram.

SCR-522 EQUIPMENT

Complete BC-624C receivers and BC-625AM Transmitters including mounting racks, plugs, connectors, P.E. 94C dynamotor. Brand new equipment with instruction manuals.

MULTI-CONDUCTOR CABLE

CO-315. Stock 3E3215. Bulk 9 conductor No. 20 A.W.G. Stranded tinned copper plastic insulated, color coded, tinned copper braided shield. Flamenol jacketed. Made by G.E. Available 1000, 1500, 2000 ft. reels. Price.....$.15 Ft.

TRANSMITTING MICA CAPACITORS

LARGE QUANTITIES IN STOCK
WRITE FOR LIST

SWEEP GENERATOR CAPACITOR

High speed ball bearings. Split stator silver plated coaxial type 5/10 mmfd. Brand new.

Price $2.25

HIGH VOLTAGE OIL CAPACITORS

	.001 MFD 50,000V DC..	$37.50
	.01 MFD 5,000V DC..	$2.95
	.02 MFD 8,000V DC..	$9.50
	.025 MFD 50,000V DC..	$45.00
	.025/.025 MFD 50,000V DC	$59.50
	.1 MFD 500V DC..	$ .95
	.1 MFD 3,000V DC..	$2.55
	.125 MFD 7,500V DC..	$6.95
	.15 MFD 12,000V DC..	$7.50
	.2 MFD 50,000V DC..	$67.50
.25 MFD	15,000V DC	$19.50
.25 MFD	20,000V DC	$26.50
.25 MFD	50,000V DC	$72.50
1. MFD	7,500V DC	$12.50
1. MFD	15,000V DC	$45.95
2. MFD	6,000V DC	$14.50

RADAR EQUIPMENT



RADAR ANTENNAS

Type SO-1 (10CM) assembly with reflector, waveguide nozzle, drive motor. New.....$279.50
Type SO-3 (3 CM.) Surface Search type with reflector, drive motor, etc., but less plumbing. New in original cases $139.50
Type SO-13. (10CM.) Assembly with 24" dish, dipole, drive motor, gearing. New.....$149.50
Also in stock — spare reflectors, nozzles, probes, right angle bends for SO-1 antennas.

MODEL AN/APA-10 PANORAMIC ADAPTER



Provides 4 Types of Presentation:
(1) Panoramic (2) Aural
(3) Oscillographic (4) Oscilloscopic

Designed for use with receiving equipment AN/ARR-7, AN/ARR-8, AN/APR-4, SCR-587 or any receiver with I.F. of 455 kc, 5.3mc or 30mc. With 21 tubes including 3" scope tube. Converted for operation on 115 V. 60 cycle source.

Price.....$245.00

Gov't Cost $1800.00.
AN/APA-10 80 Page Tech Manual.....$2.75

TERMS: Rated Concerns Net 30, FOB Bronxville, New York. All Merchandise Guaranteed Prices Subject to Change

FLUXMETER

Used to calibrate field strength of magnets from 500 to 4000 gauss and indicate polarity. Probe has gap of 1¼". Beautifully built in hardwood case with hinged cover. Instructions for operation on under side of cover. Size 12¾ x 6 x 6 in. Ideal for lab and school use. New. An exceptional value at....$29.50

CRYSTAL DIODE

Sylvania 1N31B. Individually boxed and packed in loaded foil $3.80

HIGH POT TRANSFORMER

High Voltage Trans. Westinghouse Pri: 115, 60 cy., Sec: 15,000 C.T., 60 MA. Good for Hi-Pot test set up. C. T. ungrounded.....$29.50

INVERTERS

Onan M-G.-215H. Navy type PU/13. Input 115/230, 60 cy., 1 Ph. Output: 115, 480 cy., 1 Ph., 1.2Kw and 28V DC at 4 amps. New.....$295.00
Onan M-G.-675. Navy type PU/11 Input: 115/230, 60 cy., 1 Ph. Output: 115, 480 cy., 1 Ph., 5.8 amps. and 28 VDC @ 3.8 Amps. New.....$225.00
Leland Elec. Co. PE306A. Input: 28DC at 38 Amps. Output: 80V. 800 cy. 1 Ph., 485VA. New....$22.50
G.E. 5B169172. Input: 28DC. Output: 115, 400 cy., 1 Ph. 1.5KVA. New.....$32.50
G.E. 5AS13J251IA. Model 218J. Input: 28 DC. Output: 115, 400 cy., 1 Ph., 1.8 KVA. Regulated. New.....$89.50
Elcor. 74DC to 110AC, 60 cy., 1 Ph. at 2.4 Amps. New.....$39.50

DYNAMOTORS

Navy type CAJO-211444. Input: 105 to 130DC. Output: either 26DC at 20 amps. or 13DC at 40 amps. Radio filtered and complete with line switch. New.....$89.50
Type PE94CM. For SCR-522. Brand new in overseas cases. Has wide band input and output filters. $19.50

AMPLIDYNES

G.E. 5AM21JJ7. Input: 27VDC. Output: 60VDC. 150 Watts, 4000 RPM. Type MG-27-B. New..$34.50
Edison 5AM31NJ18A. Input: 27VDC, 44 Amps. 8300RPM. Output: 60VDC at 3.8 Amps. 530 Watts. New.....$12.50
G.E. 5AM31NJ9A. 530 Watts, 7500 RPM. Input: 27VDC. Output: 60VDC. Weight 34½ lbs....$29.50

SMALL D.C. MOTORS

G.E. 5BA50LJ2A. Armature 27VDC at 3.3 Amps. Field 60VDC at 2.3A RPM 4000. H.P. 0.2. New.....$27.50
Oster E-7-5. 27.5DC. 1/30HP, 3600RPM. Shunt Wound. New.....$9.50
Dumore Co. type ELBG. 24VDC. 40-1 gear ratio. For type R-4 Intervalometer. New.....$6.75
G.E. 5BBY47AB12. ¼ H.P. Perm. Mag.—1 amp. 250V. 1725 RPM. New.....$22.50

400 CY. BLOWERS

Westinghouse. Type FL. 115V, 400 cy., 6,700 RPM. Airflow 17C.F.M. New.....$6.75

SYNCHROS

Ford Inst. Co. Synchro Differential Generator. Mod. 2 Type 58DG. 90/90V. 400 cy., Ord. Dr. 1730B. New.....$22.50
Oster. Synchro Differential Generator. Type 6DG. New.....$40.00
Hobart Mfg. Co. Synchro Differential Synchro Type XIX 115V. 60 cy. New.....$9.50

STEP BY STEP MOTOR

Bendix—Type CAL 14810 (MK1 Mod 0). 70 Volts DC input $16.50

HIGH QUALITY CRYSTAL UNITS

Western Electric — type CR-1A/AR in holders. ¼" pin spacing. 5910-6350-6370-6470-6610-6670-6690-7270-7350-7380-7390-7480-7580-9720. All fundamentals in KC.....$1.25 each

1 K.W. MODULATION TRANSFORMER

R.C.A. Broadcast Type. Primary 15,000 ohms. Secondary 5,030 ohms 0.8 KVA audio. Designed for 833 class B modulation to two 833's in final amplifier. Size 11¼ x 9¼ x 13. Weight 143 lbs. Type 900177-502. Price, now.....$97.50

ELECTRONICRAFT INC.

27 MILBURN ST. BRONXVILLE 8, N. Y.
PHONE: BRONXVILLE 2-0044

A LEADING SUPPLIER OF ELECTRONIC & AIRCRAFT EQUIPMENT

IMMEDIATE DELIVERY -- FULLY GUARANTEED

A. C. SYNCHRONOUS MOTORS

110 Vt. 60 Cycle

HAYDON TYPE 1600, 1/240 RPM
HAYDON TYPE 1600, 1/60 RPM
HAYDON TYPE 1600, 4/5 RPM
HAYDON TYPE 1600, 1 RPM
HAYDON TYPE 1600, 1 1/5 RPM
TELECHRON TYPE B3, 2 RPM
TELECHRON TYPE BC, 60 RPM

SERVO MOTORS

PIONEER TYPE CK1, 2ϕ 400 CYCLE
PIONEER TYPE 10047-2-A, 2 ϕ, 400 CYCLE, with 40:1 reduction gear.

D. C. MOTORS

BODINE NFHG-12, 27 VTS., governor controlled, constant speed 3600 RPM, 1/30 HP.

DELCO TYPE 5068750, 27 VTS., 160 RPM, built in brake.

DUMORE, TYPE E1Y2PB, 24 VTS., 5 AMP., .05 HP, 200 RPM.

GENERAL ELECTRIC, TYPE 5BA10AJ18D, 27 VTS., 110 RPM, 1 oz. 1 ft. torque.

GENERAL ELECTRIC, TYPE 5BA10AJ18D, 27 VTS., 250 RPM, 8 oz. 1 in. torque.

BARBER COLMAN ACTUATOR TYPE AYLC 5091, 27 VTS., .7 amp., 1 RPM, 500 in. lbs. torque.

WHITE ROGER ACTUATOR TYPE 6905, 12 VT., 1.3 amp., 1½ RPM, 75 in. lbs. torque.

DELCO TYPE 5069230 27 volts 145 RPM.
DELCO TYPE 5071895 27 volts 250 RPM.
DELCO TYPE 5069600 27 volts 250 RPM.
DELCO TYPE 5067127 27 volts 250 RPM.

AMPLIDYNE AND MOTOR

AMPLIDYNE, GEN. ELEC. 5AM31NJ18A input 27 vts., at 44 amp. output 60 vts. at 8.8 amp., 530 watts.

MOTOR, GEN. ELEC. 5BA50LJ22, armature 60 vts. at 8.3 amp., field 27 vts. at 2.9 amp. ½ HP, 4000 RPM.

PIONEER AUTOSYNS 400 CYCLE

TYPE AY1, AY5, AY14G, AY14D, AY20, AY27D, AY38D, AY34D.

PIONEER AUTOSYN POSITION.

INDICATORS & TRANSMITTERS.

TYPE 5907-17, single, Ind. dial graduated 0 to 360°, 26 vts., 400 cycle.

TYPE 6007-39, dual Ind., dial graduated 0 to 360°, 26 vts., 400 cycle.

TYPE 4550-2-A, Transmitter, 2:1 gear ratio 26 vts., 400 cycle.

INVERTERS

WINCHARGER CORP. PU 16/AP, MG750, input 24 vts. 60 amps. outputs 115 vts., 400 cycle, 6.5 amp., 1 phase.

HOLTZER CABOT, TYPE 149F, input 24 vts. at 36 amps., output 26 vts. at 250 V.A. and 115 vts. at 500 V.A., both 400 cycle, 1 phase.

PIONEER TYPE 12117, input 12 vts., output 26 vts. at 6 V.A., 400 cycle.

PIONEER TYPE 12117, input 24 vts., output 26 vts. at 6 V.A., 400 cycle.

WINCHARGER CORP., PU/7, MG2500 input 24 vts. at 160 amp., output 115 vts. at 21.6 amp., 400 cycle, 1 phase.

GENERAL ELECTRIC, TYPE 5D21NJ3A, input 24 vts. at 35 amps., output 115 vts. at 485 V.A., 400 cycle, 1 phase.

LELAND, PE 218, input 24 vts. at 90 amps. output 115 vts. at 1.5 K.V.A., 400 cycle, 1 phase.

LELAND, TYPE D.A. input 28 vts., at 12 amp. output 115 vts. at 115 V.A., 400 cycle, 3 phase.

ENGINE HOUR METER

JOHN W. HOBBS, MODEL MI-277 records time up to 1000 hours, and repeats, operates from 20 to 30 volts.

VOLTAGE REGULATOR

LELAND ELEC. CO. TYPE B, CARBON PILE. Input 21 to 30 volts D.C. regulated output 18.25 vts. at 5 amp.

WESTERN ELEC. TYPE BC937B, input 110 to 120 volts, 400 cycle. Output variation 0 to 7.2 ohms at 5 to 2.75 amps.

WESTERN ELEC. TRANSTAT, input 115 vts., 400 cycle output adjustable from 92 to 115 vts., rating .5 K.V.A.

AMERICAN TRANS. CO., Transtat input 115 vts., 400 cycle output 75 to 120 vts. or 0 to 45 volts, rating .72 K.V.A.

SYNCHROS

1 F SPECIAL REPEATER 115 vts. 400 cycle.
2J1F1 GENERATOR, 115 vts. 400 cycle.
2J1F3 GENERATOR, 115 vts. 400 cycle.
2J1G1 CONTROL TRANSFORMER 57.5 vts. 400 cycle.
2J1H1 DIFFERENTIAL GEN. 57.5/57.5 vts. 400 cycle.
5G GENERATOR, 115 vts. 60 cycle.
5DG DIFFERENTIAL GEN. 90/90 vts. 60 cycle.
5HCT CONTROL TRAN. 90/55 vts. 60 cycle.
5CT CONTROL TRAN. 90/55 vts. 60 cycle.
5SDG DIFFERENTIAL GEN. 90/90 vts. 400 cycle.

ALL PRICES F. O. B. GREAT NECK N. Y.

TACHOMETER GENERATOR & INDICATOR

GENERAL ELECTRIC, GEN. TYPE AN5531-1, Pad mounting 3 phase variable frequency output.

GENERAL ELECTRIC, GEN. TYPE AN5531-2, Screw mounting 3 phase variable frequency output.

GENERAL ELECTRIC, IND. 8DJ13AAA, works in conjunction with above generators, range 0 to 3500 RPM.

D. C. ALNICO FIELD MOTOR

DIEHL TYPE FD6-23, 27 vts. 10,000 RPM.

GENERAL ELECTRIC D. C. SELSYNS

8TJ9-PXAN TRANSMITTER 24 VTS.
8TJ9PDD TRANSMITTER 24 volts.
8TJ9PDH TRANSMITTER 24 volts.
8DJ11- INDICATOR, dial 0 to 360°, 24 vts.

RECTIFIER POWER SUPPLY

HAMMETT ELECTRIC MFG. CO. MODEL SPS-130. Input voltage 208 or 230 volts, 60 cycle, 3 phase, 21 amps. Output 28 volts at 130 amps. continuous duty, 8 point tap switch, voltmeter ammeter, thermo reset all on front panel.

Phase Changing Transformer

70G23 single phase 115 volt 400 cycle input, to 115 volt 3 phase output at 48 V.A.

MISCELLANEOUS

PIONEER MAGNETIC AMPLIFIER ASSEMBLY Saturable reactor type, designed to supply variable voltage to a servo motor such as CK1, CK2, CK5 or 10047.

SPERRY A5 CONTROL UNIT, part No. 644836.

SPERRY A5 AZIMUTH FOLLOW-UP AMPLIFIER, part No. 656030.

SPERRY A5 DIRECTIONAL GYRO, part No. 656029, 115 vt. 400 cycle, 3 phase.

SPERRY A5 PILOT DIRECTION INDICATOR, part No. 645262 contains AY 20.

ALLEN CALCULATOR, TYPE C1, TURN & BANK IND., part No. 21500, 28 vts. D.C.

TYPE C1, AUTO-PILOT FORMATION STICK, part No. G1080A3.

PIONEER GYRO FLUX GATE AMPLIFIER, Type 12076-1-A, 115 vt. 400 cycle.

INSTRUMENT ASSOCIATES

351 GREAT NECK ROAD, GREAT NECK N. Y.
Telephone GReat Neck 4-1147

Write for Catalog NE100

U. S. Export License-2140

Western Union address: WUX Great Neck, N. Y.

BIGGEST & BEST in Surplus Communications Eqpt!

WESTERN ELECTRIC 250/350 WATTS RADIOTELEPHONE EQPT.

- ★ Provides Complete 2-Way Long or Short Distance Radiotelephone Communication
- ★ Frequency Range—2 to 20 MC
- ★ 30 Channels Transmit & Receive. All Crystal Controlled
- ★ Monitors 3 Separate Channels Simultaneously
- ★ Voice-Operated Carrier Control or Push-To-Talk, as Desired
- ★ Motor-Driven Channel Switching Controlled by Channel Selector
- ★ Highest Degree of Construction, Salt Air Corrosion Resistant, Hermetically Sealed Transformers, Etc.



The Model 248A Radiotelephone Equipment was developed at Bell Telephone Laboratories to furnish powerful, dependable radiotelephone communication, especially on the high seas. It is ideal for ship installation, and fixed-radio installation, since its design and construction are of the highest possible degree.

Each 248A Equipment consists of: 1-48A Radiotelephone Transmitter; 1-48A Radio Receiver (cabinet has provision for a total of 3 receivers, the 48A Receiver provides 10 channels in the 2-6 MC range; a 48B Receiver provides 10 channels in the 4 to 20 MC range, available at additional cost. The 2nd and 3rd receiver may be either a 48A or 48B, available at extra cost); 1-43A Control Unit (may be installed remotely); and, 1-104A Antenna Tuning Unit (medium frequency). A 104B Antenna Unit with whip antenna for the higher frequency, is available at additional cost.

The 48A Radiotelephone Transmitter provides 30 channels of transmission, all crystal controlled, and is rated at 250 watts output. However, a Western Electric Modification Kit is supplied with each, which will increase the power to 300/350 watts. Features of this transmitter include automatic variable-gain audio amplifier; sidetone (hearing of one's own voice in the telephone receiver); interlock safety relays; provision for Selective Ringer installation within cabinet (up to 3 units, 1 for each receiver) for automatic selective calling; motor driven switches for channel selection, controlled by the 43A Remote Control Unit which incorporates a telephone handset, monitoring loudspeaker; ventilating fan for cooling and providing filtered air within cabinet; hinged transmitter and individual receivers for easy access to parts, etc.

Operation of this equipment is from 115 V., 50/60 cycles AC.

This equipment is NOT GOVERNMENT SURPLUS, and is NEW—UNUSED. Additional accessories and full spares also available. Priced far below original selling price!!

WRITE FOR DESCRIPTIVE LITERATURE AND PRICES.

W. E. MODEL 107A SELECTIVE RINGER

Latest design W.E. Selective Ringer, for use with any size Ship-to-Shore Radiotelephone. Operates from radiotelephone's receiver to ring bell when shore telephone operator has call for you. Compact, easily installed. Dim. 15⅝" L. x 8¼" H. x 6⅛" W. Wt. 12 lbs. NEW EQPT., with instruction book.
PRICE, EACH $135.00

GE 10 KW FM POWER AMPLIFIERS and RECTIFIERS

BRAND NEW, not war surplus, 10 KW FM Power Amplifiers with associated separate Power Rectifiers, designed for boosting low power FM broadcasting stations. Can be used for increasing power of television stations (sound portion), or by changing L and C can be converted to power amplifier on other frequencies. Present range 88-108 MC. Rectifier Power Supply delivers approximately 5,000 V. at 18.4 KVA. Operates from 220 V., 50/60 Cycles, 3 phase AC. Power Amplifier uses 2 GL5518 (not supplied) forced-air cooled GE high frequency tubes. Includes internal blower system, reflectometer amplifier (with tubes) and GL-8008 rectifier tubes. Beautifully constructed, new equipment at terrific price savings!
PRICE, Type BF-3-A 10 KW RF FM Amplifier and Separate Rectifier, less RF Final Tubes..... $4,900.00
RECTIFIER ONLY, if desired. **WRITE FOR PRICE.**

EXTRA!

PE-104 POWER SUPPLIES for Receiver of SCR-284, NEW, with Spare Vibrater, Export-Packed. Large Quantity Available. *WRITE FOR PRICES.*

TRANSMITTERS—RECEIVERS, ETC.

TDQ VHF 100-156 MC, 50W. AM X-mttr for 110 V. 50/60 C. AC.
BC-797 VHF 110-126 MC. 50W. AM Output for 110 V. 50/60 C. AC.
SCR-510/610. FM Trans-Receiver, 20 to 28 and 28 to 27 mc respectively. With PE-117 or 120 Vibrator Power Supply and other accessories.
SCR-619. FM Trans-Receiver, 27 to 38.9 mc, complete with all accessories. NEW units.
SCR-522. VHF, 4-Channel, 100-156 MC Trans-Recvg. Eqt. for Plane or Ground Communications.
SCR-511, Walky-Talky, 3-6 MC, Crystal Controlled Trans-Recvg. with Plug-In Units for Freq. Changing.
BC-611 and **MAB** HANDY and WALKIE-TALKIES.
SCR-300 (BC-1000) WALKIE-TALKIES, 40-48 MC 2-Channel FM Trans-Receivers.
SCR-284 Field Radio Equipment, A1, A3 emission. Complete with all Accessories.
BC-221 Frequency Meters, Excellent condition. Complete with crystal and matching Calibration Book.
BC-312/342 Receivers. Like New Units.
BEACHMASTER 250 & 500 WATT SOUND SYSTEMS for Airports, Shipyards, Amusement Parks, Civilian Defense, Etc. **Write for Prices and Literature.**
TCS X-mttr-Receivers for Ship or Shore.
TBK HF 500W, 2-20 Mc. Transmitter with MG. Starter, and Spares.
TAJ 500 W. Output, 175-550 Kc. with M.G. for AC or DC operation.

ALL MATERIAL SUBJECT TO PRIOR SALE!

CABLE ADDRESS: **TELEMARINE, N. Y.**

TAQ. Same as TAJ above but 1,000/1,500 W. output, with MG.
TBL 250 W. Output, A1, A3, I.F. & H.F. for AC or DC operation.
APN-4 Loran Eqpt. R-9A/APN-4 Receivers and 1D-6A & 6B Indicators, with tubes, crystal, etc. Reconditioned to like-new.
WRITE FOR PRICES.
GO-9 100/125 W. IF, HF Ship or Aircraft Transmitter, A1 and A2 Emission. All New with Spares.
ATD Aircraft Transmitters, 50 W. A1 & A3. 1.5 to 2.05 MC. NEW.
GP-7 Aircraft Transmitters.
ZB-3 ILAS Eqpt.
SCR-283 Recvg. & X-mttng Eqpt. Complete.
RT-3/ARN-1 Altimeter.
RADIOSONDES AN/AMQ-1A to D. New.
PE-75U Gas Engine Generators. NEW, w/Spares.
T-21/GR-3-C Sound Ranging Microphones for locating Artillery Fire.
NAA Underwater Beacon Equipment.
BD-57-B Switchboards, telephone.
HS-23, 33 Headphones.
AN-CRT-1A Sonoluoys.
OZ-2 DIRECTION-FINDERS. Aircraft or Marine, 15 to 1750 KC in 4 bands for 24/28 V.D.C. operation. With 34" or 50" Loop Extension Shaft. Complete. NEW eqpt. with Dynamotor, Loop Extension Shaft and Control, Cables, Instruction Manual, etc., all export packed in 2 cases per set.
WRITE FOR PRICES

— TELEMARINE —
COMMUNICATIONS CO.
3040 W. 21st Street, Brooklyn 24, N. Y.
Phone: ES 2-4300

EXPORTERS, GOVERNMENT AGENCIES, INDUSTRIALS!

We have a large stock of Transmitters, Receivers, Walkie-Talkies, VHF Equipment, Ship & Shore Communications, FM Broadcast Stations, Radar, Accessories, etc. Write and tell us of your requirements. Descriptive literature and prices available upon request.

SELENIUM RECTIFIERS

Full-Wave Bridge Types

Current (Continuous)	18/14 Volts	36/28 Volts	54/42 Volts	130/100 Volts
1 Amp.	$1.35	$2.15	53.70	$8.80
2 Amps.	2.20	3.60	6.40	10.50
2½ Amps.	3.10	4.20	6.80	13.00
4 Amps.	4.25	7.95	12.95	25.25
6 Amps.	4.75	9.80	13.50	33.80
10 Amps.	6.75	12.75	20.00	44.95
12 Amps.	8.50	16.25	29.50	49.00
20 Amps.	13.25	25.50	38.00	67.50
24 Amps.	16.25	32.50	45.00	95.00
30 Amps.	20.00	38.50	.....	.....
36 Amps.	25.00	48.50	.....	.....

NEW SELENIUM RECTIFIER TRANSFORMERS

PRI: 115 V., 60 cycles in. SEC: 9. 12, 18, 24, and 36 volts **Continuous Ratings**

4 Amps.	$ 8.75
12 Amps.	16.75
24 Amps.	35.75
30 Amps.	45.00
50 Amps.	59.75

NEW SELENIUM RECTIFIER CHOKES

2 Amps.—.06 Hy.—4 ohms	$3.95
4 Amps.—.07 Hy.—.6 ohm	$7.95
12 Amps.—.01 Hy.—.1 ohm	$14.95
24 Amps.—.004 Hy.—.025 ohm	$29.95

We can supply other selenium rectifiers, transformers chokes, and filter capacitors.

• THORDARSON Boxed Filament XFMR. (T-50F61) 115V.—2.5V. @ 3.5 A. $2.00

W. E. Type KS-9799—115 VAC—60 cy. Primary; Secondary: 930 VCT @ 820 MA. and 5.2 V. @ 4 Amps. (20 KV. Insul.) $8.50

W. E. Type DI75847—1000 VCT @ 500 MA. 5 Volts @ 5 Amps. 115 VAC—60 cy. PRI; Secondary; Hi-Volt Insul.—6¼" x 5¼" x 6½" $8.50

• W.E. Steel ¼" Panels 10½" x 19"—New—Comm'l. Grey $10.00

7C30 12 KW. POWER TRIODE WITH 16 VOLT FILAMENT XFMR. (TAPPED AT 11V.). 220 V. PRIMARY—COMBINATION—ALL NEW. IN STOCK. . $105.00

WESTINGHOUSE

WESTERN ELECTRIC HERM. SEALED POWER TRANSFORMERS

Official Distributor Westinghouse Reliatron* Power Tubes (*Trademark)

• New Erco 4 Channel Ship-to-Shore Marine Transmitter — Receiver — F.C.C. Approved. Brand New, Complete, less xtals @ . . . $179.50 Write for Full Details

• W.E. Chokes—New Herm. Sealed.—KS-9476 dimensions 4⅝" x 5¼" x 5"—8 hy. @ 300 MA. 75 ohms $5.00
KS-13063—4 to 7 hys.—200 to 700 MA. 42 ohms average, New, herm. sealed, 5" x 5¼" x 5" $6.00

• Vibrapacks—12 Volts Input—Mallory-350 V. @ 125 MA. Out—New $9.95

• Trimm. Model 100 "Featherweight" Headset & Band. New, in orig. mfr.'s carton $4.95

• Bliley-Type SMC100— Crystal Standards New—100 KC and 1,000 KC BAR. $6.50

CBS — Hytron Cathode-Ray Picture Tubes

First Quality in factory-sealed cartons. Full Year Warranty Card on each tube. Remember . . . no seconds; no rebuilts . . . Prices include Fed. Tax. C.R. Tubes via Express Collect.

7JP4	$8.75	16KP4	20.75
10BP4A	21.00	16RP4	30.00
12LP4A	21.50	16TP4	30.00
14CP4	24.00	17BP4A	24.75
16AP4	31.00	17CP4	25.25
17MP4	25.50
20CP4A	38.50
21EP4A	38.50
21FP4A	36.00

• Vacuum Capacitors 50 MMF.—20 KV. . . . $5.50

FULLY GUARANTEED

TUBE SPECIALS

STANDARD BRANDS ONLY

0A3/VR75	.90	2C52	4.25	3B4	.75	6BZ7	1.20	7JP4	17.50	98R	9.50
0B2	1.05	2D21	1.20	3X2500-A	131.00	6C4	.52	10 (Special)	.95	HF-100	5.50
0B3/VR90	.80	2E22	2.50	4B22	7.50	6C5	.65	10T1	.75	C-100E	2.00
0C3/VR105	.95	2E26	1.55	4B24	4.50	6C6	.65	12AT7	.88	100-TH	5.95
0D3/VR150	.95	2E30	2.05	4B25	8.00	6CB6	.59	12AU7	.85	10-F (WE)	2.50
0D3/VR150	.95	2J21/2J21A	7.95	4B28/CE225	2.95	6CD6-G	2.10	12AW6	.88	FG-105	18.50
0Z4/0Z4A	.55	2J22	6.50	4C27	21.50	6CS6/5915	1.10	12AX7	.75	VU-111	.88
1AD4	1.20	2J26	14.00	4C35	19.95	6CU6/6BQ6	2.10	12AY7	1.50	HY-114B	.40
1AE4	.90	2J27	10.95	WL4D21/		6D6	.75	12BA6	.60	1177Z1	.55
1A3	.70	2J31	25.00	4-125A	38.25	6F4	9.50	12BE6	.60	C-150	10.00
1A7GT	.77	2J32	25.00	4D22	18.50	6F5	.65	12BH7	.93	121-A	8.00
1AX2	1.05	2J34	24.00	4E27A	25.00	6F6M	.49	12BY7	1.03	F-123A	5.00
1B3GT/8016	.90	2J37	12.00	4J32	225.00					WL-172	51.00
1B22	1.55	2J39	7.95	4J36	140.00					211/VT4C	.85
1B23	6.50	2J40	27.50	4J37	225.00					RX215	8.00
1B24	9.00	2J50	36.75	4-65A	write					227	1.95
1B26	2.25	2J54	62.95	4X150A	write					RX233A	3.50
1B27	11.50	2J54B	125.00	4-400A	45.00					250-TH	16.95
1B32	2.50	2J55	68.00	4X500A	75.00					FG-271	
1B42	9.50	2J61	17.50	4X1000A	110.00					5551	57.50
1G5GT	.90	2J62	33.00	5A8	2.75					274A&B	2.75
1L4	.60	2K22	23.50	5BP1	5.00					275A (WE)	7.95
1L6	.95	2K23	11.50	5BP4	5.00					300B (WE)	7.95
1N21	.85	2K25	23.95	5C22	39.00	6F8G	.85	12SA7	.68	HF-300	17.50
1N21B	1.95	2K26	65.00	5D21	15.00	6G12	.90	12SG7	.80	304-TH	7.75
1N21A	2.05	2K28	27.50	WL5D22/		6H6	.52	12SH7	.65	304-TL	8.75
1N23B	4.25	2K29	23.00	4-250A	41.25	6J4 (RCA)	5.10	12SJ7	.55	307-A	4.00
1N23	7.25	2K30/		5FP7	5.00	6J5GT	.59	12AP4A	43.00	310-A (WE)	3.95
1N34	.75	410R	325.00	5GP1	5.00	6J6	.59	22	.95	311-A (WE)	6.50
1N38	1.20	2K33	250.00	5J29	15.00	6J6W	1.50	23D4	.55	316-A	.75
1N38A	.81	2K33A	295.00	5J30	45.00	6K4	2.25	25AV5	1.20	328-A	5.00
1N39	4.60	2K34	150.00	5JP2	25.00	6K4A	2.25	25BQ6GT	1.15	CK3598A	7.00
1N44/400B	1.20	2X2	.40	5LP3	17.00	6K6GT	.55	25L6GT	.62	359A (WE)	4.00
1N45/400C	1.30	3A4	.59	5R4GY	1.20	6K7	.60	25Z6GT	.59	371-B/	
1N48	.50	3A5	.85	5TP4(RCA)	38.50	6L6G	1.10	28D7	1.55	VT-106	.90
1N54	.75	3AP1	8.50	5U4G	.58	6L6-G	1.10	35B5	.55	373A (WE)	4.00
1N54A	1.05	3B7/1291	.20	5V4G	.95	6L6-GA	1.10	35C5	.55	374A (WE)	3.50
1N64	.75	3B22	2.40	5W4	.80	6L6-M	1.50	35L6GT	.60	387A (WE)	2.50
1N69	.60	3B24	4.75	5X4G	.75	6L7	.70	35Z3	.70	388A	2.75
1N70	1.20	3B25	3.95	5Y4G	.57	6M7	.75	35-T	2.75	394-A	4.00
1N72	1.10	3B26	3.50	C6J	14.50	6P7G	.85	35Z5GT	.55	803-B (WE)	7.50
1N81	1.00	3B28	5.95	6-4	.35	6Q7GT	.80	41	.75	404-A/3047	
C1B/3C31	2.95	3B29	8.50	6-4B	.45	6S7M	.95	42	.70	404-B	
1C5	.50	3BP1	5.00	6AB7	.95	6SD7GT	.80	45 (Special)	.60	407-A (WE)	4.50
1H4G	.90	3BP11	9.00	6AC7	.69	6SQ7	.66	47	.50	408-A (WE)	2.50
1J5GT	.60	3C21	5.00	6AF4	1.30	6SH7	.70	RK-47	6.00	417-A (WE)	7.95
1P23	1.75	3C23	6.50	6AG5	.70	6SJ7	.70	NE-48	.30	GL-434A	17.95
1P28	11.50	3C24/24G	1.15	6AG7	1.20	6SK7GT	.59	WL-5R58	5.15	GL-446A	1.95
1P40	1.75	3C27	7.50	6A'46	.88	6SL7GT	.65	50A5	.77	WL-450TH	77.00
1P42	5.00	3C33	9.50	6AJ8	1.30	6SN7GT	.69	50B5	.55	450TL	42.00
1U4	.55	3C45	10.00	6AJ5	1.95	6SR7	.65	50C5	.60	GL-471A	2.50
1Q6	.75	3D6/1299	.35	6AJ7	1.50	6T8	.88	50C6G	.55	WL-481A	4.50
1R4/1294	.59	3D21	2.75	6AK5	.70	6V6GT	.58	50L6GT	.62	CK501LX	1.25
1X2/1X2A	.90	3D21A	5.50	6AK5-W	1.50	6V6M	1.40	53A	4.95	WL-502A	1.85
1Z2	3.25	3DP1	5.95	6AK5(WE)	1.25	6W4GT	.57	RK59	1.95	527	15.00
2AP1	8.50	3DP1-Sq	5.95	6AK6	.95	6W6GT	.75	WL-5K66	5.15	559	1.95
2B22	2.95	3FP7	1.75	6AL5	.53	6Y6-G	.88	QK-60	90.00	GL-563	60.00
2C22	.15	3GP1	3.00	6AM4 (Syl)	1.50	6X5GT	.50	QK-61	90.00	575-A	15.00
2C33A	13.75	3J30	95.00	6AQ5	.48	7A4	.70	VR-65	1.50	WL-575B	15.00
2C40	6.75	3Q4	.68	6AR5	2.70	7A7	.75	QK-72	295.00	WL-KU616	22.00
2C43	14.75	3Q5GT	.68	6AS6	2.25	7A8	.69	RKR-72	1.10	WL-KU627	22.00
2C44	1.10	3RP1	8.75	6AS7-G	1.50	7B7	.76	RKR-73	1.10	WL-629	13.00
2C51	1.90	3L4	.90	6AT6	.55	7BP7	4.25	75	.65	WL-632B	29.00
				6AU6	.60	7B8	.78	76	.59	635	11.00
				6AV5	.70	7C4	.29	77	.70	651	70.00
				6AX4GT	.60	7C5	.69	78	.69	ZP-653	220.00
				6B8	.70	7C6	.69	80	.65	WL-672A	35.00
				6BE6	.53	7C30	85.00	81	.55	WL-KU676	65.00
				6BH6	.69	7E5	.59	82	.85	WL-677	55.00
				6BQ6-G	1.85	7E6	.55	83	1.15	WL-678	47.50
				6BQ6GT	11.15	7F7	.85	83-V	1.00	700A	19.00
				6BY5-G	12.50	7H7	.70	84/6Z4	.65	705-B	25.00

708-D	44.00	869-B	65.00	32	25.50						
703-A	4.95	872-A	3.50	WL-5559/							
704-A	.85	884	1.55	57	22.00						
705-A	1.90	885	1.65	5635	5.75						
707-A	7.50	WL-889-		5645	7.75						
707-B	14.00	RA	295.00	5654	7.75						
708-A	4.50	WL-891	223.00	5654	2.35						
709-A	3.50	892-R	150.00	WL-5683	3.41						
710-A	.95	902	5.00	WL-5685	31.90						
713A	1.20	302P1	9.00	5691	6.25						
714AY	10.00	SD917A	3.00	5726	1.85						
715A	5.00	910	2.20	5732	3.95						
715B	7.95	921	2.00	WL-5736	160.00						
717-A	.80	922	1.60	5744	2.60						
719A	25.00	924	2.50	5749	1.75						
721A	4.50	927	1.75	5763	2.00						
723	5.00	931A	4.75	5800	6.50						
723A/B	17.00	5N949	3.50	5814	2.29						
725A	4.70	954	.35	5829	1.75						
726B	60.00	955	.42	5837/							
726C	62.50	956	.45	SD1104	110.00						
728-EY	250.00	957	.43	5838	3.00						
730A	22.00	958	.48	5840	8.00						
801-A	.40	958A	.48	5844	3.00						
802	3.25	959	1.95	WL-5846	130.00						
803	3.35	960	1.50	5880	3.00						
803	3.35	SN949D	3.00	5901	3.95						
807	1.55	991/NE16	.50	5918	.75						
808	2.20	FM1000	.75	WL-5934	15.00						
810-A	16.25	CK-1005	.45	WL-5966	15.00						
811	2.95	CK-1027	2.75	5998	write						
811-A	2.65	1201-1201A	.45	6013	write						
812	2.95	1203A	.45	6085	write						
813-A	7.50	1206A	.57	6090	write						
WL-813	10.00	1612	2.00	6097	write						
814	1.75	1613	.95	6099	write						
816	1.20	1616	.88	6101	write						
822	19.50	1619	.35	6161	110.00						
826	1.00	1622 (5L6M)	1.95	6216							
827-R	11.50	1625	.25	(Hytron)	3.20						
828	10.50	1629	.25	7193	.35						
829	7.95	1632	.30	WL-8000	14.50						
829-A	7.40	1636	2.70	8003	11.00						
829-B	9.00	1638	.49	8005	4.95						
WL-829-B	16.25	1655	1.70	8008	6.20						
830-B	2.75	1665	1.85	8011	.75						
WL-831A	49.50	1852	write	8012	2.50						
832A	9.95	38222 (3B23)	4.90	8013A	3.95						
CK-38233	.75	38922	write	8020	1.98						
834	9.50	5514	4.75	8025	5.25						
SD-834	4.00	5516	7.75	8001	1.15						
836	5.00	WL-5550/		8002	.85						
836	1.75	681	50.00	8003	1.15						
836	3.35	WL-5552/		8004	.25						
843	.50	685	265.00	8005	1.90						
845	13.75	WL-5554/	2.50	8006	.25						
849	75.00	679	190.00	9025	write						
860	3.50	WL-5557/17	8.50								
866-A(JAN)	1.75	WL-5558/									
866-A (Hytron)	1.75										

AND MANY OTHERS write

NEW TYPES
—NOW IN STOCK—
WRITE FOR QUOTATIONS ON UNLISTED TYPES.

—TELEPHONE—
REctor 2-2562

Terms! F O B-N Y C—25% Deposit with order —or send full remittance to save C O D charges —Rated Firms (D. & B.) Net 10 days—All merchandise guaranteed. CABLE: BARRYLECT, N. Y.

BARRY ELECTRONICS CORP.

136-C LIBERTY ST. N. Y. 6, N. Y.

Want more information? Use post card on last page.

PLUGS WITH PIN CONTACTS

Type AN 3108 ANGLE PLUG

Type AN 3106 STRAIGHT PLUG

TAKE YOUR PICK!

50 cents each.

PLUGS WITH SOCKET CONTACTS

Type AN 3108 ANGLE PLUG

Type AN 3106 STRAIGHT PLUG

TALLEN Co., Inc.

ARC-PLUGS

PL	Plugs
PLP	Plugs
PLQ	Plugs

PL 59, 63, 64, 65, 74, 75, 81, 83, 108, 112, 117, 123, 147, 148, 150, 151, 152, 153, 154, 156, 164, 167, 169, 171, 172, 179, 181, 182, 183, 184, 188, 216, 219, 259, 265

PLQ 63, 64, 77

SO 92, 126, 131, 132, 180

RECEPTACLES WITH SOCKET CONTACTS

Type AN 3102 BOX MOUNTING RECEPTACLE

Type AN 3101 CABLE RECEPTACLE

Type AN 3100 SHIELDED RECEPTACLE

2,000 TYPES OF . . .

Connectors
Plugs
Sockets
Receptacles

TYPE . . .

AN	CLT
PL	NK
UG	GK
SO	DPD
ARC	FK

etc.

RECEPTACLES WITH PIN CONTACTS

Type AN 3102 BOX MOUNTING RECEPTACLE

Type AN 3101 CABLE RECEPTACLE

Type AN 3100 SHIELDED RECEPTACLE

TALLEN CO. Inc.

159 Carlton Ave.
Brooklyn 5, N. Y.

COMPASS

COMMUNICATIONS COMPANY

A Division of COMPASS ELECTRONICS CORP.

WE MAINTAIN OUR OWN FULLY EQUIPPED TESTING LABORATORY TO TEST AND GUARANTEE ANYTHING WE SELL

A WELL-INTEGRATED ORGANIZATION WITH FACILITIES AND TRAINED PERSONNEL FOR—

- **DESIGN, MODIFICATION, PRODUCTION, AND TESTING OF COMMUNICATIONS AND RADAR EQUIPMENT**
- **SUPPLY AND DISTRIBUTION OF ALL TYPES OF EQUIPMENT AND TUBES**

COMPASS has one of the largest and most diversified stocks of government surplus equipment—in its own warehouses

MARINE, GROUND AND AIRBORNE—RADIO, RADAR AND SONAR—IN STOCK

RECEIVERS

ARB
AR-88
CR-91
SLR
RAK
RAL
RAO
RBO
RBG
RBL
RBA
RBM
BC-224
BC-312
BC-314
BC-344
BC-348

AIRBORNE RADAR

APS-2
APS-3
APS-4
APS-6
APS-10
APS-13
APS-15
SCR-717
SCR-720

FIELD TRANSMITTERS

SCR-284—The famous mobile and ground equipment station for field use, complete with all accessories. Range 3.8—5.8 mcs; 20 watts cw, 5 watts phone.

SCR-510—Mobile, portable **FM** radio station. Operates from 6, 12, or 24 volt dc supply. Frequency range: 20.0 to 27.9 mcs.

SCR-610—Same as SCR-510, but with built-in speaker and range of 27.0-38.9 mcs.

SCR-528—Mobile **FM** radio station, operates from 12 or 24 volt dc. Frequency range: 20.0-27.9 mcs.

SCR-628—Same as SCR-528, but with range: 27.0 to 38.9 mcs.

BC-325—400 watts c.w., 100 watts new or voice operates from 110 or 220 volts ac. Freq. range: 1.5-18.0 mcs. Master oscillator or crystal control.

14C—400 watts phone or 800 watts c.w. Operates from 220 volts ac. Freq. range: 2.0-18.1 mcs. Has automatic dial selection of anyone of ten preset channels. Mfr. Western Electric.

—◇—

ROTATING MACHINERY

Thousands of convertors, inverters, dynamotors, and motor-generator sets in stock.

MARINE TRANSMITTERS

TCS—Collins mfd. Navy radiotelephones for shipboard and mobile use, complete with all accessories for operation from 12, 24, 110, 230 volts d.c. and 110 or 220 volts a.c.

TDE—Navy or commercial marine transmitters, complete 110 & 220 volts d.c. and a.c.

TBK—Navy high frequency transmitter, 2-20 mcs; 500 watts output. Supplied complete with m/g and starter for d.c. or a.c. operation.

TBM—same transmitter but with speech input equipment to give 350 watts phone.

TBL—Navy all-wave transmitter; 350 watts output; CW and phone. Supplied complete with m/g and starter for d.c. or a.c. operation.

TAJ—Navy intermediate freq. transmitter, 175-550 kcs; 500 watts output. Supplied complete with m/g and starter for a.c. or d.c. operation.

TBN—200-3,000 kcs, complete with 220/440 volt, 3 ph. 50-60c power supply—conservatively rated at 1 kw. output.

—◇—

RADAR BEACONS

AN/CPN . . . . . 3 cm.
AN/CPN-8 . . . . . 10 cm.
YJ and YG . . . . . for shipboard use
AN/CPN-6 . . . . . 3 cm.
AN/CPN-8 . . . . . 10 cm.

—◇—

SA, SF, SG, SD, SJ, SK, SN, SQ—both equipment and spare parts

TEST SETS

TS-3A/AP
TS-10AandB
TS-12/AP
TS-13/AP
TS-16/AP
TS-35/AP
TS-36/AP
TS-62/AP
TS-69A
TS-74/UPM
TS-89/AP
TS-100/AP
TS-101/AP
TS-125/AP
TS-173/UR
TS-278
TS-323
OAA
OAP
OBU
LAE
LM
LU
IE-19
I-46
I-56
I-208
I-222
SCR-211
and others

393 GREENWICH STREET
NEW YORK 13, N. Y.
***CABLE ADDRESS:* COMPRADIO, N. Y.**
***ALL PHONES:* BEEKMAN 3-6509**

TEST EQUIPMENT

Spectrum Analyzer, Model TSX-45E-8500-9600 MC., calibrated linear below cut-off attenuator, calibrated frequency meter, tuned mixer, 4 I.F. stages, 3 video stages, overall gain 125 db., regulated power supply.

Spectrum Analyzer, same as above but modified for 100 to 1000 MC frequency range.

X Band VSWR Test Set, TS-12, complete with linear amplifier, direct reading VSWR meter, slotted waveguide with gear driven traveling probe, matched termination and various adapters, with carrying case.

R. F. Power Meter—1 to 600 MC 0-15 and 0-60 Watt scales. May be used as dummy load for 0 to 1000 MC.—100 W maximum, VSWR less than 1.1 from 0 600 MC., less than 1.3 from 600 to 1000 MC.

X Band Pick up Horn, AT48/UP with coax fitting.

TS-45/APM-9 Signal Generator 8700-9500 MC, 110V 60-800 cps.

TS-35A/AP X Band Signal Generator, pulsed, calibrated power meter, frequency meter, calibrated attenuator, 110V 60-800 cps.

30 MC I.F. Strip, Video and Audio Amplifier and 115 volt 80-2800 cps Power Supply, Bandwidth 10 MC. new, part of SPR-2 receiver.

High Pass Filter, F-29/SPR-2, Cuts off at 1000 MC. and below; used for receivers above 1000 MC.

TS-125 Calibrated S Band Power Meter with attenuator.

TS-110 S Band Echo Box 2400 to 2700 MC., Portable.

S Band Signal Generator Cavity with cut-off attenuator, 2300 to 2950 MC., 2C40 Tube, with modulator chassis.

VD-20K Voltage Divider for measuring high video pulses, ratio's 1:10 and 1:100, transmission flat within 2db 150 cps to 5 MC.

Waveguide Below Cut-off Attenuator L101-A, UHF connectors at each end, calibration 30-100 db.

TAA-16 Tuned Linear Audio Amplifier, 300 to 8000 cps, output meter reads direct in VSWR or Power DB. Regulated power supply, 110V 60 cps.

FPM 3 X Band Power and Frequency Meter, frequency meter 8500 to 9800 MC., accuracy ± 4 MC absolute, ± 0.5 MC on frequency difference up to 60 MC. Calibrated attenuator 0-30 db, power measuring range .1 to 1000 MW, pulsed or CW without external attenuator, video detector, self-contained battery powered, portable, with coaxial and waveguide adaptors.

TBS/APT 5, 300 to 1800 MC, 40 watt noise modulated transmitter.

110-330 MC Oscillator Butterfly.

80-300 MC. Mixer Butterfly with socket for 955 (used as diode).

400-800 MC. Oscillator Butterfly with 703 tube mounted on it.

Field Intensity Meter, RCA 308A, 120 to 18000 KC.

S Band Signal Generator—2K28 Klystron, self-pulsed or ext. triggered.

Mark 5, "S" Band Signal Generator—3.4 to 3.4 KMC 2C40 Oscillator, Meter tuned.

X Band Receiver, tunable, waveguide input 9200-9600 MC.

QX Checker, Boonton, Type 110-A.

Synchroscope—Sylvania Model 5.

Synchroscope—Model P4.

D.C. Amplifier—TS 580/U-GR Model 715 AM.

Hetrodyne Frequency Meter—GR616C, 100 to 5200 KC.

Noise Distortion Analyzer—H.P. Model 325B.

Sweep Speed Calibrator, 200 KC, 1 MC, 5 MC.

Tuning Units P/O APR-4 TN16 30-80 MC, TN17 80-300 MC., TN18 300-1000 MC. TN19 1000-2200 MC., TN54 2200-4000 MC.

AN/APR 1 Receiver, used with above tuning units. 110V 60 cycle.

Measurements 75 Standard Signal Generator, Calibrated output, 124 to 510 MC.

Rotary Joints, Coaxial, S Band.

Antenna, Coaxial, pressurized S Band. Can be used with parabolic reflector.

"S" Band Waveguide Components, Tuners, T's, Directional Couplers, Terminations, etc.

Microvolter—Ferris Model 10B + 10C.

Frequency Standard—James Knight Co. 1, 5 and 10 MC check points.

F.M. Test Set—X Band, with wavemeter and wattmeter, 110V 60 cycle AC.

Recording Ammeter—Esterline Angus 0-5MA.

Recording Ammeter—Esterline Angus 0-1MA.

TS-36—8.5 to 9.6 KMC Power Meter .1-1000 MW.

TS-338.7 to 9.5 KMC Frequency Meter and Video Detector.

K Band—slotted line, gear driven traveling probe.

K Band—Attenuator 27 to 34 KMC.

K Band—Misc. Waveguide + Waveguide components.

Dummy Loads.

TS-13/AP Consists of Signal Generator "Xa" Band, Wavemeter + wattmeter.

TS-14—Test Set for "SA" Band radar—uses 2C40 oscillator, self-contained, power monitor, self-pulsed 115V 60-800 cycles.

Impedance Bridge—Type TBX-1BR 8.5 to 9.6 KMC—CRT Indicator.

Audio Signal Generator—Hewlett Packard 205A 10-20,000 cycles.

HIGH POWERED DUMMY LOADS

X Band, 1¼" x ½" guide, choke or plain flange, dissipates 350 watts average power continuously in still air. VSWR less than 1.15 between 7 and 10 KMC, weight 3¼ pounds.

X Band, ½" x 1" guide, choke flange, dissipates 250 watts average power continuously in still air, VSWR less than 1.15 between 8.2x12.4 KMC, weight 3¼ pounds.

X Band 1¼" x ¼" guide, plain flange, dissipates 200 watts average power continuously in still air, VSWR less than 1.15 between 7-10 KMC, weight 3¼ pounds.

X Band, 1¼" x ¼" guide, plain flange, dissipates 250 watts average power continuously in still air, weight 2 pounds 4 ounces.

S Band, 1½" x 3" guide dissipates 1,500 average power in still air, VSWR less than 1.15 between 2.5 to 3.7 KMC, choke flange, weight 13 pounds.

NIBUR SALES CORPORATION

P. O. Box 811 — Red Bank, New Jersey

Telephone: Red Bank 6-5810

OVER 250,000 TYPE J POTENTIOMETERS

55¢ EACH

(To Quantity Buyers)

75¢ in Smaller Quantities

10¢ Extra for Locking Bushing

Ohms	Shaft	Bushing	Ohms	Shaft	Bushing
50	¼S	½L	20K	¼F	¼
60	¾F	¼	20K	¼R	¼
60	¼R	¾	20K	¼S	½L
75	¼R	¾	25K	2¼F	¼
100	¼S	½L	25K	¼S	¾
100	2¼F	¾	25K	¼R	¼
200	¼S	½L	25K	2¼F	¾
100	¼S	½L	30K	¼F	¼
500	¼S	¾	50K	¼S	¾
500	¼R	¾	50K	¼S	¼
500	¼S	¾	50K	¼F	¼
1000	¼S	¾	50K	¼R	½L
1000	¼S	½L	50K	¼S	½L
1500	¼S	¾	50K	¼R	¼
1500	¼S	½L	50K	¼F	¾
1500	¼F	¼	50K	¼S	¾SW
2000	¼F	¼	60K	¼S	½
2000	¼S	¼	60K	¼S	½L
2500	¼S	½L	70K	¼S	¾
2500	¼S	¼	100K	¼R	¼
2500	¼F	¼	100K	¼F	¼
2500	1S	¾	100K	¼R	¾
5000	¼F	¼	100K	¼S	½L
5000	¼S	¾	100K	2¼R	¾
5000	¼S	½L	150K	¼S	½L
5000	¼R	¾	150K	1S	¾
6500	¼S	¾	150K	¼R	¾
7500	1S	¾	200K	¼F	½L
10K	¼R	¼	200K	¼R	¾
10K	¼S	¼	200K	¼R	¾
10K	¼R	½	200K	¼S	¼
10K	¼R	¾	250K	¼S	½L
10K	¼S	½L	250K	¼S	¾
10K	¼R	¾	250K	¼S	½L
10K	¼S	¼	250K	2¼F	¾
10K	¼F	¾	500K	¼S	¾
10K	¼F	¼	500K	¼S	¾
10K	½R	¾	500K	2¼F	¾
10K	2¼R	¾	500K	2¼R	¾
10K	2¼F	¾	1 Meg	¼S	¼
15K	¼S	¼	1 Meg	¼S	¾
15K	½S	¾	1 Meg	¼S	½L
20K	1¼R	¾	1 Meg	2¼R	¾
20K	¼S	¼	1 Meg	½S	¾
20K	¾R	¾	4 Meg	¾R	¾
20K	½R	¾	5 Meg	2½F	¾

TYPE "JJ"—$1.25 EA.

($1.50 in Small Quantities)

Ohms	Shaft	Bush	Ohms	Shaft	Bush
250-250	2¼R	¾	25K-25K	2¼F	¼
500-500	½S	½L	25K-10K	2¼F	¼
600-600	¼R	¼	35K-35K	¼S	½L
1K-1K	2¼R	¾	50K-50K	¼S	¾
2K-30K	¼F	¾	100K-100K	2¼R	¾
5K-3K	¼S	¼	150K-150K	½S	½L
5K-500	¼F	¼	175K-225K	¼R	¾
5K-500	½S	½L	250K-250K	¾S	¼
10K-10K	2¼R	¾	250K-250K	¼R	¾
15K-15K	½S	½L	250K-250K	2¼R	¾
20K-350K	¼F	¾	300K-300K	½S	½L
20K-800K	½R	¼	500K-500K	2¼R	¾

OVER 100,000 ELECTROLYTICS BATHTUB TYPE

10¢ EACH

(To Quantity Buyers)

MFD	Volt.	Style Terminals	MFD	Volt.	Style Terminals
10/10/30			50	25	Side*
/30	25	Side	50	25	Side
12/12	50	Side	50	25	Top*
16/16/16	250	Side	50	40	Side
20	50	Side	50	50	Side
20	350	Side	100	25	Side
25	50	Side*	100	50	Top
25	50	Top*	200/200	9	Side
25	250	Bottom	* can common		

SPECIAL

10 MFD—220 VAC

85¢ EACH

Largest Stock of Oil Filled Condensers in the East in Bathtub, Rectangular and Round Types. Send Us Your Requirements.

Industrial Assembly Corp.

46 Howard St., New York 13, N. Y.

Phone CAnal 6-3474

CONDENSERS

. . . CONDENSER SPECIALS . . .

6 mfd—600 V $1.49
Top Quality—Qua. disc.

6 mfd—150 V . . . . . $.35
Three term. dual 3mfd. oil cond. complete with brackets, measuring 4¼"x 1¾"x1". Ideal for audio crossover networks.

3 x .1 mfd—600 V . . . . $.22
Avox #618 Channel, 3 Terms, bot. mntg.

1 mfd—600 V . . . . . $.59
Top Term. Bathtub. Lots of 100 10% disc.

OVER 16,000 SOLD

10 mfd—600 V . . . . . $.98
Three term. bot. mtg. channel type. Dims. 3¼"x2⅛"x2". Two 5 mfd. sections rated 400 V at 72 deg "C". 1500-V test. Meets commercial specs. for 600 V operation up to 40 degs "C". Ideal for filter or power factor application. Repeat sales prove this rugged high-quality condenser to be of outstanding value. Carton of 24, weight 42 lbs. Large qua. available **$.89**

16 mfd—600 V $1.89
Dual 8 mfds. hermetically sealed and packed. Tobe type PT-SC-11 measuring 3⅝"x2⅛"x2⅛". Stud mntg centers 2". Plugs into standard four prong socket.

12 mfd—450 V . . . . . $.69
Rectangular case—Electrolytic

4 mfd—600 V $1.10
Dual 2mfd section; 4 glassseal term. Standard dimensions.

5 mfd—1000 V $1.99

.5 mfd—400 V . . . . . $.20
Avox #616MCT, 100 10%, 500 25%

Mfd	Volts	Price
.0018	15KV	$8.75
.005-.005-		
.01	10KV	4.75
.013	25KV	22.50
.02	10KV	4.50
.02	20KV	17.50
.025-.025-		
	6KV	15.00
.05	10KV	15.98
.035	10KV	12.98
.05	6KV	3.50
.05	7500V	2.95
.05	12.5KV	15.95
.1	1500V	.59
.1	2500V	1.39
.1	3000V	1.49
.1	5000V	1.95
.1	7500V	1.75
.1	10KV	12.98
.1	12KV	14.98
.1	15KV	17.98
.1	18KV	19.98
.1	25KV	P.U.R.
.1-.1	7500V	2.50
.1-.1-.1	6000V	1.95
.2	10KV	19.98
.2	15KV	17.98
.25	2000V	1.15
.25	3000V	2.95
.25	6000V	1.98
.25	15KV	15.95
.25	20KV	19.98
.25	30KV	24.98
.25	2000V	1.45
.4	10KV	19.98
.4	15KV	24.98
.5	2000V	1.45
.5	2500V	2.98
.5	3000V	2.98
.5	4000V	3.15
.5	5000V	4.15
.5	7500V	4.15
.5-.1	600V	.89
.5-.5	600V	.89
.5-.5	1000V	.98
	2KV	15.00
1	400V	.46
1	600V	.59
1	1000V	1.15
1	1500V	1.35
1	2000V	1.98
1	2500V	2.98
1	3000V	3.50
1	4000V	3.98
1	5000V	4.98
1	6000V	5.98
1	7500V	12.98
1	10KV	P.U.R.
1	15KV	P.U.R.
1	18KV	P.U.R.
1	20KV	P.U.R.
1	30KV	P.U.R.
2	600V	.89-.79
2	1000V	.98
2	1000V	TLA1.29
2	1500V	1.49
2	2000V	2.98
2	2500V	3.95
2	3000V	4.98
2	4000V	5.98
2	5000V	8.98
2	6000V	9.98
2	7500V	12.98
2	10KV	P.U.R.
2	15KV	P.U.R.
2	18KV	P.U.R.
2	20KV	P.U.R.
2	30KV	P.U.R.
2	600V	.89-.79
2	1000V	.98
2	1000V	TLA1.29
2	1500V	1.49
2	2000V	2.98

TYPE "G" MICA CAPACITORS

Mfd.	Volts	Price
.00005	10KV	$24.95
.00005*	40KV	89.50
.0001	10KV	16.95
.0001	20KV	33.50
.0001	30KV	55.50
.0001	40KV	89.50
.0001S	10KV	19.95
.0002	5KV	16.00
.0002	10KV	23.95
.0002	20KV	38.95
.0002*	25KV	49.25
.0002	30KV	67.50
.0003	5KV	6.00
.00034	10KV	24.95
.00036	10KV	22.95
.0004	10KV	25.95
.0004	20KV	44.50
.00042	20KV	44.50
.00035	20KV	32.50
.00035	25KV	55.50
.0004	30KV	49.50
.0005	5KV	6.00
.0006	10KV	24.95
.0007	25KV	47.75
.0008	20KV	36.75

*Faradon

TRANS. MICA CONDS.

Mfd	Wvde	Price
.000024	2500	$.23
.00003	2000	.65
.00047	2000	.29
.00047	2500	.32
.0005	1200	.12
.0005	2500	.32
.0008	1250	.29
.0009	2500	.29
.001	600	.22
.001	1000	.25
.001	1500	.33
.001	2000	.39
.001	2500	.45
.0015	5000	1.95
.002	600	.25
.002	1250	.29
.0025	1000	2.95
.0027	2500	.41
.0033	2500	.41
.003	600	.28
.0031	1500	.32
.0033	2500	.45
.004	4500	1.25
.0047	4000	2.25
.0047	5000	2.25
.005	600	.27
.005	1200	.49
.005	2500	.49

Mfd	Volts	Price
.0053	30KV	$6.95
.001	20KV	32.50
.001	25KV	49.50
.0012	15KV	32.50
.002	5KV	5.25
.002	20KV	49.50
.0024	25KV	79.00
.0025	12KV	29.00
.0025	15KV	29.00
.0025	20KV	59.50
.0025	25KV	79.00
.0025	30KV	5.95
.002	10KV	32.25
.0033	20KV	59.50
.0033	25KV	85.00
.00475	10KV	35.00
.01*	15KV	85.00
.01	20KV	89.50
.011	4KV	9.25
.0225	3KV	33.75
.045	1KV	14.95
.05	1500V	8.95
.05	1600V	8.95
.1	15KV	89.50

*Type Terms.

CHANNEL COND.

Mfd	Wvde	Price
.025	600	.16
.05	1000*	.22
2x.05	600	.25
.1	300	.18
.1	600	.21
.1	1000	.28
.1	2500	1.25
2x.1	600	.49
2x.1	1000	.59
2x.1	400	.49
2x.1	600	.49
2x.1	1000	.62
.25	400V	.39
.25	600V	.39
.25	600	.48
.25	1000*	.48

Mfd	Wvde	Price
.4	600	.36
.5	400*	.21
.5	600*	.31
.5	600	.49
.5	1000	.59
.5	600	.39
.5	1000*	.49
.5-.1	600	.39
1	400	.39
1	600	.58
1	1000*	.79
1	600	.62

*Top Terms.

METAL TUBULAR OIL CONDS.

Mfd	Wvde	Price
.0025	600	$.18
.005	600	.14
.01	300	.08
.01	600	.15
.01	2000	.19
.02	400	.14
.03	400	.14
.05	200	.07

Mfd	Wvde	Price
.05	600V	.16
.05	1000V	.19
.1	400V	.17
.1	600V	.20
.25	600V	.18
.5	600V	.19

Quans. of 100, 10% disc.

MICA CONDENSERS

5, 6, 8, 10, 15, 25, 30, 34, 39, 50, 70, 75, 100, 140, 150, 185, 200, 230, 240, 250, 300, 350, 390, 400, 470, 500, 510, 600, 650, 700, 750, 1000, 1200, 1250, 1400, 1500, 2000, 2200, 2400, 3000, 3300, 3700, 3900, 4000, 4700, 5000, 5100, 6000, 6200, 6500, 7900, 7950, 7960, 8000, 9100 & 10,000 mmfd.

PRICE SCHEDULE

5 to 750 mmfd . . . . . 5¢
1000 to 1500 mmfd . . . . . 6¢
2000 to 5100 mmfd . . . . . 10¢
9100 to 10000 mmfd . . . . . 26¢

Special Mica Kit—100 @ $3.50

SILVER MICA CONDENSERS

7, 24, 25, 33, 50, 60, 75, 95, 100, 120, 150, 170, 200, 270, 300, 320, 390, 400, 450, 500, 750, 800, 1000, 1400, 1450, 1700, & 2800 mmfd.

7 to 95 mmfd . . . . . 8¢
1000 to 1700 mmfd . . . . . 14¢
100 to 800 mmfd . . . . . 9¢
2500 mmfd . . . . . 16¢

Special S. Mica Kit—100 @ $6.50

BATHTUB CONDS.

Mfd	Volts	Price
.01-.01	600	$.25
.02-.02	600	.28
.04-.04	600	.28
.05	600	.28
.05-.05	600	.28
.05-.05	1000	.44
.06-.06	600	.38
.1	600	.39
.1	1000	.42
.1	1200	.48
.1-.1	600	.39
.1-.1	600	.39
.1-.1	1000	.48
2x.1	600	.49
.2	1000	.21
.25	600	.28
.25	400	.28
.25	600	.41

Mfd	Volts	Price
.25-.25	600	.48
3x.25	600	.48
.25	1000	.48
.3	400	.38
.3	600	.48
.5	600	.47
.5	1000	.62
2x.5	600	.58
2x.5	600	.58
.5	1000	.62
1	200	.38
1	400	.48
1	600	.58
1-1	600	.58
2	400	.48
4	100	.48

Sq. Bathtub Kit 15 @ 1.50

Available in Other Sizes

—TRANSTAT—

115 V, 1 phase, 100 amps., Kva. 115, Range 0-115 V Amertran #29145. Specially priced.

DIESEL GEN.

25 KW 3 phase 60 cy. Hill diesel, G.E. gen. Complete with control panel & starting batteries. Ready for immediate operation. Guaranteed, P.U.R.

TYPE "J" POTS $.89

OHMS	SHAFT	OHMS	SHAFT
50	1/8 S	25000	1/8 & 1/8 S
65	1/8 LS	30000	1/8 S
150	1/4 S	40000	1/8 LS
500	3/8 S	50000	1/4 & 1/8 S
500	3/8 & 1/8 S	50000	1/8 LS
1000	1/8 S	100000	1/2"
1500	1/4 S	150000	2 1/2
2000	1/8 LS & 3/8 S	200000	1/8 LS
2500	1/8 S	250000	1/8 LS, 9/16 & 1/8 S
3000	1/8 LS	300000	1/8 S (2 terms)
5000	1/4	1 Meg.	1/8 S & 1/4 LS
10000	1/8 LS & 3/8	Other Types Available	
10000	3/8 & 1 1/2		
15000	1/8 S		
50000	1 1/4 & 1/8 LS		

—WANTED—

Condensers of all Types in any quantity. Also other standard components.

Write ART HANKINS, Owner

MONMOUTH RADIO LABORATORIES

BOX 159 Long Branch 6-5192 OAKHURST, N. J.

MAGNETRONS KLYSTRONS
New JAN Boxed

2J27	Ray	$17.95
2J32	"	27.80
2J33	"	23.95
2J34	"	24.95
2J61	"	24.00
2J48	"	24.50
2J31	"	79.00
QK59	"	85.00
QK62	"	85.00
417A	—	7.75
715B	"	9.95
725A	"	7.49
724B	"	3.89

2C51 (396A) w.o. $4.75

1N21 xtal diode checked Gtd. 69¢

Cycle Inverter — Soundscriber — 115?/any freq./ Brand new in orig. pkg. $12.00
Selenium Rectifiers—2-½ A bridges back to back—in 12 vac out 6v DC-150 MA. 20
Sockets all types 4-5-6-7-8 Prg. Ceramic, Bake, Mica.

CONDENSERS

.5 400v ST. BT. 32¢
.1 300v TT. BT. 15¢
.02 1500v TT. BT. 20¢
.1 1000 Pigtail . . . . . 15¢
oil . . . . . 35¢
.001 600 Pigtail . . . . . 8¢
oil imp. . . 8¢
Resisters
Standard Brands
20 % off
current prices
Mica Cond.
Rec. and
xmtr. types
low prices

Handset T511 like new $5.75
Telechron motor 1 RPM 110V 60 cy 1.95
Hayden Motors ½ to 5 RPM many types 110V, 220V etc. from 1.98
ARB Receiver compl. 39.95
R9B/APN4 L.N. 25.00
APR4 Butterfly Cond. Approx. 485 Mc. 12.95
Parts available: ARC1, ARC5, ARC1, BC348 BC312, BC191, SCR 284, APN4, 522, 433, ARN7, ART13, etc.

TELEPHONE RECTOR 2-1591

TELECTRAD 148 CHAMBERS ST. NEW YORK, 7, N. Y.



AN/APR-4 LABORATORY RECEIVERS

Complete with all five Tuning Units, covering the range 38 to 4,000 Mc.; wideband discone and other antennas, wavetraps, mobile accessories, 100 page technical manual, etc. Versatile, accurate, compact—the aristocrat of lab receivers in this range. Write for data sheet and quotations.

We have a large variety of other hard-to-get equipment, including microwave, aircraft, communications, radar; and laboratory electronics of all kinds. Quality standards maintained. Get our quotations!

We will buy any Electronic Material at top prices. SCHOOLS—unload your dusty surplus for cash or credit.

ENGINEERING ASSOCIATES

434 PATTERSON ROAD DAYTON 9, OHIO

$2.95 EACH OR 2 FOR $5.00!

Genuine Telephone Company Upright telephone complete with cord in Tested and Guaranteed condition. For inter-communication or extension. Complete line of telephones and parts. Inter-communication systems, switchboards, handsets, magneto and dial telephones, etc. Write for free list. C.O.D. orders accepted. All shipments F.O.B.

TELEPHONE ENGINEERING CO.
Dept. 22. Simpson, Pa.

HIGH FREQUENCY EQUIPMENT
BRAND NEW!

Ballantine MG set, 1KVA, 1-ph., 400-cy. alternator, 115V, self-excited; belt-driven by 2HP motor, 220V, 3-ph., 60-cy. With voltage regulator & variable speed sheave $300.00
MG sets of many sizes and frequencies in stock for immediate delivery. Your inquiries are invited.

EDWARD WOLF COMPANY
P. O. Box 82 Mattapan, 26, Mass.
BLuehills 8-1254

CARRIER EQUIPMENT

Western Electric CF-1A 4-channel carrier telephone terminals.
EE-101-A 2-channel 1000/20 cycle carrier ringers.
CFD-B 4-channel carrier pilot regulated telephone terminals complete with four channels 1000/20 cycle ringing.
CFD-B 4-channel pilot regulated telephone repeaters.
C-42-A V. F. telegraph in from 2- to 12-channel terminals.
FMC 1 or 2 channels carrier telephone terminals, automatic regulation, duplex signaling each channel. Carrier frequencies above 35 KC. Ideal for adding channels above type "O".
Complete engineering and installation services offered.

RAILWAY COMMUNICATIONS, INC.
Raytown, Missouri
Telephone: FLeming 2121

TYPE G MICA CONDENSERS

MFD	Voltage	Type	Price
.06	1 KV	G-1	$12.50
.09	1.5 KV	G-1	16.30
.08	1.5 KV	G-1	16.30
.0005	3 KV	UC-2509K	13.75
.02	3 KV	G-1	19.50
.0066	5 KV	C-D45276	14.50
.0015	5 KV	CRV-48416	15.50
.006	5 KV	CRV-48415	15.50
.00025	6 KV	PL-586-59	15.50
.00024	6 KV	G-1	15.50
.0008	6 KV	G-1	16.40
.0004	6 KV	G-1	16.25
.0002	6 KV	1958-287	16.50
.004	6 KV	G-1	19.50
.005	6 KV	G-1	17.50
.0012	7 KV	CRV-48157	15.00
.005	7 KV	UC-3048	17.50
.002	8 KV	UC-2372	27.50
.000375	10 KV	CRV-48418	28.50
.000048	10 KV	MX-61	28.50
.00057	10 KV	CD-38897-2	28.50
.00025	10 KV	CRV-48156	28.50
.00015	10 KV	UC-3123	26.50
.00062	10 KV	UC-3292	25.50
.0015	10 KV	CRV-48417	28.50
.0008	10 KV	UC-2617	28.50
.0002	10 KV	48278-B5	28.50
.001	10 KV	UC-3296	28.50
.02	10 KV	PL-113-52	27.50
.0025	12 KV	XPXW	27.50
.006	12 KV	G-4	62.40
.00125	15 KV	1958-218	140.40
.00062	15 KV	MX-69	69.50
.002	15 KV	G-3	52.90
.0025	15 KV	1976-218	54.10
.01	15 KV	1946-225	92.50
.00125	20 KV	PL-280-51	62.40
.00125	20 KV	G-3	52.40
.0015	20 KV	1976-404	53.50
.0050	20 KV	PL-1391-978	59.50
.0008	20 KV	G-3	54.70
.0002	20 KV	UC-3112K	54.70
.0002	20 KV	G-3	52.50
.0001	20 KV	G-3	49.50
.004	20 KV	G-3	99.50
.0025	25 KV	G-4	280.80
.002	30 KV	1946-217	210.60
.0006	35 KV	G-4	210.60
.002	35 KV	1946-214	225.00
.001	75 KV	PL-49-728	360.00

MICA CONDENSERS

TYPE 4

MFD	VDC	Price
.00005	1200	$ .60
.0022	1200	.60
.022	600	1.40
.022	600	1.35
.004	1200	.60
.001	600	.60
.01	600	.60
.01	1200	1.35
.01	1200	1.35
.05	2500	2.25

TYPE 9

MFD	VDC	Price
.0005	1200	$ .60
.001	2500	1.00
.005	2500	1.00
.005	2500	1.00
.01	2500	1.00
.01	2500	2.00

TYPE F MICA

MFD	VDC	Price
.00025	1000	$4.00
.00025	5000	4.00
.0005	5000	4.00
.0005	5000	4.00
.001	5000	4.00
.001	5000	4.00
.01	5000	4.00

TYPE E

MFD	VDC	Price
.00025	5000	$7.50
.001	5000	10.25

FILAMENT TRANSFORMER — AMERICAN TRANSFORMER CO. — TYPE EF8:
Primary: 210/240 volts, 60 cycles. Secondary: 5 volts @ 10 amps. Johnson socket. 125-211—60 watt. Height 12" $14.95

SPECIAL
PRECISION RESISTOR
Wire Wound
IRC TYPE WWI
3 Meg. 1W 1%
Quantities Available
4.00 ea.

POWER UNIT PE 143 G

28.5 VOLTS DC
175 AMPS 5 KW
MFG BY ONAN
TRAILER MOUNTED, COMPLETE WITH BATTERY AND LEADS
LIKE NEW
1200.00

PULSE NETWORKS

SPRAGUE:

6-A8-1/4-2000-50M
8-A1-.25-2000-50P
8-A1-.5-2000-50P
8-A1-1-2000-50P
10-E3-.5-2000-50P
10-E3-1-400-50P
10-E3-1/4-400-50P (Vitamin "C")
10-E3-1-400-50P
12-E4-1-400-50P
12-E3-.5-2000-50P
12-E3-1-800-50P
25-E3-4-120-50P

K BAND CAVITY — TKF-78W:
Gear Tuning, calibrated range 23400 — 24500 MCS. Panel mounting $47.50

PULSE TRANSFORMERS

UTAH:

9280	9295	9348
9281	9296	9349
9282	9297-D	X 121 T2
9283	9298	X 134 T1
9284	9299	X 143 T1
9285	9310	X 146 T1

RAYTHEON:

UX 7287	UX 7351 A	UX 10864
UX 7288	UX 10862	U 12520

WESTINGHOUSE:

1P1	1132 AW	148 EW2
1P2	1132 BW	148 EWP
1P4	1132 BW2	166 AW
1P6	1132 DW	176 AW
1P12	1133 AW	487 CW2
1P24	1133 EW	
1P25	148 EW	

GENERAL ELECTRIC:

6BQ627	6BQ834	8BQ26
6BQ666	6BQ875	8BQ625
6BQ7GTB1	6BQ913	
6BQ813	6BQ918	

FREED:

#22647	K 2470	K 353 866-D2
	K 2721A	BX 17-17
K 2440	K 2728	7472467
K 2450	K 2748 A	

HIGH VOLTAGE CAPACITORS

MFD	VDC	Type*	Price
.0005	25 K	14F1103	$22.50
.0005	25 K	14F1222	22.50
.0005	25 K	10A20	25.50
.0005	25 K	10A25	25.50
.0005	25 K	Y-5005	1.25
.0005	600 K	P6705	1.25
.0005	10 K	D-6406	10.75
.005	10 K	877	10.75
.005	15 K	22F1218	10.75
.005	15 K	22F1220	10.75
.005	15 K	22F1228	10.75
.005	15 K	14F1618	5.50
.005	15 K	7630	7.50
.005	15 K	6020	7.50
.005	15 K	14F1715	92.50
.01	15 K	Vitamin "C"	27.50
.01	15 K	26F1201	27.50
.01	15 K	26F1202	27.50
.01	20 K	YR 2000A2 - 2	42.50

MFD	VDC	Type*	Price
.25	25 K	D-31201	$57.50
.25	25 K	14F127	72.50
.25	25 K	26F267	22.50
.5	25 K		22.50
.5	6.5 K		42.50
.5	10 K	LD	42.50
.5	10 K	14F1202	42.50
.5	25K	PC 21A5	22.50
.5/.5	25 K	LS	42.50
.5	10 K		42.50
1	7.5 K	26F213	22.50
1	10 K	14F1207	22.50
1	10 K	14F1307	42.50
1	15 K	26F213	42.50
1	15 K	14F63	42.50
1	15 K	YZ	92.50
1.25/1.25	7.5 K	26F260	22.50
2	7.5 K		27.50
2	32 K	45J663-Z50	210.00

PORTABLE SONAR
QBG

Portable U. S. Navy equipment for sonic, supersonic listening and echo ranging under water for locating submerged targets. Includes:

1 Ea. Driver-Receiver CFF-43043 with all tubes; including carrying case.
1 Ea. Power Supply case CVW-19041 less A & B batteries (standard type)
1 Ea. Projector, CFF-78187 and cables.
1 Ea. Set accessories.
1 Ea. Set spare parts and tubes in chest.
1 Ea. Instruction Manual.

ALL NEW AND COMPLETF

RADIO DIRECTION FINDER
DAE-1

Made by R.C.A. for U.S. Navy small craft. Frequency range 240 to 2000 Kcs. in three bands. Designed for 115 volts AC input. (Converters available for any voltage input, DC or AC.) Includes:

1 Ea. Radio Receiver CRM-46153 with tubes.
1 Ea. Loop assembly CRM-69074.
1 Ea. Set spare parts and tubes in chest.
1 Ea. Set accessories and cables.
1 Ea. Instruction Manual.

ALL NEW AND COMPLETE

Complete Stocks of Radiotelephones, Transmitters, Receivers, Communication Accessories and spare parts.

TWX NY-1-223

COMMUNICATION DEVICES COMPANY

2331 Twelfth Ave. — New York 27, N. Y.
Cable: Communidev — Tel: ADirondack 4-6174

NEW — AN/APR4 — USED
RECEIVERS

With following TUNING UNITS in stock..TN16 -17-18-54

We buy any electronic material at top prices!

Write for our new 1953 Catalog!

Shipments FOB warehouse. 20% Deposit on orders. Minimum order $5.00. Illinois residents, add regular sales tax to remittance. Prices subject to change without notice.

R W ELECTRONICS

Dept EL, 1712-14 S. Michigan Ave.
Chicago 16, Ill.
PHONE HArrison 7-9374

GOVERNMENT SURPLUS PUMPS!

Brand new Cenco Megavac Vacuum Pumps, Model 92010A, complete with connecting cord, hose assembly and attachment plug. Specially priced at $137.50 each, f.o.b. New York.

MEDICAL SALVAGE CO., Inc.
217 East 23rd St.
New York 10, N. Y. MUrray Hill 4-4267

HEAVY DUTY SWITCHES

H&H 4.P.D.T. Toggle Switch. 5 AMP. @ 250 Volt. 10 AMP. @ 125 Volt. Single ¾" hole mount. Ball handle.
Stock No. 6203A — Price Each $1.95

CUTLER HAMMER TYPE 8905K628
4 Pole D.T. Neutral Center Toggle Switch. Luminous Trip—Bat Handle. 2 Hole Mtg.
Stock No. 6291A — Price Each $1.95

FILAMENT TRANSFORMER
20 VOLTS TAPPED AT 14 VOLTS @ 20 AMPS. PRIMARY TAPPED IN 5 VOLT STEPS FROM 210 TO 240 VOLTS 50-60 CYCLE STANCOR #S10696. 4" x 5" x 5" HIGH.
Stock No. 6292A — Price Each $4.95

FILAMENT TRANSFORMER
PRIMARY: 107.5; 112.5; 117.5; 122.5; 215; 225; 235 and 245 Volts 50/60 cycle
SECONDARY: 6.3 Volts @ 6.3 AMPS and 6.3 Volts @ 3 AMPS. Ceramic bushings with solder lug terminals. Rated for continuous duty under Mil-T-27. Class "A" Grade 1 specs. Hermetically sealed case, 2¾" x 3½" x 3⅝" high.
Stock No. 6284A — Price Each $2.50

HIGH VOLTAGE TRANSFORMER
21,000 volt 100 MA. Half Wave oil filled. Maloney Electric Co.
Stock No. 5728A — Price Each $300.00

ARC—3 RELAYS
Large Quantities in Stock of These Popular Relays Manufactured by G.E. Send us your requirements.

THORDARSON AUDIO PASS FILTERS

Band pass 300 to 1200 cycles input 10000 ohms — Output 25000 Ohms Level 10DB
Stock No. T48300 — Price $5.50 ea.

THORDARSON BAND PASS FILTERS
600 ohms to 600 ohms 1700 cycles to 3300 cycles Attenuation 25 D B at 1400 cycles or 50 DC at 4800 cycles. Size 6" x 6⅝" x 5"
Stock No. 5897A — Price Each $8.00

FILTER REACTORS
4 Henry @ 1.75 Amps. Thordarson Tru-Fidelity. 15,000 Volt Test. 10 Ohms D.C.
Stock No. 6400A — Price Each $35.00

Swinging Choke. Thordarson Tru-Fidelity. 10-20 Henry @ 500 to 50 M.A. 7500 Volt Test. 55 Ohms D.C.
Stock No. 6401A — Price Each $20.00

PLATE TRANSFORMER
Thordarson Tru-Fidelity Plate Transformer. Primary 208-210-220-230-240 Volts 60 Cycle. Secondary 3310 V.C.T. @ .86 Amps. 10,000 Volt Insulation. Brand new—limited quantity.
Stock No. 6390A — Price Each $60.00

SENSITIVE RELAYS



MIDGET TYPE RELAYS
Automatic Electric Type R-45, 6500 ohm Coils. Normally open contacts except as noted.

Stock No.	Contacts	M. A.	Price Each
102152	S.P.S.T.	2.0	$1.25
102249	2.P.S.T.*	4.5	1.50
102264	3.P.S.T.	6.0	2.00

* 1 Norm. open-1 Norm. closed.

Same type and style as above, but has 24 V.A.C. coil. Intermittent duty. Will operate on 6 V.D.C. Continuous duty. Contacts: S.P.S.T.-N.O. and S.P.D.T.
Stock No. 102248A — Price Each $1.25

4 MFD.—1000 VOLT
Chicago Condenser Corp. Type 1327. 1¼" x 3⅝" x 3⅞" High Can. Solder Lug Terminals.
Stock No. 6449A — Price Each $2.25

304TL's EIMAC JAN 304TL's
INDIVIDUALLY BOXED $10.95

RESISTORS PRODUCTION QUANTITIES
In stock of late carbon and wire wound resistors. ½—10 watt sizes, savings 10—25%. Send us your requirements.

Open Accounts to rated or Acceptable reference accounts. Others pre-payment of 25% deposit with order, balance C.O.D. Price F.O.B. Chicago and subject to change without notice. Merchandise subject to prior sale.

RADIO SURPLUS CO.
DIVISION OF CAPITOL COMMODITIES CO., INC.

1229 W. Washington Blvd.
Chicago 7, Illinois
Phone: TAylor 9-3405

LOOKING FOR HARD-TO-FIND PARTS & EQUIPMENT?

Just a partial list of our present stock:

- BC-348 • BC-342 • ART-13
- ARC-3 • APN-9 • LM
- BC-221 • BC-611
- VARIOUS TEST EQUIPMENT

NEW EXPORT DIVISION FOR ALL FOREIGN ORDERS
Prompt attention to all inquiries—all languages

Attn: Schools, Labs, Hams!
WE PAY MORE
FOR RADIO PARTS & EQUIPMENT
Cash in on your surplus equipment—or we'll trade for something you really need. Write today!

Write for FREE Surplus Catalog.

HARJO SALES CO
4109 BURBANK BLVD.
P. O. Box 1187
Magnolia Park Station
BURBANK, CALIFORNIA
Cable: HARJO

TUBES! SMASHING LOW PRICES!

0C3/VR105	$ .99	3JP12	7.95	30SP	.48	707A	9.95
0D3/VR150	.85	4B22/EL5B	5.50	45SP	.45	721A	2.45
1A3	.78	4B25/EL6CF	5.50	53A	2.50	723AB	22.50
1A5GT	.62	EL/C5B	5.50	QK59	65.00	724A	2.55
1B22	1.95	EL/C6A	5.50	QK60	65.00	724B	2.95
1B24	9.10	4J36	145.00	QK61	65.00	725A	8.50
1B27	13.50	4J37	145.00	71A	.69	726A	13.50
1B32/532A	2.19	5BP1	4.69	QK72	1.25	801	.85
1N21	1.00	5D21	18.50	RK72/CRP72	1.00	803	3.95
1N22	1.19	5FP7	1.65	FG90	4.50	804	10.50
1N23	1.19	5JP2	19.50	100TH	10.50	805	3.95
1N27	1.65	6AC7	.89	VR105	.99	807	1.65
1P23	2.75	6AG7	.99	112A	.49	810	10.95
1R4	.59	6AJ5	1.25	VT127	2.10	811	2.85
1T4	.59	6AJ6	1.00	VR150	.85	813	8.95
2A3	.95	6B6G	.75	211/VT4C	1.25	814	2.79
2AP1	7.50	6C6	.74	227A	4.50	815	3.40
2B22	2.25	6C8G	.74	274B	2.95	816	1.25
2C33/RX233	2.75	6H6	.59	EL-302-S	1.50	826	1.25
2C40	14.50	6K7	.63	304TH	13.95	830B	2.65
2E22	2.25	6S7	.97	304TL	19.50	832	7.95
2J21	7.95	6SH7GT	.79	GL-316A	2.50	832A	9.50
2J21A	8.50	6SH7	.79	350A	4.50	838	3.50
2J22	9.50	7C4/1203A	.75	359A	1.50	866A	1.00
2J27	14.95	7E5/1201	.89	371B	2.95	872A	3.65
2J34	29.95	7E6	.55	388A	2.50	884	1.25
2J50	69.50	10Y	1.30	394A	3.50	902P1	5.50
2J55	84.50	12A6	.85	WL-417A	19.50	954	.45
2X2	.69	12C8	.79	GL434A	19.50	CK-1089	.75
2X2A	1.50	12J5GT	.52	GL-446A	2.50	957	.45
3A4	.79	12SF7	.59	464A	6.75	1616	1.25
3B7/1291	.62	12SJ7GT	.55	CK-501X	.69	1619	.75
3C23	9.50	14H7	.69	532A/1B32	2.25	1624	1.45
3C24/24G	1.95	14J7	.69	GL-603	49.95	1625	1.00
3DP1	3.50	15R	.75	WL-653B	69.00	1629	.79
3D6/1299	.62	C822	.95	ZP653	50.00	1655/65C7	.97
3EP1	4.50	RK25	3.69	705A	2.95	1846	95.00
3FP7	2.95	23D4	.65	706AB	19.50	2051	.95
3GP1	3.95	FG27A	6.50	706AY	57.50	8005	5.85
						8008	5.00
						9001	1.10
						9002	1.00
						9003	1.49
						9004	.65
						9006	.59

Box 11E — IT'S EASIER TO ORDER BY MAIL!

Free! *Better than ever! Save money and time with Radio Shack's new 1954 electronic parts mail-order catalog! 224 pages!*

RADIO SHACK
CORPORATION
167 Washington St., Boston 8, Mass.

Want more information? Use post card on last page.

SAVE ON **TUBES** BRAND NEW **TUBES** GUARANTEED **TUBES**

OA2	$0.95	2J42	$10.00	4J29	$49.50	5T4	1.50	VT-127A	2.75	KU676	2.75
OA3/VR75	1.10	2J48	24.50	4J30	199.50	C6L/5528	2.50	FG172	29.50	WL677	3.75
OB2	1.35	2J49	85.00	4J31	99.50	6AL5W	1.75	HF200	14.50	700/B/C/D	16.50
OB3/VR90	1.00	2J50	89.50	4J34	149.50	6AN5	2.50	204A	49.50	702A	2.75
OC3/VR105	1.00	2J51	35.50	4J41	99.50	6AN8	2.00	211/VT4C	.95	703A	4.75
OD3/VR150	.80	2J52	35.00	4J52	200.00	6AS6	2.30	217C	4.95	705A	1.50
1B22	2.00	2K22	19.95	4-125A	22.50	6AS7G	4.50	221A	1.95	706AY	39.50
1B23	6.50	2K25	22.95	4-250A	32.00	6BF7	2.00	RX233A	2.50	706BY	39.50
1B24	8.50	2K26	30.00								
1B26	2.30	2K28	32.00								
1B27	12.00	2K34	150.00								
1B32/832A	2.50	2K41	125.00								
1B35	20.50	2K45	110.00								
1B42	17.50	2K48	99.50								
1B61	9.50	3B23	4.95	4X150A	25.00	6BL8	48.50	250R	8.95	700GY	29.50
1N21B	2.50	3B24	4.75	4X500A	75.00	6BM8	48.50	250TH	16.50	700FY	39.50
1N22	1.25	3B26	1.50	C5B	7.50	6C21	19.95	250TL	15.00	700GY	39.50
1N23B	3.40	3B28	5.95	5AP1	4.50	6F4	3.95	FG253A	89.50	707A	7.50
1N34A	.70	3B29	12.50	5AP4	4.50	6J4	5.25	FG258A	149.50	707B	13.50
1N35	1.50	3B29	2.50	5BP1	4.50	6K4	3.00	274B	3.25	708A	3.95
1N38	1.50	3C22	72.50	5BP4	4.50	6SU7GTY	2.00	304TH	7.95	713A	.95
1N47	4.50	3C23	9.95	5CP1	7.50	6X5WGT	1.00	304TL	7.95	715A	6.70
1N64	.89	3C24/24G	1.50	5CP1A	14.50	7C23	69.50	307A/RK75	3.75	715B	8.00
1N65	2.75	3C27	3.75	5C22	37.50	12AY7	1.89	310A	3.95	715C	18.50
1N68A	1.25	3C33	9.95	5D21	18.50	12DP7	16.95	310B	12.95	717A	.90
1N69	.60			5FP7	1.95	12GP7	25.00	316A	1.25		
1N83/K63	2.39					12HP7	13.50	327A	4.50		
1N89	.60					15R	.88	331A	10.95		
1N79	2.40					FG17/5557	3.95	349A	8.50		
1P25	10.00					RX21	8.50	350B	5.95		
1Z2	1.75					FG32	12.95	368AS	6.00		
V6-2	9.80					35TG	5.95	371B	.75		
2AS15	4.25					RK47	4.95	374B	4.95		
2C21/1642	.60					EF50	.75	388A	1.49		
2C39	12.50					52HAPT	write	393A	5.95		
2C39A	14.50					FG57/5555	15.00	394A	3.95		
2C40	7.25					RK60/1841	2.25	417A	8.50		
2C42	19.95					RK65/5D23	29.50	434A	15.00		
2C43	14.95					RK72	.95	446A	1.19		
2C44	1.10	3C45	12.50	5FP14	16.50	RK73	1.20	446B	3.50	719A	24.50
2C46	19.95	3D22	18.95	5HP1	4.50	5ST	5.95	450TH	44.50	720AY	249.50
2C51	1.90	3E29	11.95	5HP4	4.50	7ST	5.95	450TL	44.50	720AY	249.50
2C52	1.95	3FP7	1.95	5JP1	22.50	7STL	5.95	451	3.95	720DY	349.50
2D21	1.25	3GP1	3.95	5JP2	19.95	83V	1.10	464A	10.95	721A	2.95
2D21W	2.40	3HP7	3.95	5JP4	22.50	FG95/5540	22.50	469	13.95	722A	1.95
2E22	2.75	3JP1	12.50	5JP5	27.50	VT98	19.95	527	11.50	723A	9.95
2E24	1.10	3K30	250.00	5JP7	39.50	98R	5.95	WL530	16.95	723A/B	16.95
2E26	1.25	4B24	6.95	5JP8	write	100TH	9.50	531	5.75	724B	2.75
2J21A	7.86	4C27/GV92	17.50	5J25	11.95	FG-104/5561	29.50	CK536AX	.95	725A	4.50
2J22	6.95	4C28	35.00	5J30	39.60	FG-105	19.00	559	1.19	726B	45.00
2J26	14.95	4C35	19.50	5J33	25.00	VU-111	.95	726C	49.50	726C	49.50
2J27	12.95	4E27	14.50	6NP1	5.95	HF120	9.95	575A	13.95	730A	29.00
2J31	25.00	4J22	129.50	6R4GY	1.25	F-123A	7.75	KU627	17.50	801A	.39
2J32	25.00	4J23	129.50								
2J33	25.00	4J26	129.50								
2J34	25.00	4J27	129.50								
2J36	89.00	4J28	129.50								

OUR SURPLUS PRINTED
Very High

803	3.75	K1003P7	write	1613	.89	1616	.98	1625	.39	1626	.39	1629	.39	1642	.69	1644	.89	2050	1.40	2051	1.10	5529	5.50	5586	175.00	5613	115.00	5637	4.00	5643	write	5646	8.95	5647	2.75	5654	1.75	5656	14.95	5657	299.00	5670	4.30	5772	1.29	5675	1.25	5687	3.75	5694	2.60	5702	2.95	5703	1.30	5704	2.50	5719	6.95	5719	6.95	5750	3.10	5787	6.00	5814	2.75	5844	4.50	5876	14.95	5902	8.95	5904	17.50	5905	17.50	5963	1.20	6005	4.50	6072	2.25	6121	9.95	8005	4.95	8012	1.95	8020	1.25	8025	4.75	8025A	4.75	9001	1.15	9002	.98	9003	1.15	9004	.69	9005	1.50	9006	.49
---	---	---	---	---	---	---	---	---	---	---	---

WANTED
ARC-1, 3, ART-13, BC-342, 348, APS-10, 15, TS-13, 35, 146, 147, 148, 174, 175, 263 ETC. All SCR, BC, AN, TS. ALL TUBES.

RADALAB

1964 Webster Ave., Bronx 57, N. Y.
TEL: WE 3-3232-3

TERMS—Minimum order $25.00 all prices FOB New York City. 25% deposit with order, balance COD. Rated firms open account. Prices subject to change without notice.

SCR-291A

1.5-30mc automatic direction finder. This equipment used to take bearings on transmitters within its freq. range. Complete equipments available comprising the following: BC-1147A Rec., PN 31, Power Panel, BC-1159, automatic bearing goniometer, RC-223 antennae system consisting of 5 masts with legs, MC-412, MC-413 phase inverters calibrating transmitter, cables, 115v 60 cyc gasoline generator. Complete equipment overhauled and guaranteed.....**POR**

AN/APN-3

Shoran navigation surveying and bombing equipment. Complete equipments consisting of: Ind. IND/17 with R-15 rec., T-11 transmitter, comparator CM-3. Computer K-1 available for bombing use. Racks, Plugs, etc. This equipment operates with AN/CPN-2 ground beacon stations operating freq. 290 mc. Accuracy of this equipment is 10 feet up to 300 miles. Shoran equipment is in wide use by oil and surveying companies thru out the world .....**POR**

DISTANCE MEASURING EQUIPMENT

AN/APN-2 and SCR-729 airborne DME equipment consisting of: Transmitter-receiver, cathode ray indicator, control box, plugs, etc. This equipment works in conjunction with either AN/TPN-2 long range airport beacon or AN/PPN-1 light weight portable paratroop beacon. Also provides left-right bearing indication to heme on ground beacons in addition to its distance measuring facilities. Range 100 miles in three ranges. Input 115v 400 cyc. .....**POR**

RC 184 & RC 188

High power ground IFF. This equipment is used with BC-966 and ADK airborne IFF equipment. The RC 184 is used with the SCR 584. The complete equipment is mounted in a 6 ft. rack containing transmitter-receiver, power supply, Cathode Ray monitor and distance indicator calibrated in yards, enabling the operator to determine the range to the aircraft carrying the IFF. Input 115v 60 cyc. **POR**

BM-1

Shipborne IFF used with ABK airborne IFF. Consists of transmitter-receiver, power supply, cathode ray monitor in a three ft. cabinet, very compact equipment. Input 115v 60 cyc. .....**POR**

VE REMOTE PPI INDICATOR

This is a remote PPI indicator "7 in." screen for use with any Radar for remote viewing. Contains all indicating circuits and is driven by the main Radar. Input 115v 60 cyc. **POR**

MOBILE RADIO SCR-508

10 Channel FM Receiver and Transmitter. Frequency Range 20-27.9mc. Receiver is manually tuned, transmitter is crystal controlled. Consists of 2 BC-603 Receivers, BC-604 Transmitter, FT-237 mount, Box 80 xtals BC-606 Control, A-62 Phantom Ant., Headsets, mike, and antenna. Input 12v DC. SCR-608 also avail. .....**POR**

SCR-522

Airborne Transceiver, Freq. 100-156 Mc. This unit is crystal controlled 4 channel. Power output approx. 10 watts. Consists of: BC-624 Receiver, BC-625 Transmitter, FT-244 mount, BC-602 control box, PE-94 dynamotor, antenna, plugs **$127.50**
12 volt installations available.....**POR**

BC 1268 145-600 mc in two bands, with power supply .....**POR**
AN/CRT-4 Sono-buoy used with AN/ARR-16 receiver. Rotates in water and sends magnetic bearing signals to receiver to locate submarines. .....**POR**
B-29 central fire control system. Electronic and optical computer and sighting head type P-4. This equipment is used to direct guns in the B-29 from a central station. Brand New. Mfg. Sperry.....**POR**
AN/APR-4 38-4000 mc precision receiver consists of receiver and five tuning units to cover the full range. Each tuning unit is calibrated directly in mc. Input 115v 60 cyc.....**POR**
AN/APA-11 Pulse Analyzer. Will measure and display on CR tube pulse rate, width, duration .....**POR**
BC-348R CAA and Military approved model. **POR**
AN/APT-5 300-1200 mc transmitter 30 watts output. **$189.50**
AN/APR-5 1000-3100 mc receiver
BC-639 100-156 mc
AN/APS-10 3cm airborne navigation Radar **POR**
AN/APS-15 3cm bombing Radar.....**POR**
AN/UPN-4 3cm portable Radar beacon. **POR**
AN/CRN-2 Portable ILS system.....**POR**
TS-250/APN CAA approved altimeter test set.
TS-13AP 3cm sig. generator
TS-146 3cm sig. generator.
TS-35 3cm sig. generator
TS-102 Range calibrator
TS-62 3cm echo box
TS-89 Voltage divider
TS-148 3cm spectrum analyzer
BC-221 Freq. meter

SPECIAL PURPOSE TUBES AVAILABLE. WRITE

SPECIAL PURPOSE TUBES

1B23	6.00	3C23	6.75	6BM6	52.50	HF-300	15.00	701A	4.50	829B	9.00
1B24	7.25	3B28	4.50	6C21	16.75	304TH	6.75	702A	2.00	832	6.50
1B32	1.50	3C24	1.00	6J4	4.75	304TL	5.00	705A	1.00	832A	7.50
1B35	8.00	3C31	2.50	7BP7	3.75	307A	3.50	706AY	35.00	833A	28.50
1B42	8.50	3DP1	3.00	9LP7	3.50	310A	3.00	706FY	35.00	836	3.00
2AP1	5.75	3EP1	4.00	12DP7	12.50	311A	3.25	706GY	35.00	837	1.00
2C40	6.25	3GP1	2.75	12GP7	15.50	313C	3.00	707A	4.00	838	3.00
2C43	10.50	3JP12	15.00	FG-17	3.00	316A	1.00	707B	9.50	846	100.00
2C44	1.00	3KP1	9.75	RX-21	7.50	323B	9.75	709A	2.75	849	18.50
2D21	1.00	4C27	12.75	RK-23	2.25	328A	4.25	715A	3.00	851	45.00
2E22	1.75	4E27	17.25	RK-62	2.00	329A	6.00	715B	4.00	860	2.25
2J22	5.25	4J34	112.50	RK-72	1.00	348A	6.50	715C	15.00	866A	1.00
2J26	13.50	4J35	150.00	RK-73	1.00	350A	5.00	719A	16.50	874	1.00
2J27	9.75	5BP1	3.50	F-128A	38.50	352A	7.50	721A	2.00	878	1.25
2J31	20.25	5BP4	3.50	F-129B	90.00	353A	3.25	723A/B	13.50	884	1.00
2J32	22.50	5C30	3.00	VT-158	38.75	354A	15.00	724A	1.75	869B	55.00
2J33	20.25	5CP1	4.25	FG-190	7.75	355A	15.00	724B	2.00	892R	262.00
2J34	18.75	5CP7	7.50	204A	28.75	375A	10.50	725A	4.25	923	1.00
2J36	75.00	5D21	12.00	F-207	100.00	393A	8.00	726A	8.75	927	1.00
2J38	10.25	5FP7	1.25	WL-218	28.75	394A	2.50	726B	40.00	CK-1006	1.50
2J50	18.50	5FP14	12.25	F-232CH	100.00	417A	7.50	726C	60.00	959	1.75
2J55	50.00	5HP1	3.25	249B	3.00	GL-434A	12.00	728CY	35.00	1603	4.50
2J56	112.50	5JP1	16.75	250R	6.00	446A	1.00	728DY	35.00	1614	1.50
2J61	30.00	5JP4	16.75	250TH	13.50	446B	3.00	728EY	35.00	1622	1.50
2K25	20.25	5JP11	16.75	250TL	8.50	450TL	37.50	728GY	35.00	1624	1.00
2K41	93.73	5J23	30.00	264C	3.00	GL-451	3.00	803	2.50	2050	1.25
3AP1	5.00	5J30	29.50	267B	7.00	464A	7.00	807	1.25	ZB-3200	125.00
3BP1	3.75	5J32	60.00	271A	6.50	527	8.75	808	1.50	GL-8002R	85.00
3B24	4.25	5LP1	13.00	274B	2.25	631-P1	3.75	814	2.50	8013	2.00
3B24W	6.75	5R4GY	1.00	276A	6.50	WL-530	14.50	815	4.50	8020	1.00
3B25	3.50	C6A	4.50	282A	10.25	700A	14.50	826	1.00	8025	3.00
3B26	2.75	6BL6	52.50	283A	3.25	700D	14.50	829A	6.75	PD8365	50.00

- *Receiving tube listings—upon request*
- *Usual terms apply*

western engineers

ELK GROVE, CALIFORNIA

GEORGE WHITING, OWNER

- *Unconditional guarantee extended*
- *Subject to prior disposition*

FOLLOW ARROW FOR
MILITARY ELECTRONICS

VHF CONTROL TOWER

Complete Transmitter-Receiver, Frequency Meter, Power Supply. All mounted on standard racks, 6 ft. high. Frequency range: 100-156 MC. 110/220 v. 60 CPS. Like new. Guaranteed. Write for complete literature.....P.U.R.

TRANSMITTER TA-2J-24

High powered crystal controlled, long-range transmitter. Frequency range: 300-600 Kc and 2.9-15 MC. Eight separate channels are provided. New. Send for complete literature P.U.R.

Radar

APR-4 New, Complete	APT-3	RC-234
	APT-4	RC-266
APR-5	Mark 16	RT34/APS12
APS-4 New, Complete	MD4/APM	T-45/APT-5
	MD5/APM5	TP-104-/APT-5
APS-6 New, Complete	MD22/UPN2	MD38/APQ13
	RC-1841FF	
APT-1	APT-2	BC-214

FOLLOW ARROW TO GET HIGHEST PRICES FOR YOUR NEW AND USED RADIO GEAR! What have you to sell? WRITE TODAY!

SOUND POWERED HANDSET R.C.A. MODEL MI-240

With mounting rack.....New $19.95 ea.

Sound Powered Head & Chest Set

RCA MI-2475 Head and Chest Set. Brand New For Work Requiring Free Use of Hands. Heavy Duty—Consists of Headset with 2 Phones and Chest Mike. Includes 20 Ft. Rubber Cord.....EACH $19.95

Test Equipment

Complete Line

DuMont 224-A Oscilloscope		TS127/U
1-77 Hickok Tube Checker		TS131
1-208 FM Signal Generator		TS-148/UP
RPC Model 644 Multimeter		TS-173/UR
Hewlett Packard 200-C		TS-174/UR
I-199	TS-23/APN	TS175/UR
BC-638	TS-24A	TS182/UP
BC-1255	TS-28/UPN	TS184A/AP
CWI-60ABJ	TS27/TSM	TS204/AP
1E-96	TS-33	TS-218
1-95	TS34/AP	TS251
1-96-A	TS-35/AP	TS323/UP
1-122	TS36/AP	I-146
1-130A	TS-45A	TS-268/U
1-139	APM-3	Boonton Mod. 78B Sig. Gen.
1-148	TS-59/APN	
1-213	TS61/AP	Boonton Type 102FSig. Gen.
1-222	TS80	
TS-3A/AP	TS92	LAD Sig. Gen.
TS19A/APN	TS100/AP	LAE-5
TS12/AP	TS-102	LAVOIE Freq Meter: 500-600 Mc.
TS-13 Spare Parts Kit	TS111/CP	
	TS-116/AP	
TS16/APN	TS126	TS-56A/AP
TS19/APQ		I-100 ADF Test

HEWLETT-PACKARD #205 Set

RECEIVERS—TRANSMITTERS

2-METER EQUIPMENT
R-28/ARC-5 Receiver
T-28/ARC-5 Transmitter
Excellent Cond. .....BOTH $74.50

ARC-1	PE-125AX	RTA/1B
ARC-3	R-9/APN-4	SCR-522
R-4/ARR-2	BC-783-D	TA3J-24
ID-6/APN-4	R-87/ARN	R-89/ARN
MP-10G	BC-788-A-AM-C	R-1/ARR-1
BC-640	BC-639	RM-25
RM-26	SCR-284	SCR-536
SCR-540	MN-26 Complete Installation	
SCR-561 Equip. Motorola Model Fstr-250		R-44/ARR-5

EE 8B phone amplifier

GOVERNMENTS, AIRLINES AND INDUSTRIALS!
Send for FREE Catalogue No. 112 for complete list of Military, Industrial and Aviation Electronics. WE HAVE THE LARGEST INVENTORY OF SUCH EQUIPMENT IN THE UNITED STATES.

ARROW SALES INC.
Cable Address: P. O. BOX 28781 N. HOLLYWOOD CALIF.
Office-Warehouse: 5240 VERNA AVENUE N. HOLLYWOOD CALIF.
Phone: 3-1810 • Stanley 7-6805 • Cable Address: ARROWSALES

TELEPHONE RELAYS

Large Stock of
CLARE, TYPES C D & E
COOKE, AUTOMATIC—ELECTRIC
ALL TYPES of COILS and PILE-UPS
Send Us Your Specs. for Our Quote

CLARE TYPE C STANDARD SIZE SENSITIVE TELEPHONE RELAYS

	Coil	Contacts	Will Close at	Price
1)	6500 ohms	1A	4 MA	$2.25 ea.
2)	6500 ohms	1C	2 MA	3.00 ea.
3)	6500 ohms	1B-1C	3.5 MA	2.75 ea.
4)	6500 ohms	2A	4 MA	3.00 ea.
5)	6500 ohms	2A	4 MA	2.50 ea.
6)	6500 ohms	1A-1B	4 MA	2.50 ea.
7)	6500 ohms	5A	5 MA	3.25 ea.

CLARE TYPE G HALF SIZE SENSITIVE TELEPHONE RELAYS

	Coil	Contacts	Will Close at	Price
1)	6500 ohms	2A	5 MA	$2.50 ea.
2)	5000 ohms	2A	4 MA	2.50 ea.
3)	5000 ohms	2B-1C	5 MA	2.50 ea.
4)	4850 ohms	1C	4 MA	2.50 ea.
5)	3000 ohms	1C	6 MA	2.50 ea.
6)	4850 ohms	1A	5 MA	2.50 ea.
7)	2300 ohms	(None) ACTUATOR		1.50 ea.

All above Relays may be used for continuous duty operation on 110V. D.C.

OTHER TYPE G TELEPHONE RELAYS

1)	1300 ohms	1A-1C	24 or 48V	$2.50 ea.

CONTACT SYMBOLS
A=Norm. Open B=Norm. Closed C=S.P.D.T.

G.E. Relays #CR2791-B109P36 Coil—10,000 ohms Contacts 1A, 1B Operates on 8 MA....Price $1.65
Signal Wheelock Relays #K89665 Coil—2,000 ohms Contacts-1A, 1B, 1C Oper. at 9 Ma Price—$2.75 ea.
Leach Relays Type 1025-SN-BF. Coil—24V. 425 ohms. Contacts—D.P.S.T. Norm. closed. Rated at 10 Amps.....Price—$1.50 ea.
FIVE Prong CR-2791 G.E. Plug In Relays.
1) C-103C25 2200 ohms SPDT 4.5 MA....$4.00 ea.
2) C-104B33 700 ohms SPDT 6 MA.....$3.00 ea.

CLARE TYPE A Tel. Relay. Coil—55 Volts AC 60 cy. Contacts—3PDT (3 form C) Price—$3.50 ea.

Clare SK-5032 (Hermetically Sealed) Plug-in Relays. Coil—30 ohms 6 volts Contacts—DPDT. Price—$4.00 ea.

SIGMA TYPE 5F SENSITIVE RELAYS. Has two 70 ohm coils. Contacts—SPDT...Price—$3.00 ea.

TYPE H TRANSMITTING MICA CONDENSERS

1)	.005 MFD	2500v.	DCW	$.45 ea.
2)	.01 MFD	1200v.	DCW	.45 ea.
3)	.001 MFD	1200v.	DCW	.35 ea.

Chase Electronic Supply Co.
105-07 225 St.
Queens Village, N. Y.
HOllis 4-5033

YOUR BEST SOURCE OF SUPPLY FOR JAN TYPE SPECIAL PURPOSE AND RECEIVING TUBES

2C39A—Machlett or Eimac	8.75
2C42—G.E.	7.50
2C46—G.E.	7.50
3DP1—G.E., R.C.A.	3.50
6C21—G.E., Westgh'e.	18.00
7BP7—G.E., R.C.A., N.U.	5.00
211/VT4C—G.E.	.49
FG235A—G.E.	69.50
282A—Western Electric	9.75
307A—Sylvania, KenRad	3.25
394A—Kuthe, W.E.	3.00
715B—Western Electric	7.50
715C—Western Electric	15.00
872A—JAN	3.15
Crystal Diodes	
1N23A—SYLV., W.E.	2.80
1N23B—SYLV., W.E.	2.75
1N26—SYLV., W.E.	7.80

ATTENTION PURCHASING AGENTS:
We are equipped to handle all of your Electronic Tube Needs. We invite your inquiries. Over one million tubes available. Attractive discounts to quantity buyers. Send for our listing. F.O.B. N.Y.C. Write, Phone or Wire.

ALLIED ELECTRONIC SALES
74 Cortlandt St. New York 7, N. Y.
Phone BARCLAY 7-5839—5840

T47A/ART-13 TRANSMITTERS
BC-610-E TRANSMITTERS
BC-312, BC-342, BC-348 RECVRS.
BC-221 & LM FREQUENCY METERS

ALLTRONICS
BOX 19, BOSTON 1, MASSACHUSETTS
Richmond 2-0918, LYnn 8-3100



WESTON 433
High Frequency A.C. Voltmeter Portable Laboratory Standard

Frequency Range from 25 to 2400 Cycles, for 0-150 Volts; Manufactured by Weston to an accuracy of ½ of 1% from 25 to 1000 cycles, and within 1¼% up to 2400 cycles.

The most commonly used ranges are 60 and 400 cycles and we have tested each one against Primary Standards and guarantee that these ranges are accurate within ½ of 1%.

Knife edge pointer; hand calibrated mirror scale; shielded iron vane movement; Resistance approx. 2800 ohms; scale length 4.04" in case 5" x 6" x 3¼". (Illus. to illust.)

BRAND NEW—SURPLUS—GUARANTEED
Only 59 In Stock
List Price Approx. $70.00
YOUR NET COST FOB NYC $45.00

MARITIME SWITCHBOARD
Instrument & Accessories
336 CANAL STREET, NEW YORK 13, N. Y.
WOrth 4-8216 (7)

RESISTORS*

- ALL MAKES
- ALL OHMAGES
- ALL TOLERANCES

½ WATT—1 WATT—2 WATT

AMERICA'S BEST

EB ½ W	10%	.03 each
GB 1 W	10%	.06 each
HB 2 W	10%	.09 each

For 5% add 100%
Minimum per Item — $2.00
Minimum per Order — $10.00

LEGRI S COMPANY
158 West 99 Street, New York, N. Y.

RADIO - RADAR - INSTRUMENTS
AIRCRAFT - PHOTO EQUIPMENT

TEST EQUIPMENT

Complete Line

DuMont 224-A Oscilloscope
I-77 Hickok Tube Checker
I-208 FM Signal Generator
Hewlett Packard 200-C

I-198	TS16/APN	TS-118/AP
BC-638	TS23/APN	TS-126
BC-1255	TS-24A	TS-127/U
CWL-60ABJ	TS-28/UPN	TS-131
IE-36	TS27/TSM	TS-148/UP
I-95	TS-33	TS-170/ARN
I-96-A	TS34/AP	TS-173/UR
I-122	TS-35/AP	TS-174/UR
I-130A	TS36/AP	TS-175/UR
I-139	TS-45A	TS-182/UP
I-145	TS-59/APN	TS-184A/AP
I-121	TS61/AP	TS-204/AP
I-222	TS89	TS-218
TS-3A/AP	TS92	TS-251
TS10/APN	TS100/AP	TS-323/UP
TS12/AP	TS-102	I-146
TS-12 Spare Parts Kit	TS111/CP	TS-268/U

Boonton Mod. 78B Sig. Gen. — LAD Sig. Gen. LAE-2
Boonton Type 102C Sig. Gen. — LAVOIE Freq. Meter: 300-600 Mc.

RADIO AND RADAR

APR-4 New Complete	APS-3	RC-184IFF
APR-5	APS-6 New Complete	RC-214
APS-4 New Complete	APS-2 MARK 28	RC-224
		RC-266
RT34/APS13 T-85/APT-5		PP-104/APT-5 APS-6

BC433 G Radio Compass 32.50
AM-26/AIC Interphone Amp. 22.50
RT-19/ARC-4 Transceiver 35.00
APN-1 Absolute Altimeter 9.95
CBT-3 Gibson Girl, 2-Channel 75.00

MISCELLANEOUS

Tubes - Selsyn synchro motors - AN Cannon - British Coaxial fittings, plugs

GOVERNMENTS - AIRLINES
Send for FREE catalogues on

- Communication Equipment ☐
- Inverters - Dynamotors ☐
- Radio-Radar Test Equip. ☐
- Aerial Photographic Equip. ☐

EQUIPMENT WANTED

Semler Industries, Inc.

6853 Lankershim Blvd., North Hollywood, Calif.

MOTORS:

24 VDC REVERSIBLE

MOTOR — 3.7 RPM, 40 lb. Torque Motor Size: 5-¼" x 4-1/32" x 3-5/16". Shaft size: 21/32" x 5/16". Also operates 24 VAC. Philco No. 441-1002 ..... $5.95

27.5 VDC — 6000 RPM, 1.5 oz. in. Shaft Size: 1-¼" x ¼". Motor Size: 2-⅛" x 1-⅛". No. 5069-207 ..... $6.95

27 VDC—1-10 HP—3500 RPM. Shaft Size: ⅝" x ¼". Motor Size: 4" x 3-¼". Air Assoc. No. EE-763. $6.95

80 VDC—1/50 HP—3000 RPM. Shaft Size: ⅝" x ¼". Motor Size: 5" x 3". G.E. No. 5 PN38HA10. ... $8.95

28.5 VDC—1/35 HP—2300 RPM. Shaft Size: 1-⅛" x ⅛". Motor Size: 4-⅛" x 3-⅝". Electrolux No. 16876 ..... $5.95

2800 RPM Reversible Motor—Size: 5-¼" x 3-⅛". Shaft Size: 1" x ¼". Emerson No. 184-0412. Price $6.95

GEAR HEAD for above motor. Ball Bearing Geared Shaft, 10 to 1 reduction. Price $5.95

COMBINATION: Motor & Reduction Gear $10.00

24 VAC OPEN FRAME—30 RPM Double Shaft Back Gear Motor with Disengage Clutch. Shaft size: 1-½" x 3/16" ..... Price: $6.95

24 VAC OPEN FRAME—3 RPM Back Gear Motor. Shaft size: ⅝" x 3/16" ..... Price: $5.95

24 VDC REVERSIBLE—5000 RPM with Magnetic Brake. Flange Mount Spline Shaft—size: ⅝" x 3/16". Motor: 4" L. x 2-½" Dia. GE Motor only #5BA25AJ32A ..... Price: $6.95

24 VDC AIRWAY MOTOR — Model #Z-350. Approx. 5000 RPM. Motor size: 2-¼" x 1-⅝". Shaft size: ⅛" x ⅛" ..... Price: $4.95

26 VOLT 60 CYCLE—60 RPM Synchronous Cramer Motor #1147. Shaft size: 1" x ⅛" $1.95

110 VDC 1/70 HP, 1550 RPM. Motor size: 4" x 3-⅛". Shaft size: 1" x 3/16". Redmond #187. $4.95

6 VDC 1/20 HP. 4000 RPM. Motor size: 5" x 3". Shaft size: ⅝" x ¼". Redmond #E-56. Price: $4.95

12 VDC 1/30 HP. 4300 RPM. Motor size: 3" x 3-⅛". Shaft size: 1" x 3/16", Delco #5047530 ..... $4.95

A.C. INDUCTION MOTOR

115 VOLTS 60 CYCLE 1.9 RPM: Torque On. in. 75; Watts—9; with variable Multiple Disc Cooler Wheel and Micro Switch mounted on Bracket Assy. Holtzer Cabot Motor Type HWC 2506—Price $24.95

BLOWERS



115 Volt 60 cycle BLOWER (pictured) — approx. 100 CFM Dia. 2¼" intake; 2" outlet. Quiet running Motor size: 2⅛"x3¼". NEW — not Gov't. surplus. Order No. 1C939 ... **$8.95**

DUAL BLOWER — Same as BN-520 above, except has blower assembly in each side of motor. Order No. 1C880 ..... $13.95

COMPACT TYPE — 108 CFM. motor built inside squirrel case, 4-¼" Intake: 3-⅝" x 2" Dia. Complete size: 4-¼" W. x 9-⅝" H. x 3-¼" D. Order No. 2C967 ..... $14.50

FLANGE TYPE—140 CFM. 3-¼" Intake: 3-½" Dia. Complete size: 8-¼" W. x 7-¼" H. x 6-¼" D. Order No. 1C807 ..... $12.95

FLANGE TWIN—275 CFM. 4-¼" Intake: 3-¼" x 2" Dia. Complete size: 11-¾" W. x 9-⅝" H. x 6-1/16" D. No. 2C069 ..... $21.95

COAXIAL CABLES:

RG-8/U (SPECIAL) 51.5 ohms. Same size as RG-8/U. Prices: 1 to 100 ft. @ 5¢ per ft.—100 to 500 ft. @ 7½¢ per ft.—500 to 1000 ft. @ 7¢ per ft.—1000 ft. rolls @ 6½¢ per ft.
RG-34/U—71 ohms, 145 ft. length $15.00

PE-103 DYNAMOTOR

With Filter Base and Cables, 6 or 12 VDC input; output 500 VDC 160 MA. .....NEW: $39.95—USED: $29.95

TRANSFORMERS—100V. 60 Cycle Pri.

6 VOLT CT-25A—10,000 V. Ins. OPEN FRAME—6" x 5" x 4-½" $7.95
Sec. Two 12 V. 4 A. Windings—gives 12 V. 8 A. or 24 V. 4 A. $8.95
Sec. 24 V. ½ A. ..... $1.50 Sec. 24 V. 1 A. $1.95
Sec. 24 Volt 2 Amps. $3.95
Sec. 6-24 or 30 Volts, 8 Amps. $8.95

FREE SURPLUS CATALOG

Just off the press—our brand new Catalog! Send for your FREE copy today! Mailed promptly on request!

LOOK AT THESE ITEMS WE HAVE IN STOCK! MANY, MANY MORE NOT LISTED WRITE US YOUR NEEDS—IMMEDIATE REPLY!

ANTENNAS:	DYNAMOTORS:	RADAR* RECEIVERS* TRANSMITTERS:	MISCELLANEOUS:
AN-104B	DM-31		RL-42B
A-104A	DM-35		MC-235
AN-109	DM-32	APS-3	HS-30
AN-117	DM-34	RT-5/APS-4	M-396
AN-138	DM-40	T-28/APT	M-359
AN-131	DM-41	T-39/APQ-9	BC-434A
AN-147	DM-42	AM-14/APT	BC-1366
AN-95	DM-43	AM-18/APT	BC-450
MS-49 to 56	DM-45	AM-33/APT	MC-476
AB-38-GR	PE-86	BC-645	FT-470
BC-173	PE-94	BC-946	WT-7A
AT1/APN-2	PE-103	BC-454	T-10A
AT2/APN-2	BD-77	BC-455	ME-57
AT37/APT	BD-87	BC-456	BC-347
AT38/APT	BD-93	RA-10DA	BC-709
AT42/APT	DY-23	RT-7/APN-1	BD-72
AT49/APR-4	DA1-A	AN/CRW-2	BD-116
AS27/ARN-5	MP-28BA	T-2/CRN-1	EE-65
AS61/ARN-5	MP-10G	MARK II	K-13
AS62/APR-2	PE-206	SCR-284	N-6A

ADDRESS DEPT E • All Prices Are F.O.B., Lima, Ohio • 25% Deposit on C.O.D. Orders

FAIR RADIO SALES • 133 SOUTH MAIN ST LIMA, OHIO

RADIO TUBES at New Low Prices

Type	Our Price	Type	Our Price	Type	Our Price	Type	Our Price	Type	Our Price
OZ4A	$.59	6AG5	.62	6K6GT	.54	12SR7	.69	805	3.00
1R5	.57	6AL5	.49	6K8G	.80	12SQ7	.56	808	1.75
1S4	.69	6AQ5	.50	6SG7	.60	35Z4GT	.59	830B	2.40
1T4	.61	6AX4GT	.90	6SK7 Met.	.58	35Z5GT	.40	864	.20
1A5GT	.62	6B8G	.70	6SH7	.60	50L6GT	.50	866A	1.10
1B3GT	.93	6B8	.75	6SK7GT	.55	42	.60	9002	.80
1U5	.60	6BE6	.52	6SN7GT	.65	2E22	1.90	9004	.38
2X2	.56	6BQ6GT	1.00	6SS7	.80	5CP1	5.00	9006	.35
5T4	1.59	6C6	.59	6X5GT	.50	5BP	4.00	2050	1.50
5U4G	.56	6H6 Met.	.54	7Q7	.60	100TH	6.00		
6A3T	.80	6J5 Met.	.50	12AU7	.65	357A	7.00		
6AC7	.80	6J5GT	.40	12SK7 Met.	.50	803	2.50		

SPECIAL
100th List $18.50
Our Price $6.00

Purchasing Agents: NOTE: all tubes are New, Standard Brands, Packed in original cartons. Immediate delivery. Terms 25% with order, balance C.O.D. Minimum order: Transmitting tubes $25.00, Receiving tubes—50 per type, or multiples of 50. Discounts on large orders. State quantity. Call or write today for detailed price list.

We are world-wide suppliers to Air lines, Government Agencies and the Radio Industries

METROPOLITAN OVERSEAS SUPPLY CORPORATION
1133 Broadway **New York 10, N. Y.** **Chelsea 3-1105**

TUBES: Industrial Receiving Transmitting

Specialists in JAN Tube Types

Standard Brands Only

0A2	5.90	3B25	3.95	304TH	2.75	872A	3.75
0A3	1.20	3B26	3.50	304TL	3.75	923	2.00
0A4G	1.00	3B28	5.95	316A	.90	954	1.85
0B2	1.00	3B29	8.90	388A	7.00	955	.35
0B2	1.00	3BP1	4.95	389A	4.00	956	.35
0C3	1.00	3C21	8.90	GL414	120.00	989	2.00
0D3	.95	3C24	1.15	GL434A	17.50	990	1.90
1B22	1.85	3C45	16.00	GL446A	1.95	991	1.70
1B23	6.50	3DP1	3.95	703A	4.95	1614	2.95
1B24	9.00	3E29	9.95	705A	.85	1616	.90
1B26	2.25	3FP7	1.95	708A	1.90	1620	12.75
1B27	12.00	3GP1	3.00	707A	7.75	1625	.25
1B32	2.50	4B22	7.75			1626	6.25
1B42	9.50	4B25	6.00			1628	.90
1P25	49.50	4J32	225.00			1629	2.70
1P28	2.75	4J35	140.00			1642	2.75
1P29	11.50	5BP1	5.00			1643	28.00
1P40	2.75	5BP4	5.00			1644	18.50
1P41	2.00	5D21	16.00			1650	10.00
1P42	5.00	5FP7	1.75			1651	60.00
2B22	2.95	5J29	15.00			1653	8.50
2C40	7.95	5LP5	17.00			1654	14.00
2C43	17.50	5R4GY	1.20			1658	22.00
2C44	1.85	5R4WGY	4.00			1659	28.00
2C51	3.75	6AC7W	3.25			1665	15.15
2D21	1.20	6AK5(WE)	1.25			1672	4.50
2D21W	3.35	6AM6	2.75			1673	3.00
2J26	29.00	6AS6	1.50			1675	17.00
2J31	25.00	6AS7G	3.90			1676	12.50
2J37	12.00	C33	14.50			1677	3.00
2J40	22.50	6C24	40.00			1685	3.00
2J50	36.75	6F4	1.50			1686	1.65
2J54	62.95	6J4	3.75			1688	10.00
2J56B	125.00	6K4	1.75			1851	.80
2J61	39.95	6K4A	1.50			1852	3.25
2K22	23.00	6L6WGA	2.45			1853	3.50
2K23	13.50	7AK7	7.00			1866	1.90
2K25	30.00	7C10	85.00			1867	2.75
2K28	27.75	9C24	150.00			1868	7.75
2K29	25.00	15E	1.50			5762WA	4.50
2K39	125.00	FG17	14.00			5763	3.20
2K33	250.00	FG33	21.00			5763WA	5.50
2K33A	250.00	2BDT	7.50			5784	2.80
2K34	175.00	35T	1.50			5718	6.90
3B24	8.90	FG105	12.50			5719	8.50
3B24W	9.00	FG17	12.50			5720	23.00
		250TH	25.00				
		250TL	14.00				
		274B	2.75				

Receiving Tubes

6AQ5	$.48
6SN7GT	.69
6V6GT	.50
12AT7	.73
12AU7	.60
12SL7	.60
12SN7	.69
12SQ7	.50
25L6GT	.60

All Other Types in Stock. Write for Quotes

Fully Guaranteed

707B	14.00	5725	4.25
708A	4.50	5726	1.50
709A	3.50	5734	2.15
713A	3.75	5740	2.15
714AY	65.00	5750	2.30
715B	7.95	5751	2.30
717A	5.75	5763	6.00
5702WA	4.50	5783	6.00
5703	3.20	5787	4.25
5703WA	5.50	5814	2.25
5704	2.80	5825	12.75
5718	6.90	5829	.75
5719	8.50	5839	110.00
5720	23.00	5840	7.75
		5844	2.00
		5847	2.50
		5881	6.50
		5902	11.00
		5910	.75
		5915	1.20
		5932	3.50
		5937	24.00
		5963	1.20
		5964	1.40
		5965	6.00
		6005	3.75
		6072	5.50
		6080	2.95
		6082	5.50
		6090	write
		6096	write
		6097	write
		6099	write
		6101	write
		6111	11.50
		6112	11.50
		6127	2.75
		6146	4.95
		6163	3.25
		6201	1.50
		6813A	1.95
		6826	5.25
		6829	5.25
		1N21A	1.20
		1N21B	1.20
		1N21BR	2.25
		1N34A	2.25
		1N44	1.20
		1N45	1.50
		1N54	.75
		1N64	.75
		1N64A	1.00
		1N65	1.00
		1N69	1.50
		1N70	1.35

MILGRAY ELECTRONICS, INC.

120 Liberty St.
New York 6, N. Y.
REctor 2-1297-8

CHECK AND COMPARE OUR COMPLETE STOCKS

The following is just a partial list of the current electronic and aircraft equipment now in our warehouse. Write for complete information. Prompt replies to all inquiries.

RC-103 & AN/ARN-5 ILS
New in original cartons. Complete. Consists of all accessories, plus AS-27A, R89B/ARN-5 and BC-733D. Modified to flag alarm.

TBS 4 & 5, NEW, COMPLETE
IE-17 TEST SET
AN/ARN-7 COMPLETE
SCR-269 COMPLETE
AN/ARC-1 BHF EQUIPMENT

BC-611 & BC-721 HANDIE TALKIES, Plus SPARE PARTS. Quantity available.

AN/ART-13 EQUIPMENT

ATC XMTR	T-47A/ART-13 XMTR
T-47/ART-13 XMTR	CU-24 ANT. LOAD
CU-25 ANT. LOAD	DY-11 & 12 Dynam't'r
MT-283 MOUNT	0-16 LFO
MT-284 MOUNT	ATC DYNAM'T'R
SA-22 ANT. LOAD	C-87 CONTROL BOX

AN/APG-13A RADAR
Absolutely complete, brand new

AN/APN-2	MG-153
SCR-729 New	APS-2, 3, & 15 Components
TA2J-24	AN/ARC-5 VHF
RTA-1B	SCR-274 & ARC-5, Command Equipm't
BC-1016	R-4/ARR-2 Receivers
APA-6 INDICATOR	BC-640 VHF XMTR
APA-11 INDICATOR	SCR-510
APA-17 RADAR	SCR-522
HS-33 HEAD SETS, NEW	MG-153
MG-149F & H	

SPARE PARTS

SCR-720	SCR-522
SO-7	AN/ART-13
AN/ARN-7	AN/ARC-1
SCR-269	BC-611

SCR-718 A, AM, B & C
Altimeter equipment—complete

To insure the finest of service and quality of merchandise, we have just recently put into operation our own reconditioning and function-testing plant, complete with all facilities.

WANTED
CFI UNITS ART-13 BC-788
1-152 BC-348 Q & R
TOP DOLLAR PAID

EXPORT INQUIRIES INVITED
We carry an unusually large stock of Airline Equipment, Test Equipment, Radar Sets, etc. Write for our low prices and complete information. We furnish immediate answers to all inquiries. Write today!

V & H ELECTRONIC INDUSTRIES INC.
2033 West Venice Blvd.—Dept. E-23
Los Angeles 6, California
Phone: REpublic 3-1127

DYNAMOTORS

Type	Input		Output		Excellent Used	Brand New
DM-32A	28V	1.1A.	250V	.05A.	$4.99	$7.50
DM-33A	28V	5A.	575V	.16A.	2.25	3.95
	28V	7A.	540V	.25A.		
DM-34D	12V	2.8A.	220V	.090A.	14.50	....
DM-37	25.5V	9.2A.	625V	.225A.	14.75	....
DM-40	14V	3.4A.	172V	.138A.	7.40	9.50
DM-38	28V		234V	.07A.	3.95	6.95
DM-21	14V		235V	.09A.	6.95	10.50
PE-73	28V	20A.	1000V	.350A.	9.50	12.50
PE-98	28V	1.35A.	250V	.060A.	2.95	5.50
PE-94A	28V	10A.	300V	.200A.	7.50	11.50
			150V	.101A.		
PE-94B	28V	10A.	300V	.200A.	8.50	11.75
			150V	.101A.		
PE-94C	28V	10A.	300V	.200A.	10.00	12.75
			150V	.101A.		
PE-96	14V	21A.	300V	.200A.	22.50	37.50
			150V	.101A.		
PE-101-C	13V	12.6A.	400V	.135A.	3.75	4.95
	26V	6.3A.	9V AC	1.12A.		
PE103	6V		500V	.180A.	27.50	44.50
	12V		300V	.160A.		
PE-104	6V	1A.	84V	.09A.	12.50	14.50
(Vibrator)	12V	5A.	51V	.03A.		
			1.4V	.400A		
DM-414 (with filter)	14V	2.8A.	220V	.080A.	....	12.50
PE-225 (with filter)	28V	3.2A.	375V	.150A.	....	10.50
EICOR Dynamotor D-401	27V	6.05A.	300V	.200A.	....	9.95
PE-135AX (with filter)	24V	12A.	500V	.300A.	....	34.50
			18V AC	2.2A.		

GENERATORS

GN-30-F (16"L, 8" dia. 50 lbs.)	14.6V	25A.	1000V	.350A.	39.50

INVERTERS

PE-206 Inverter—Leland In: 28V DC—38A. Out: 800V 800 cyc. 80VA, 1 Ph..... 9.75 12.50

PE-218 Inverter—Leland-Wincharger-GE. In: 28V DC—62A. Out: 115V 380/500 Cyc. 1500VA. 1 Ph.. 16.50 24.50

Please include 25% Deposit with Order—Balance C.O.D. F.O.B. our Warehouse N. Y. C.

G & G RADIO SUPPLY CO Dept E-11
51 Vesey St., New York 7, N.Y.
Phone COrtlandt 7-4605
Branch 16 W. Kinzie St., Chicago, Ill.

PEAK FOR SURPLUS

RAYTHEON PLATE TRANSFORMER
Pri. 230 Volt single phase, tapped, 60 cycle. Secondary. 6000 Volts to 8000 Volts at 1 amp. in 400 volt steps. Price $69.50 each.

ACME PLATE TRANSFORMER
Pri. 230 volt, 50/60 cy. 3 phase, delta connected. Secondary 3 phase, Y connected, 2632 volts at 7.5 KVA. Price $99.50 each.

Leeds and Northrup Wheatstone Bridge. Model 5300. Excellent condition. $95.00 ea.

Weston Model 341 Dynamometer 0-75/150/300 Volts AC/DC. Accuracy ¼%. Excellent Condition. Price $137.00 each.

CERAMIC CASED MICA
.0025 MFD, 25.0 0 VDC, 23 Amps at 3000 KC. Type G4 ..... ea. $27.97

BLOWER MOTOR
Squirrel Cage, Redmond, 115 V 60 Cycle Motor, 140 CFM. Silent operation. Brand New..... $7.97

PANEL METERS
NEW GOVT SURPLUS STANDARD BRANDS

2" METERS

DB meter—10 to +50	$3.49
0-500 ma DC	3.49

3" METERS

0-200 Microamps	6.95
0-400 Microamps	5.95
0-500 Microamps	5.95
0-150 Milliamp	4.50
0-200 Milliamp	4.50
0-1000 Milliamp	4.50
0-1.5 Volts AC	4.95
0-3 Volts AC	4.95

4" METERS

0-200 Microamps	$8.95

OIL CONDENSER BARGAINS

4 MFD 600 VDC	$ .97
10 MFD 600 VDC	1.77
2 MFD 1000 VDC	.97
6 MFD 1500 VDC	2.97
8 MFD 1500 VDC	3.57
50 MFD 330 VAC	6.97
2 MFD 4000 VDC	5.27
3 MFD 4000 VDC	5.97
100 MFD 4000 VDC	47.57
1 MFD 5000 VDC	2.97
3 MFD 5000 VDC	6.97
2 MFD 12,500 VDC	29.97
.25 MFD 25,000 VDC	17.97
.5 MFD 25,000 VDC	26.97
5 MFD 10,000	69.97
5 MFD 10 KVDC	69.97

Min. Order $3.90—25% with Order

PEAK ELECTRONICS CO.
66 West Broadway, New York 7, N. Y.
Phone WOrth 2-5439

RELAYS

Our stock of more than a million relays — in over a thousand different types — is the world's largest. Don't delay your production for want of large or small quantities of relays of any type.

Telephone, wire or write for quotations.

NEW AND MORE COMPREHENSIVE

1953 RELAY SALES CATALOG

NOW READY

Be sure to send for your copy

Relay Sales

Telephone SEeley 8-4146

833 W. CHICAGO AVE.

DEPT. 4, CHICAGO 22, ILL.

GRAIN OF WHEAT LAMPS

#322	3 V.	.19 amp.
#328	6 V.	.2 amp.

100 for $25.00 10 for $3.00

MARKTIME 5 HOUR SWITCH

A 10 amp. timing device. Pointer moves back to zero after time elapses. Ideal for shutting off radios and TV sets when you go to bed. Limited supply at this special PRICE **$4.90**

Also available in 15 min., 30 min., 1 hr. at $5.90

10 Seconds to 24 Minutes Timer

A hand wound electric TIMING SWITCH. Pointer moves back to ZERO and shuts off RADIO—TV—Electric Mixer—Photographic Devices—Time Delay etc. Furnished with Calibration Chart and Pointer Knob. Biggest bargain we ever had..... **$1.25**

3" Round Elapsed Time Meter **$13.75**

General Electric $15.50

Westinghouse Square ... $16.00

Genuine TELECHRON Motors

2 RPM....	$2.90
3 RPM....	3.90
4 RPM....	3.90
3.6 RPM...	3.15
1 RPM....	3.95
60 RPM....	4.30

1800 RPM SYNCHRONOUS Motor: 115 volts AC, 18 watts 1¼ lbs.: 2"x3"x2" **$4.50**

New Sound Powered HAND SET TELEPHONES. 50' Flex. Rubber covered cable FREE. Pair **$19.00**

REDMOND Powerful 5" Blower or Ventilator 115 volts AC 60 cycles 18 watts. For Kitchen — Laboratory. Heat or Cold or Chemicals.... $7.50

Hand Cranked A.C. Generators Removed from Ancient Telephones — 2 bar. $4.50; 3 bar. $5.50; 5 bar. $6.50

Polarized Bell or Buzzer Works on Magneto or 115 volt A.C..... **$1.50**

Complete 2 Station Magneto Ringer Telephones, Incl. Batteries—wire..... **$17.50**



Perhaps the smallest reversible GEARED-MOTOR in the world

Delco-PM-Permanent Magnet Alnico Field Motor 250 RPM, 27 volts, 110 m.a. Speed depending on the voltage. Designed to be used in bombsights, automatic pilots, etc. Cost at the factory $26.10. Delivery 4 months.

#5067127 ¼" shaft.
#5071895 ¼" shaft.
and some with 11/16" gear.
OUR PRICE, Immediate Delivery!! **$17.50**

Clamps to hold motor: $1.50 ea.

#5068600..... **$18.50**

NE-2	1/25 Watt NEON Pigtail lamp. 10 for $1.00, 100 for...	$7.50
NE-16	¼ Watt NEON lamp D.C. Bayonet Base, 10 for.....	$3.00
NE-21	¼ Watt NEON lamp S.C. Bayonet Base, 10 for.....	$2.50
NE-48	¼ Watt NEON lamp D.C. Bayonet Base, 10 for.....	$2.00
NE-29	½ Watt NEON lamp D.C. Bayonet Base, 10 for.....	$3.50
NE-30	1 Watt NEON lamp D.C. Bayonet Base, 10 for.....	$3.50
AR-1	2 Watt ARGON lamp Med. Screw Base, 10 for.....	$3.00
NE-40	3 Watt NEON lamp Med. Screw Base, 10 for.....	$3.50

HAYDON SYNCHRONOUS TIMING MOTOR

110 v. 60 cycle 30 RPM....	$2.60
110 v. 60 cycle 1/10 RPM..	$2.35
110 v. 60 cycle 1 RPM.....	$2.85
220 v. 60 cycle 2 RPM.....	$1.65

ZENITH Motorized Remote control made for T.V. but ideal for opening doors—windows—Turntables—Gadgets—Tuning Radios. Complete with Transformer 16 ft. cable and reversing button. A few more left..... **$8.95**

ALL PRICES F.O.B. N. Y.

EST. 1923 **BLAN** EST. 1923

64-0 Dey St. New York 7, N.Y.

PULSE TRANSFORMER

Tube base plug in type



TOP VIEW

Here are precision made, high quality compact pulse transformers wound on hypersil cores. They are built in octal bakelite tube bases and can be adapted to many uses. They are completely impregnated and sealed.

SUGGESTED USES

★—Blocking Oscillator, Multivibrator and Scope Circuits.
★—Wherever Accurate Timing and Triggering are necessary.
★—Unexcelled in circuit applications for generating low power and low voltage pulses.
★—Can be used in circuits utilizing repetition rates from 0 to well over 1 MC and pulse widths ranging from .05 Microsecond up.

TYPE UX 7350
Each Coil—50-T #36E
Max. DC Res. Ohms
1 & 8= 4.02Ω
2 & 7=4.54Ω
3 & 4=2.38Ω
5 & 6=2.18Ω



Price $4.50 each

HATRY and YOUNG

THE Elect IN ELECTRONICS

811 Boylston St., Boston 16, Mass. CO 7-4700

Public Auction Sale

San Diego, Calif.

NOV. 5, 1953

See Page 479

RELAY SPECIALISTS

AUTHORIZED FACTORY DISTRIBUTORS
STRUTHERS-DUNN POTTER & BRUMFIELD

MIDGET RELAY—1¼" Long

DPNO + SPDT—6/12 or 24 V. coil $15.00/doz.
Allied Control Relay—SO 628—DPDT—24v. DC coil $1.99

RADIO DEVELOPMENT & SALES CO.
323 ATLANTIC AVE. ULSTER 5-0488 BKLYN 1 N.Y.

Want more information? Use post card on last page.

ASSOCIATED INDUSTRIES

BC-640 TRANSMITTERS



FREQUENCY
100-158 Mcs.

POWER
110-125 V or
220-250 V
60 cy. Sing. Ph.

OUTPUT
75 Watt push-pull HK 246

MODULATION
Class B - AM

An efficient crystal controlled ground station complete with power amplifier, oscillator driver, modulator, control panel, dual power supplies, and power control.

Although originally designed for communications from ground to plane, it is currently used by police, taxi, ambulance and other special installations operating within these frequencies.

BC-639 RECEIVERS

Designed to work in conjunction with the BC-640 Transmitter at 100-158 Mcs. Supplied with RA-42, 115V 60 cy power supply. One RF and three IF stages AM or CW.

Technical Manuals

We recently purchased, from the government, a large quantity of technical and operating manuals on **RADIO, RADAR and AIRCRAFT** equipment. Send for our listings.

AN/ARN-6 ADF

We believe this is the . . .
FIRST U. S. GOVT. RELEASE . . . of a quantity of ARN-6 Radio Compass Equipment. All sets are complete with receiver, indicators, control boxes, racks, plugs, cables, and loop antenna. Spare AS 313 antennae and other components are available.

SCR-274N Comm'nd

Complete Installation or Components

BC-453-A Rad. Rec.	DM-32-A Dyn.
BC-454-A Rad. Rec.	DM-33-A Dyn.
BC-457-A Rad. Trans.	BC-456-A Mod.
BC-696-A Rad. Trans.	FT-277-A Rack
BC-496-A Rad. Con. Box	FT-226-A Rack

Plugs, couplings, adapters and tuning shafts

RADAR EQUIPMENT

Complete Installation or Components

SCR-291, APS-3, APS-4, APS-6, APS-15, APQ-13, Mark 16, Mark 28.

Certified - Guaranteed

All equipment is sold with our **certified, unconditional guarantee**, checked and tested in our own shop. We are a recognized and approved supplier for **Foreign and U. S. Govt. Agencies**. We invite your inquiries for supply or technical data.

A DIVISION OF
Arnold A. Semler, Inc.
6855 TUJUNGA AVENUE
NORTH HOLLYWOOD, CALIF.

POWER RHEOSTATS

ohms	W	Ea.	ohms	W	Ea.	ohms	W	Ea.
.1	150	4.89	50	50	2.10	500	100	3.68
.5	25	1.86	50	25	1.86	500	150	4.63
.5	50	2.34	75	25	1.86	500	300	6.93
.5	150	4.89	75	50	2.10	750	25	1.86
1	50	2.34	75	75	3.25	750	150	4.90
2	50	2.34	90	50	2.10	1000	25	2.10
2	100	3.68	100	25	1.86	1000	50	2.22
3	100	3.68	100	100	3.68	1250	225	6.41
3	225	6.41	125	25	1.86	1250	50	2.22
5	25	1.86	150	50	2.10	1250	150	4.90
5	50	2.10	175	25	1.86	1500	25	2.10
5	100	3.68	175	25	1.86	1500	50	2.22
5	150	4.63	200	25	1.86	1500	60	2.22
6	25	1.86	200	100	3.68	1500	150	4.15
6	50	2.10	200	150	4.63	2000	25	2.10
6	75	3.25	225	50	2.10	2000	50	2.22
7	25	1.86	250	25	1.86	2250	150	4.15
7.5	75	3.25	250	50	2.10	2500	50	2.22
7.5	225	6.41	300	50	2.10	2500	100	3.71
8	50	2.10	300	75	3.25	2500	150	4.15
10	25	1.86	300	100	3.68	3000	25	2.22
10	50	2.10	350	25	1.86	3000	100	3.71
10	100	3.68	350	100	3.68	5000	25	2.22
12	25	1.86	350	150	4.63	5000	50	2.34
12	50	2.10	375	25	1.86	7500	50	2.34
15	25	1.86	375	150	4.63	7500	100	3.68
15	75	3.25	400	25	1.86	10000	50	2.50
15	100	3.68	450	75	3.25	10000	100	4.75
20	50	2.10	500	25	1.86	15000	25	2.75
22	50	2.10	500	50	2.10	20000	150	6.98
25	25	1.86	500	75	3.25			

Specify Type Shaft Required—¼" SS or Knob Type
(Special Prices to Quantity Users)

HIGH POWER TR. MICA

G-1 TYP		.0005	10KV	.006	10KV
.0001	6KV	.00065	10KV	.015	7KV
.0001	6KV	.001	10KV	.25	1.6KV
.0002	6KV	.002	10KV	G-4 TYPE	
.0004	6KV	.03	2KV	.00025	30KV
.0006	6KV	.045	2KV	.0006	35KV
.001	6KV	G-3 TYPE		.0035	25KV
.01	4KV	.0001	30KV	.0039	20KV
.032	2KV	.00015	30KV	.0075	15KV
.04	1KV	.00025	30KV	.01	15KV
.051	1.5KV	.0004	30KV	.01083	12KV
.08	1.5KV	.00045	15KV	.03	8KV
.09	1.5KV	.00047	20KV	.056	5KV
G-2 TYPE		.0005	20KV	OTHERS	
.0001	10KV	.00095	5KV	.000155	30KV
.00015	10KV	.001	20KV	.00044	30KV
.0002	10KV	.0012	20KV	.000533	30KV
.0003	10KV	.00124	15KV	.001	30KV
.000375	10KV	.0015	20KV	.007	15KV
.004	5KV	.0051	10KV	(Many Others)	

TRANSMITTING MICAS TYPE "4" and "5"

mfd.	wv	type	ea.	mfd.	wv	type	ea.
.0001	600	4	.36	.0015	600	4	.36
.003	600	4	.36	.00162	600	4	.42
.00025	600	4	.29	.002	600	4	.39
.0025	2500	9	.57	.002	1200	4	.72
.0001	600	4	.29	.00225	600	4	.39
.0001	2500	9	.57	.003	600	4	.43
.00015	600	4	.36	.004	600	4	.48
.0002	600	4	.29	.005	1200	9	.99
.00025	600	4	.29	.0047	600	4	.47
.005	600	4	.29	.005	2500	9	1.86
.0005	2500	4	.75	.006	600	4	.54
.0005	2500	9	.77	.01	600	4	.85
.0006	2500	9	.85	.01	1200	9	1.41
.0007	600	4	.36	.02	600	4	.92
.00075	600	4	.36	.02	1250	9	2.12
.0008	600	4	.36	.025	600	4	1.08
.0009	600	4	.38	.03	300	4	.89
.001	600	4	.36	.03	600	4	1.34
.001	1200	4	.54	.043	600	4	1.75
.001	1200	9	.57	.05	300	4	1.39

Many other sizes in stock

TYPE "J" POTENTIOMETERS

TYPE "J" 95¢ TYPE "JL" $1.25 TYPE "JJ" $2.95

ohms	ohms	ohms	ohms	ohms
150*	4000†	80K†	500-500*†	130K-130K†
200†	5000*†	100K*†	600-600†	150K-150K†
250†	6500*†	125K*	1000-1000*	200K-200K†
300†	9000†	150K†	2000-2000*†	250K-250†
400*†	10K*†	165K†	2000-50K*	300K-300K†
500*†	12K†	250K*	2200-25K	350K-350K*
600†	15K*†	300K†	5000-35K†	2meg-2meg†
650*†	20K*†	400K*	25K-10K† sw	25K-25K*†
750†	25K*†	1meg*	2000-20K†	10K-10K*†
1000*	30K*†	1meg†	25K-10K†	1meg-1meg†
1400†	50K*†	2meg*†	7K-1meg†	5K-5K*†
1500*†	60K*	3meg*	100K-5K†	400K-400K†
2000*†	75K†		25K-400K†	800K-800K†
			1meg-500K†	50K-50K*†

Type "JJJ" $4.95

20K-200K-2 sh†	750K-750K-750K†
45K-27K-2.5n ¼ sh	800K-800K-800K†
700K-700K-700K†	1meg-1meg-1meg†

(*) ¼" screwdriver slotted shaft. (†) Knob type shaft. (*†) Both types.

Many other Hard-To-Get Items available for Immediate delivery from our large inventory. Send us your requirements and let us quote.

New MICA listing now ready.

A. MOGULL CO.

17 Warren St., N. Y. 7, N. Y.
Phone: WORTH 4-0865-6431

BLOWER BUY

Limited quantity of 250 FASCO BLOWERS 100 CFM—3" dia. rotor $7.50 EA. 10% discount quantity purchases.
(Cat. #BLTH100)
with automatic motor overload protection

Rotor: 3" dia. x 3" width.
Housing: Sheet steel, black. Inlet dia: 2-⅝". (grilled) with adjustable slide panel air volume control. Discharge: 2⅛" i.d., with welded mounting flange 4" o.d.
Motor: Thermally protected, totally enclosed, 2 pole, A.C., 60 cyc., 115 v., .48 amp., with mounted junction box. Bronze bearings.
Rating: .1"-100 cfm; .2"-82; .3"-65; .4"-76; .5"-65; .6"-44.
Dimensions: entire unit-viewing discharge: approx. 6" wide x 6" deep x 7" high.

BODINE MOTOR BUY. 200 Bodine ball-bearing electric motors, A.C., 1/50 HP, 115 volts, 1725 RPM, 40° C., continuous duty, single phase, 5/16" dia. motor shaft. Rotation easily reversible by interchanging leads. Resilient mounted. Ventilated, internal fan cooled. $11.50 ea.

Many Other Blowers and Motors in Stock. Your Inquiry Will Receive Prompt Attention.
All offerings subject to prior sale, F.O.B. 313 Canal St., NYC

ELECTRIC TRADING CO.
313-315 Canal Street, N.Y. 13, N. Y. CAnal 6-0675

HAZELTON INSTRUMENT CO.
128 Liberty Street, New York 6, N. Y.

All Makes of Electrical

Instruments and Testing Equipment Repaired. Write for free catalogue on new and used instruments at a savings.

An Investment!

Productive advertising is an INVESTMENT rather than an EXPENDITURE.

"Searchlight" advertisers almost invariably report prompt and satisfactory results.

BE CONVINCED — send us your advertisement TODAY.

Address
Classified Advertising Division

ELECTRONICS

330 W. 42nd St., N. Y. 36, N. Y

SPECIAL
6F5 Metal $.55
6SH7 ..... $.60
6SS7 ..... $.80

EMELTONE ELECTRONICS CO.

71 W. Broadway - N. Y. 7, N. Y. Phone REctor 2-1696

SPECIAL
VT 98 ENGLISH TYPE $15.00
5687 ..... $4.00

Crystal Diodes
Standard Brands Only

SPECIAL PURPOSE TUBES

Receiving Tubes
Klystrons, Magnetrons

CRYST AL DIODES
1N21A 1.75
1N21B 2.00
1N21C 20.00
1N22 ..... 1.70
1N23 ..... 1.95
1N23A 2.25
1N23B 2.50
1N25 ..... 6.25
1N26 ..... 8.00
1N27 ..... 6.00
1N28 ..... 4.25
1N31 ..... 6.00
1N34 ..... .75
1N34A ..... .75
1N35 ..... 2.25
1N38 ..... 1.10
1N40 ..... 11.50
1N41 ..... 12.00
1N43 ..... 1.75
1N44 ..... 1.50
1N45 ..... .62
1N46 ..... .60
1N52 ..... 1.27
1N54 ..... .50
1N55 ..... 1.25
1N60 ..... .61

2AP1 ..... 10.00
3AP1 ..... 10.00
3AP1A 12.00
3BP1 ..... 5.00
3CP1-51 ..... 2.00
3DP1-52 ..... 7.50
3GP1 ..... 5.00
4BP1 ..... 5.00
4CP1 ..... 5.00
4FP7 ..... 5.00
4GP1 ..... 5.25
5LP1 ..... 20.00
7BP7 ..... 5.00

0A2 ..... 1.00
0A3-VR75 ..... 1.10
0B2 ..... .90
0B3-VR90 ..... .90
0C2-VR150 ..... .90

1B21A 2.50
1B22 ..... 7.00
1B23 ..... 7.00
1B24 ..... 12.00
1B26 ..... 3.50
1B27 ..... 13.00
1B29 ..... 2.75
1B32 ..... 2.75
1B35 ..... 5.00
1B42 ..... 5.00
1B53A 60.00
C1B 5.00
1P21 ..... 20.00
1P22 ..... 20.00
1P23 ..... 1.50
2B22 ..... 1.50
2C24A ..... .60
2C26 ..... 1.50
2C31 ..... 20.00
2C39A 21.00
2C40 ..... 16.00
2C43 ..... 17.50
2C44 ..... 4.50
2C45 ..... 30.00
2C50 ..... 5.00
2C51 ..... 5.00
2C53 ..... 13.00
2D21 ..... 1.50
2E22 ..... 2.50
2E26 ..... 3.40
2E27 ..... 3.50
2E30 ..... 3.50
2J21A 10.50
2J22 ..... 16.50
2J23 ..... 20.00
2J27 ..... 16.00
2J31 ..... 16.00
2J32 ..... 24.00
2J35 ..... 16.00
2J36 ..... 16.00
2J37 ..... 16.00
2J38 ..... 16.00
2J39 ..... 16.00
2J40 ..... 16.00
2J41 ..... 16.00
2J42 ..... 150.00
2J48 ..... 45.00

2J49 ..... 63.00
2J51 ..... 250.00
2J55 ..... 30.00
2K22 ..... 30.00
2K23 ..... 30.00
2K25 ..... 30.00
2K26 ..... 100.00
2K28 ..... 30.00
2K29 ..... 30.00
2K39 ..... 100.00
2K41 ..... 30.00
2K45 ..... 125.00
2X3 ..... 95.00
3A5 ..... 1.50
3B22 ..... 1.50
3B24 ..... 5.50
3B24W 6.50
RK60 ..... 6.50
RK65 ..... 6.00
7ET4 ..... 4.50
100TH 4.50
FG-172 ..... 25.00
721 Sp 1.50
GL-218 ..... 30.00
2A3H 7.00
2A5G 7.00
2A7H 6.50
250TH 20.00
250TL 20.00
252A 28.00
254A 28.00
255B 130.00
256B 10.00
304TH 9.00
304TL 9.00
307A 4.00
308A 2.50
310A 21.00
321B 11.00
327A 4.00
328A 6.00
329A 6.00
332A 46.00
336A 6.00
350B 6.00
5R4GY 1.50

6AK5W 2.00
6AN5 ..... 1.50
6AN8 ..... 1.25
6AQ5 ..... 1.00
6AS6 ..... 2.25
6AS7G 4.00
6BQ7 ..... 1.00
6C21 ..... 22.00
6C24 ..... 55.00
10Y ..... .45
12A6 ..... .45
15E 2.00
15R 1.75
FG-17 ..... 6.00
RX21 ..... 6.00
35T 2.00
RK60 ..... 6.00
RK65 ..... 12.00
7ET4 ..... 4.50
100TH 11.50
FG-172 ..... 25.00
721 Sp 1.50
GL-218 ..... 30.00
249B 7.00
249C 7.00
249H 6.50
250R 20.00
250TH 20.00
250TL 20.00
252A 28.00
254A 28.00
255B 130.00
256B 10.00
304TH 9.00
304TL 9.00
307A 4.00
308A 2.50
310A 21.00
321B 11.00
327A 4.00
328A 6.00
329A 6.00
332A 46.00
336A 6.00
350B 6.00
5R4GY 1.50

357A 19.00
371A ..... .25
371B ..... .25
388A 1.00
394A 12.00
396A 4.00
407A 5.50
408A 5.00
417A 15.00
434A 30.00
446A 5.00
446TH 80.00
446TL 80.00
450 ..... 5.00
471A 1.00
707B 1.00
707C 1.00
708B 1.00
708C 24.00
715A 24.00
715B 24.00
715C 24.00
723A/B 20.00
724A 1.00
724B 1.00
725A 10.00
726A 14.00
726B 40.00

726C 61.00
731A 4.00
731A 4.00
805 ..... 2.50
808 ..... 2.50
808A 2.50
809 ..... 4.00
810 ..... 15.00
811 ..... 2.50
811A 2.50
812 ..... 2.50
813 ..... 7.00
814 ..... 2.50
815 ..... 11.00
826 ..... 1.00
829 ..... 11.00
829B 11.00
832 ..... 7.00
832A 7.00
833A 45.00
834 ..... 11.00
836 ..... 1.45
837 ..... 1.95
841 ..... 15.00
845 ..... 15.00
849 ..... 15.00
851 ..... 14.00
860 ..... 26.00
861 ..... 26.00
864A 5.00
865B 90.00
866 ..... 1.00
872A 1.75
873 ..... 1.75
874 ..... 1.75
876 ..... 1.00
931A 45.00
954 ..... .45

955 ..... .47
956 ..... .45
958A 1.00
1613 ..... 1.00
1614 ..... 1.00
1616 ..... 1.00
1619 ..... 11.00
1620 ..... 1.00
1621 ..... 1.00
1622 ..... 1.00
1623 ..... 1.00
1624 ..... 1.00
1625 ..... 1.00
1626 ..... 1.00
1627 ..... 1.00
1629 ..... 11.00
1630 ..... 1.00
1631 ..... 1.00
1632 ..... 1.00
1633 ..... 1.00
1634 ..... 1.00
1635 ..... 1.00
1636 ..... 1.00
1641 ..... 1.00
1642 ..... 1.00
1644 ..... 1.00
1645 ..... 1.00
1648 ..... 1.00
1649 ..... 1.00
1654 ..... 1.00
1655 ..... 1.00
1656 ..... 1.00
1657 ..... 1.00
1658 ..... 1.00
1659 ..... 1.00
1660 ..... 1.00
1661 ..... 1.00
1662 ..... 1.00
1663 ..... 1.00
1664 ..... 1.00
1665 ..... 1.00
1666 ..... 1.00

SUPERIOR VALUES FROM

AMERICA'S LARGEST ELECTRICAL CONVERSION HOUSE

400 CYCLE MG UNITS

G.E. HIGH CYCLE POWER UNIT. (PU-9/TPS-2) Alternator Type ASB, 115V, 1ϕ, .825 kva, 8000 RPM belt-driven by Lawson engine Model TLC351, 1.8 hp. New, in portable carrying case. ..$199.95

KATO 400 CYCLE MOTOR GENERATOR SET: Motor operative at 220/440-3-60 V belted to self-excited alternator 300 VA 115V, 1ϕ, 400 cyc. 2000 RPM. NEW ..$475.00

SPECIAL MG SET. Motor: 3 HP, 220/440-3-60. Self-exc. Alternator with output of 1.25 KVA, 115 V., single ph. 400 cyc. PRICE ..$325.00

LOUIS-ALLIS 1 KVA M.G. UNIT: Motor input 220/440 volts, 3ϕ, 60 cyc., 3460 R.P.M., direct conn. to alternator type POGH, 115 volts, 1ϕ, 400 cyc., 1 KVA. New. Price ..$383.00

LOUIS-ALLIS 3 UNIT MG SET. Consists of 5 HP motor operative at 220/440-3-60 directly coupled to alternator with output of 115 volts, 1 ph., 400 cyc. and with exciter unit all mounted on steel base. 1.6 K.V.A. Price ..$68.00

LELAND MG. SET. Consists of 5 HP Motor operative at 220-3-60 direct connected to self exec. alternator with output of 3 KVA, 120/208 V. 3 ph. 400 cyc. PRICE ..$960.00

LELAND MG SET Consists of 7½ HP Motor operated at 220-3-60 Direct Connected to Self Exc. Alternator with output of 2KVA, 115 V., 1 Phase, 400 Cyc. Price ..$565.00

BOGUE LABORATORY 400 CYCLE SUPPLY: Motor 7.5 HP, 220/440-3-60 direct-coupled to self-excited alternator output, 5 KVA, 120/208 V. 3ϕ, 400 Cy. Complete with Meter Panel. Harmonic content less than 1%. NEW ..$1890.00

BRITISH 5 KVA 400 CYC. M.G.: Consists of 10 HP motor of 220/440-3-60 V-belted to alternator with output of 5 KVA, 115 volts, 1ϕ, 400 cyc. PRICE ..$1095.00

AMERICAN 400 CYCLE SETS. A precision built motor generator set ideal for laboratory test work. Consists of 10 H.P. motor directly connected to alternator with output of 5 KVA, 120/208 Volts, three phase, 400 cycles. With electronic exciter—voltage regulator. Frequ. variation ±5%; Voltage variation ±1%; Total harmonic cont. 1.2%. PRICE ..$1850.00

LOUIS-ALLIS FREQUENCY CHANGER SETS. Pri: 25 H.P. 220/440-3-60; Sec. 15/19.8 K.W. 3300/2200 RPM/306/220 Volts 35/35 Amps. 2 ph. 800/380 C.P.S. Brand new. PRICE ..$1250.00

We can supply these units for 400 cycle output and with transformers to supply 3 phase, wye output. Write for further information.

KATO MG SET. Motor: 12.5 HP, 220/440-3-60. Output: 7.5 KVA, 230 Volts, 1ϕ, 250 cyc. with direct conn. exciter. Brand New. PRICE. $1395.00

CARSON PERMO-MAGNET 400 CYCLE M.G.: Motor 7.5 H.P., 220/440-3-60, dir. conn. to alternator 120 volts, 1ϕ, 400 cyc., 41.6 amps. (no brushes). PRICE ..$699.95

We have been fortunate in procuring several large size motor-generator units which we are able to offer at a very attractive price. These sets consist of a 75 H.P. motor dir. conn. to an alternator mfg. by Kato. The obtainable outputs are as follows:

A. 45 KVA, 115 V, 3ϕ, 400 cyc.
B. 45 KVA, 120/208 V, 3ϕ, 400 cyc.
C. 30 KVA, 115 V, 1ϕ, 400 cyc.

Harmonic content approximately 1%. We can furnish MG unit with voltage regulation and meter panels. Write for full information.

FAIRBANKS MORSE FREQUENCY CHANGER: Motor, synchronous, 77.5 HP, 220/440-3-60-1800 driving alternator type TAZB, 62.5 KVA, 50 KW, 440 Volts, 1ϕ, 360 cyc. with exciting M.G. PRICE ..$2650.00

KATO 400 CYCLE SUPPLY Motor: 15 hp, 220/440/3/60, 1750 rpm, Alternator: 10 kva, 120/208 Volts, Wye-connected, 3 ph. 400 cycles, end-mounted exciter, voltage regulation 1%, harmonic content 3%. NEW ..$2250.00

WE ARE ABLE TO QUOTE ON 400 CYCLE MOTOR GENERATOR UNITS FROM 500 WATTS TO 100 KW. SEND YOUR REQUIREMENTS AND WE WILL BE HAPPY TO FORWARD OUR QUOTATION.

GENERAL ELECTRIC RUNNING-TIME METERS. Model #8KT8D2, 115 volts, 60 cycles. Price ..$9.95

WESTINGHOUSE 25/50 CYCLE FREQUENCY-CHANGING MG. Motor: 220/440 Volts, 3 ph. 25 cycles. 40 HP, Frame 505, gearhead, direct conn. to Alternator: 25 Kva 120-1-60, 900 rpm. NEW ..$1450.00

MASTER LV MG SET. Motor: 15 HP, 220/440-3/60, 1730 RPM, Nema frame. Generator I: 24 V, 208 amps. 5 KW. Generator II: 12 V, 416 amps, 5 KW. New. PRICE ..$1235.00

ELECTRIC PRODUCTS LW FREQ. SUPPLY. Motor: 220/440-3-60. Gen: 230 V., 3 ph. 60 cyl, .8 PF. 900 RPM. PRICE ..$712.00

This MG unit will supply 2 KW of 1 phase current. New.

DELCO-DIEHL LV MG. Motor: 7.5 HP, 220/440 V, 1750 RPM, 18.4/9.2 amps. Gen: 40 V, 125 amps., 5 KW, drip proof. Will deliver 37 or 32 VDC, 125 amps. New. PRICE ..$395.00

General Electric Frequency Changer, Motor: 20 HP, Tricied, 550/1/60, 3400 RPM. Direct connected to Frequency Converter. Model 5MK445BJ1, with secondary of 30 KW, 440 volts, 3 phase, 240 cycles. PRICE ..$1850.00

INVERTERS

BENDIX 800 CYCLE AERO UNIT. Type 800, DC Input 24-28 vdc, 62 amps, 8000 rpm, Output 115 V, 7 A, 1 ph, 800 Cycles ..$37.50

PIONEER 12117-6B, Input 24 V, 1 amp, output 26 v, 400 cy, 6 VA, .6 PF ..$22.50

PIONEER 12126-2A, Input 27.5 vdc, 1.25 amps, output 26 V, 3 ph, 10 VA, .6 PF ..$22.50

GENERAL ELECTRIC 10486-182, Input 27.5 V, 12.5 amps, 8000 rpm, output 175 VA, 115 V, 3 ph, 400 cy. ..$40.50

LELAND ELECTRIC 10363, Input 28.5 vdc, 13 amps, output 115 V, 3 ph, 400 cy, 115 VA. ..$55.00

G. E. INVERTER UNITS. Model 5AT12UJ2B; Input: 24 VDC, 55 amp. 6000 RPM. Output: 115 Volts, 3 phase, 400 CPS, 750 VA. and secondary output of 26 Volts, single phase, 400 CPS. 250 VA. With automatic voltage and frequency regulation, built in. Rebuilt and warranted equal to new. SPECIAL PRICE ..$67.50

GENERAL ELECTRIC 400 CYCLE UNITS. Operate at 26 VDC 100 Amp. Output: 115 VAC 1ϕ, 400 CPS 1500 V.A. With filter system built-in. PRICE ..$39.50

WINCHARGER PU-7/AP: Input 28 VDC. 160 Amps. Output: 115 VAC, Single ph. 2500 V.A. 400 C.P.S. Frequency and voltage regulation built-in. PRICE ..$67.00

WINCHARGER PU-15/AP INVERTER. Type MG-750. Input: 28 volts, 60 amp. Output: 115 volts, 6.5 amp., 400 cyc., 1 ph. Brand new. PRICE. $69.50

HOLTZER-CABOT MG218. Compact 2 bearing units for low current 400 cycle output. Operative at 115 VDC, 2.3 amp. Output: 110 Volts, 1.0 amp. 1 ph. 400 CPS. Brand new. PRICE ..$79.50

LELAND INVERTER: Input 25-28 VDC, 52 amps. Output 250 VA, 25-28 VAC, 3ϕ, 400 cyc., 40% P.F. also delivers 750 VA, 115 VAC, 400 cyc., 90% P.F. PRICE ..$89.50

LELAND INVERTER: Input 28 VDC, 12.5 amps. Output 115 Volts, 3ϕ, 400 cyc., 80% P.F. PRICE ..$53.50

MG 153 HOLTZER-CABOT

Input: 24 V. DC, 52 amps; Output: 115 volts—400 cycles, 3-phase, 750 VA. and 26 Volts—400 cycle, 250 VA. Voltage and frequency regulated. ..$95.00 ea.

HIGH FREQ. UNIT. Motor: 24 VDC 50 amp. Alternator: 17 VAC. 1500-1600 cyc. sep. exc. at 24 VDC. 1.25 BHP. 4000 RPM. Made in Canada by Electric Tamper & Equ. PRICE ..$82.50

Alternators only to same specifications as above, sep. exc. at 24 VDC. PRICE ..$44.50

GE 400 CYCLE GENERATOR. General Electric Type 5ASB31JJ3; 400 cycles out at 115 volts; 7.3 amps; 8,000 rpm.; size 6 long x 6" dia. New. ..$99.50 ea.

ONAN H.F. MG. Model MG-0-75, Type PU/11. Input: 115/230 volts, 1 Ph., 60 Cy. Output: 115 V. 1 Ph., 480 Cy., 5.3 A. Also: 26 V, 5.8 A. PRICE ..$169.50

MISCELLANEOUS MG UNITS

BARDCO MOTOR GENERATOR SET. Model #MG5AD, Motor operative at 220-3-60, 7.5 H.P., Generator output 5 kw, 125 vdc, compd. wndg. 1750 rpm, complete with control cabinet including DC voltmeter, ammeter, rheostat, and AC motor starter. Marine encl., Ball-bearing. NEW ..$590.00

GENERAL ELECTRIC HIGH FREQUENCY MG. Consists of motor and dual output generator mounted on steel base. Motor operates at 220/440-3-60 direct connected to alternator with output of 115 Volts, 1 Ph, 1050 Cycles, 1 KVA and 115 Volts, DC., 2 KW. With field rheostat. PRICE ..$525.00

"TRANSFORMERS"

GENERAL ELECTRIC TRANSFORMER. Cat. #75G885, 2.5 KVA, 60 Cy., 1 Ph., Pri: 440. Sec: 110. PRICE ..$31.50

GENERAL ELECTRIC TRANSFORMER. Cat. #76G970, 1.6 KVA, 60 Cy., 1 Ph. Pri: 437/460/483. Sec: 115/230. PRICE ..$25.50

GENERAL ELECTRIC CURRENT TRANSFORMER. Type #JY-285. Amp. 150:5, Ratio 30:1. Cy. 25/125. PRICE ..$18.50

GENERAL ELECTRIC TRANSFORMER. Cat. #78G214, 1 KVA, 60 Cy., 1 Ph. Pri: 457/460/483. Sec: 115/230. PRICE ..$22.50

KUHLMAN LOW VOLTAGE TRANSFORMER. 72 KVA, 60 Cycles, 1 Ph, Pri. 460 volts, sec. 18/36 volts, 2000 amps. Tap switch, aircooled, three available ..$425.00

GENERAL ELECTRIC STEP-DOWN TRANSFORMER. Cat. 79G600, 60 KVA, 60 Cycles, 1 Ph, Pri. 460 volts, sec. 230 volts. Tapped at 210, 185, 160, 139 volts, aircooled, eight available. ..$400.00

WESTINGHOUSE PRECIPITRON TRANSFORMER. Style 1256505. Pri: 115 V, 25 cyc. Sec: 7500 V, 4 MA, with tap at 5500 V. Filament windings 2.5 V. Can be operated at 60 cyc. to obtain 18 KV., 6.5 MA. PRICE ..$14.95

WILLIAM I HORLICK COMPANY

IF IT'S FROM ONE FREQUENCY TO ANOTHER, FROM DC TO AC OR AC TO DC, IF IT'S FROM ONE VOLTAGE TO ANOTHER, THEN CALL ON US.

Est. in 1922
266 SUMMER ST.
BOSTON 10 MASS.

INDEX

SEARCHLIGHT

NOVEMBER, 1953

This index is published as a convenience to the readers. Care is taken to make it accurate but ELECTRONICS assumes no responsibility for errors or omissions.

EMPLOYMENT
Positions Vacant 470-478
Selling Oportunities Offered 470
Positions Wanted 471

SPECIAL SERVICES
Repairing 506

BUSINESS OPPORTUNITIES
Offered 471

NOTICES
Auction 479

EQUIPMENT MERCHANDISE
(Used or Surplus New)
For Sale 480-511

WANTED
Equipment 479

ADVERTISERS INDEX

Admiral Corporation 474
Allied Electronics Sales 502
Alltronics 502
Arrow Sales Inc 502
Associated Industries 506

Barry Electronics Corp 493
Bell Telephone Laboratories Inc 471
Bendix Aviation Corp., York Div 477
Bendix Pacific Division 470
Blan 505
Blonder-Tongue Laboratories Inc 474

Capehart-Farnsworth Co 478
C & H Sales Co 487
Chase Electronic Supply Co 502
Clark Electronic Corp 507
Communication Devices Corp 479, 498
Communications Equipment Co 488, 489
Commercial Surplus Sales 500
Compass Communications Co 495
Connector Corp. of America 500
Convair 477
Cook Research Laboratories 478

Deluxe Coils Inc 479

Electric Trading Co 506
Electro Sales Co., Inc 509
Electronic Engineering Co. of California 476
Electronicraft Inc 490
Electronics Corp. of Nebraska 500
Electronics Inc 498
Emeltone Electronics Co 507
Empire Electronics Co 507
Engineering Associates 497

Fair Radio Sales 503
Finnegan, H. 479

TO THE ADVERTISERS

NOVEMBER, 1953

SEARCHLIGHT SECTION
(Classified Advertising)
H. E. Hilty, Mgr.

General Motors Corp., A.C. Spark Plug Div. 472
General Precision Laboratory Inc. 474
G & G Radio Supply Co. 504
Goodyear Aircraft Corp. 473

Harjo Sales Co. 499
Harvey-Wells Electronics, Inc. 472
Hatry & Young 505
Hazleton Instrument Co. 506
Hoffman Laboratories Inc. 478
Horlick Co., Wm. I. 508
Houde Supply Co. 507

Industrial Assembly Corp. 496
Industrial Research Laboratories 476
Instrument Associates 491

JSH Sales Co. 500

Kollsman Instrument Corp. 476

Lapirow Bros. 507
Lectronic Research Laboratories 484
Legri S. Co. 502
Liberty Electronics Inc. 482, 483

Maritime Switchboard Co. 502
Maxson Corp., W. L. 470
Medical Salvage Co., Inc. 498, 500
Melpar Inc. 476
Metropolitan Overseas Supply Corp. 503
Milgray Electronics Inc. 504
Mogull, Alexander 506
Monmouth Radio Laboratories 497

National Cash Register Co., The 471
Nibur Sales Corp. 496

Peak Electronics Co. 504
Photocon Sales 507

Radalab 497, 501
Radio Corporation of America 475
Radio Development & Sales Co. 505
Radio & Electronic Surplus 507
Radio Shack Corp. 499
Radio Surplus Corp. 499
Railway Communications Inc. 497
Raytheon Manufacturing Co. 477
Relay Sales 505
Reliance Merchandizing Co. 485
R. W. Electronics 498

Semler Industries Inc. 503
Snow Inc., Cory 470
Southwestern Industrial Electronics Co. 476
Stavid Engineering Inc. 478
Stromberg-Carlson Co. 470

"TAB" 510, 511
Tallen Co., Inc. 494
Technagraph Co. 470
Telectrad 497
Telemarine Communications Co. 492
Telephone Engineering Co. 497
Tung-Sol Electric Inc. 479

Universal General Corp. 486
Universal Winding Co. 479

V & H Electronic Industries Inc. 504

Weiss Co., David 479
Western Engineers 501
Weston Laboratories Inc. 480, 481
Wilcox Electric Inc. 472
Wolf Co., Edward 497

THE *Electro* INDEX

HIGH VOLTAGE CAPACITORS

Cat. No.	Mfd.	Wvdc	Price
2LXP30	120	3KV	$99.50
22F985	2	4KV	14.50
22F225	4	4KV	22.50
PFD48244	7	4KV	34.50
22F225	1	5KV	14.50
14F1	4	5KV	32.50
14F2	7	5KV	49.50
15F7210	0.1	6KV	12.50
A7548	2x.25	6KV	17.50
TK00820	2	6KV	27.50
26F513	2x.68	7.5KV	27.50
7520	2x1.0	7.5KV	27.50
14F138	4.5	7.5KV	79.50
CC21B	2x0.5	9KV	32.50
3DA20-136	.02	10KV	7.50
18020	0.1	10KV	9.95
Inertown	1.0	10KV	25.00
14F13	5	10KV	124.50
26F68	0.1	12KV	9.95
TK120065	.45	12.5KV	19.95
15020	.25	15KV	19.50
14F17	1	15KV	49.95
14F63	1	15KV	49.95
14F18	1.5	15KV	62.50
20020	.25	20KV	27.50
14F64	.25	20KV	27.50
37485	.25	20KV	27.50
XSW200	.25	20KV	27.50
PC1925	2x.25	20KV	37.50
20005	0.5	20KV	45.00
14F22	1.0	20KV	62.50
14F139	.01	22KV	15.50
26F585	.06	25KV	17.50
Inertown	.5	25KV	57.50
25020	.25	25KV	67.50
14F24	.5	25KV	97.50
14F83	.75	25KV	72.50
Inertown	1.0	25KV	85.00
A6734	1.0	25KV	85.00
S1258441	1.5	25KV	124.50
14F112	.001	50KV	24.50
14F98	2x.025	50KV	37.50
14F127	.025	50KV	37.50
14F126	.2	50KV	70.00
14F97	.25	50KV	70.00

DIEHL AC CONTROL MOTORS

FP25-2, 22V 2ph 60~ .85A 1680RPM $22.50
FP25-3, 28V 2ph 60~ .5A 3280RPM 22.50
FPE25-8, 75/75V 60~ .11/.11A 2ph 2 watts, 2 pole 24.50
FPE25-9, 100/100V 400~ .44/.44A 2ph 4 watts, 2 pole 27.50
FPE25-11, 75/75V 60~ .11/.11A 2ph 4 watts, 2 pole 29.50
FPE25-12, 115/115V 60~ .16/.16A 2ph 5 watts, 2 pole, 3200rpm 34.50
FPE25-14, 20/20V 60~ .5/.5A 2ph, 2 pole 22.50
FPE25-16, 20/20V 60~ .85/.85A 2ph, 2 pole, 1680RPM 24.50

SINE-COSINE GENERATORS

(Resolvers)

Diehl Type FPE43-1, (Single Phase Rotor), Two stator windings 90° apart, provides two outputs equal to the sine and cosine of the angular rotor displacement. Pri: 115V, 400~; Sec: Sinusoidal, 228V 400~ 2ph, 2 pole 1380Ω 30.00
Diehl Type FJE43-9, same as above except output is 55V 400~ 2ph 2 pole 89Ω 30.00
Diehl Type FJE43-10, same as above except output is 13.5 volts 400~ 30.00

TACHOMETER OR RATE GENERATORS

Elnico Type PM-1, DC Generator $29.50
Elnico Type PM-2, DC Generator 29.50
Elnico Type F-15, AC Generator 29.50
Elnico Type B-16, AC Generator 29.50
Elnico Type F-17, AC Generator 34.50
Elnico Type B-35, DC Generator 29.50
Elnico Type B-35D, DC Generator 29.50
Elnico Type B-44, DC Generator 29.50
Elnico Type FBZ-55, DC Generator 29.50
Elnico Type FB-84, DC Generator 34.50
Elnico Type FB-286, DC Generator 39.50

SELSYNS—SYNCHROS

Immediate Delivery—From Stock

1CT Control Transformer, 90/55V 60~ $44.50
1HCT Control Transformer, 90/55V 60~ 80.00
1G Generator, 115/90V 60~ 44.50
1HG Generator, 115/90V 60~ 80.00
1DG Differential Generator, 90/90V 60~ 64.50
1HDG Differential Generator, 90/90V 60~ 80.00
1F Synchro Motor, 115/90V 60~ 44.50
2J1M1 Control Transformer, 105/55V 60~ 59.50
1N Synchro Motor, 115/90V 60~ 49.50
1SF Synchro Motor, 115/90V 400~ 17.50
1F Special Motor, 115/90V 400~ 17.50
2J1D1 Generator, 115/90V 400~ 12.50
2J1F1 Generator, 115/57.5V 400~ 9.50
2J1F3 Generator, 57.5/57.5V 400~ 9.50
2J1G1 Control Transformer 57.5/57.5V 400~ 9.50
2J1M1 Differential Generator 57.5/57.5V 400~ 12.50
2J1M2 Generator, 115V 400~ 17.50
2JDL1 Motor, 115/90V 400~ 15.00
3F Motor, 115/90V 60~ 84.50
3HCT Control Transformer, 90/55V 60~ 84.50
2JDSR1 Motor, 115/90V 400~ 27.50
5SF Motor, 115/90V 400~ 32.50
5SG Generator, 115/90V 400~ 32.50
5SDG Differential Generator 90/90V 400~ 32.50
K55050 Generator, 115/90V 400~ 19.50
K55050L2 Generator, 115/90V 400~ 22.50
2JA39BB2 Motor, G.E., 110/55V 60~ 55.00
2J5FB1 Control Transformer 105/55V 60~ 60.00
2JDSC2 Motor, 115/105V 60~ 60.00
2J5M1 Generator, 115/105V 60~ 60.00
2J5NA1 Generator, 115/105V 60~ 60.00
2J5A6 Generator, 115/105V 60~ 60.00
2J5S1 Differential Generator 90/90V 60~ 60.00
2JDSJ2 Motor 115/90V 60~ 60.00
2J5LA1 Generator 115/105V 60~ 60.00
2J65F1 Generator 110/55V 60~ (used) 35.00
2JD123A16 Motor, 110/40V, 60~ 55.00
5A Generator, 115 Volts 60 Cycles 22.50
5B Generator, 115 Volts 60 Cycles 22.50
5CT Control Transformer 90/55V 60~ 60.00
5HCT Control Transformer 90/55V 60~ 80.00
5D Differential Motor, 115/90V 60~ 60.00
5DG Differential Generator, 90/90V 60~ 60.00
5F Motor, 115/90V 60~ 60.00
5G Generator, 115/90V 60~ 60.00
5M Motor, 115 Volts 60 Cycles 22.50
5N Motor, 115 Volts 60 Cycles 22.50
2J6F1 Generator, 115/90V 60~ 44.50
2J6F2 Generator, 115/90 Volts 60~ 44.50
6SG Generator, 105/90 Volts 60~ 60.00
6CT Control Transformer, 90/55V 60~ 60.00
6DG Differential Generator 90/90V 60~ 60.00
7G Generator, 115/90V 60~ 60.00
7G Generator, 115/90V 60~ 69.95
C44968-6 Type II-1, Repeater, 115V 60~ 22.50
C56701 Type II-4 Repeater, 115V 60~ 22.50
C56776-1 Repeater AC Syn. 115V 60~ 22.50
C69424 Diehl FJE44-8 Transmitter 115V 60~ 22.50
C69406-1 Type II-2 Repeater, 115V 60~ 22.50
C77610 Type III Repeator, 115V 60~ 22.50
C78248 Transmitter AC Syn. 115V 60~ 24.50
C78249 Differential AC Syn. 115V 60~ 9.50
C78254 Type XII Differential, 115V 60~ 22.50
C78411 Transmitter AC Syn. 90V 60~ 14.50
C7841414 Transmitter AC Syn. 115V 60~ 49.50
C78350 Diehl 84-4, Receiver 115V 60~ 22.50
C78368 Diehl 84-5, Transmitter 115V 60~ 22.50
C78386 Type XV Transformer 115V 60~ 22.50
C78791 Transmitter AC Syn. 115V 60~ 22.50
C78331 Type I-4 Transmitter 115V 60~ 22.50
C81369 Type II-8 Repeater, 115V 60~ 22.50
PATT-6547 Admiralty Transmitter 115V 60~ 17.50
PATT-6548 Admiralty Transmitter 115V 60~ 17.50
Type I-82A Radio Compass Indicator 7.95
Type I-82F Radio Compass Indicator 9.00

SPECIAL OF THE MONTH

High Kva Mica Capacitors

Leading Mfg'er, Type 57
Cat. # 676-57 .002 Mfd 40 KV
$85.00

These listings represent only a small portion of our tremendous Electronic inventories. If your requirements are not listed, write and allow us to quote you accordingly. Prices subject to change without notice. Terms: Rated firms net 10 days, Non-rated 25% with order balance COD. FOB Boston. Minimum order $10. Merchandise Fully Guaranteed.

ELECTRO *Sales Company Inc.* ESCO
50 EASTERN AVE., BOSTON 13, MASS. CAPITOL 7-3456

Electro INDEX to *Electronic Component* VALUES

Want more information? Use post card on last page.

TACHOMETER GENERATOR
GENERAL ELECTRIC
PART #2CM6-AAK-28
MARK V STUD MTG
NEW ..... $4.98; 2 for $8.89

STORAGE BATTERIES
6 Volt WILLARD Mini-BRAND NEW & Sealed, Portable, Models ...95c; 4 for $3
Four 2V BATTERIES w/acid* 3.98
6V 20AH Willard FLOATING Vibrator 2.98
6V 20AH Batt. W/Vib. & Acid* 2.98
6V/24AH Gould 2.98
6V/40AH Willard WL6/DS2140 ..... 2.98
6V/60AH Batt. W/Acid* 3.98
6V/40AH Willard 3.98
6V/40AH Batt. W/Acid* 3.98
* Acid is shipped in Bottles, R'Exp only.

LAB or HI-FI POWER SUPPLY
Gets constant voltage power transformer mounted on chassis with 2 octal rectifier sockets.
New Mfgrd By Dumont
Furnishes 400VDC/250MA to filter system 12.6VCT/6A
AMP or 2x6.3V/6AMP (common tap) and 5V/6AMP regulated special $17.98
With filter condensers, choke and rectifier tubes. SPECIAL $18.98

PRECISION RESISTORS
2 MILLION IN STOCK
GUARANTEED 1% TOLERANCE
ORDER ANY VALUE YOU NEED
42 to 470K OHM ..... 10cc 10 for $1.25
1MEG & UP ..... 70cc 10 for $4.45

CLOCK RADIO
"WAKE UP TO MUSIC"
Just set the dial, & radio automatically turns on.
Beautiful plastic cabinet. MAHOGON OR IVORY
Powerful 5 tube design.
"TAB" SPECIAL $22.95
Same Less Clock $17.98

YOU PICK THEM 39¢ Lots of 10 WHILE THEY LAST

ELECTROLYTIC CONDENSERS
•8MF/25VDC	2X15MF/350VDC
•8MF/450VDC	1X20MF/150V, 10MF/450V
•5MF/100VDC	40MF/250V, 25MF/25V
•8MF/150VDC	3X150MF/25VDC
•100MF/25VDC	50/15/10MF/250VDC

ALL SIZES & TYPES NEW STOCK

EICO TEST EQUIPMENT
Stock #	Type	Kit Price	Built Price
145K	Sig Tracer	$19.95	$28.95
211K	Volt Meter	14.95	
221K	Volt Meter	29.95	40.95
315K	Sig Gen	19.95	29.95
324K	Sig Gen	21.95	34.95
368K	Sweep Gen	32.95	49.95
377K	Audio Gen	23.95	40.95
460K	Oscilloscope	79.95	129.95
625K	Tube Tester	39.95	49.95

Industrials & Schools Write Qty Price

TEST CORDS
15 Foot Extension Cord, Hvy Duty, 8J Rubber Covered Insulation as Shown 79c
4 Foot Instrument Test Leads, High Quality Red & Black. Per Pair ..... 89c; 2 for 98c
TV Cheater Cord Approx 25" ..... 25c; 6 for $1.00

SELSYNS
2J1E1 GE Selsyns ..... Each $6.98
2J1F3 GE Brand New 115V/400 cy. set 9.75
CT8248 Sync. Trans. 115/60 or 38.9Ø; 2 for $8.00
CT8249 Sync. Diff. 115V 60 or 52.8Ø; 2 for $8.00
CT8247 Repeater 115-60 ..... 2 for $8.00
Bendix Autosyns AY1 & AY5 ..... 3 for $.95
Bendix AY5Ø New Qty Orders $2.98
OTHER TYPES IN STOCK

DYNAMOTORS
INPT 6VDC, Output 300V/100ma, or 12/24V Output 600V/50ma. IP Mtgs. 4 Illustrated 6.95
INPT 28VDC/1.4A Output 250V/60ma 3.50
DA82A 28V/10.5A and 300VDC/300ma 115VDC/10ma. 16.5vds/5amp 6.75
PE94 Plate Supp., Uses DA82A (SCR328) 8.95
PE97 Plate Supp., Less Tubes 4.95

FL-5 FILTER
Noise or voice. Filters 1050 cycle audio, excellent for CW Work ..... 89c; 2 for $1.69

BANDPASS FILTER
Sharp Cutoff HIQ, Cased & Shielded 60, 90 or 120 cycle ..... Each $1.79; 2 for $3.50
UTC B24, 1024 - 1280 Cyc. Ea. $1.98; 2 for $3.50

OIL CONDENSER SPECIAL
10 MFD 600 VDC $1.75 ea
LOTS OF 2
Case Dimensions, Not Including Insulators
4¼M"W-2¾"D
Quantities Less Than 2, Ea $1.98

OIL CONDENSERS
WAREHOUSE CLEARANCE SALE
RECTANGULAR CASE
.5MFD	1500VDC	95c; 2 for $1.80
.1MFD	600VDC	1.95; 3 for 5.00
.1MFD	3100VAC 10000VDC	4.95; 2 for 9.00
2x2MFD	400VDC	1.95; 2 for 3.50
BATHTUB SIDE TERMINALS		
.1MFD	600VDC	1.95; 3 for 5.00
2MFD	1KVDC	1.95; 3 for 5.00
.1MFD	2000VDC	1.95; 3 for 4.50
2x.1MFD	400VDC	49c; 3 for 1.00

CONDENSER SPECIALS
2 MFD 1000 VDC 330 VAC "CD" MFGR 25¢ LOTS OF 10
Smaller Quantities Each ..... 49c; 3 for $1.25
10MFD 500VDC Cornell-Dubilier With Adjustable Mounting Clamp ..... 2 for $1.98

FREQUENCY METER AND WAVE METER
BC1152 Control Unit. Part of RC1150 & SCR270 Radar Equipment 10 Tube Line Op., Operates 150-210 Megacycles, 115V 60cy. Includes Heavy Duty Power Supply. Excellent Condition Less Tubes $15.95
Two for $30

"TAB" THAT'S A BUY

"AN" CONNECTORS REDUCED UP TO 90% OFF LIST
	EXTRA 10%	QUANTITIES OFF 10%
AN3102-10S-2P	22c	AN3106-22-4S $1.12
AN3101-12S-3S	22c	AN3106-22-4S 2.98
AN3102-12-3P	22c	AN3102-22-4S 2.98
AN3102-14S-5P	45c	AN3057-4 25c
AN3108-14S-7S	45c	AN3057-5F 25c
AN3102-16-1P	72c	MN-CS-22 1/32 $.35
AN3057-20	51c	GK-S-325 64c
AN3102-20-29P	72c	Others In Stock, <

866A KIT AND XFORMER
2 Tubes, 6ckts, sfmr 115v 60cyc inp. outpt. 2.5vct, 10 A/W least. SPECIAL $4.98

DIODE PROBE TUBE
Unsealed for No-Loss VHF testing. Ultra sensitive subminiature-envelope. New, w/data & VHF ..... 25c; 6 for $1.

DC POWER-SUPPLY

0 to 12VDC/3 AMP Variable DC supply—from 115v/60 cy. Usable LAB supply, filament D.C. plating, battery charging, model railroad includes voltage or speed control and center off reversing sw. Ideal for two "HO" loco's. ..... $29.95; 2 for $58.90

RHEOSTAT SPECIALS
15 ohm 25W w/knob	$1.49; 2 for $2.49
30 ohm 50W Model J	1.98; 2 for 3.50
60 ohm 50W w/knobcap	2.39; 2 for 3.98
100 ohm 50W Model K	2.39; 2 for 3.98
200 ohm 25 Model D	1.49; 2 for 2.49
250 ohm 25W	1.39; 2 for 2.25
500 ohm 25W Model F	2.98; 2 for 5.00
250, 500, 5000 ohm tapped shaft, 25 watt	79c; 2 for 2.00

Many Other Types in Stock

"TABS" NEW TRANSFORMER STOCK
2.5VCT/10A 12.5KVING Kenyon ..... $6.98; 2 for $10
VPM2VCT/200MA 5V/3A, 6.3VCT/6A, Thordarson ..... $6.98; 2 for $15.
800VCT/250MA Stancor ..... $3.98; 2 for $15.
800VCT/250MA 5V/3A, 6.3V/6A, 6.3V/3A $6.49
2500VDC/200MA MIV Transformers Power & Rivirs Filaments @ 4/5KV Special $25.00
600VCT/80MA, 6.3V/2A, 6V/1A, 5V/1A $2.49

TRANSFORMERS
All 115 V 60 Cyc Input TV & CR Pwr Xmfr up to 20" tube. HI VOLTS to 20 KV (w/quadrupler ckt.) ALL Tubes, PL & Fil wndgs 300 VDC/275Ma Full Wave, 6.4V 10.2A, 5.4V/6A, 7.5V/3A. Hypersil Core. Or Improv. 36.49; Two for $12.49
1000VCT/45MA, 750VCT/60MA, 350VCT/60MA, 5V/3A, 6.3VCT/1A, 6.3VCT/2A CBD. WIRING CAN BE USED 2X RATING RAYTHEON RK34 PERMIL CORE $4.96
750VCT/100MA, 5V/2A, 6V/1A, 10V/1.5A WESTERN ELECT $6.49
660V/25MA, 2X6.3V/3A, 1200V/ 1.5MA, TWO 2X2 FIL WNDGS $2.25
700VCT/250MA: 5V/6A, 12.6V/5.5A $2.98
770VCT/250MA, 5V/6A, 12.6V/5.5A $2.98
720VCT/80MA, 6.3V/1.5A, 6.3VCT/2A, 700VCT/120MA, 2X6.3V/3A, 6.3V/1A Triad ..... $3.98; Two for $7.25
750VCT/200MA, 6.3V/6A, 700V/1A ..... $4.98; 2 for $12.
24.115VDC @ 11A & 230 VAC $1.49

FILTER CHOKES
15Hy/80ma/82Ktms	2.25
10Hy/75ma	1.25
10Hy/125ma/CT/CT/CT Hold/1 KVIns.	1.49
60Hy/125ma/Ctr/H Sld	2.89
15Hy/300ma/5K Ins.	4.95
20Hy/300ma or 15Hy/400ma/ 17KVIns Kenyon	9.95
18.5Hy/1A ma/17KVing/Raytheon	29.95
Dual 2 Hy/300ma UBN	95c; 2 for 1.49
6 Hy 175ma 280 Ohm	$1.49; 2 for 2.49
10 Hy 100ma Fried	1.29

FILAMENT TRANS.
6.3V/2AMP $1.98; Two for $3.5
2.5V/3A @ 7½, 7 for $2.49, 10 for 3.49
2.5VCT/10A 5KVING 3.89
7.5VCT/12A CBD KENYON 15 KVING 10.95
24V/1.25A CBD @ $1.98 Two for 3.49
2X12V/1A or 24V/2A @ $3.89 Two for 6.98

ELECTROLYTIC CONDENSER KIT
POPULAR VALUES 25¢ EA
LOTS OF 25
25 ASSORTED CONDRS. ONLY $3.75

METER BUYS

0-20 VDC "AN" $1.98; 2 for $3.25
0-60 ADC "AN" Type M16 Less Shunt ..... 2.98; 2 for 5.00
0-1MADC Weston 2¾" Sq RA86 LN 6.49
0-300 MADC/2¾" Rnd Triplett 221T 4.98
0-1mADC Weston 2¾" Rnd 800cr 14.95
0-150 VAC/Weston/3½ Sq 3.49
0-150 VAC/25-120cy/3½" Square 2.98
0-1MADC Weston 2¾" Sq RA86 LN 6.49
0-300 MADC/2¾" Rnd Triplett 221T 4.98
0-1mADC Weston 2¾" Rnd 800cr 14.95
0-150 VAC/Weston/3½ Sq 3.49
0-150 VAC/25-120cy/3½" Square 2.98
0-1 MA RF 3½" Rnd Weston 301 ..... 12.95

RELAY SPECIAL
SPST Mini Size 115VAC 2A CTS ..... 98c; 2 for $2.75
SPST Mini 115VAC 2A CTS ..... $1.39; 3 for $3.75
DPDT DC/DC 2A CTS 2.95
DPDT 6.3VAC/DC 2A CTS 2.95
6 LMED ..... $3.49; 2 for $6.50
SPNO 115VAC/10A CTS 1.98
6 Ptns ..... $2.98; 2 for $5.50
DPDT A SPNO 12 VDC/10A CTS ..... 2.95; 2 for $5.75
DPDT Clare SK5010, Octal Base, 10-28V 2A Contacts, Mitroseal $2.50

INFRARED SNOOPERSCOPE
SEE IN DARK TUBE
Image-Converter Tube Bilensitivity amplified design 3 dia. Window, screen—Resolution up to 250 lines. Complete data & tube ..... $4.98; 2 for $8.49
Snooperscope for Bugging & 1500VDC/35MA Using Inverter Ckt. Transformer, Rectifiers, Resistors, Capacitors and Diagram 115V/60cy Oper $6.98

FEDERAL "ITT" SELENIUM BATTERY CHARGER RECTIFIER
10-0-10 Volts (CT) 100 Amp (Fan-Cooled). Replace Your Old Inefficient Sulphide Rect. with the New Selenium Type. SPECIAL $11.95

SELNIUM RECTIFIERS
½ WAVE FOR RADIO & TV
CURRENT (Cont.)	LIST "TAB" PRICE	PRICE	QTY 12 FOR
65MA @ 130V	$1.69	$0.49	$4.49
130MA @ 130V	1.98	.79	6.98
260MA @ 130V	2.25	.79	6.98
300MA @ 130V	2.98	1.29	10.98
400MA @ 130V	3.98	1.49	12.98
500MA @ 130V	4.98	1.98	16.98
600MA @ 130V	5.98	2.49	20.98
750MA @ 130V	6.98	2.98	25.98
230MA @ 26V	1.49	.49	3.98
460MA @ 26V	2.49	.79	6.98
230MA @ 300V	4.95	1.39	14.98

SELENIUM RECTIFIERS
We specialize in Rectifiers and Power supplies to your specifications. Immediate delivery.

Current Cont.	18/24 Volts	36/50 Volts	64/80 Volts	130/160 Volts
1 Amp	$1.98	$2.25	$2.75	$7.50
2 Amp	2.25	2.98	3.98	10.98
3 Amp	2.98	3.98	5.98	15.95
4 Amp	3.98	4.98	7.98	20.95
6 Amp	4.98	6.98	10.98	29.95
10 Amp	6.98	10.98	15.98	45.00
15 Amp	9.98	14.98	22.98	65.00
20 Amp	12.98	19.98	31.98	75.00
24 Amp	14.98	22.98	35.98	90.00

Full Wave Bdge Trans. 115V/60cy inputs, up to 16VDC at 12 amps $23.98
up to 28VDC at 12 amps 34.98
up to 56VDC at 12 amps 49.98
up to 125VDC at 12 amps 125.00
C "TAB" fast delivery SPECIALS

RECTIFIER XFMRS
PRIMARY 115V 60 cy.
SECONDARY 9-9-12-15-24-28V CONT. 4 amps $5.75
CURRENT 12 amps 10.75
24 amps 15.75
30-30-36-36V/4A 5.95
18 Volt 2 amp 2.95

RECTIFIER CHOKES
4 Amp	.07 Hy	.6 Ohm	$7.98
12 Amp	.01 Hy	.1 Ohm	14.95
4 Amp	.004 Hy	.025 Ohm	29.95

MERCURY THERMO REGULATOR
DUAL CKT, 108° F & 82° F. Extremely sensitive & accurate for most exacting requirements—Research, Fire Prev., Process, Ht Control, or Max-Min Temp Control. Brand New, w/data & ckt. Ea. 95c; 12 for $10.90

KURMAN RELAY DC
Double Pole 10MG & 5MC 4MA Sens 650 Ohm 6 Amp CTS
$3.95 LOTS OF 3
Less Than 3 Each $4.75

New "LENK" 180 Watt Perfect Balance Soldering Gun
No other soldering gun offers all these features at any price. 115VAC 180 Watt, light weight 18 oz. melts solder 2½ secds, swivel 180 deg. lug. Special alloy Koroglass tip, heavy duty transformer, Positive trigger—easy action. Balanced luger pistol finish. "TAB" special $7.45

AUDIO COMPONENTS
GE RPX041 Phono Cart	$4.49
GE RPX050 Triple Play Cart	6.98
Electrovoice Triple Play	6.98
Pickup Arm & Xtal Hi-Output	2.39
PM 12" Hi-FI British Speaker	4.98
PM 8" GOLDEN 8 Speaker	19.50
PM 8" Blue 8T10-1 Permdum	12.00
PM 8" Speaker Gud Tone	1.98
PM 10" Hi-FI Woofer & Separate Horn Tweeter. 10 Watt 40-20000 cy.	19.98
Crystal Mike & Cable	2.98
Crystal Mike Cartridge (Lapel Type)	2.98
Crystal Mike Cart. Ceramic Wedged	3.98

AUDIO AMPLIFIERS READY TO GO

Model 20SMP 5 Watt Ampl. as Pictured Above Features Mike & Phono Input. W/Bsp. Cabinet. Latest Compensated Tone Cntrl Design. Complete with Tubes $24.98
Model 302PA 3 Tube Phono Ampl. Ideal for Custom Building Your Phonograph $4.98
Model 20SMO Mike & OSC. Broadcasts Through Your Radio with No Direct Connection. W/Tube. "TAB" SPECIAL $6.98
Model 10SPO Phono OSC. Phonograph Broadcasts Through Your Radio. No Direct Hookup. W/Tube. "TAB" SPECIAL $4.98
TAB 30S Pre & Pwr Amp 8 Watt 30 to 20 KC $26.77
GARRARD RC 80 & GE XPX-050 ..... 42.00
WRITE FOR DETAILS & PRICES

ART 13A HI-VOLTAGE CERAMIC CONDENSERS
185MMF-20KVMMF
250MMF-40KVMF
Slip/2C0900-47A/11 All Four Condensers $2.49

CU-24/ART 13 LOADING CONDENSERS
Three 25MMF 10,000V cer. denscrs P/o ART13 XMTTR. NEW $2.49

ODDS & ENDS CLEARANCE SALE
Heliopot 50K ohm 10 Turn 0.5% 50EA2S $6.95
Attenuator 7470 & 1095 dual 15 step 3.45
Daven Attenuator T325D dual 600 ohm, 20 step 1½ DB per/step 10.98
Kennedy 6V Rectifier 1401 Battery 2.95
Locking cord 60 Waxed for cables 1.39
Locking cord 912 Waxed, linen 1.49
K. Miller stringer #100 & cutter 2.98
Carbide drills for TV/Ant ¼, ⅝, ½" ..... 2 for 3.49
Nytron adapter BR27, 28, 29 Asst ..... 3 for 5.00
Line filter F/S AR/ARC3 Installation, used, as-is 1.98

. . SPECIALS . . Powerstats & Test Equipment
Type 20/0-136V3Amp/(M) $16.98
Type 116U/0-136V/7.5 Amp/(M) 14.98
Type 116 As above, except cased (M) 16.49
Type 1126/0-136V/15 Amp/(LN) 29.50
Type 1156/0-136V/25 Amp/(LN) 41.98
SIMPSON-269 MIKRO-VOM Prepaid 83.00
EMC-206P Mu-Tube CHKR Prepaid 100.00
GR 50A/0-135V/15 Amp/5KV/(LN) 160.00
GR 50B/0-270V/21 Amp/5KV/(LN) 166.00
Simpson Model 260 VOM Prepaid 53.00
Hickok 600A Mu-Tube CHKR Prepaid 153.00
GE ST4A Beep Generator (M) 295.00
GE ST5A Marker Generator (M) 275.00
GE ST12A Oscilloscope (M) 275.00
HP-1 Oscilloscope (M) Special 79.95
(M) NEW & (LN) LIKE NEW

KITS AND COMPONENTS
Oil Condensers Assorted	5 for $1.25
Electrolytics Assorted	5 for 1.25
Silver & Mica Condors	15 for 1.25
Controls, Popular Values	5 for 1.25
Resistors, ½ & 1W	100 for 1.25
Vitreous W W Resistors	5 for 1.25
Sockets, 4, 5, 6, 7 & 8P	10 for 1.25
Iron Core Slugs & Screw	10 for 1.25
Knobs, Assrd. w/Insert	10 for 1.25

"TAB" PICK 'EM YOU $1.00
Special Lots of 5

CRYSTAL DIODES
IN23B Sylvania $1.89
New, Boxed & Jacketed Lots of 10
Smaller Quantity, Unit Price $2.25 ea
1N21	$1.69; 6 for $ 4.98
1N23A	$2.49; 4 for 7.98
1N23B	$1.89; 4 for $ 5.98
1N27	$1.49; 4 for 5.98
1N46	69c; 5 for 3.25

CIRCUIT BREAKER FUSES
PUSH TO RESET
Amps 3-5-7-10-15-20 No. 27c
4 for $1.; 28 for $5.; 100 for $15.
Circuit Breaker Fuse W/S Mounting Clips 25c; 6 for .. $1.00; 20 for .. $3.; 100 for .. $14.
Fuse 1 SAO Size. Operates up to 24 Volts. Please State Amps (current) desired.

MICA CONDENSERS

Fig. Mark	MFD	WVDC	PRICE
A	.02	600	49cc; 5 for 2.39
A	.03	600	49cc; 5 for 2.39
A	.015	2500	1.75; 2 for 3.00
A	.01	1000	49cc; 5 for 2.39
B	.01	1000	49cc; 5 for 1.25
B	.01	1200	69cc; 5 for 1.49
B	.005	2500	1.19; 3 for 3.00
B	.004	600	49cc; 5 for 1.49
B	.002	1200	49cc; 5 for 1.25
A	.002	2500	49cc; 5 for 1.25
A	.001	1200	49cc; 5 for 1.25
C	.0007	2500	49cc; 5 for 1.49
C	.0004	2500	49cc; 5 for 1.49
A	.0001	600	25cc; 5 for 1.49
C	.0001	2000	25cc; 5 for 1.49
C	.0001	3000	25cc; 5 for 1.49
C	.00005	3000	25cc; 4 for 1.49

¼" Electric Drill Model 200J

High torque (powerful) UL aprvd. 3400 RPM 115V AC/DC motor tested & geared for shock & hvy. self aligning silicon ball thrust bearing, comfortable & easy to handle. "TAB" special $14.95
Model 210 Drill stand, converts above 200J to a Drill press, special $9.49
79 Drills Chrome Vanadium Brand Steel. Quality for Machinists or All Purpose Use. 1/16 to ½ by 64th's. w/"Rust" Drill Index $9.69
Drills, 53 Pcs 1/16" to ½" in Index 2.49
Drills, 13 Pcs 1/16" to ¼" C.V. w/Index 1.49
Drills, 12 Pcs 1/16" to ¼" C.V. 1.49
¼" Speed Electric Drill with Jacobs wormgear chuck & 29 Pcs Drills & Index $39.00

AUDIO COMPONENTS

Western Electric Push-Pull Pentode Output Transformer 107A. Rated 10 Watts for 6V6's or 6A6's. Response Flat 30 to 10000 Cycles. Secondary 600 Ohm. "TAB" Special ..... $3.49; 2 for $6.98
UTC Varimatch line to voice coil or line 20 Watt New $1.98; Six for $10.
XFMR HMT-81D UTC Super Hivoltric 2 Wdg. 600 Ohm Ct & 400 Tapped 250 & 150 Ohm. Can be Used Mike to Grid, Line to Line & Line to Grid. Special 49c ..... 10 for $4.49; 100 for $35.00

UHF ANTENNAS

Microwave Antenna AB126/APB 1000 to 2400 MC W/UG48U Pigtail. Inbuilt Hi Pass filter. Flange mtg Special $4.98
Mobile Whip Ant 6 ft., Spring Steel. Broad response, with tenna. matching Base $2.49
UHF Antenna 12" 30CM ATV/ARRL mobile Dipper & Ham band, Insul coax Terminal, Mobil mounting ..... 39cc; 4 for $1.00
PL-259 plug for above antenna 69c

VARIABLE CONDENSER
Dual 715MMF Ea Section 1000V Gap Req $2.98 98¢ EACH
Vernier Drive 10 to 365MMF Each 89cc; 2 for 99c
Midget 3 to 15MMF, Mfdma Rack 29c
Hyfergell VM-40PE 35 to 312MMF, Cap. in Made Solit Stator. New 49c
2¼ Meter Butterfly Condenser 30MMF W/Knob ..... 89cc; 2 for 99c
Twin & Choke ..... 89cc; 2 for 99c

CONTACTOR

6 SPDT Clare CRS8013G34G Heavy Duty Electric Starter. Transmitter or Motor Starter Switch. For 115 or 3 or 2 Phase Appl. Rated 1 Phase 2HP/110V 7½ HP/230V 3 HP/460V Rated 3 Phase 7½ HP/110V, 15HP/230 V, 25HP/460V Control Input. 230V/12MA/60 Cy. Contacts rated 45 Amp Enclosed, 65 Amp Open. SPECIAL ..... $14.; 6 for $80

THAT'S A BUY "TAB" THAT'S A BUY
Dept. 11E 111 Liberty Street, New York 6, N. Y., U. S. A. PH. RECTOR 2-6245

Money Back Guarantee (Cost of Mdse. Only)
$5 Min. Order FOB N Y C. Add Shpg. Charges or 25% Dep. Tubes Gtd. via R-Exp. only. Prices Subject to Change Without Notice

INDEX TO ADVERTISERS

Ace Engineering & Machine Co., Inc..... 288
Acheson Colloids Company..... 37
Acme Electric Corporation..... 391
Advance Electric & Relay Co..... 320
Aeronautical Communications Equipment, Inc. 465
Aerovox Corporation 331
A'G'A Div. of Elastic Stop Nut Corporation of America..... 387
Air Marine Motors, Inc..... 335
Airborne Instruments Laboratory Inc... 57
Aircraft-Marine Products, Inc.....86, 87
Airpax Products Company..... 212
Alden Products Company..... 100
Alfax Paper & Engineering Co..... 439
Allen-Bradley Co. 102
Allen Co., Inc. L. B. 467
Allied Control Company, Inc. 54, 55
Allied Industries, Inc. 401
Allied Radio Corp. 366
Allmetal Screw Products Co., Inc. 260
Alpha Metals, Inc. 446
American Lava Corporation..... 277
American Phenolic Corporation.....96A, 96B
American Television & Radio Co..... 441
American Time Products, Inc. 287
Amperite Co., Inc. 282
Ampex Electric Corp. 367
Anaconda Wire & Cable Company...116, 117
Anti-Corrosive Metal Products Co., Inc... 418
Armco Steel Corporation 76
Arnold Engineering Co. 343
Art Wire & Stamping Co. 435
Assembly Products, Inc. 289
Astron Corporation 315
Atlas Engineering Co., Inc. 451
Audio Devices, Inc. 301
Audio Products Corp. 358
Automatic Mfg. Corp. 124
Aviation Engineering Div., Avien-Knickerbocker, Inc. 112

Ballantine Laboratories, Inc. 240
Barco Chemical Products Co. 423
Barker & Williamson, Inc. 378
Barnstead Still & Sterilizer Co. 382
Barrett Division, Allied Chemical & Dye Corporation 100, 101
Barry Corp., The..... 15
Bead Chain Mfg. Co. 390
Beaver Gear Works Inc. 348
Bell Telephone Laboratories 327
Bendix Aviation Corporation
Eclipse-Pioneer Div. 406
Red Bank Div. 272
Bentley, Harris Manufacturing Co. 337
Berkeley Division Beckman Instruments, Inc. 369
Berndt-Bach Inc. 467
Bird & Co., Inc., R. H. 448
Bird Electronic Corp. 440
Birnbach Radio Co., Inc. 411
Birtcher Corporation 385
Biwax Corporation 443
Bliley Electric Company 295
Boesch Manufacturing Co., Inc. 452
Boonton Radio Corp. 199
Bomac Laboratories, Inc. 200
Brand & Co., Inc., William 390
Bridgeport Brass Company 423
Bristol Brass Corporation 96
Brown Electro-Measurement Corp. 408
Brush Electronics Company 278
Burlington Instrument Company..... 405
Burnell & Company 21
Burroughs Corporation, Electronic Instruments Div. 221
Bussmann Mfg. Co. 329

Cambridge Thermionic Corp. 74
Cannon Electric Company 226
Centralab, A Div. of Globe-Union Inc. 11, 12, 13
Chester Cable Corp. 361
Chicago Standard Transformer Corp..234, 410
Chicago Telephone Supply Corp. 72, 73
Cinch Manufacturing Corp. 195
Citation Products Co. 463
Clarostat Mfg. Co., Inc. 361
Cleveland Container Co. 305
Cohn Corp., Sigmund 421
Collectron Corporation 395
Collins Radio Company 273
Columbian Carbon Company 447
Communication Accessories Co. 85
Communication Products Co., Inc. 431
Conrad & Moser 454
Consolidated Vacuum Corp. 211
Constantine Engineering Laboratories Co..514
Continental Connectors, DeJur Amsco Corp. 99
Continental-Diamond Fibre Co. 271
Control Engineering Corp. 23
Cornell-Dubilier Electric Corp. 325
Corning Glass Works 225
Cornish Wire Co., Inc. 456
Cosa Corporation 289
Cosmic Radio Corp. 443
Coto-Coil Company 459
Crane Packing Company 350
Crescent Company, Inc. 340
Cross Co., H. 515
Crowley & Co. Inc., Henry L. 41
Crucible Steel Company of America..... 217

Dage Electric Company, Inc. 444
Dale Products, Inc. 366
Dalmo Victor 233
Dano Electric Co. 425
Davelle Laboratories, Inc. 75
Daven Co., The .....Third Cover
Davis Electric Company 286
DeJur Amsco Corp. 99, 408
Devtronics Inc. 449
Dialight Corporation 208
Diehl Manufacturing Company..... 352
Driver-Harris Company 229
Dumont Laboratories, Inc., Allen B....36, 79
du Pont de Nemours & Co. (Inc.) E. I. Polychemical Department 241
Durant Mfg. Company 450

Eastman Kodak Company, Special Products Sales Div. 215
Edison Incorporated, Thomas A. 336
Edo Corporation 92
Elsler Engineering Co., Inc. 397, 467
Eitel-McCullough, Inc. 31
Elco Corporation 451

TAB THAT'S A BUY!

Money Back Guarantee (Cost of Mdse Only) $5 Min. Order FOB N. Y. C. Add Shpg. Charges & 25% Dep. Prices Subject to Change Without Notice. Phone: REctor 2-6245 Cable: "Tabparts"

TUBE SPECIALISTS

0A2 $8.00 | 0A2/VR75 1.04 | 0B2 1.30 | 0B2/VR90 .26 | 0C2/VR105 .92 | 0D3/VR150 .87 | 1B3/8016 .80 | 1B22 1.82 | 1B23 1.82 | 1B24 8.98 | 1B26 2.24 | 1B27 11.50 | 1B32/532A 2.40 | 1B35 14.87 | 1B36 29.46 | 1B40 49.50 | 1B42 17.46 | 1B46 1.98 | 1B63 45.00 | 1L4 .48 | 1L5 1.98 | 1LD5 .98 | 1LN5 .78 | 1P5 .98 | 1P21 33.00 | 1U4 .92 | 1U5 .78 | 1V2 .78 | 1X2A 1.39 | 2C35 27.00 | 2C39A 29.50 | 2C40 7.50 | 2C43 17.46 | 2C44 1.35 | 2C46 1.35 | 2D21 1.35 | 2E43 2.49 | 2J31 27.50 | 2J32 29.48 | 2J33 27.90 | 2J34 24.98 | 2J37 12.70 | 2J38 69.98 | 2J39 4.90 | 2J42 148.98 | 2J48 24.50 | 2J49 14.00 | 2J50 99.98 | 2J55 84.00 | 2J56 149.- | 2J62 .- | 2K22 23.48 | 2K25 11.48 | 2K26 28.48 | 2K25/725AB 23.88 | 2K28 27.48 | 2K29 215.00 | 2K30 134.99 | 2K41 126.00 | 2K42 145.00 | 2K43 129.48 | 2K48 99.48 | 2P2 294.50 | 2X2 .42 | 3B22/RK23 1.49 | 3B24 4.70 | 3B25 1.35 | 3B26 7.98 | 3B28 7.98 | 3C22 85.00 | 3C23 .- | 3C31/C16 1.45 | 3C33 3.53 | 3C45 14.50 | 3D6/1J99 .69 | 3D21A 8.98 | 3D22 12.98 | 3D23 6.50 | 3E29 14.49 | 4C18 23.49 | 4D21 13.99 | 4E27 22.49 | 4J32 129.50 | 4J33 .- | 4J52 199.98 | KL5BND 13.98 | 5C21/C6J 3.95 | 5C22 38.95 | 5D21 14.98 | 5J29 11.97 | 5R4GY 1.29 | 5R4GYW 1.29 | 5T4 1.48 | 5U4G .86 | 5V4G .86 | 6AG5 .71 | 6AG7 1.14 | 6AH6 1.22 | 6AJ5 1.49 | 6AK5 .77 | 6AK5W 2.98 | 6AL5 .48 | 6AL7GT .98 | 6AN5 2.98 | 6AQ5 .92 | 6AQ5W 2.29 | 6AQ6 .81 | 6AQ7GT 1.29 | 6AR6 2.98 | 6AS6 .78 | 6AS6 2.29 | 6AS7G 3.29 | 6AT6 .84 | 6AU5GT 1.10 | 6AU6 .78 | 6AV5GT .98 | 6AV6 .49 | 6B4G 1.18 | 6BA6 .78 | 6BA7 1.27 | 6BC5 .98 | 6BC7 1.29 | 6BD5 .98 | 6BE6 .59 | 6BF6 .78 | 6BQ5 1.19 | 6BN6 .63 | 6BJ6 .89 | 6BK7 1.49 | 6BL7GY 1.98 | 6BN7 1.98 | 6BQ6GT 1.29 | 6C4 .62 | 6C21 24.50 | 6CB6A .78 | 6CD6G 1.69 | 6D4 2.79 | 6E5/6C21 5.49 | 6F6 .89 | 6F8G .98 | 6G6G .89 | 6GA4 1.49 | 6L6 1.49 | 6L6GA 1.49 | 6L6GAY 1.98 | 6SA7GT .66 | 6SC7 .98 | 6SF5 .73 | 6SF7 .73 | 6SG7 .84 | 6SH7 .98 | 6SJ7 .98 | 6SK7GT .98 | 6SL7GT .98 | 6SN7GT .98 | 6SQ7GT .62 | 6SR7 .62 | 6SS7 .98 | 6V6 .98 | 6V6GT .62 | 6W4GT .62 | 6X5GT .58 | 6Y6G .89 | 7A8 .62 | 7B7 .98 | 7F7 .82 | 7F8 1.24 | 7H7 .82 | 7N7 .92 | 7V7 1.06 | 7Y4 .68 | 8D21 298.00 | 12AL5 .76 | 12AT6 .54 | 12AT7 1.25 | 12AU6 .78 | 12AU7 .82 | 12AV6 .78 | 12AV7 .98 | 12AW6 1.18 | 12AX7 .98 | 12AY7 1.88 | 12BA6 .60 | 12BA7 .94 | 12BD6 .78 | 12BE6 .60 | 12BF6 .85 | 12BH7 1.25 | 12SA7GT .68 | 12SC7 1.08 | 12SF5GT .72 | 12SF7GT .84 | 12SG7 .60 | 12SH7 .62 | 12SJ7GT .62 | 12SK7 .62 | 12SL7GT .82 | 12SN7GT .84 | 12SQ7GT .84 | 12SR7 .66 | 12SX7 3.50 | 24G/3C24 1.32 | 25B06GT .88 | 25L6GT .98 | 25Z5 .98 | 25Z6GT .98 | FG27A 9.24 | 28D7 1.50 | 35Z5GT .84 | 35Z4GT .68 | 35W4 .68 | 45Z3 .88 | 48 1.98 | 50A1 .98 | 50C5 .62 | 50L6GT .62 | FG67 14.50 | HY69 4.98 | 71A .74 | 78 .78 | RK61/XFG1 2.85 | 80 .66 | 81 1.30 | 83 1.30 | 807 1.72 | 83V .- | 84/6Z4 .62 | 100TH 9.50 | FG104 24.50 | FG105 57.64 | 211/VT4C 1.95 | 211/VT4C 1.98 | 1372GT .98 | VXR136 4.50 | CV148 4.50 | FG148 4.50 | FG177 29.00 | 211/VT4C .- | RK21A 7.49 | RK23A 4.78 | 250TH 15.97 | 250TL 17.75 | 304TH 5.98 | 304TL 3.98 | 311A .- | 388A 1.49 | WL417A 1.49 | 417A/4B32 14.50 | GL434A 12.00 | 446A .98 | 446B 1.45 | 450TH 49.97 | 450TL 52.00 | 450/MP250 19.98 | CK502AX .- | CK505AX 1.49 | CK506AX 1.79 | CK508AX 1.98 | CK511DX .- | CK512DX .- | WL532A 1.98 | CK533AX 1.29 | CK534AX .- | CK535AX .- | CK536AX .- | CK537DX .- | CK538DX 2.19 | CK540DX .- | CK542DX .- | CK544DX .- | CK546DX .- | CK571AX/ 1.98
5686 2.49
CK573AX/
6070 3.49
WL632 14.95
WL676 14.95
703A .- | 707A .- | 707B .- | 707C .- | 715B .- | 715C 17.50 | 717A .- | 718EY 44.50 | 718GY 44.50 | 719A 24.48 | 721A 2.69 | 721A/3BY 2.69 | 723A/B 10.50 | 724A 1.98 | 725A .- | 725B .- | 726A 14.48 | 726B 44.48 | 726C 64.48 | 803 1.98 | 805 1.98 | 807 1.98 | 808 1.98 | 809 1.98 | 810 10.98 | 813 3.98 | 814 3.98 | 815 11.48 | 816 4.98 | 826 7.98 | 829B 12.50 | 832 7.98 | 832A 39.48 | 836 6.95 | 837 1.49 | 838 20.48 | 845 3.98 | 861 1.98 | 865 1.98 | 872A 1.98 | 917 2.89 | 927 1.98 | 927/CK26 1.79 | CK1005 .98 | 1613 .- | 1614 1.98 | 1620 .- | 1621 .- | 1622 .- | 1623 .- | 1624 1.98 | 1625 1.98 | 1626 1.98 | 1642 .98 | 1644 .- | 1648 1.98 | 2050W 7.48 | 5635 11.97 | 5636 11.97 | 5640 11.97 | 5641 7.53 | 5643 11.97 | 5644 11.97 | 5645 11.97 | 6065 3.34 | 6064 1.72 | 6066 1.72 | RK15057 298.48 | 6067 1.48 | 6072 1.98 | CK1072 1.98 | CK1075 1.98 | 6082 7.34 | 6083 2.79 | 6939 1.98
Xtal Diodes
1N21A $1.95 | 1N22 1.12 | 1N23 1.12 | 1N23A 1.12 | 1N23B 1.12 | 1N25 1.12 | 1N26 1.12 | 1N27 1.12 | 1N34 .84 | 1N34A .98 | 1N34A 1.49 | 1N35 1.49 | 1N41 1.49 | 1N42 14.95 | 1N43 .98 | 1N45 .98 | 1N47 .98 | 1N48 .98 | 1N54 4.98 | 1N55 .98 | 1N56 .98 | 1N56A 1.49 | 1N56B 1.49 | 1N63/K63 2.49 | 1N64 .49

"TAB" Dept. 11E 111 Liberty St. New York 6, N. Y., U. S. A. REctor 2-6245 Cable; "Tabparts"

Headquarters for all the leading brands in the tube industry. We stock 5000 different tube types. Send us your queries we either have it, or can get it, at a price that can't be beat. We stock almost a 1000 different tube types. All tested & guaranteed. "TAB" SERVES THE INDUSTRY.

Want more information? Use post card on last page.

Electric Regulator Corp. 319
Electrical Industries, Div. of Amperex Electronic Corp. 333
Electrical & Physical Instrument Corp.. 451
Electro Engineering Products Co. 431
Electro Tec Corporation 249
Electro-Technical Products, Div. of Sun Chemical Corp. 338
Electronic Associates Incorporated 262
Electronic Ceramics Co. 463
Electronic Expediters 97
Electronic Instrument Co., Inc. 515
Electronic Parts Manufacturing Co., Inc.. 389
Electronic Transformer Company 52
Electronic Tube Corporation 356
Electrons, Inc. 105
Emerson & Cuming, Inc. 326
Empire Devices Products Corp. 445
Engineering Co. 400
Epco Products, Inc. 419
Erie Resistor Corporation 43
Ethylene Chemical Corporation 468

TUBE CHECKER by MANSON

TRANSMITTING-TUBE STATIC-CHARACTERISTIC CHECKER
FOR TUBES FROM 20 W TO 250 KW PLATE DISSIPATION



For point-by-point pulse-technique measurements of characteristics of large transmitting tubes. Overall accuracy within 2%. Entire unit completely interlocked for safety and is operable by a technician.

Measurements by a built-in synchroscope and pulse amplifier, which can be calibrated without auxiliary equipment. Wide Range of available TUT Voltages.

Plate Currents from 300 A (or more) to 30 ma; **Screen** Currents from 30A to 3 ma; and **Grid** Currents from 200A to 10 ma.

Almost any range of Voltages and Currents can be supplied. Outline your requirements when requesting details and prices of test equipment.

MANSON LABORATORIES / Industrial Control Devices — Electronic and Electro-Mechanical Instruments

207 Greenwich Avenue • Stamford, Conn.

Fairchild Camera & Instrument Corp. .. 304
Fairchild Engine & Airplane Corporation 210
Fansteel Metallurgical Corp. 252
Federal Telephone & Radio Corp. 81
Federated Metals Div. American Smelting & Refining Co. 328
Ferranti Electric, Inc. 309
Ferroxcube Corporation of America 93
Film Capacitors, Inc. 461
Five Star Company 467
Ford Instrument Company 425
Freed Transformer Co., Inc. 293
Frequency Standards 444
Furst Electronics 439

Get It FREE... Use It!

Your Helping Hand!

Most Complete Electronic BUYING GUIDE

FREE! 1954 HUDSON MASTER CATALOG

. . . your helping hand for Everything in Electronic Equipment. Over 1000 pages of the latest in Radio, TV and Industrial Electronics. High Fidelity and PA Sound Equipment PLUS JAN Type Electronic Components. If it's new . . . HUDSON has it FIRST! Leading Authorized Distributor in the East. Our new Catalog is Quick, Convenient . . . Time and Money Saving! ONE Complete Dependable Source . . . ONE Order . . .

HEADQUARTERS FOR RCA

RCA AUTHORIZED DISTRIBUTOR

TUBES • PARTS • BATTERIES
TEST EQUIPMENT

One Call for All!

AUTHORIZED FACTORY DISTRIBUTORS
Hudson
RADIO & TELEVISION CORP.
ELECTRONIC & SOUND EQUIPMENT

Three Great Fully Stocked Salesrooms to Serve You!

Adjoining Radio City: 48 West 48 St., New York 36, Circle 6-4060
Downtown New York: 212 Fulton St., New York 7, Circle 6-4060
In New Jersey: 35 William St., Newark 2, N. J., MArket 4-5151

Engineers, Purchasing Managers, Qualified Executives . . . You NEED our Great New Catalog in your daily work — Send in your request today, on your company letterhead, for YOUR FREE COPY. Dept M-11

G-M Laboratories, Inc. 391
G-V Controls, Inc. 392
Gabriel Laboratories, The 290
Gamewell Company 220
Garlock Packing Company 222
Gee-Lar Manufacturing Co. 417
General Ceramic & Steatite Corp. 88
General Electric Company
Apparatus Dept. 80, 107, 126, 127, 297
Chemical Div. 354
Electronic Dept. 33, 77
Tube Dept. 45, 120, 121
General Precision Laboratory, Inc. 275
General Radio Company 17
General Transformer Co. 432
Good-all Electric Mfg. Co. 239
Goodmans Industries Limited 42
Green Instrument Co., Inc. 431
Gries Reproducer Corp. 442
Gudebrod Bros. Silk Co., Inc. 431

Hammarlund Manufacturing Co. Inc. ... 216
Hanovia Chemical & Mfg. Co. 417
Hart Manufacturing Company 292
Hathaway Instrument Co. 434
Haydon Company, A. W. 445
Haydon Manufacturing Co., Inc. 374, 375
Heath Company 297
Helland Research Corp. 238
Heldor Manufacturing Corp. 65
Helipot Corporation, a division of Beckman Instruments, Inc. 291
Heminway & Bartlett Mfg. Co. 405
Hermaseal Company, Inc. 247
Hermetic Seal Products Co. 39

Hetherington, Inc. 363
Hewlett-Packard Company 82, 83
Hexacon Electric Co. 415
Heyman Manufacturing Company 456
Hickok Electrical Instrument Co. 427
Hinde & Dauch 346
Hitemp Wires Inc. 318
Hofmann Needle Works, Inc. 393
Hopkins Engineering Co. 232, 451
Hudson Radio & Television Corp. 512
Hudson Tool & Die Company, Inc. 106
Hudson Wire Co. 307
Hughes Aircraft Company 251
Hughes Research & Development Laboratories 250
Hycor Sales Company of Calif. 399

I-T-E Circuit Breaker Co. 436
Ideal Industries Inc. 438
Illinois Condenser Co. 459
Industrial Control Co. 463
Industrial Hardware Mfg. Co., Inc. 425
Industrial Mica Corporation 435
Industrial Test Equipment Co. 459
INFRA Electronic Corp. 447
Institute of Radio Engineers, The..... 311
Instrument Corp. of America 104
Instrument Resistors Co. 393
Insulation Manufacturers Corp. 330
International Crystal Mfg. Co. 388
International Instruments, Inc. 421
International Nickel Company, Inc. 64
International Rectifier Corp. 344
International Resistance Co. 28, 29
Ippolito & Co., Inc., James..... 395
Irvington Varnish & Insulator Co. 110

Jelliff Manufacturing Corp., C. O. 443
Jennings Radio Mfg. Co. 328
Johnson Company, E. F. 342
Jones Div., Howard B. Cinch Mfg. Co.... 419
Joy Manufacturing Company 56

Kahle Engineering Company 407
Kaibfell Laboratories, Inc. 296
Karp Metal Products Co., Inc. 111
Kartron 467
Kay Electric Company 351
Kearfott Company, Inc. 430
Keller Tool Co. 50, 51
Kepco Laboratories, Inc. 363
Kester Solder Company 245
Ketay Manufacturing Corp. 321
Keuffel & Esser Company 58, 59
Keystone Bolt & Nut Corp. 425
Keystone Electronics Company 409
Keystone Products Company 365
Kirk & Blum Mfg. Co. 422
Klein & Sons, Mathias 236
Knights Company, James 310
Kollsman Instrument Corporation 214

Laboratory for Electronics, Inc. 283, 385
Lambda Electronics Corporation 449
Lampkin Laboratories, Inc. 467
Lamson & Sessions Co. 30
Landis & Gyr, Inc. 460
Lapp Insulator Company, Inc. 306
Lavoie Laboratories, Inc. 415
Lear, Inc. 303
Lenkurt Electric Sales Co. 376, 377
Lewis Engineering Co. 385
Lewis Spring & Mfg. Co. 334

For the "Firsts" in Fluorocarbons

SEE U.S.G.

TEFLON* and KEL-F† STOCK and FABRICATED PARTS

The United States Gasket Company offers the most complete line of sheets, rods, tape, tubing, bars, cylinders and fabricated parts — custom-molded and machined to specifications.

This means one source for all your requirements—with uniform high quality assured by the most modern specialized facilities for low-cost, close-tolerance production. Ask for Catalog No. 300 and 500.

TEFLON "ALLOYS"

Chemelec Mixtures, which are "alloys" of Teflon, offer the product engineer a whole new family of materials. These alloys retain most of the outstanding qualities of pure Teflon and add new properties to meet particular material requirements.

If you want TEFLON "alloyed" with metal, glass, ceramics, carbon, mica, quartz, alnico, asbestos, silicate, calcium, or boron, etc., bring us your problems. Ask for Catalog No. MI-400.

SOLDERABLE TEFLON

Chemelec Multi-Bond Metal Faced Teflon permits the bonding and hermetic solder sealing of this dielectric material to metal components.

The bond between metal surface and the Teflon is microcrystalline in nature—an interlocking metal-permeated surface layer of the fluorocarbon.

Metal facings include practically all the ferrous and nonferrous metals, the ferro-magnetic group and the precious metals. Catalog No. MI-424.

CEMENTABLE TEFLON

Chemelec Multi-Bond Cementable Teflon is a specially prepared fluorocarbon which will adhere to metal, glass, wood, fibre, asbestos, plastics, leather, ceramics, or other substances by the use of suitable commercial cement.

A broad field of electrical, mechanical and chemical applications is opened to product engineers. Write for Catalog No. MI-443.

UNITED STATES GASKET COMPANY

FLUOROCARBON PRODUCTS DIVISION
CAMDEN 1, NEW JERSEY

Representatives in Principal Cities Throughout the World

*duPont Trademark
†M. W. Kellogg Trademark

Celco **Manufacturers of:**

TRANSFORMERS VARIABLE REACTORS MAGNETIC AMPLIFIERS



1. OUTPUT, MATCHING, COUPLING, AND POWER SIGNAL 400 CYCLE TRANSFORMERS: used where reliability and miniature size is required, such as control amplifying systems. Supplied with any special lead wires or terminations.

2. DUAL MAGNETIC AMPLIFIERS: all types used in latest 400 cycle aircraft control amplifiers for Servo Systems.

3. VARIABLE REACTOR: used today in tuned resonant circuits for vacuum tube voltage regulating systems. Suitable for experimental laboratory work where a HI-Q and wide range of inductance is required.

4. TRIPLE MAGNETIC AMPLIFIER: used in aircraft automatic pilots, by both the Army Air Force and Navy.

5. HERMETICALLY SEALED TRANSFORMERS: designed to conform to military specifications for hermetically sealed transformers, magnetic amplifiers and reactors.

6. FLY BACK: HORIZONTAL OUTPUT AND HIGH VOLTAGE TELEVISION TRANSFORMER: manufactured for extra quality performance of very low costs.

COMMERCIAL USE

Omni-Range; Dme; Line Course Computers; Automatic Pilots; Navigation; Transmitters and Receivers; Oil Burner Ignition; Fly Back; Vertical Output; Linearity Controls.

MILITARY USE

Servo Amplifiers; Adjustable Reactors; Transistor Magnetic Amplifier; Class H Transformers; Drone Control; Guided Missile; Voltage Control; Marine Control; Sonar; Celco Research.

Celco Gives Prompt Service—send us your requirements for our immediate attention.

Celco *Constantine Engineering Laboratories Co.*

ISLAND AVENUE MAHWAH, NEW JERSEY

Linde Air Products Co., A Div. of Union Carbide & Carbon Corp. 427
Link Aviation, Inc. 284
Lion Fasteners, Inc. 382
Littelfuse, Inc. 123
Litton Engineering Laboratories 46

MB Manufacturing Co., Inc. 32
MacLaughlin Corp. J.L.A. 383
Magna Driver Corp. 395
Magnatran Incorporated 440
Magnecord Inc. 242
Magnetics, Inc. 457
Mallory & Co., Inc., P. R. 128, 197
Manson Laboratories 512
Marconi Instrument, Ltd. 332
Marion Electrical Instrument Co. 258
McGraw-Hill Book Co. 401
Measurements Corporation 421
Mepco, Inc. 38
Mercury Tube Co. 459
Metal Textile Corp. 403
Metals & Controls Corp., General Plate Div. 257
Mica Insulator Company 235
Micro, A Division of Minneapolis-Honeywell Regulator Co. 294
Midland Manufacturing Co., Inc. 267
Miles Reproducer Co. 467
Millen Mfg. Co., Inc., James 265
Millivac Instrument Corp. 386
Milwaukee Transformer Co. 384
Miniature Precision Bearings Inc. 208
Minneapolis-Honeywell Regulator Co., Industrial Div. 84
Minnesota Mining & Mfg. Co. 323
Mission-Western Engineers, Inc. 340
Mitchell-Rand Insulation Co., Inc. 357
Moloney Electric Company 243
Motordyne Inc. 465
Muirhead & Co., Ltd. 3

National Company, Inc. 280
National Moldite Co. 27
National Pneumatic Co., Inc. & Holtzer-Cabot Divisions 259
National Research Corporation 339
National Vulcanized Fibre Co. 47
Natvar Corporation 98
New London Instrument Co. 419
New York Transformer Co., Inc. 402
Ney Company, J. M. 458
Nielsen Hardware Corp. 447
Northeastern Engineering Inc. 347
Notheifer Winding Laboratories 448

Ohmite Mfg. Co. 32A, 32B
Olympic Metal Products Co., Inc. 330
Opad-Green Company 462
Oster Manufacturing Co. John 393

PM Industries, Inc. 78
Pacific Scientific Company 450
Panoramic Radio Products, Inc. 223
Par-Metal Products Corp. 280
Penn Engineering & Manufacturing Corp. 368
Phalo Plastics Corporation 312
Phaostron Company 447

Phelps Dodge Copper Products Corp., Inca Manufacturing Div. 48, 49
Pheoll Manufacturing Co. 254
Pickard & Burns, Inc. 420
Pix Manufacturing Co., Inc. 409
Polarad Electronics Corporation 58
Polymer Corporation of Penn. 360
Polytechnic Research & Development Company, Inc. 317
Potter Instrument Company, Inc. 426
Precise Measurement Co. 467
Precision Apparatus Co., Inc. 516
Premier Instrument Corp. 454
Precision Paper Tube Co. 387
Price Electric Corp. 291
Pye Limited 122
Progressive Manufacturing Co. 286
Pyroferric Co., Inc. 281

Quality Products Co. 407

R. F. Electronics Inc. 443
Radio Corporation of America ..... Back Cover
Radio Materials Corporation 108
Radio Receptor Company, Inc. 66
Railway Communications, Inc. 404
Railway Express Agency, Air Express Div. 207
Rapid Electric Co. 401
Rauland Corporation 313
Rawson Electrical Instrument Co. 461
Raybestos-Manhattan, Inc. 237
Raytheon Manufacturing Company 19
R-B-M Division, Essex Wire Corp. 204
Reeves Hoffman Corporation 372
Representatives of Electronic Products Manufacturers, Inc. The 468
Republic Foil & Metal Mills, Inc. 274
Resin Industries, Inc. 461
Resistance Products Co. 322
Revere Copper and Brass Inc. 219
Rex Rheostat Co. 467
Rome Cable Corporation 113
Rutherford Electronics Co. 443

Sanborn Company 355
Sanders Associates, Inc. 349
Sangamo Electric Company 398
Saratoga Industries, Inc. 348, 439
Schuttig & Co. Incorporated 457
Scientific Electric Div. of "S" Corrugated Quenched Gap Co. 407
Scientific Electronic Labs. Inc. 459
Scintilla Magneto Div., Bendix Aviation Corporation 263
Secon Metals Corporation 417
Servo Corporation America 248
Shallcross Manufacturing Co. 218, 416
Shure Brothers, Inc. 415
Sierra Electronic Corporation 284
Sigma Instruments Inc. 302
Signal Engineering & Mfg. Co. 407
Simmons Fastener Corporation 341
Smith, Inc., Herman H. 296
Sorensen & Company, Inc. 2
Southern Electronics Co. 435
Sprague Electric Company 9, 224
Stackpole Carbon Co. 25
Standard Electric Time Company 265
Standard Electrical Products Co. 314
Standard Piezo Co. 419
Stanford Research Institute 453
Sterling Engineering Company, Inc. 256
Sterling Transformer Corp. 327

GRIP ON

TO YOUR SMALL PARTS HANDLING PROBLEM...

with the NEW AUTOMATIC PICK-UP TWEEZER

A practical, versatile, ALL STAINLESS STEEL instrument designed to make the handling of small objects an easier, less time consuming operation.

Indispensable for picking-up, positioning or holding hot, sterile, highly polished, or oddly shaped objects and for GETTING INTO HARD TO REACH SPACES.

Pressing the plunger causes 3 Strong, Hooked, Spring Steel Fingers to extend from the tip and flare out.

Releasing the plunger causes them to withdraw. Any object within their grasp is then firmly held WITHOUT CONTINUED FINGER PRESSURE.

Send for your Tweezers today, and see how and where this practical versatile tool can aid you:

- In manufacturing
- Component assembly
- Precision work
- Maintenance work of all types
- Laboratory situations

Price $2.25—4½" length. Other sizes available. Write for quantity prices.

WIN SALES COMPANY
Dept. E., P.O. Box 257
Forest Hills, N. Y.

for the ELECTRONIC INDUSTRIES

Quality Ribbons STRIPS

MOLYBDENUM
TUNGSTEN
TANTALUM
FORMED PIECES

Your Special Metals Rolled to Thin Sizes & Close Tolerances

YOUR INQUIRIES WILL RECEIVE PROMPT ATTENTION

H. CROSS CO.
15 BEEKMAN ST., N. Y. 38, N. Y.
WOrth 2-2044 and COrtlandt 7-0470



425K 5" Scope Kit $44.95. Wired $79.95.

YOU BUILD EICO KITS IN ONE EVENING-

221K VTVM Kit $25.95. Wired $49.95.

but they last a lifetime... and you save 50%

24 INSTRUMENTS - the industry's most complete line of MATCHED TEST INSTRUMENTS

565K Multimeter Kit $34.95. Wired $59.95. 20,000 ohms/volt.

¼ - **million** EICO instruments are now in use the world over! That's the proof of EICO's leadership in **Value.**

NEW 377K Sine & Square Wave Audio Gen. Kit $31.95. Wired $49.95

For latest precision engineering, finest components, smart professional appearance, lifetime performance and rock-bottom economy—**see** and **compare** the EICO line **at your jobber's** today **before you buy any higher-priced equipment!** You'll agree with over 100,000 others that only EICO Kits and Instruments give you the industry's greatest values at lowest cost.

360K Sweep Gen. Kit $34.95. Wired $49.95

Write NOW for FREE latest Catalog E-11

1040K Battery Elim. Kit $28.95. Wired $34.95.

625K Tube Tester Kit $34.95. Wired $49.95

Laboratory Precision at Lowest Cost

Prices 5% higher on West Coast.

EICO

©1952 INSTRUMENTS & KITS
ELECTRONIC INSTRUMENT CO., Inc.
84 Withers Street, Brooklyn 11, N. Y.

PRECISION

SERIES EV-10A
VTVM-Megohmmeter

TRUE ZERO CENTER VTVM
7" FULL VIEW METER
with DIRECT PEAK READING HIGH FREQ. SCALES
Plus Standard 1000 Ohms per Volt Functions

59 Ranges to: 6000 Volts, 2000 Megohms, 12 Amperes, + 77DB

D.C. VTVM ranges to ±60 KV when used with TV-4 High Voltage Safety Test Probe.

RANGE SPECIFICATIONS

★ **EIGHT ZERO-CENTER VTVM RANGES:** ±3, ±12, ±60, ±120, ±300, ±600, ±1200, ±6000 volts D.C.

★ **HIGH INPUT RESISTANCE—** 13⅓ megs. to 600 V. 26⅔ megs. at 1200 V. 133⅓ megs. at 6000 volts.

★ **FOUR DIRECT PEAK READING RANGES:** 0-3-12-60-120 peak volts. (Requires Series RF-10A High Frequency Probe described below.

★ **SIX OHM and MEGOHMMETER RANGES:** 0-2000-200,000 ohms. 0-2-20-200-2000 megohms.

★ **EIGHT EXTRA A.C.-D.C. VOLT RANGES** at 1000 /V. for routine circuit testing. 0-3-12-60-120-300-600-1200-6000 volts.

★ **EIGHT D.C. CURRENT RANGES:** 0-300 microamperes. 0-1.2-6-30-600-1200 MA. 0-1.2 Amperes.

★ **EIGHT DB RANGES:** —20 to + 77 db. Calibrated for 1 MW., 600 ohms zero db.

IMPORTANT FEATURES

★ **Voltage Regulated-Bridge Type Circuit.**

★ **True Zero-Center VTVM**—Simultaneously indicates both voltage and polarity.

★ **Rotary Range and Function Selectors.**

★ **Recessed 6000 volt Safety Jacks.**

★ **Shielded Coax Test-Cable Connectors** for both D.C. and R.F. probes.

★ **Electronic-Bridge Ohm-Megohmmeter.** Uses 2 self-contained 1.5 V. batteries.

★ **Extra-large 7" Rectangular PACE Meter.** 200 microampere, ±2% sensitivity.

★ **1% Film Type and Wire-Wound Resisters.**

EV-10A (MCP) in black ripple finished, heavy gauge steel case. Size 10½" x 12" x 6". Complete with coaxial circuit isolating test probe, shielded ohmmeter test cable, standard test leads, ohmmeter battery and manual.....**$99.75**

SERIES RF-10A R.F. Probe

Accessory for Series EV-10A above; affords direct high frequency peak voltage measurements. Employs 9002 miniature tube.....**$14.40**

PRECISION APPARATUS CO., INC.

92-27 Horace Harding Boulevard, Elmhurst 13, New York

Export Division: 458 Broadway, New York 13, U.S.A. Cables: Morhanex

In Canada: Atlas Radio Corp. Ltd., 560 King Street, W., Toronto 2B

Stevens Manufacturing Co., Inc. 266
Stoddart Aircraft Radio Co., Inc. 380, 381
Stone Paper Tube Company, Inc. 345
Struthers-Dunn, Inc. 364
Stupakoff Ceramic & Mfg. Co. 213
Sturtevant Co., P. A. 463
Sun Parts Distributors, Ltd. 467
Superior Electric Co. 35
Superior Tube Co. 114
Sylvania Electric Products, Inc....7, 299, 397, .. 466
Synthane Corporation 61

Taylor Fibre Company 67
Tech Laboratories, Inc. 270
Technical Service Corp. 435
Technitrol Engineering Co. 403, 458
Technology Instrument Corp. 428, 429
Telner Company, Inc., Roland 427
Tektronix, Inc. 446
Tel-Instrument Co., Inc. 394
Telechrome, Inc. 391
Teletronics Laboratory, Inc. 60, 467
Telewave Laboratories, Inc. 453
Telex, Inc. 437
Tensolite Insulated Wire Co. Inc. 411
Terpening Co., L. H. 258
Texas Instruments, Inc. 227
Thomas & Skinner Steel Products Co., Inc. 90, 91
Thompson-Bremer & Co., Sub. of American Machine & Foundry Co. 125
Thor Ceramics, Inc. 399
Tinnerman Products, Inc. 68
Titeflex, Inc. 255
Tobe Deutschmann Corp. 424
Trad Television Corp. 464
Transistor Products, Inc. 452
Trans-Sonics, Inc. 462
Transradio, Ltd. 232
Triplett Electrical Instrument Co. 44
Tung-Sol Electric, Inc. 64A, 64B

Ucinite Co. 118
Union Carbide & Carbon Corp., Linde Air Products Div. 427
Union Switch & Signal, Div. of Westinghouse Air Brake Co. 62, 63
United-Carr Fastener Corporation 119
United Electronics Corporation 269
United Manufacturing & Service Company 399
United States Gasket Co. 513
United States Radium Corp. 379
United States Wire & Cable Corp. 373
United Transformer Co. .....2nd Cover
Universal Mfg. Co. 467
U. S. Components, Inc. 438

Van Nostrand Co., Inc. D. 464
Varflex Sales Co., Inc. 285
Varian Associates 279
Veeder-Root, Inc. 40
Vickers Electric Div., Vickers, Inc. 266
Victoreen Instrument Co. 306
Victory Engineering Corp. 460

Waldes Kohinoor, Inc. 115
Ward Leonard Electric Co. 70, 71
Warren Wire Co. 84
Waterman Products Co., Inc. 276
Webber Mfg. Co., Inc. 415
Western Gear Works 105
Westinghouse Electric Corp.....89, 94, 95, 359
Weston Electrical Instrument Corp. 231
White Dental Mfg. Co., S. S. ...370, 371, 400
Wiley & Sons, Inc., John 405
Williams & Cox., C. K. 411
Willys Electronics Division of Willys Motors, Inc. 60
Winchester Electronics, Inc. 316
Win Sales Company 515
Workshop Associates, Div. of Gabriel Company 334

Xcelite, Inc. 439

Zophar Mills, Inc. 437

PROFESSIONAL SERVICES..... 469

SEARCHLIGHT SECTION
(Classified Advertising)
H. E. HILTY, Mgr.

SEARCHLIGHT ADVERTISERS INDEX
508, 509

This index is published as a convenience to the readers. Every care is taken to make it accurate, but ELECTRONICS assumes no responsibility for errors or omissions.

Want more information? Use post card on last page.



Three-in-one—Easily Portable

DAVEN TRANSMISSION MEASURING SET TYPE 12-A

For Measuring the Characteristics of Microwave Relay Systems

This unit provides the necessary information on transmission characteristics for the installation of terminal equipment, for the maintenance of terminal equipment, and for the field service of transmission lines and terminal equipment for microwave relay systems.

In one portable unit for efficient field use are combined the functions which normally would be performed by a separate Vacuum Tube Voltmeter, Audio Oscillator and Equalization Filters.

This unit has filters for providing response curves for accurate indication of 144, F1A or flat transmission lines. The 12-A also has provision for measurement of harmonic distortion and has its own self-contained low distortion 1000 cycle oscillator with variable amplitude.

The amplifier of the 12-A provides range levels from plus 20 to minus 80 DBM in calibrated steps of 10 Db. The associated meter is calibrated in 0.5 Db steps. The dynamic characteristics of the indicating meter are such that its response approximates the speed of appreciation of sounds by the ear.

This unit has line blocking capacitors for use across central battery and dial telephone lines.

Write for additional specific information and for catalog material.

THE DAVEN CO.
191 Central Avenue
Newark 4, New Jersey

WORLD'S LARGEST MANUFACTURERS OF ATTENUATORS

10,000 HOURS—*Minimum Life!*

For dependable service in Industrial, Aircraft, and Military Equipment

RCA-5690 is your answer for a "long-life" rectifier designed especially for industrial and aircraft applications. The tube is conservatively rated to take a peak inverse plate voltage up to a maximum of 1120 volts, a peak plate current up to 375 ma per plate, and an average plate current up to 75 ma per plate. Operating at maximum rated voltages, RCA-5690 will withstand a continuous vibration of 2.5 g at a frequency of 25 cps for hundreds of hours —and impact accelerations of 500 g for short periods.

In this tube each rectifier unit has its own heater and cathode—with separate base terminals for each. The heaters can be operated in parallel from a 6.3-volt supply—or in series from a 12.6-volt supply. Unique tube base design provides exceptionally high resistance to leakage between base pins and minimizes arc-over at high altitudes (you can operate the RCA-5690 at full ratings up to 40,000 feet).

For rectifier applications where 10,000-hour life and extreme dependability are paramount, specify RCA-5690's—and be secure. Get technical data from RCA, Commercial Engineering, Section 42HR, Harrison, N. J. Or call your nearest RCA Field Office:

(EAST) Humboldt 5-3900
415 S. 5th St., Harrison, N. J.
(MIDWEST) Whitehall 4-2900
589 E. Illinois St., Chicago, Ill.
(WEST) Madison 9-3671
420 S. San Pedro St., Los Angeles, Cal.

Other RCA "Special Red" Tubes
(Minimum life—10,000 hours)

RCA-5691	RCA-5693	RCA-5692
High-Mu Twin Triode	Sharp-Cutoff Pentode	Medium-Mu Twin Triode

RADIO CORPORATION of AMERICA
ELECTRON TUBES **HARRISON, N.J.**